

TOWN OF ASHLAND CITY Planning Commission Meeting February 05, 2024 5:30 PM Agenda

Chairwoman: Nicole Binkley

Committee Members: Vivian Foston, Gerald Greer, JT Smith, Steve Stratton, Mike Stuart, Jerome Terrell

CALL TO ORDER
ROLL CALL
APPROVAL OF AGENDA
APPROVAL OF MINUTES

1. January 08, 2024 PC Meeting Minutes

PUBLIC FORUM

2. Procedure for Speaking Before the Council

- * Speakers must complete the information form and submit it to the transcriber prior to the public forum. Be prepared to speak when your name is called.
- * Each speaker will be allowed 4 minutes.
- * Speakers may comment on issues scheduled for consideration at the meeting or other appropriate concerns pertinent to the operation of the town.
- * Each speaker should state the following:
 - his/her name
 - whether they are an Ashland City resident and/or property owner
- * No person shall be allowed to make obscene, derogatory, or slanderous remarks while addressing the Council/Board. Persons doing so will be asked to stop speaking and will forfeit the remainder of their time.
- * All remarks shall be directed to the Council/Board as a body only.
- * No person shall be allowed to disrupt or interfere with the procedures.
- * Remarks shall end when the speaker's allotted time has expired. No time shall be shared with other speakers.
- * Questions from the council/board members may be asked for clarification as well as council/board members may have brief comments; however, no person shall be permitted to enter any discussion or debate either directly with or through any member of the Council/Board or anyone present at the meeting.
- * No one shall make open comments during the meeting.

ELECT OFFICERS

- 3. Chair
- 4. Vice-Chair
- 5. Secretary

OLD BUSINESS

- 6. Site Plan Approval: Sleep Inn
- 7. AO Smith/ Ashland City Plat Approval

NEW BUSINESS

8. Rezoning of County Property

OTHER

9. Article IV Continued

ADJOURNMENT

Those with disabilities who require certain accommodations in order to allow them to observe and/or participate in this meeting, or who have questions regarding the accessibility of the meeting, should contact the ADA Coordinator at 615-792-6455, M-F 8:00 AM – 4:00 PM. The town will make reasonable accommodations for those persons.



TOWN OF ASHLAND CITY Planning Commission Meeting January 08, 2024 5:30 PM Minutes

CALL TO ORDER

Vice-Chairman Gerald Greer called the meeting to order at 5:30 p.m.

ROLL CALL

PRESENT

Committee Member Gerald Greer

Committee Member Steven Stratton

Committee Member Vivian Foston

Committee Member JT Smith

Committee Member Jerome Terrell

ABSENT

Chairwoman Nicole Binkley

Committee Member Mike Stuart

APPROVAL OF AGENDA

A motion was made by Committee Member Stratton, Seconded by Committee Member Foston, to approve the agenda. All approved by voice vote.

APPROVAL OF MINUTES

November 06, 2023 PC Meeting Minutes
 A motion was made by Committee Member Foston, Seconded by Committee Member Stratton, to approve the minutes as written. All approved by voice vote.

PUBLIC FORUM

None.

NEW BUSINESS

2. Site Plan Approval: Sleep Inn

Brian Hamilton and Amanda Bell spoke on behalf of the Sleep Inn. Mr. Gregory recommended approval once all deficiencies were corrected. A motion was made by Committee Member Foston, Seconded by Committee Member Stratton, to defer the site plan until all comments were addressed. All approved by voice vote. Motion Passes.

3. AO Smith/ Ashland City Plat Approval

A motion was made by Committee Member Stratton, Seconded by Committee Member Foston, to defer the plat since it is not ready. All approved by voice vote. Motion passes.

OTHER

4. Article IV Continued

Mr. Gregory and the Planning Commission reviewed Article IV of the zoning ordinance.

ADJOURNMENT

A motion was made by Committee Member Stratton, Seconded by Committee Member Foston, to adjourn the meeting. All approved by voice vote and the meeting adjourned at 6:55 p.m.

VICE-CHAIRMAN GERALD GREER	SECRETARY	



233 Tennessee Waltz Parkway Suite 103 Ashland City TN 37015 (615) 792-6455

APPLICATION FOR SITE PLAN APPROVAL

Site Plan Review Fee: \$100.00

Date Received: OC	ctober 16, 2023	}
	P/O 1203 Old Hyd	
_{Мар #} <u>062</u>	Parcel # <u>006</u>	Acreage: 1.82
Property Owner(s):	TERRY JOSHUA RI	EVOCABLE TRUST
Phone: 615-202-	9135	
Description of proje	ect being reviewed: Ne	w 48 Room Hote

Having submitted plans for review by the Ashland City Planning Commission, I understand that I am responsible for all review fees incurred by the Town of Ashland City. In understand that the fee paid at the time of submittal is not applicable for the fees incurred through review. With my signature, I verify that I fully understand that I am responsible for said fees, and that I have received a copy of Ordinance #165.

Oct 16, 2023

Applicant Signature

Date

PLANNING COMMISSION SUBMITTAL

for:



Located:



Vicinity Map

OLD HYDES FERRY PIKE &
SANDY RUN ROAD
ASHLAND CITY
CHEATHAM COUNTY
TENNESSEE

SHEET INDEX:

GENERAL:

CO COVER SHEET

PLAN SHEETS:

C1	EXISTING CONDITIONS
C2	SITE AND UTILITY PLAN
C3	GRADING AND DRAINAGE PLAN
C4	INITIAL EROSION CONTROL PLAN
C5	INTERMEDIATE EROSION CONTROL PLAN
C6	FINAL STABILIZATION PLAN
C7	DETAILS AND SWPPP NOTES
a201	EXTERIOR ELEVATIONS
L1	LANDSCAPE PLAN
L2	PHOTOMETRIC PLAN

Plan Prepared By:

Nashville Civil LLC
Site Design • Engineering
700 51st Avenue North
Nashville, TN 37209
P 615.353.9622
b@nashvillecivil.com

Architect:


Barnettdesignstudio.com 324 Main Street Suite 200 Frankline, TN 37064


COVER

CO

Project #: NC 23-472 | ITEM # 6.







Site Design • Engineering

architect:

Barnettdesignstudio.com 324 Main Street Suite 200 Frankline, TN 37064



sheet title: SITE AND UTILITY PLAN



located:

OLD HYDES FERRY PIKE SANDY RUN ROAD

ASHLAND CITY CHEATHAM COUNTY **TENNESSEE**

Original Issue Date:

1 19Oct23 - Property Line Change


2 13Nov23 - Additional Planning

Submittal 3 22Dec23 - Additional Planning

Submittal 4 29Dec23 - Planning Comments Addressed

5 25Jan24 - Planning Comments Addressed

Construction Drawings



Site Design • Engineering

700 51st Avenue North Nashville, TN 37209 P 615.353.9622 b@nashvillecivil.com

architect:

Barnettdesignstudio.com 324 Main Street Suite 200 Frankline, TN 37064



sheet title: GRADING AND DRAINAGE PLAN



located:

OLD HYDES FERRY PIKE & SANDY RUN ROAD

ASHLAND CITY CHEATHAM COUNTY TENNESSEE

Original Issue Date:

16 Oct 2023

1 19Oct23 - Property Line


Change 2 13Nov23 - Additional Planning Submittal

3 22Dec23 - Additional Planning Submittal 4 29Dec23 - Planning Comments

Addressed 5 25Jan24 - Planning Comments Addressed

Construction Drawings

Grading and Drainage Plan



Site Design • Engineering

architect:

Barnettdesignstudio.com 324 Main Street Suite 200 Frankline, TN 37064



sheet title: INITIAL EROSION CONTROL PLAN



OLD HYDES FERRY PIKE & SANDY RUN ROAD

ASHLAND CITY CHEATHAM COUNTY TENNESSEE

Original Issue Date:

1 19Oct23 - Property Line

Change 2 13Nov23 - Additional Planning


Submittal

3 22Dec23 - Additional Planning

Submittal 4 29Dec23 - Planning Comments

Addressed 5 25Jan24 - Planning Comments

Addressed



Site Design • Engineering

700 51st Avenue North Nashville, TN 37209 P 615.353.9622 b@nashvillecivil.com

architect:

Barnettdesignstudio.com 324 Main Street Suite 200 Frankline, TN 37064



sheet title:

located:

OLD HYDES FERRY PIKE & SANDY RUN ROAD

ASHLAND CITY CHEATHAM COUNTY TENNESSEE

1 19Oct23 - Property Line

Change 2 13Nov23 - Additional Planning


Submittal 3 22Dec23 - Additional Planning

Submittal 4 29Dec23 - Planning Comments Addressed

5 25Jan24 - Planning Comments Addressed

Construction Drawings

Intermediate Erosion Control Plan




Nashville Civil LLC Site Design • Engineering

700 51st Avenue North Nashville, TN 37209 P 615.353.9622 b@nashvillecivil.com

architect:

Barnettdesignstudio.com 324 Main Street Suite 200 Frankline, TN 37064



sheet title: FINAL STABILIZATION PLAN



located:

OLD HYDES FERRY PIKE SANDY RUN ROAD

ASHLAND CITY CHEATHAM COUNTY TENNESSEE

Project #: NC 23-472

Original Issue Date:

16 Oct 2023

Revisions:

1 19Oct23 - Property Line

. Change

2 13Nov23 - Additional Planning Submittal 3 22Dec23 - Additional Planning

Submittal 4 29Dec23 - Planning Comments Addressed

5 25Jan24 - Planning Comments Addressed

Construction Drawings

STORMWATER POLLUTION PREVENTION PLAN NOTES

1. The contractor is responsible for making sure that a copy of the SWPPP is retained on-site at or near the construction entrance. If a construction trailer in not available, the contractor shall provide a waterproof enclosure near the construction entrance to place the SWPPP. In addition to the SWPPP, the contractor shall make certain that the following information must also be posted at the construction site (in a construction trailer or in the waterproof enclosure): a.) A copy of the notice of coverage (NOC) with the NPDES permit tracking number for the construction project number, b.) name, company name, email address, telephone number and address of the project site owner or a local contact person; c.) a brief description of the project; d.) the location of the SWPPP if an on-site location for storing the plan is not available.

The owner of this project site will provide erosion control measures as shown on this SWPPP. If the owner sells this property, the new property owner will be required to obtain coverage under this permit from the governing federal, state and local agencies and the new property owner shall assume operational control and responsibility for the portion of the site that he/she purchases.

3. Prior to the commencement of any clearing or grubbing, the contractor shall erect "construction fencing", tree protection fencing, caution tape, etc. along the limits of disturbance to protect trees, stream bank buffers, etc. that are not to be disturbed.

4. Prior to any type of construction activity, the contractor shall install the stone based construction exit, the silt fence and the sediment traps/basins when indicated on the SWPPP. Additional erosion control measures such as rock check dams, diversion swales, temporary creek crossings, temporary mulching of disturbed areas, final seed and straw application and general erosion control maintenance shall be provided as construction progresses and these measures become necessary. The contractor shall be responsible for implementing all of the erosion control measures.

5. All erosion control measures shall be installed and maintained in accordance with the manufacture's specifications and recommendations. It is the purpose of all control measures to slow runoff so that rill and gully formation is prevented. The contractor shall inspect the control measures periodically and replace and/or modify the controls for relevant site situations.

6. Where the application of temporary or permanent grass seed is specified as part of the SWPPP the contractor shall use an appropriate grass seed mixture for the time of year that the seed is sowed. Use fescue during the spring and summer months and a mixture of fescue and winter rye during the fall and winter months. Sow at a rate of 6 lbs. per 1000 s.f. of area. Provide adequate amounts of water to establish a healthy stand of grass.

7. If sediment escapes the construction site, it is the contractor's responsibility to remove the sediment that has escaped the site. The contractor shall obtain the permission of the landowner where the sediment has accumulated before removal can begin. If sediment enters a stream, the contractor must also gain the written permission of the State before remediation/restoration can 8. The contractor shall remove sediment from sediment traps, silt fences, sedimentation ponds, and other sediment controls as necessary and must be removed when capacity has been reduced

9. Litter, construction debris and construction chemicals exposed to storm water shall be picked up and removed from the site to prevent them from becoming a pollutant source for storm water discharges. After use, materials used for erosion prevention and sediment control should be removed

10. There are no other construction activities or industrial activities associated with this project site that are covered under a separate permit.

11. There are no streams or wetlands on or near this project site, therefore no additional permits associated with these features are required

14. This project does not disturb more than 50 acres, but areas of the completed phase must be

12. All earth stockpiles, whether on the project site or off-site shall include erosion control measures to prevent the material from be washed from the site by storm water runoff.

13. Clearing and grubbing must be held to the minimum necessary for grading and equipment operation.

stabilized with in 15 days. 15. For projects that have a disturbed area of greater than 50 acres, the contractor shall provide a phasing plan to only disturb 50 acres or less at one time. Submit the phasing plan to the state and local

agencies for their review. 16. Erosion prevention and sediment control measures must be in place and functional before earth moving operations begin and must be constructed and maintained throughout the construction period. Temporary measures may be removed at the beginning of the workday, but must be replaced at the end of the workday.

17. The contractor shall maintain a rain gauge and daily rainfall records at the site.

18. The contractor shall initiate stabilization measures in portions of the site where construction activities have temporarily or permanently ceased. Temporary or permanent soil stabilization at the construction site must be completed no later than 15 days after the construction activity on that portion of the site has temporarily or permanently ceased.

19. The contractor shall construct temporary diversion swales to divert off-site runoff from crossing the disturbed areas. These diversion swales, when necessary, shall be field located to avoid existing trees wherever possible

20. No work shall be allowed in or around streams or wetlands without the proper permits. Prior to the commencement of any construction activities in these areas, the contractor shall obtain a copy of the permits from the property owner, which allows this work. He shall not begin work without obtaining a copy of these permits or stiff fines from the federal and state agencies may be levied.

Existing 6in W

To Be Provided

Contractor

Reduced Pressure

Backflow Preventer

Seperate Power To — Meters & BPs

And Installed By The

21. Muddy water to be pumped from excavation and work areas must be held in settling basins or filtered prior to its discharge into surface waters. Water must be discharged through a pipe, well-grassed or lined channel or other equivalent means so the discharge does not cause erosion and sedimentation. Discharged water must not cause an objectionable color contrast with the

22. After construction is complete, all disturbed areas, which are not covered with impermeable surface (i.e. asphalt, concrete, buildings, etc.), shall be covered with topsoil (4-inch thick minimum), grass seed and straw. The contractor shall maintain the seed and straw until a solid, healthy stand of permanent grass covers the disturbed areas.

23. Silt fence shall be used along the lower edge of disturbed areas that have sheet flow runoff. Where runoff is concentrated (such as swales and ditches), bumpus fences or rock check dams shall be used to slow the velocity and allow settling of sediment.

24. All construction and waste material shall be collected and removed from the site on a periodic basis. All construction and waste material shall be located outside of any existing or proposed drainage ways and shall be covered and protected from the rain until they are removed from the site. Any liquid materials or chemicals stored on-site shall be located away from any existing or proposed drainage ways and a berm of sufficient height to contain the entire volume of the liquid shall be constructed to completely encompass and impound the stored materials to prevent a spill from flowing off of the site.

25. All soil, plants, trees and other vegetation in protected streams and wetlands and along the banks of same are protected by State law and therefore a prohibited from being removed. The contractor shall ensure that these areas remain undisturbed during construction. He shall erect construction barriers or take other means necessary to insure that the areas remain protected.

26. The contractor shall employee a person to inspect the erosion control measures as required by the State and local agencies. The inspector must have successfully completed the "Fundamentals of Erosion Prevention and Sediment Control" course provided by the State. A copy of the certification or training record for inspector certification should be kept on site.

27. Inspections described in the Tennessee General Permit shall be performed at least twice every calendar week and shall be performed at least 72 hours apart. Inspect all erosion control measures, disturbed areas, storage of material areas, outfall points, construction access points, etc.

28. Inspections shall also be performed before anticipated storm events (or series of storm events such as intermittent showers over one or more days), and within 24 hours after the end of a storm event of 0.5 inches or greater.

29. Any inadequate control measures or control measures in disrepair shall be replaced or modified or repaired as necessary before the next rain event if possible, but in no case more than 7 days after the need is identified. The contractor shall provide additional érosion control measures where necessary to insure adequate control so that no silt exits the project site.

30. Inspections shall be documented and include: the scope of the inspection, name and title of personnel making the inspection, the date of the inspection, major observations relating to the implementation of the storm water pollution prevention plan (including the location of discharges of sediment or other pollutants from the site and of any control device that failed to operate as designed or proved inadequate fro a particular location), and actions taken in accordance with the General Permit. Inspections documentation will be maintained on site and made available upon request. Inspection reports must be submitted to the State (TDEC) within 10 days of the request. Use the inspection report form provided in Appendix C of the General Permit and complete on a

31. Sediment removed from sediment control structures is to be placed at a site that has been permitted by local and state agencies. The contractor is responsible for obtaining the site to waste" the sediment material. The sediment shall be treated in a manner so that the area around the disposal site will not be contaminated or damaged by the sediment in the storm water run-off. Cost of this treatment is to be included in the price for the earthwork.

32. The contractor shall seed and straw all disturbed areas as soon as possible after final grading\ is completed, unless otherwise indicated. The contractor shall take whatever means necessary to establish permanent soil stabilization. Any areas that do not include construction activity for more than 14 days shall be temporarily covered with straw to help prevent erosion.


33. Remove sediment from all drainage structures, pipes and swales before acceptance by the developer or the local governing agency.

34. Remove the temporary erosion and water pollution control devices only when in the opinion of the owner's representative, they are no longer needed. 35. During the period between the end of the construction and the establishment of the permanent

vegetation, erosion control measures shall remain in place and maintained. Once permanent

vegetation is established, then the erosion control measures may be removed. 36. This SWPPP is developed in accordance with the Tennessee General NPDES Permit (TNR100000) for storm water discharges associated with construction activity (TNCGP), and is prepared using sound engineering practices. Nashville Civil, LLC personnel involved with the development of this plan have completed the design of vegetative and structural measures for erosion and sediment control course available from the State of Tennessee.

As instructed by Part III.F of the TNCGP, this plan and all attachments are hereby submitted to the local Environmental Assistance Center (EAC), along with the complete, correctly signed Notice of Intent (NOI). Construction will not be initiated prior to 30 days from the date of submittal of this document, or prior to receipt of a Notice of Coverage (NOC) from the Tennessee Department of Environment and Conservation (TDEC). This SWPPP is an evolving document that can change with field adjustments. And changes in the field need to be noted and TDEC provided a copy of the changes.



(TYP, BOTH SIDES) AS REQUIRED CANE BOLT, TY LINE OF FOUNDATION BELOW →BRICK WALL CONC SLAB ELEVATION "A" *2' FEET MIN. ABOVE DUMPSTER HEIGHT PROVIDE ADDITIONAL COLLAR, BRACED BACK INE OF CONC. - BRICK TO MATCH BUILDING (TYP. BOTH SIDES)-" SCH. 80, TYP. BRICK WALL PLAN


6 BRICK SINGLE DUMPSTER ENCLOSURE not to scale

PRESS-IN
- POST CAP
(PVC/NYLON)

6"x2" Threaded Tapping Tee 6"Fire Meter Service Meter To Be Provided And Installed By The Contractor -6" PIV - Post Indicator / Reduced Pressure Backflow Preventer Fire Department,

REFLECTIVE WHITE PAVEMENT PAINT ─EXTEND STONE BASE 12" BEYOND EDGE OF BINDER — EXTEND BINDER 12" BEYOND BACK 1. USE 3500 P.S.I. CONCRETE. 2. PROVIDE CONTROL JOINTS @ 10' CENTERS. 3. PROVIDE EXPANSION JOINTS @ 50' CENTERS. 4. WHERE BINDER COURSE IS NOT PROPOSED, PLACE CURB DIRECTLY ON STONE BASE. STONE TO EXTEND 12" BEHIND BACK OF CURB. CENTERLINE OF Parking space

2EXTRUDED CURB not to scale




Plan Prepared By:

Site Design • Engineering 700 51st Avenue North Nashville, TN 37209 P 615.353.9622

architect:

b@nashvillecivil.com

Barnettdesignstudio.com 324 Main Street Suite 200 Frankline, TN 37064



CIVIL DETAILS AND SWPPP NOTES

located:

OLD HYDES FERRY PIKE SANDY RUN ROAD

ASHLAND CITY CHEATHAM COUNTY **TENNESSEI**

Project #: NC 23-472 Original Issue Date:

16 Oct 2023

Revisions: 1 190ct23 - Property Line Change

2 13Nov23 - Additional Planning Submittal 3 22Dec23 - Additional Planning

Submittal 4 29Dec23 - Planning Comments Addressed 5 25Jan24 - Planning Comments

Addressed

Construction Drawings

ITEM # 6.

Civil Details And SWPPP Notes

5 POOL FENCE DETAIL not to scale

TS 2"x2" FENCE POST-

FOUNDATION BELOW

ELEVATION "B"

 $8' - 3\frac{3}{4}"$ [2534] $8'-2\frac{3}{4}"$ [2508] (PANEL WIDTH)


 $8'-1\frac{3}{4}"$ [2483] (R.O.)

3 HANDICAP PARKING SYMBOL not to scale 4 WATERLINE DETAIL not to scale


- Page 11 -

PER POST (TYP.)









CONSTRUCTION

CONSTRUCTION

CONSTRUCTION

COPYRIGHT © 2023

This drawing and the design shown is the property of the Architect. The reproduction, copying, or use of this drawing without their written consent is prohibited and any infringement will be subject to legal action.

B A R N E T T
D E S I G N
SUITE 105 || FRANKLIN, TN || 37064

consultants:


proje

SLEEP INN

revisions

date: 11.14.2023
project no.: 2312

EXTERIOR
ELEVATIONS



TREE PLANTING DETAIL NOT TO SCALE


Tree Quality Notes:

Landscape Notes:

I. Unless specifically noted, all trees shall be of specimen quality, exceptionally heavy, symmetrical, and so trained or favored in development and appearance as to be unquestionably and outstandingly superior in form, compactness, and symmetry. They shall be sound, healthy, vigorous well branched, and densely foliated when in leaf; free of disease and insects; and shall have healthy, well-developed

root systems. They shall be free from physical damage or other conditions that would prevent vigorous growth.

2. Trees with co-dominant leaders and/or included bark shall be rejected. Trees with a damaged or crooked leader, girdled trunk, bark abrasions, sunscald, disfiguring knots, insect damage, sheared crown, cuts of limbs over 3/4" diameter that are not completely closed shall be rejected.




SHRUB PLANTING DETAIL

NOT TO SCALE

1. All work shall be performed by fully qualified Plantsmen. Use good Horticultural practices to keep all plants and plant material

- installed in a living, healthy condition up to the date of termination of the contractor's responsibility for care. 2. The Landscape Contractor shall be responsible for examining fully both the site and the bid documents. Discrepancies in the documents or the actual site conditions shall be reported to the Landscape Architect in writing at the time of bidding or discovery. No account shall be made after contract completion for failure to report such condition, or for errors on the part of the Landscape Contractor at the time of bidding.
- 3. The Landscape Contractor is responsible for locating all underground utilities and shall avoid damage to utilities during the course of the work. The Landscape Contractor is responsible for repairing any damage to utilities, site structures, etc., resulting from landscape construction.
- 4. The Landscape Contractor shall be responsible for securing all necessary applicable permits and licenses to perform the work set forth on this plan set and the
- specifications. 5. The Landscape Contractor shall verify all material quantities. In the event of a discrepancy, the quantities shown on the plan will take precedence.
- 6. No material shall be planted before finish grading has been completed.
- 7. The plants delivered to the project site shall be planted as soon as site conditions permit. Take care in scheduling plant deliveries
- and the size of the deliveries so that long periods of storage are avoided. Adequately protect plants placed in temporary storage from the sun and wind; water plants so as to maintain their appearance and health. Plants that have not been properly maintained during
- temporary storage may be rejected by the Landscape Architect. 8. Should the Contractor encounter unsatisfactory surface or other subsurface drainage conditions, soil depth, latent soils, hard pan, stem of utility lines or other
- conditions that will jeopardize the health and vigor of the plants, he must advise the Owner's Representative in writing of the conditions prior to installing the plants. Otherwise the Contractor warrants that the planting areas are suitable for proper growth and development of the plant material to be installed and contractor shall take responsibility for the cost of any revision. 9. It is the responsibility of the Contractor to verify that each excavated tree or shrub pit will percolate (drain) prior to adding topsoil of planting mix and installing trees
- or shrubs. The Contractor shall fill the bottom of selected holes with six inches of water. This water should percolate out within a 24-hour period. If the soil at a given area does not drain properly, a PVC drain or gravel sump shall be installed or the planting relocated to and area approved by the Owner's Representative. 10. Prior to installation of plant materials, the width and length of all parking lot landscape island and median areas are to be excavated to a depth of 24 Inches below the proposed top of pavement elevation. Excavated material is to be removed from the landscape areas and disposed of off site or in an area approved by the
- Project Engineer. No asphaltic construction trash and/or materials are to be left in the topsoil and planting mix backfill and/or subgrade of any proposed parking area islands and/or planting medians and strips. Parking lot islands and medians are to be backfilled with sifted topsoil as per project specifications and to the elevations indicated on the grading plans.
- 11. All shrub and ground cover beds not in parking lot islands or median strips are to be excavated to a depth of 12 Inches and disposed of off site or in an area approved by the Project Engineer. Trees in these bed areas shall be installed per the tree planting detail. The bed area is to be backfilled with sifted topsoil to the elevations indicated on the grading plans as per the specifications.
- 12. The optimum time for planting is from October 1 to April 1. Scheduling for planting at other times must be approved in writing by the Landscape Architect.
- 13. Existing trees to remain shall be protected from construction damage. Selectively prune dead wood.
- 14. New tree plantings are to be staked per planting details. Trees that are not staked according to detail will be rejected.
- 15. All deciduous trees, existing and proposed shall be pruned to provide 4' minimum clear trunk unless otherwise noted.
- 16. The Landscape Contractor shall stake or mark all plant material locations prior to installation. The Landscape Contractor shall have the Owner's Representative approve all staking prior to installation.
- 17. All plant material which dies, turns brown, or defoliates (prior to total acceptance of the work) shall be promptly removed from the site and replaced with material
- of the same species quantity and size and meeting all plant list specifications. 18. The Landscape Contractor shall grade planting beds, as required, to provide positive drainage and promote optimum plant growth.
- 19. Chemical Weed Control (pre-emergent, i.e. Treflan) shall be applied to all landscape areas prior to any plant installation.
- 20. All planting areas shall receive a 3" layer of the mulch as specified in the materials schedule, which is to be watered-in after installation.
- 21. All plants shall be vigorous, healthy material, free of pests and disease.
- 22. All plants and trees must meet all requirements specified in the plant list, details, and specifications.
- 23. The standards set forth in "American Standard for Nursery Stock" represent general guideline specifications only and will constitute minimum quality requirements for plant material. All plants must meet minimum size noted at the materials schedule. Trees shall be No. I grade specimen and shrubs shall be heavy well shaped specimens as well.
- 24. All disturbed areas shall be planted with turf as indicated on the materials schedule.
- 25. Existing sod shall be removed as necessary to accommodate new plantings. 26. Any existing sod areas that are unnecessarily disturbed during the landscape installation shall be resodded to match existing.
- 27. The Landscape Contractor is responsible for completely maintaining the work (including but not limited to: watering, mulching, spraying, fertilizing, of all planting areas and lawns per project specifications until total acceptance of the work by the owner.
- 28. The Landscape Contractor shall completely guarantee all work for a period of one year beginning at the date of total acceptance. 29. The Landscape Contractor shall provide the owner with written instructions on the proper care of all specified plant materials prior to final payment.
- 30. The Landscape Contractor will be responsible for the collection, removal, and proper disposal of any and all debris generated during the installation of this project. 31. ATTENTION OWNER/INSTALLER:
- This landscape plan has been designed to meet the minimum requirements of the Ashland City zoning ordinance, the approval of the planning commission, and planning department policy. Relocating, substituting, resizing, reducing or deleting material may cause the site to no longer conform to the requirements; Thus problems may arise with releasing the performance/maintenance bond for landscaping. Deviation from the approved landscape plan shall not be nade without first consulting Greenspace Design and then obtaining approval from either the planning commission or the planning department.











sheet title: LANDSCAPE PLAN

located:

Project #: NC 23-472

Original Issue Date: 20 Nov 2023


Revisions:

03 Jan 2024


Construction Drawings


Photometric Plan





FOUNDATION DETAIL FOR OUTSIDE LIGHTING NOT TO SCALE







233 Tennessee Waltz Parkway Suite 103 Ashland City TN 37015 (615) 792-6455

11. Location and area of open space. $Noted C2$
12. A table showing the ground coverage, total floor area and building heights. Site Data on C2
13. Location, dimension and heights of all fences and walls with materials specified. None Planned.
14. Location, type and amount of landscaping. Landscape Play Provided
15. Proposed means of surface drainage, including locations and sizes of all culverts, ditches and detention structures, storm-water system to be designed as per the requirements of the Ashland City Planning Commission. Surface Drainage to Bio-Retention Fonds.
16. Dimensioned location of all easements and right-of-ways. Shown. No proposed.
17. Location of all portions of the site that are within the floodway and the 100-year floodplain. A note will be included which gives the FEMA map number from which this information was developed. In addition, if portions of the site are in the 100-year floodplain and/or the floodway, the 100-year flood elevation(s) at the site will be listed on the plan. FEMA NOTE on C3. NO Floodplain on
18. Location, size, and distance to all public utilities serving the site including all fire hydrants.
 19. Location, by type and size of all proposed signs, (Please note that signs larger than 40 sq. ft. are not permitted per the sign ordinance for the Town of Ashland City. Entrance 5 ign 40 SF 20. Vegetation, show at minimum the following: a. Existing tree masses and hedgerows b. General description of the tree types and sizes within the tree masses b. General description of trees 15" in caliper (measured 4' above the ground) or larger c. Location and identification of trees 15" in caliper (measured 4' above the ground) or larger d. Description of landscaping requirements for the site based upon surrounding land uses (see Zoning Ordinance Section 3, 140)
21. Identification of slopes greater than 15% and identification of those soils (SCS soil mapping is acceptable) on those slopes. **No Slopes** > 15%**
22. Site plan application fee \$100
23. Additional engineering review etc., site inspection charges are subject to Section 14-301 of the Ashland City Municipal Code per Ordinance #165.
24. Three (3) sets of the construction plans for the site.



233 Tennessee Waltz Parkway Suite 103 Ashland City TN 37015 (615) 792-6455

PLANNING COMMISSION SITE PLAN CHECKLIST

NAME OF SITE Sleep Inn
LOCATION 1203 Old Hydes Ferry Pike ZONING DISTRICT C2
OWNER TERRY JOSHUA REVOCABLE TRUST
ENGINEER Brian Hamilton, PE with Nashville Civil LLC
1. Three (3) copies of the site plan. Please indicate at time of application if you would like any of the remaining copies after your case is heard and voted on.
2. Three (3) copies and an electronic PDF of revised site plans made available to the Fire, Building and Life Safety Department – according to planner/engineer comments. Also written response to all comments to match what was changed on revised site plans.
3. Location map of the site at a scale of not less than 1"=2000' (USGS map is acceptable). Map must show the following: a. Approximate site boundary Exact boundary provided b. Public streets in the vicinity 3 hown c. Types of development of surrounding parcels Noted on Cl d. Public water and sewer lines serving the site Shown on All gleets e. Map # and Parcel # of site location Noted All Sheets
4. Site boundary, stamped and signed by a registered surveyor. Cl - stamped
5. The shape, size and location of all existing buildings on the lot. No Existing Buildings
 The existing and intended use of the lot and of structures on it. If residential, give the number of dwelling units per building. Δ2 - 5 He Plan Notes
7. Topographic survey of the site with contour intervals at no greater than 5' intervals, stamped and signed by a registered surveyor. Survey Provided, 2ft Confours
8. Location of all driveways and entrances with dimensions from the centerline of the drive to the nearest property corner and to the nearest intersection (if the intersection is closer than 200 feet).
9. Dimensioned layout and location of all parking spaces including handicapped spaces. Shown on C2
10. Dimensioned layout and location of off-street loading bays and docks.
Show on C2



233 Tennessee Waltz Parkway Suite 103 Ashland City TN 37015 (615) 792-6455

25. Submittal must be made at least 20 working days prior to the Planning Commission meeting to be h	e hear	oe h	o h	g to	meeting	sion	ommissi	Co	ning	Plan	the	or to	pr	days	king	wor	20	least	at	made	be	must	Submittal	25.
--	--------	------	-----	------	---------	------	---------	----	------	------	-----	-------	----	------	------	-----	----	-------	----	------	----	------	-----------	-----

26. If application is requesting a variance, application is to be submitted to the Building Official in accordance with Section 7.080 of the Ashland City Zoning Ordinance.