



CITY of BRISBANE

Planning Commission Meeting Agenda

Thursday, August 24, 2023 at 7:30 PM • Hybrid Regular Meeting

• Brisbane City Hall 50 Park Place, Brisbane CA

The public may observe/participate in Planning Commission meetings using remote public comment options or attending in person. Planning Commissioners shall attend in person unless remote participation is permitted by law. The Commission may take action on any item listed on the agenda.

TO ADDRESS THE COMMISSION

In Person:

Location: 50 Park Place, Brisbane, CA 94005, Community Meeting Room

Masks are no longer required but are highly recommended in accordance with California Department of Health Guidelines. To maintain public health and safety, please do not attend in person if you are experiencing symptoms associated with COVID-19 or respiratory illness.

To address the Planning Commission on any item on or not on the posted agenda, fill out a Request of Speak Form located in the Community Meeting Room Lobby and submit it to the City staff.

Remote Participation:

Members of the public may observe/participate in the meeting by logging into the Zoom webinar listed below. Planning Commission Meetings may also be viewed live and/or on-demand via the City's YouTube channel at youtube.com/brisbaneca, or on Comcast Channel 27. Archived videos may be replayed on the City's website, brisbaneca.org/meetings. Please be advised that if there are technological difficulties, the meeting will nevertheless continue.

The agenda materials may be viewed online at brisbaneca.org/meetings at least 24 hours prior to Special Meetings, and at least 72 hours prior to a Regular Meeting.

Remote Public Comments:

Meeting participants are encouraged to submit public comments in writing in advance of the meeting. Aside from commenting while in the Zoom webinar the following email and text line will be also monitored during the meeting and public comments received will be noted for the record during Oral Communications or during an Item.

Email: jswiecki@brisbaneca.org or **Text:** 415-713-9266

Zoom Webinar: (please use the latest version: zoom.us/download)

brisbaneca.org/pc-zoom

Webinar ID: 970 0458 3387

Call In Number: +1 (669) 900-9128

SPECIAL ASSISTANCE

If you need special assistance to participate in this meeting, please contact the Community Development Department at (415) 508-2120 in advance of the meeting. Notification in advance of the meeting will enable the City to make reasonable arrangements to ensure accessibility to this meeting.

WRITINGS THAT ARE RECEIVED AFTER THE AGENDA HAS BEEN POSTED

All written communications are provided to the Planning Commission. Any written communication that is received after the agenda has been posted but before 4 p.m. of the day of the meeting will be available for public inspection at the front lobby in City Hall and online at brisbaneca.org/meetings. Any writings that are received after the agenda has been posted but after 4 p.m. of the day of the meeting will be available on the internet at the start of the meeting (brisbaneca.org/meetings), at which time the materials will be distributed to the Planning Commission.

Commissioners: Funke, Gooding, Lau, Patel, and Sayasane

CALL TO ORDER

ROLL CALL

ADOPTION OF AGENDA

CONSENT CALENDAR

Please Note: Items listed here as Consent Calendar Items are considered routine and will be acted upon collectively by one motion adopting the Planning Department's recommendation unless a member of the public, the Commission, or its staff asks to remove an item to discuss it. Prior to the motion, the Chairperson will ask if anyone wishes to remove an item from the Consent Calendar.

- A. [Approval of draft meeting minutes of May 25, 2023](#)
- B. [Approval of draft meeting minutes of June 8, 2023](#)

ORAL COMMUNICATIONS (Limited to a total of 15 minutes)

WRITTEN COMMUNICATIONS

OLD BUSINESS

None

NEW BUSINESS

- C. [PUBLIC HEARING: 5 Beatty Ave; 2023-UP-5, 2023-UP-6, 2023-EX-2; HC and C-1 districts; Baylands Interim Use Permit, Parking Modification Use Permit and Grading Permit to allow for parking of approximately 199 San Francisco District School buses](#)

and placement of an approximately 2,880 square foot office trailer for bus operations management on a 3.3 acre, gravel surfaced site, which was formerly used for San Francisco 49ers parking; with grading of approximately 493 cubic yards of cut and 240 cubic yards of fill to level certain settlement monitoring stations and soil berms; and finding that this project is categorically exempt from environmental review under CEQA Guidelines Section 15301 and 15304(a)(e); Travis Duncan, applicant; Baylands Development Inc. (BDI), owner.

- D. **PUBLIC HEARING: 3708 Bayshore Boulevard; Use Permit 2022-UP-7, Grading Review 2022-EX-5, Lot Merger 2022-LLA-3, Habitat Conservation Plan Compliance 2022-HCP-1; SCRO-1 Zoning District; Expansion of the current contractor's storage yard permitted under UP-9-12; and finding that this project is categorically exempt from environmental review under CEQA Guidelines Sections 15301 and 15311; Sean Brennan, applicant; MK Yard LLC, owner.**

ITEMS INITIATED BY STAFF

ITEMS INITIATED BY THE COMMISSION

ADJOURNMENT

- E. Adjournment to the regular meeting of September 14, 2023

APPEALS PROCESS

Anyone may appeal the action of the Planning Commission to the City Council. Except where specified otherwise, appeals shall be filed with the City Clerk not later than 15 calendar days following the Planning Commission's decision. Exceptions to the 15 day filing period include the following: appeals shall be filed with the City Clerk within 6 calendar days of the Planning Commission's action for use permits and variances and 10 calendar days for tentative maps and advertising sign applications. An application form and fee is required to make a formal appeal. For additional information, please contact the City Clerk at 415-508-2110.

File Attachments for Item:

A. Approval of draft meeting minutes of May 25, 2023

DRAFT
BRISBANE PLANNING COMMISSION
Action Minutes of May 25, 2023
Hybrid Meeting

ROLL CALL

Present: Commissioners Funke, Gooding, Lau, Patel, and Sayasane
Absent: None
Staff Present: Director Swiecki, Senior Planner Ayres, and Associate Planner Robbins

CALL TO ORDER

Chairperson Funke called the meeting to order at 7:30 p.m.

ADOPTION OF AGENDA

A motion by Commissioner Gooding, seconded by Commissioner Patel to adopt the agenda. Motion approved 5-0.

CONSENT CALENDAR

A motion by Commissioner Gooding, seconded by Commissioner Patel to adopt the consent calendar (agenda item A). Motion approved 5-0.

ORAL COMMUNICATIONS

Jameel Munir, Brisbane resident, inquired about the status of the 2023-2031 Housing Element and General Plan updates.

WRITTEN COMMUNICATIONS

Chairperson Funke acknowledged 13 written correspondences pertaining to agenda item B.

NEW BUSINESS

- B. PUBLIC HEARING: 25 Visitacion Ave; 2023-DP-1/2023-UP-3;** NCRO-2 District; Demolition of an existing commercial building and construction of a new two-story, 4,078 square foot mixed-use structure including one single-family dwelling unit and attached accessory dwelling unit constructed above and behind a 734 square foot storefront; and finding that this project is categorically exempt from environment review under CEQA Guidelines Sections 150301(l), 15303(a), and 15303(c); Xie Guan, applicant; Bonnie Boswell and Joel Diaz, owners.

Senior Planner Ayres gave the staff presentation and answered questions from the Commission about the setbacks of the new structure in relation to neighboring buildings and how the applicant could provide the required parking.

Chairperson Funke opened the public hearing.

DRAFT
Brisbane Planning Commission Minutes
May 25, 2023
Page 2

Joel Diaz, applicant, answered questions about the number of bedrooms within the residential unit, timetable to construct the project, and potential construction impacts to neighbors.

Jameel Munir, Brisbane resident, spoke in favor of the project.

With no one wishing to address the Commission, a motion by Commissioner Patel, seconded by Commissioner Gooding to close the public hearing was approved 5-0.

During deliberations, Joel Diaz publicly withdrew his request for a parking modification to reduce the parking requirement of the project. A motion by Commissioner Gooding, seconded by Commissioner Sayasane, to approve the design permit and use applications as modified by the applicant, with a condition of approval that the project shall meet the parking requirement of three off-street parking spaces, was approved 5-0.

Resolution 2023-DP-1/2023-UP-3 will be amended by staff to reflect the applicant's withdrawal of the request to modify the parking regulation and capture the modifications made by the Commission, and brought back to the Commission for approval at the next regular meeting.

Chairperson Funke read the appeals process.

ITEMS INITIATED BY STAFF

Director Swiecki informed the Commission that the [2023-2031 Housing Element was certified by the State](#) and closure of the comment period for the [Baylands Notice of Preparation of an EIR](#) on May 26, 2023.

ITEMS INITIATED BY THE COMMISSION

There were none.

ADJOURNMENT

Chairperson Funke declared the meeting adjourned to the next regular meeting of June 8, 2023 at approximately 8:45 p.m.

Attest:

John A. Swiecki, Community Development Director

NOTE: A full video record of this meeting can be found on the City's YouTube channel at www.youtube.com/BrisbaneCA, on the City's website at <http://www.brisbaneca.org/meetings>, or on DVD (by request only) at City Hall.

File Attachments for Item:

B. Approval of draft meeting minutes of June 8, 2023

DRAFT
BRISBANE PLANNING COMMISSION
Action Minutes of June 8, 2023
Hybrid Meeting

ROLL CALL

Present: Commissioners Funke, Lau, Patel, and Sayasane
Absent: Commissioner Gooding
Staff Present: Director Swiecki, Senior Planner Johnson, Senior Planner Ayres

CALL TO ORDER

Chairperson Funke called the meeting to order at 7:30 p.m.

ADOPTION OF AGENDA

A motion by Commissioner Patel, seconded by Commissioner Lau to adopt the agenda. Motion approved 4-0.

CONSENT CALENDAR

A motion by Commissioner Patel, seconded by Commissioner Sayasane to adopt the consent calendar (agenda item A). Motion approved 4-0.

ORAL COMMUNICATIONS

There were none.

WRITTEN COMMUNICATIONS

Chairperson Funke acknowledged one written correspondence for an item not on the agenda.

WORKSHOP

B. Preliminary Zoning Ordinance Amendments for Compliance with SB 478, Housing Element Implementation and Zoning Ordinance Cleanup

Senior Planners Johnson and Ayres gave the staff presentation and answered questions from the Commission about how the proposed changes to building heights would be applied and eliminating minimum lot width standards, and provided clarification on the proposed modifications to the City's current and various setback exceptions.

ITEMS INITIATED BY STAFF

DRAFT
Brisbane Planning Commission Minutes
June 8, 2023
Page 2

Director Swiecki recapped the May 31, 2023 Planning Commissioners workshop sponsored by 21 Elements attended by Commissioners Gooding and Lau and encouraged the Commission to attend the next workshop in the series in October.

ITEMS INITIATED BY THE COMMISSION

There were none.

ADJOURNMENT

With the cancellation of the June 22, 2023 meeting, Chairperson Funke declared the meeting adjourned to the next regular meeting of July 13, 2023 at approximately 8:40 p.m.

Attest:

John A. Swiecki, Community Development Director

NOTE: A full video record of this meeting can be found on the City's YouTube channel at www.youtube.com/BrisbaneCA, on the City's website at <http://www.brisbaneca.org/meetings>, or on DVD (by request only) at City Hall.

File Attachments for Item:

C. PUBLIC HEARING: 5 Beatty Ave; 2023-UP-5, 2023-UP-6, 2023-EX-2; HC and C-1 districts; Baylands Interim Use Permit, Parking Modification Use Permit and Grading Permit to allow for parking of approximately 199 San Francisco District School buses and placement of an approximately 2,880 square foot office trailer for bus operations management on a 3.3 acre, gravel surfaced site, which was formerly used for San Francisco 49ers parking; with grading of approximately 493 cubic yards of cut and 240 cubic yards of fill to level certain settlement monitoring stations and soil berms; and finding that this project is categorically exempt from environmental review under CEQA Guidelines Section 15301 and 15304(a)(e); Travis Duncan, applicant; Baylands Development Inc. (BDI), owner.



PLANNING COMMISSION AGENDA REPORT

Meeting Date: August 24, 2023

From: Ken Johnson, Senior Planner

Subject 5 Beatty Ave; 2023-UP-5, 2023-UP-6, 2023-EX-2; HC and C-1 districts; Baylands Interim Use Permit, Parking Modification Use Permit and Grading Permit to allow for parking of approximately 199 San Francisco District School buses and placement of an approximately 2,880 square foot office trailer for bus operations management on a 3.3 acre, gravel surfaced site, which was formerly used for San Francisco 49ers parking; with grading of approximately 493 cubic yards of cut and 240 cubic yards of fill to level certain settlement monitoring stations and soil berms; and finding that this project is categorically exempt from environmental review under CEQA Guidelines Section 15301 and 15304(a)(e); Travis Duncan, applicant; Baylands Development Inc. (BDI), owner.

REQUEST: The applicant requests approval of a 5-year Interim Use Permit to allow the prospective operator, Zum, to park approximately 199 San Francisco School District buses on the 3.3-acre, gravel surfaced site. The site was formerly used for 49ers overflow parking. A 2,880 square foot office trailer would also be placed at the site as a bus operations management office, for approximately 10 people. The site is located atop the Baylands landfill, which closed to operations in the 1960's. Prior to occupying the site with the proposed use, certain landfill settlement monitoring stations and soil berm areas, located within the parking area, would be graded to be level with the surrounding parking area, resulting in grading cut of approximately 493 cubic yards and fill of 240 cubic yards. Also, since the parking for the office trailer is proposed to be accommodated on the existing gravel surface and not paved, as provided in the off-street parking standards, a parking modification use permit is requested.

RECOMMENDATION: Approve Interim Use Permit application 2023-UP-5, 2023-UP-6, 2023-EX-2 via adoption of Resolution 2023-UP-5, 2023-UP-6, 2023-EX-2 containing the findings and conditions of approval (See Attachment A).

ENVIRONMENTAL DETERMINATION: The project is categorically exempt from the provisions of the California Environmental Quality Act (CEQA) per Sections 15301 and 15304(a)(e) - this project falls within a class of projects which the State has determined not to have a significant effect on the environment. The exceptions to this categorical exemption referenced in Section 15300.2 of the CEQA Guidelines do not apply.

APPLICABLE CODE SECTIONS: Brisbane Municipal Code (BMC) Chapter 17.41, provides procedures, required findings and conditions for the approval of interim uses in the Baylands subarea. Required findings for interim use permits are provided in BMC Section 17.41.060 and mandatory conditions of approval are provided in Section 17.41.070. BMC Sections 17.40 and 17.34.050.I provides the procedures and findings for granting a parking modification use permit. BMC Sections 15.01.110 and 17.32.220 provides for Planning Commission review of grading of more than 250 cubic yards, with findings contained in Section 15.01.110.B.

Note that the General Plan designation is split for this proposed use area between the Heavy Commercial HC and Baylands Planned Development subareas. While the zoning is in the process of being updated through an ongoing specific plan process, the current more restrictive BMC zoning provisions of the Baylands interim use permit prevail for this application. Both subareas allow for the use by conditional use permit. However, the interim use permit limits the term to 5-years and has added findings for approval, as further detailed in Attachment A.

ANALYSIS AND FINDINGS:

Background

The site is located at the northwest corner of the 5 Beatty Ave property, on the same parcel that is used by Brisbane Recycling Co, but to the north of the soil recycling operations. The subject site area has previously been graded and surfaced with gravel and has historically been used for San Francisco 49ers overflow parking, as approved by the Planning Commission beginning with Use Permit UP-15-10 (9/23/10), then in 2012 by City Council, via Use Permit UP-5-12, for the 2012/2013 season. That was for parking up to 600 vehicles on game days. The 49ers moved to Santa Clara in 2014. Also, in 2014, Use Permit UP-3-14 was approved by the Commission for a Peterson Cat earth moving equipment demonstration event, utilizing the same area for event parking.

While the site has previously been surfaced with gravel for parking, there are a few isolated areas that are either a few feet lower or higher than the surrounding grade, either having soil berms or depressed areas that were used for landfill settlement monitoring stations. These stations are no longer in use and the applicant proposes to grade these to match the surrounding parking grade level.

Description of Proposed Use

The applicant has provided a project description, which describes the work needed to occupy the site and the day-to-day operations. See Attachments C and D for the applicant's project description and plans. The project is also described as follows.

The proposal is to park approximately 199 school buses at the site to serve the schools of the San Francisco School District. A 5-year term is requested. The entrance to the site is from a paved 2-lane entrance drive from Beatty Ave, which is near the on-off ramps to U.S. 101. The

driveway is shared with Brisbane Recycling Co. which is located to the south on the same parcel.

The bus parking yard would be supported by an approximately 2,880 square foot, mobile office trailer and a portable toilet facility. Approximately 10 office workers managing the bus operations would occupy the site. A 6-foot high perimeter fence is proposed around the use area with three gates. The installation of portable solar powered light standards and security cameras is also proposed.

The applicant has indicated that they would have electrical power service to the building from a nearby power pole located just south of the use area, on the site. Since the site is located atop a former landfill, excavation for water and sewer utilities would be a costly and time-consuming endeavor. Given the temporary nature of the use, it is proposed that the site would not be served by an off-site water supply or sewer. Instead, a portable toilet would be maintained on site. A water tank may also be located on site for fire suppression, as may be required by the North County Fire Authority through the building permit process. A condition is also included to require the operator to provide bottled drinking water.

The applicant has proposed minimal alterations to the site, in keeping with the requested time frames for this use and respecting the existing conditions of the site. Currently, stormwater infiltrates into the soil or runs off to a nearby stormwater collection swale and additional on-site stormwater collection and treatment facilities are not proposed.

As indicated above, the applicant's project description indicates that the modular office would be staffed by approximately 10 people and approximately 199 drivers would come and go from the site. Typical hours of operation would be Monday through Friday from 5 am to 7 pm, although most of the bus activity would be between 7 am and 4 pm. Roughly 30 percent of the bus routes return to the parking facility during the day, while the remainder stays close to their pick-up and drop off locations during the day. Occasionally, there would be other trips outside these hours for extracurricular activities. These may include some weekend trips in support of special school events. The applicant has provided a route map, which shows that the bus trips would be directly on Beatty Ave to and from U.S. 101, with some bus trips to or from Tunnel Ave under unusual circumstances, such as road closures or local serving buses as may be approved by the Planning Director. The highest concentration of hourly vehicle trips would occur between 6 and 7 am on weekdays, estimated at approximately 100, trips, including arriving personal cars. The applicant's project description showed significantly fewer personal car trips are estimated versus bus trips each day, which is attributed to the use of public transportation and carpooling.

The buses would range in size from minivans to standard school buses. Most of these will be shuttle bus size or smaller, less than 23 feet in length, which better serve the urban nature of San Francisco.

Since the proposal is to conduct the use on the existing gravel surfaced lot, dust control measures would be implemented on an ongoing basis, per a City approved dust control plan.

Findings

The proposal, including the conditions of approval, complies with all of the findings for approval. The listing and analysis of findings is provided in Attachment B.

In summary, the proposed use is consistent with the surrounding industrial uses. Its location provides for ready access to U.S. 101 for the buses and associated personal vehicles that would come and go from the site. A building permit will be required to establish the use. Lighting would be provided via portable light standards and would be required to be directed downward onto the site and a dust control plan will be required by the City Engineer for both the initial establishment of the use and on an ongoing basis.


Finally, this application was provided to the Building Dept, North County Fire Authority, Dept of Public Works, Police Dept, County Health Dept, and the Regional Water Quality Control Board, San Francisco PUC, and Bayshore Sanitary District for review and comment. Recommended conditions of approval have been provided by some of these departments and are included in the draft resolution. Given the conditions of approval, none of the departments or agencies raised objections to the proposed use

ATTACHMENTS

- A. Draft Resolution 2023-UP-5, 2023-UP-6, 2023-EX-2
- B. Site Location Map/Vehicle Routing
- C. Applicant's Project Description
- D. Applicant's Plans



Ken Johnson, Senior Planner



John Swiecki, Community Development Director

ATTACHMENT A

Draft

RESOLUTION 2023-UP-5, 2023-UP-6, 2023-EX-2

A RESOLUTION OF THE PLANNING COMMISSION OF BRISBANE
 CONDITIONALLY APPROVING INTERIM USE PERMIT, PARKING MODIFICATION AND GRADING
 PERMIT 2023-UP-5, 2023-UP-6, 2023-EX-2
 AT 5 BEATTY AVE

WHEREAS, following a public hearing on August 24, 2023, the Planning Commission granted Interim Use Permit 2023-UP-5, Parking Modification Use Permit 2023-UP-6, Grading Permit 2023-EX-2 to utilize a vacant, approximately 3.3 acre portion of the Baylands, located at the north end of 5 Beatty Ave, which approvals took effect on August 31, 2023 following closure of a 6-calendar day appeal period during which no appeals were filed; and

WHEREAS, the above-referenced permits have a pending expiration date of March 6, 2023, five years following the effective date of UP-8-16; and

WHEREAS, Travis Duncan, the applicant, applied to the City of Brisbane for Interim Use Permit 2023-UP-5, Parking Modification Use Permit 2023-UP-6, Grading Permit 2023-EX-2, with 2023-UP-5 being for a 5-year term, as provided in BMC Section 17.41.080.D; and

WHEREAS, on August 24, 2023, the Planning Commission conducted a public hearing on the applications, publicly noticed in compliance with Brisbane Municipal Code Chapters 1.12 and 17.54, at which time any person interested in the matter was given an opportunity to be heard; and

WHEREAS, the Planning Commission reviewed and considered the staff memorandum relating to said applications, the applicant's plans and supporting materials, and the written and oral evidence presented to the Planning Commission in support of and in opposition to the application; and

WHEREAS, the Planning Commission finds that the proposed project is categorically exempt from the provisions of the California Environmental Quality Act; pursuant to Section 15304(e) of the State CEQA Guidelines; and

WHEREAS, the Planning Commission of the City of Brisbane hereby makes the findings attached herein as Exhibit A in connection with the application.

NOW THEREFORE, based upon the findings set forth hereinabove, the Planning Commission of the City of Brisbane, at its meeting of August 24, 2023, did resolve as follows:

Interim Use Permit 2023-UP-5, Parking Modification Use Permit 2023-UP-6, Grading Permit 2023-EX-2, is approved for a period of 5 years, per the findings and conditions of approval contained in Exhibit A to this resolution.

ADOPTED this twenty-fourth day of August, 2023, by the following vote:

AYES:

NOES:

ABSENT:

ROEL FUNKE

Chairperson

ATTEST:

JOHN A SWIECKI, Community Development Director

**ATTACHMENT A
continued****Draft
EXHIBIT A**

Action Taken: Conditionally approve 2023-UP-5, 2023-UP-6, 2023-EX-2 per the staff memorandum with attachments, via adoption of Resolution 2023-UP-5, 2023-UP-6, 2023-EX-2

Findings:**Standard Use Permit Findings**

1. In considering an application, the planning commission has considered and given due regard to the nature and condition of all adjacent uses and structures, and to general plan. A specific plan has not yet been adopted for the area in question.
2. The planning commission has determined that the establishment, maintenance or operation of the use applied for will not, under the circumstances of the particular case, be detrimental to the health, safety, comfort and general welfare of the persons residing or working in the neighborhood of such proposed use, nor will it be injurious or detrimental to property and improvements in the neighborhood or the general welfare of the city.

Interim use permit Findings

3. The proposed interim use and the conditions under which it would be operated will not be detrimental to the public health, safety or welfare, or injurious to properties or improvements in the vicinity.
4. The proposed interim is CEQA categorically exempt, as detailed in the agenda report and resolution, and the use will not create any significant unmitigated adverse environmental impacts.
5. The proposed interim use will not obstruct, interfere with, or delay the intended redevelopment of the property in accordance with the uses anticipated in the general plan or any adopted specific plan applicable to the site.
6. The public utilities and other infrastructure improvements required in order for the interim use to be conducted in a safe, sanitary, and lawful manner are either available at the site or shall be installed by the applicant, prior to occupancy, in a manner approved by the city engineer. This includes power for a nearby pole and sanitation facilities will be provided by portable toilet and water tank facilities.
7. The use will provide the benefit provision of needed services of school bus transportation to children.

8. In accordance with Policy No. 328.2 of the general plan, a program will be established by the operator of the interim use to encourage employment of Brisbane residents, to the extent it is reasonably possible to do so, in the construction and operation of the interim use. Implementation of such program shall be made a condition of the interim use permit.

Parking Modification Findings

9. Strict enforcement of the specified regulation, of paved and striped parking for the administrative office, is not required by either present or anticipated future traffic volume or traffic circulation on the site; and
10. The granting of the use permit will not create or intensify a shortage of on-street parking spaces, given. Per the condition of approval street parking is not permitted.
11. Full compliance with the parking requirements is not reasonably feasible due to existing structural or site constraints, given its location atop a landfill.

Grading Review Findings

12. The proposed grading will reflect or fit comfortably with the site context and natural topography. In this case, the existing flat topography of the site.
13. The proposed grading will not include retaining walls.
14. The proposed grading will not result in removal of trees.

CONDITIONS OF APPROVAL:

Prior to Occupancy

- A. The operator shall obtain a business license through the City's Finance Dept.
- B. A building permit, for placement of the modular structures and fencing, shall be obtained from the City and the improvements shall comply with all requirements imposed by the City and applicable outside agencies, including the County Environmental Health Division. Specific conditions of approval are detailed below, but additional conditions may be applied by the individual departments or agencies through the building permit process:
 - a. North County Fire Authority:

- i. Provide on-site water supply acceptable to NCFA for firefighting operations.
 - ii. Provide site access per CFC Appendix D & NCFA apparatus requirements.
 - iii. Key Box is required for gated access. Apply for approved hardware at NCFA Administration.
 - iv. Portable fire extinguishers(s) are required for building. Mount fire extinguishers 3-5 feet above floor.
 - b. Building Dept:
 - i. Accessible parking and path of travel shall be provided for the office trailer and restroom.
 - c. Public Works/City Engineer
 - i. See dust control plan requirement and grading permit requirement below
 - d. Bayshore Sanitary District
 - e. San Mateo County Environmental Health
 - i. All structures on the footprint of the Brisbane landfill will require methane detection systems (e.g., temp restroom(s) and trailer for the yard)
 - ii. Any structure that sits flush to the surface of the asphalt will require a geomembrane or like, to prevent methane intrusion (i.e., If the trailer is lifted via wheels to allow air passage, no membrane is needed).
 - iii. An action plan is required for activities that may result in exhuming waste for activities to complete the project (e.g., gate posts, grading activities, etc.)
 - f. Planning:
 - i. The project shall comply with the Water Board's C.3 requirements. If new impervious surfaces exceed 5,000 sq ft, the project shall be considered a regulated project.
 - ii. Submit the documentation of the Bayshore Sanitary District (BSD) approval of the exemption allowing for a portable toilet along with the building permit plans.
- C. A grading permit application shall be provided to the City Engineer for approval prior to grading.
- D. A dust control and monitoring plan shall be provided to the City Engineer for approval prior to grading. The dust control plan shall address both construction and ongoing operations.
- E. In case the operator desires to occupy the site with buses prior to placement of the office building, a plan for this phased work shall be submitted to the Planning Director for approval prior to such occupancy. All other applicable conditions shall still apply.

- F. Although not anticipated with this scope of work, excavation into waste will require immediate notification to the Water Board and San Mateo County Health Division and will require repair of the landfill cap in compliance with Title 27.

Operational Conditions

- G. The operator's business license shall be maintained in good standing on an ongoing basis.
- H. The Interim Use Permit is approved for school bus parking for approximately 199 buses and a temporary office and portable restroom as detailed in the agenda report. Increase of more than 10 percent in the total buses shall require notice to the Planning Director and may be referred to the Planning Commission for modification of the interim use permit.
- I. Typical hours of operation are to be Monday through Friday from 5 am to 7 pm.
- J. Typical bus routing is to be directly to and from Beatty and U.S. 101, except under unusual circumstances, such as road closures or local serving buses as may be approved by the Planning Director.
- K. Fire access gates and drive aisles shall be maintained, to the satisfaction of the NCFA and Planning Director.
- L. The operator shall provide bottled drinking water in the office for employees.
- M. On-site maintenance of vehicles and storage of non-operable vehicles is prohibited.
- N. All parking shall be provided on site. No street parking is permitted for this use.
- O. The site shall not be open to the public. Access shall be restricted to the operator's employees, contractors and representatives and security maintained by the operator.
- P. Gravel shall be maintained to prevent water from ponding on the site and to provide for dust control, to the satisfaction of the City Engineer and San Mateo County Environmental Health Department.
- Q. The project shall comply with all applicable stormwater NPDES requirements, including compliance with the site's Stormwater Pollution Prevention Plan.
- R. Aside from the initial grading for removal of settlement stations and berms identified in the plans and maintenance of the existing gravel surface, this project does not include sitework, such as paving with an impervious surface or other sitework. Any such

proposal would be subject to further review and approval by the City departments and outside agencies.

- S. The perimeter fencing shall comply with the provisions of BMC Section 17.32.050, including use of green or black, vinyl coated chain link fencing. Barbed wire and razor wire are not permitted.
- T. Security lighting shall be shielded and directed downward to avoid offsite light spillage and glare. The Planning Director at his/her discretion may require lighting to be adjusted if deemed to be a hazard or nuisance.
- U. The portable toilet facility shall be properly maintained for use by employees.
- V. Trash shall be collected interior to the building and shall be legally and regularly disposed of, so as not to become a nuisance or hazard. Any exterior trash collection area shall be subject to approval by the City through a building permit.
- W. The site shall be maintained free of weeds, trash and debris.
- X. The operator will submit job openings to the Brisbane Public Library for posting on the library bulletin board. In addition, job openings will be sent to the Brisbane Chamber of Commerce for posting to the Chamber's website.

Hold Harmless Requirements

- Y. The permittee agrees to indemnify, defend and hold the City and its officers, officials, boards, commissions, employees and volunteers harmless from and against any claim, action or proceeding brought by any third party to attack, set aside, modify, or annul the approval, permit or other entitlement given to the applicant, or any of the proceedings, acts or determinations taken, done or made prior to the granting of such approval, permit or entitlement.

Mandatory Conditions for Interim Use Permits, per BMC Section 17.41.070

- Z. The permit shall require both the owner and the operator to furnish the city with an agreement (or a copy of a lease containing such agreement) that: (i) the operator's right to possession of the premises for the purpose of conducting the interim use is dependent upon the interim use permit having been granted and maintained in full force and effect; and (ii) the operator's right to possession of the premises for the purpose of conducting the interim use will terminate upon any expiration or revocation of the interim use permit; and (iii) it shall be the responsibility of the owner to terminate the operator's possession of the premises upon any expiration or revocation of the

interim use permit if the operator continues to utilize the premises for the conduct of such interim use.

AA. Each permittee shall be jointly and severally liable for all costs and expenses, including attorneys' fees, the city may incur to enforce the conditions of the interim use permit upon any breach thereof by the permittee, or to abate and remove the interim use upon any failure by the permittee to discontinue such use, or to evict the operator of such use, upon the expiration or revocation of the interim use permit.

Interim Use Permit Cessation, Revocation Procedures and Term Limit

BB. In the event that the continuation of the use approved with this interim use permit would obstruct, interfere with, or delay the intended redevelopment of the property in accordance with the uses anticipated in the general plan or any adopted specific plan applicable to the site, the operator shall vacate the site and remove improvements as required by the City or property owner, within 90 days written notice by the City or property owner.

CC. Minor modifications may be approved by the Community Development Director in conformance with all requirements of the Municipal Code.

DD. Material violation of any of the Conditions, including material deviations from the approved project description, may be cause for revocation of this permit and termination of all rights granted there under.

EE. This Interim Use Permit is subject to the revocation procedures established in Brisbane Municipal Code Chapter 17.41.100 - Revocation of Interim Use Permit.

FF. This Interim Use Permit is for a 5-year term from the effective date of the permit. The expiration date is August 31st, 2028.

ATTACHMENT B

Analysis of Findings for Approval

The proposal, including the conditions of approval, complies with all of the findings for approval. The findings for approval are outlined below in italics and underlined followed by staff's analysis on each finding. Note that specific findings are provided for each permit type 1) interim use permit 2) parking modification use permit and 3) grading permit. Additionally, the standard use permit conditions of approval are also referenced in the provisions for approval of the parking modification, but are reviewed holistically for the use.

Standard Use Permit Findings (per BMC Section 17.40.060)

The following two findings are standard for uses in most of Brisbane's zoning districts, except on the Baylands where interim use permits apply. However, they are also referenced for approval of a parking modification use permit, in addition to the parking modification findings, and so they are included with this suite of applications.

A. In considering an application, the planning commission shall consider and give due regard to the nature and condition of all adjacent uses and structures, and to general and specific plans for the area in question.

The area of the proposed use is at the northern boundary of the Baylands subarea, bordering Beatty Ave. This area is industrial in nature. Recology's waste recovery and processing facilities are located on the north side of Beatty Ave from this site and their parking facility is located immediately to the west. Also sharing the western border with 5 Beatty Ave is Avis' rental car parking lot. South of the proposed use area, but sharing the same parcel is the Brisbane Recycling Co. soil recycling operation.

The proposed use is consistent with these other uses and is not expected to have an impact on them.

The traffic volumes are seen as low, with a peak of up to 100 trips anticipated between 6 am and 7 am, and traffic was not raised as a concern by the City Engineer. Traffic to and from the site will have direct access to and from U.S. 101 from Beatty Ave. Due to the proposed use of a gravel yard surface, a City Engineer approved dust control plan will be required.

The use is consistent with the General Plan. The site is within both the Beatty Heavy Commercial (HC) and Baylands Planned Development Non-residential (PD-NR) subareas. Both subareas designate a commercial/industrial class of uses and fit the nature of the use. At the time of this application, there is no adopted specific plan for this area, although a draft Baylands specific plan is in the review process. Once adopted and the specific plan becomes effective, a condition of approval is included, that could require vacating the use to allow development to proceed. The timing of the specific plan and future development is not known at this time. In the interim, the Baylands Interim Use Permit is the operative tool for processing

this application, having the most restrictive use permit findings. The HC district does not place a 5-year limit on use permits.

Note also that, the improvements proposed for this operation are all temporary in nature and while a building permit will be required, there would be no permanent structures or facilities.

B. The planning commission shall determine whether or not the establishment, maintenance or operation of the use applied for will, under the circumstances of the particular case, be detrimental to the health, safety, comfort and general welfare of the persons residing or working in the neighborhood of such proposed use, or whether it will be injurious or detrimental to property and improvements in the neighborhood or the general welfare of the city. If the planning commission finds that the aforementioned conditions will not result from the particular use applied for, it may grant the use permit.

The location of the use is generally hidden from view, being far from the nearest residence and neighborhood serving businesses, and therefore should have no impact on residential neighborhoods. As noted above, it is consistent with the neighboring industrial uses. For parking conformance, no parking for this use will be needed or allowed along Beatty Ave, but all parking will be maintained onsite. Also, lighting will be using portable, adjustable light standards and will be required to be adjusted downward and at heights that will not have a significant impact on neighboring properties or the public right-of-way.

Findings for issuance of interim use permit (per BMC Section 17.41.060)

A. That the proposed interim use and the conditions under which it would be operated will not be detrimental to the public health, safety or welfare, or injurious to properties or improvements in the vicinity;

The proposal complies with this finding. The site is in an industrial use, in an area that is industrial in character, and this outdoor vehicle storage use is consistent with that character.

The only use of the site would be storage and movement of vehicles and the management office. The intensity and operational characteristics of the proposed yard are consistent with the surrounding area and will not adversely impact nearby businesses or the public health, safety or welfare. The management office will be required to conform the applicable California Building Code (CBC) sections, as will be required through the processing of a building permit, to ensure safety of the workers.

B. The proposed interim use will not create any significant unmitigated adverse environmental impacts, as determined by an environmental analysis pursuant to the California Environmental Quality Act;

The proposal complies with this finding. The site overlies the former landfill and was previously used for parking of vehicles and is categorically exempt from CEQA, as noted in the Environmental Determination section above.

- C. The proposed interim use will not obstruct, interfere with, or delay the intended redevelopment of the property in accordance with the uses anticipated in the general plan or any adopted specific plan applicable to the site;

As noted above, the project would not include any permanent buildings and the proposed perimeter fence may be readily removed upon termination of the use.

The site lies in proximity to the proposed extension of Geneva Avenue associated with the Baylands Specific Plan. Given that, portions of the site could be impacted by the future roadway alignment and/or associated grading. To ensure that the project would not interfere with the roadway extension, in the event that it proceeds during the term of the interim use permit and the use would be an obstruction, a condition of approval is included that the applicant is to cease operations upon 90-day notice from the City or property owner. Based on these considerations, the proposal complies with this finding.

- D. All public utilities and other infrastructure improvements required in order for the interim use to be conducted in a safe, sanitary, and lawful manner are either available at the site or shall be installed by the applicant, prior to occupancy, in a manner approved by the city engineer;

This proposal complies with this finding. Electrical power may be supplied from a nearby power pole located on the site. Sanitary services will be provided with a portable toilet on a trailer, which will be regularly maintained and so plumbed water or sewer will not be required. In essence, the nature of the building is temporary. The Fire Dept has indicated that a fire suppression water supply may be provided from an onsite tank.

- E. The use will provide either or both of the following benefits:
1. A benefit to the property, including, but not limited to, the elimination of blight or unsightly or hazardous conditions, or the installation of improvements that will facilitate redevelopment of the property, or
 2. A benefit to the public, such as the creation of jobs or revenues or the provision of needed goods or services.

The bus parking proposed for the site provides a public benefit by allowing for needed transportation for school-age children in San Francisco at a location immediate to the U.S. 101 on and off-ramps, at the San Francisco border.

- F. In accordance with Policy No. 328.2 of the general plan, a program will be established by the operator of the interim use to encourage employment of Brisbane residents, to the extent it

is reasonably possible to do so, in the construction and operation of the interim use.
Implementation of such program shall be made a condition of the interim use permit.

The applicant reports that they will submit job openings to the Brisbane Public Library for posting on the library bulletin board. In addition, job openings will be sent to the Brisbane Chamber of Commerce for posting to the Chamber's website. Additionally, the applicant has indicated that the jobs are union and have full benefits.

Parking Modification Findings (per BMC Section 17.40.060)

In addition to the findings required for the granting of a use permit, as set forth in Section 17.40.060, for a modification to a parking regulation the planning commission shall also find that:

1. Strict enforcement of the specified regulation is not required by either present or anticipated future traffic volume or traffic circulation on the site; and

The BMC provides that administrative office buildings provide paved parking at a ratio of 1 space per 300 square feet of office area (10 spaces for the proposed building), this would include any accessible spaces that are required by the CBC. The BMC does not provide separate standards for buildings that are temporary in nature. Also, the Building Official has indicated that the required accessible space may be provided with pervious surface alternatives, which would be implemented through the building permit process.

The BMC does allow for the Planning Commission grant exceptions to any of the parking standards through a parking modification use permit. In this case it would be to allow for an unpaved parking lot.

Given the large area of parking for both school buses and office workers relative the number of spaces, there would be more than adequate space on site and paving for those spaces is not necessary. Nor would the existing gravel surface versus a paved surface have any impact on the traffic volume or circulation on the site.

2. The granting of the use permit will not create or intensify a shortage of on-street parking spaces, given, for example, the availability of existing or improved on/off-street parking which may not fully meet the requirements of this chapter.

Given the size of the site, all parking can be accommodated on site. A condition of approval is included to specify no on-street parking will be allowed on Beatty Ave for this use.

3. Full compliance with the parking requirements is not reasonably feasible due to existing structural or site constraints.

Full compliance with the parking requirements for paving is not reasonably feasible given the site's location atop a former landfill site. Paving would result in alteration of the surface and

trigger additional requirements for stormwater capture and treatment under the Water Board's Municipal Regional Permit C.3 (new development) provisions and significantly impact the project and likely make it infeasible, due to improvement costs and delay. It would likely also necessitate more grading than the minimal grading proposed to capture and treat stormwater on site.

Grading Review (per BMC Section 15.01.110)

Where planning commission review of an application for a grading permit is required by subsection A of Section 15.01.110, the review shall be based upon a consideration of the following potential impacts of the proposed grading. The City Engineer will take into account the Planning Commission's findings in his/her review of the grading permit, which is to be submitted to the City Engineer following this review.

1. Will the proposed grading be designed to reflect or fit comfortably with the site context and natural topography?

The proposed grading would serve to level former settlement station level depressions and berms to match the surrounding area. While there is no "natural topography", since the entire area is Bay fill, it would reflect and fit with the existing site context.

2. Will the proposed grading be designed to ensure that retaining walls visible to the public are designed to be as visually unobtrusive as possible by means including, but not limited to:
(i) Ensuring walls are architecturally integrated with proposed or existing structures on the site;
(ii) Ensuring wall faces are decorative and treated with color, texture, architectural features, trelliswork or other means to visually break up the wall expanses;
(iii) Screening with water conserving, non-invasive landscaping that at maturity will soften and reduce the visible expanse of walls?

There are no retaining walls proposed. Rather the grading would level out the graded areas with the surrounding grade. Additionally, except for distant hillside views, the site is largely screened from public view by an area of shrubs along the south edge of Beatty Ave. These shrubs will remain.

3. Will the proposed grading be designed to minimize removal of:
(i) Existing street trees (see Section 12.12.020); (ii) Any California Bay Laurel, Coast live Oak or California Buckeye trees; (iii) Three (3) or more trees of any species on the same site having a circumference of at least thirty (30) inches measured twenty-four (24) inches above grade?

No street trees will be removed and no trees of the size or species identified are located within the proposed use area.

4. Where removal of existing trees is necessary, will the landscape plans for the project include the planting of appropriate replacement trees?

Not applicable.

ATTACHMENT C
APPLICANT'S DESCRIPTION**Description of the Proposed Use:**

This project proposes to park school buses on a portion of the land currently vacant and unimproved at 5 Beatty, the NE corner of the Baylands property. See the site plan for the leasable premises. The site is currently a gravel lot and the shared access road (also serves "Brisbane Recycling Company") is paved. A perimeter 6' fence will be installed for security and include screen for privacy and dust control purposes. The fence will have two main ingress/egress points and will have security cameras at the entry points. North County Fire has requested a gate to the southern end of the leasable area, which is included but will be generally locked with fire department access available in an emergency. The site also includes a fire access drive aisle at the request of the Assistant Fire Marshall.

In the north east corner of the site, a temporary office trailer and restroom trailer will be installed. These temporary facilities (trailer and restroom) will not be connected to permanent utilities. As this site is above the landfill, permanent utilities are not possible to be brought to the site under this interim use. The restroom will be served by a water tank and septic system which will be hauled offsite. Bayshore Sanitary District has approved of this condition in their July meeting. Furthermore, as this project cannot limit the development timeline of the Baylands project and is thus temporary in nature, limited to 5 years initial term per the interim use permit. Power will be provided by an existing power pole just south of the project, run overhead and connected to the trailer and lights across the parking field. Light towers will be utilized to illuminate the site for bus maneuvering. These lights will be pointed downward and shielded from public view and only active during hours of operation.

The existing surface on site is compacted gravel which will remain, there will be some minor earth moving (see grading plan) to remove a couple of mounds, and fill in a couple of small depressions. A Grading Permit Application is also being processed concurrently for the site. There is an existing SWPPP covering the Baylands property (the document is included in the resubmittal "background information" folder). Per the SWPPP prepared by Burns and McDonnell in 2018 and the Existing Conditions Plan on C1.0, the site currently slopes towards an existing catch basin located on the northeast end of the site. This existing catch basin collects the site runoff and conveys the stormwater to the storm drain main in Beatty Avenue which drains to the SFPUC's Sunnydale storm drain facility which detains and pumps flows for treatment. The site's drainage pattern will remain the same, we propose no changes to the existing drainage condition. Furthermore, the project proposes to disturb less than 5,000sf of area as part of this project and is thus exempt from C3 requirements.



See Plans included in submittal for details existing conditions, topography and proposed condition.

Supporting Statements - CONDITIONAL USES PER DISTRICT REGULATIONS

1. How has the project been designed and operated in order to be compatible with the nature and condition of all adjacent uses and structures, and with general and specific plans for the area in question?

RESPONSE: The site is currently a gravel lot, unoccupied and unused. Previously the site has been used for overflow parking at Candlestick park, which was the last permitted use on the site – though not for nearly 10 years. To the south is Brisbane Recycling Company, an industrial use, and to the west is Avis where they park vehicles. To the north is Recology. The proposed use of a school bus parking yard is complementary to the surrounding uses; it is permitted by zoning; and it has been previously used for a very similar use. Further, its proximity to the 101 allows for quick and easy access north to SF where all of the buses will be headed. See Bus routing and timing below. A new perimeter fence will be installed which will improve the aesthetics of the private paved interior drive aisle that Brisbane Recycling Company uses. Finally, buses operate at regular hours with defined schedules and are highly compatible with the other uses surrounding. In summary, the project is designed and operates to be compatible with the nature and condition of all of the adjacent uses and with the general and specific plans for the area.

2. How will the propose use be designed and operated in order to not be detrimental to the health, safety, comfort and general welfare of the persons residing or working in the neighborhood?

RESPONSE: The site location in the north east corner of Brisbane, with direct connectivity via Beatty to HWY 101 makes the impact on the community extremely limited. Please see the attached Bus Routing Map to see the ingress and egress from the site north to San Francisco. None of these Zum buses serve any jurisdiction but San Francisco, so all the buses will be travelling northbound when leaving the site, or exiting at Beatty and entering the site upon returning. It is possible that a tiny minority of buses utilize Tunnel Ave, to implement a route serving a non-standard pickup or drop off (e.g. a field trip, sporting event, etc.) This project is making little change to the existing condition, except to add a perimeter fence and some temporary trailers. As such, the proposed project will not be detrimental to the health, safety, comfort, and general welfare of the persons residing or working in the neighborhood.

3. How will the proposed use be designed and operated in order to not be injurious or detrimental to property and improvements in the neighborhood or the general welfare of the city?

RESPONSE: Zum is a professional organization serving the needs of the community's children. As they are working with children, their drivers are highly trained, unionized and competent. Zum's business is quickly and effectively picking up and dropping off children and, specifically they utilize the "right" bus for the job. For example, a route with only a handful of students may utilize a car or van, instead of a normal bus, this leads to quicker pick up and drop off, more efficient rides for students, and reduced emissions vs traditional bus companies. Furthermore, as outlined in the responses above the proposed project makes not significant changes to the current site. Please visit RideZum.com for additional information on Zum and their programs. In

summary, Zum's operations will not be injurious or detrimental to the property and improvements in the neighborhood or the general welfare of the city.

Days and Hours of Operation: The typical hours of operations are Monday through Friday, 5am to 7pm. Though most bus activity will be at the start and end of school times (approx. 7am and 4pm). During the early hours of the day, office and dispatch staff arrive around 5am, with drivers arriving around 5:45am inspect buses and mobilize onto their routes. During most of the day, the majority of buses are in the field and there is likely to be little activity on the site. Roughly 30% of bus routes have buses return to the parking facility during the day, the reminder stay closer to their pick up and drop off location during the day. At the end of the day, buses return between 4-6pm and prepare for the following day. Occasionally, there will be trips later on weekdays and on weekends for extracurricular events, sporting events, etc. Times will vary based on the needs of the students and teacher. See the approximate typical bus schedule in Exhibit 1.

Number of Employees on Site: Approx. 10 on site staff and approx. 199 bus drivers.

Company vehicles and equipment on site: Approx. 199 buses will be stored on site. Buses vary in size, see plan Sheet C2.0 for an outline of the sizes of the spaces proposed.

List the types and quantities of hazardous, toxic, flammable or explosive materials or wastes are involved with the use: None

List any governmental permits required for the handling or storage of the hazardous materials involved with the use: None

List any materials and equipment which will be stored outside and explain how these will be screened from public view: The School Buses will be stored outside which will be behind the perimeter fence with screen.

Will the use generate air emissions, odors, smoke or dust? If so, how will these be controlled? The parking of school buses will not be contributing any significant odors, or smoke. Dust will be limited as the site is currently a gravel lot and the shared access road with "Brisbane Recycling Company" is paved. The perimeter of the site will have a fence with dust screen, and the Baylands has a stand-by water truck to be used as needed. A Construction Dust Control Plan (DCP) will be provided to the City prior to starting work on site, and at minimum this Construction DCP shall include watering the site during grading. A, Operations DCP will be provided to the City prior to starting operations, and at minimum will include watering the site once per week.

Will the use generate noise or vibration? If so, how will these be controlled? The proposed project will not generate any significant noise or vibration

Will the use generate glare, heat or other impacts? If so, how will these be controlled? The proposed project will not generate any significant glare, heat or other impacts

Will the use generate waste materials? If so, how will these be disposed? Any trash produced by the temporary office will be picked up by at minimum weekly janitorial service and hauled offsite.

How will waste materials from the use be prevented from polluting storm water runoff? Any trash produced by the temporary office will be picked up by at minimum weekly janitorial service and hauled offsite. The janitorial service will also include a sweep of the lot picking up any debris at minimum once per week.

What utilities and other infrastructure are required for your use? Are these existing on the site? If not, how will they be provided? The proposed project only requires power which is currently available on site. The temporary restroom will be served by water tank and septic storage which will be hauled off the site (no drainfield will be utilized). Due to the site's location above the landfill, getting permanent utilities at this site would be nearly impossible – thus **NO PERMANENT** water or sewer utility connections are proposed. This has been reviewed and approved by the Bayshore Sanitary District in their July Board Meeting. The existing drainage condition for the site will be maintained per the approved SWPPP.

The Brisbane Municipal Code requires that your use benefit the property. List the benefits below:

- (a) eliminating blight or unsightly or hazardous conditions,
- (b) by installing improvements that will facilitate redevelopment of the property,
- (c) other:

The proposed project improves the site from its current vacant and unused state into a job rich use that enables children to get to school. By bringing in a reputable user, they will ensure that the property is kept in good repair, attractive and well-utilized. This use enhances the current condition and provides a much-needed public service to the community.

The Brisbane Municipal Code requires that your use benefit the public. List the public benefits below:

- (a) creating jobs,
- (b) generating revenues,
- (c) providing needs goods or services,
- (d) other:

The proposed project will create jobs in Brisbane as the drivers and employees of Zum will be closer to Brisbane and likely to increase their retail spending in town – this knock-on spending effect will serve to bolster the local economy. Furthermore, these jobs are good-paying and unionized without requiring higher education. There will be additional tax revenue to the City of Brisbane through the business licensing, and of course, Zum is providing a critical service to the region by enabling children to get to school. The proposed project meets the goals and objectives of (a), (b) and (c).

Will you establish a program to encourage employment of Brisbane residents in the construction and operation of the use? Explain:

The focus of Zum's hiring efforts take place in the summer prior to the start of the school year – they have a strong emphasis on local hiring as it improves employee satisfaction and increases employee retention when they live nearby. Zum will submit job openings to the Brisbane Public Library for posting on the library bulletin board. In addition, job openings will be sent to the Brisbane Chamber of Commerce for posting to the Chamber's website. The jobs are union (via SMART), well paid (\$40/hr), and have full benefits. Zum also runs a comprehensive training program for new drivers.

Will your use include any of the following?

The manufacture, processing, handling, treatment, transportation, recycling, or storage of hazardous, toxic, flammable or explosive materials or wastes in quantities for which a permit is required from any governmental agency.

No, the proposed project is not subject to any such permits

The dumping, processing, sorting, recycling, recovery or storage of garbage, debris, scrap materials, or similar items (excluding the recycling of concrete or brick and the storage and processing of soils, rock, and other similar materials).

No, the proposed project will not include any of those items.

Uses that create unsightly visual impacts or the appearance of blight as seen from any other location with the city, such as automotive dismantling and wrecking yards, junk yards, outside storage of used equipment, trailers, or vehicles not being offered for sale, and outside storage of glass, metal, paper, cardboard, or other material collected for recycling or disposal (except as otherwise permitted).

No, the proposed project will not include any of those items.

Heavy manufacturing operations, including concrete or asphalt batch plants, foundries and other activities involving the fabrication of metal products from raw materials, processing of chemicals, and the rendering or refining of oils or animal materials

No, the proposed project will not include any of those items.

What is the length of time for which you are applying for an Interim Use Permit?

We propose an initial term of 5 years, subject to renewal options under the interim use and conditions use application guidelines.

Exhibit 1 – Facility Operations, Bus Timing & Routing Diagram

As all of the buses on site will be serving San Francisco, there will be no bus traffic heading south.

Inbound Route: South on 101, Exit Tunnel Ave, Turn into site

Outbound Route: Exit project site onto Alana Way, turn right onto Harney Way, North on 101

It is possible that a bus might utilize Tunnel Ave if a non-standard route (sporting event, field trip, etc) took them down that direction, but would be highly unusual.



Approximately 25% of employees commuting to site will use public transportation, while another 30% will carpool to the site. The remaining employees use their personal vehicles and park in the bus spaces. When buses start up in the morning, they idle for approximately 10-15 minutes. Upon arrival, they idle for only 1-2 minutes.

Approximate Schedule of Bus Departures and Arrivals on a Typical Day:

Hour	Buses Departing	Buses Arriving	Cars Departing	Cars Arriving	Note
6:00 – 7:00	90	-		10	Buses departing / Morning staff arrive
7:00 – 8:00	90	-			Buses departing
8:00 – 9:00	19	-			Buses departing
9:00 10:00	-	-			
10:00 – 11:00	-	70			Approx 35% of buses return midday, remainder stay in the field
11:00 – 12:00	-	-			
12:00 – 1:00	-	-			
13:00 – 14:00	35	-			Buses that returned depart
14:00 – 15:00	35	-	10	10	Morning Staff Depart / Afternoon Staff Arrive
15:00 – 16:00	-	-			
16:00 – 17:00	-	65			Buses arriving
17:00 – 18:00	-	69			Buses arriving
18:00 – 19:00	-	65	10		Buses arriving / Afternoon staff departing

Note: Number of buses exceeds count as approximately 70 make two trips. A few buses may depart prior to 6am, and arrive after 6am based on field trips or athletic needs.

Exhibit 2 - Photos of the Site:

Photo Description List:

Project: 5 Beatty Avenue, Brisbane, CA

Photographer: Sam Khoja, Baylands

Date: 5/30/2023

PHOTO LEGEND:



Image #1407: Photo taken facing to the north, from the southern section of the property.



Image #1414 – Photo taken facing to the north, from the east side of the property



Image #1421: Photo taken facing to the east, from the northern section of the property.



Image #1455: Photo taken facing east, from the center of the property.




Image #1468: Photo taken facing south, from the southern portion of the property.




60' X 48' MODULAR OFFICE BUILDING A-B-B-D MODEL



EXAMPLE OFFICE TRAILER






EXAMPLE OFFICE TRAILER

10' X 30' MODULAR RESTROOM


EXAMPLE RESTROOM TRAILER



Item C.




**Photos are not representative of specific asset, they are example only



EXAMPLE RESTROOM TRAILER



DRAWING NAME: \\BKF-r-c\vol\4\2023\230906_5.Beatty_Road_Brisbane\ENG-L\Plots\C3.0 PRELIMINARY GRADING.dwg
PLOT DATE: 07-27-23 PLOTTED BY: ashe



FILL QUANTITY	
HOLE #1	57 CY
HOLE #2	160 CY
HOLE #3	23 CY
TOTAL	240 CY

CUT QUANTITY	
MOUND #1	134 CY
MOUND #2	359 CY
TOTAL	493 CY




NOTES:

- FENCE LINE SHOWN IS ALSO CONSIDERED LEASING BOUNDARY. SEE DETAIL 2 ON SHEET C4.0 FOR MORE INFORMATION.
- EXISTING DECOMPOSED GRANITE IS PERVIOUS AND WILL BE MAINTAINED AS IS.
- FILL QUANTITIES ARE APPROXIMATE AND DO NOT INCLUDE DECOMPOSED GRANITE. HOLES TO BE FILLED ACCORDING TO DETAIL 1 ON SHEET C4.0. FILL MATERIAL TO BE NATIVE BACKFILL.
- CUT QUANTITIES ARE APPROXIMATE. CUT MATERIAL CAN BE USED TO BACKFILL HOLES. ADDITIONAL FILL MAY BE REQUIRED TO BACKFILL HOLES.
- EXISTING TOPOGRAPHY BASED ON AN AERIAL TOPO COMPLETED ON FEBRUARY 17, 2021 BY VERTICAL MAPPING RESOURCES ON NAD 83.
- 3" LAYER OF COMPACTED ASPHALT GRINDING TO BE ADDED OVER THE TOP OF THE PARKING LOT SURFACE TO KEEP THE DUST DOWN.
- CONTRACTOR TO SLOPE SURFACE TO MATCH EXISTING GRADES AT CONFORM LINE.

LEGEND:

- PROPOSED FENCE, SEE DETAIL 2 ON C4.0
- LIMIT OF CONFORM
- GRADE BREAK
- PROPOSED DECOMPOSED GRANITE, SEE DETAIL 1 ON C4.0
- EXISTING MOUND TO BE REMOVED
- EG 34.00 PROPOSED GRADES



5 BEATTY AVENUE ZUM BUS PARKING LOT
PLANNING AND GRADING PERMIT APPLICATION
PRELIMINARY GRADING PLAN

CITY OF BRISBANE

07.27.2023

PLANCHECK RESPONSE 1

Revisions

Date 06/06/2023

Scale SEE PLAN

Design SG

Drawn AM/SH

Approved LKY

Job No 20230906

Drawing Number:

C3.0


PRELIMINARY - NOT FOR CONSTRUCTION

COUNTY OF SAN MATEO


CALIFORNIA

BKF Engineering


255 SHORELINE DRIVE
REDWOOD CITY, CA 94065
(650) 482-6300
www.bkf.com



1
PAVEMENT SECTION
NTS



2
AC PAVEMENT SECTION
NTS



- NOTES:
- FENCE WILL CONFORM TO CALTRANS STANDARD SPECIFICATIONS.
 - CHAIN LINK FENCE WILL CONFORM TO CALTRANS STANDARD DETAIL B11-7 EXCEPT AS SHOWN ABOVE OR LISTED BELOW:
 - HANDRAIL WILL BE OMITTED.
 - ANCHORAGE DETAIL WILL BE AS SHOWN HEREON.
 - BOTTOM TENSION WIRE WILL BE USED AS SHOWN.
 - CHAIN LINK GATE WILL CONFORM TO CALTRANS STANDARD DETAIL A85.
 - THE FIRE ACCESS GATE WILL BE LOCKED AT ALL TIMES, BUT THE FIRE DEPARTMENT WILL HAVE ACCESS TO UNLOCK THE GATE IN THE EVENT OF AN EMERGENCY.

3
CHAIN LINK FENCE WITH GATE
NTS

Sunray LTS-160

National's LTS-160 Solar Light Tower is our brightest and boldest in the solar series. With exceptionally powerful 160W lamps, this tower can fulfill virtually every lighting need. It's versatile enough to be placed in most environments, can be used almost anywhere and is designed for maximum efficiency. Additionally, its three brightness settings put you in control of its battery usage, so you can manage how long to go before recharging.

To maximize solar charging, we installed LED meters for the solar array. Now you can position your tower by pointing the array at the sun and view its charge output. Dual battery controllers monitor battery charging and automatically keep the batteries performing at optimum charge. By separating the tower control from the battery box, you don't have to worry about rental customers accessing batteries.

- No fuel, no fuel trips, no fuel spills, no fuel bills
- Sealed, maintenance-free batteries
- Separate control from battery enclosure
- Slide out solar collectors to minimize foot print
- Custom coiled cord to reduce sagging
- 104,800 total lumens

Specifications

Lamps	(4) 160W each, high intensity, modular lamps
Brightness	26,200lm @ 160W, 17,460lm @ 100W, 8,730lm @ 53W
Dimmer	Low, med, high
Solar Array	750W, 1,000W optional
Batteries	AGM 660Ahr
Mast Height	20'
Winch	Manual with optional electric
Width across fender	78"
Length	121"
Weight	2,500 lbs
Battery Charger	30A, 110VAC, external plug
Tires/Wheels	ST205/75D15



Specifications subject to change any time without notice. Copyright 2022 National Signal, Inc. All rights reserved. Printed in the United States.

2440 Artesia Avenue
Fullerton, CA 92833
United States of America


info@nationalsignalinc.net
www.nationalsignalinc.net
1-888-994-0300



Access our website by scanning our QR code


NOTE:
TEMPORARY LIGHT TOWER TO BE NATIONAL SUNRAY LTS-160, SUNBELT 4000 WATT LED LIGHT CART OR APPROVED EQUIVALENT LIGHT TOWER.

4
TEMPORARY LIGHT TOWER
NTS



Return to Table of Contents

5
CALTRANS STANDARD DETAIL A85
NTS



Return to Table of Contents

6
CALTRANS STANDARD DETAIL B11-7
NTS



File Attachments for Item:

D. PUBLIC HEARING: 3708 Bayshore Boulevard; Use Permit 2022-UP-7, Grading Review 2022-EX-5, Lot Merger 2022-LLA-3, Habitat Conservation Plan Compliance 2022-HCP-1; SCRO-1
Zoning District; Expansion of the current contractor's storage yard permitted under UP-9-12;
and finding that this project is categorically exempt from environmental review under CEQA
Guidelines Sections 15301 and 15311; Sean Brennan, applicant; MK Yard LLC, owner.



PLANNING COMMISSION AGENDA REPORT

Meeting Date: August 24, 2023

From: Jeremiah Robbins, Associate Planner

Subject: 3708 Bayshore Boulevard; Use Permit 2022-UP-7, Grading Review 2022-EX-5, Lot Merger 2022-LLA-3, Habitat Conservation Plan Compliance 2022-HCP-1; SCRO-1 Zoning District; Expansion of the current contractor's storage yard permitted under UP-9-12; and finding that this project is categorically exempt from environmental review under CEQA Guidelines Sections 15301 and 15311; Sean Brennan, applicant; MK Yard LLC, owner.

REQUEST: The applicant requests approval of the above-referenced permits to allow an approximately 5,000 square foot expansion of the current contractor's storage yard permitted under UP-9-12. The project includes a combined 820 cubic yards of soil cut and fill and a merger of three underlying parcels located within the Brisbane Acres Administrative Parcel of the San Bruno Mountain Habitat Conservation Plan area.

RECOMMENDATION: Approve Use Permit 2022-UP-7, Grading Review 2022-EX-5, Lot Merger 2022-LLA-3, Habitat Conservation Plan Compliance 2022-HCP-1 via adoption of Resolution 2022-UP-7/2022-EX-5/2022-LLA-3/2022-HCP-1 containing the findings and conditions of approval.

ENVIRONMENTAL DETERMINATION: The project is categorically exempt from the provisions of the California Environmental Quality Act (CEQA) per Sections 15301 and 15311 - this project falls within a class of projects which the State has determined not to have a significant effect on the environment. The exceptions to the categorical exemptions referenced in Section 15300.2 of the CEQA Guidelines do not apply, as confirmed by the biological resources assessment attached to this agenda report.

APPLICABLE CODE SECTIONS: Brisbane Municipal Code (BMC) [Chapter 17.16, SCRO-1 Southwest Bayshore Commercial District](#); [Chapter 17.40, Use Permits](#); [§17.32.220, Grading Permit- When Required](#); [§16.12.070, Merger of parcels initiated by the property owner](#). The [San Bruno Mountain Area Habitat Conservation Plan \(HCP\)](#) governs development of properties within the Southwest Bayshore subarea (part of Administrative Parcel 2-03 of the HCP). The Operating Program for Administrative Parcel 2-03 establishes the general obligations applicable to properties and property owners in regards to HCP compliance.

ANALYSIS AND FINDINGS:

Existing Conditions and Site Context

MK Pipelines is an underground utilities contractor and performs local public works projects; they are operating under Use Permit UP-9-12 (previously UP-6-11, UP-5-11, UP-5-08, UP-6-07 and UP-3-06) for a contractor's storage yard. They currently employ 27 employees, including four based at the subject property, and own approximately 35 pieces of construction equipment, i.e.,

2022-UP-7/2022-EX-5/2022-LLA-3/2022-HCP-1
8/24/2023 Meeting

excavators, backhoes, and pick-up trucks. This equipment, as well as materials, generally move between jobsites, though surplus material and/or special-order items with longer lead times are stored behind the building. The yard is currently screened by a chain-link fence with brown plastic slats and the hours of operation are between 7:00 am and 5:30 pm.

The subject property is comprised of three contiguous lots located within the SCRO-1 zoning district and Administrative Parcel 2-03 (Brisbane Acres) of the HCP. The two southern properties are developed and occupied by MK Pipelines Inc., while the northern property was recently acquired and is undeveloped. The combined area of the three parcels is approximately 676,885 square feet (15.5 acres) and the site is accessed via Bayshore Boulevard from the front (east) property line. The property includes a relatively level area within the first 65-80 feet of the front property line, where the existing building and paved parking lot for MK Pipelines is located, and then slopes up (westward) sharply from Bayshore Boulevard with an overall slope of approximately 46%, as measured per BMC Section 17.02.730.

The project site is not immediately adjacent to any development. Adjacent parcels to the south, west, and north are vacant and undeveloped, and to the east across Bayshore Boulevard is the Caltrain right of way and tracks and the Brisbane Lagoon. The nearest developed parcels are approximately 470-610 feet away and include residential uses to the west on Thomas Avenue and Tulare Street and the mobile home park to the south.

The biological resources assessment (Attachment E) for the project site found no special status wildlife or plant species on the parcel or the surrounding 60-foot buffer that was included in the survey area. No sensitive plant communities, wildlife connectivity features, or waters or wetlands were observed in the survey area, and based upon the habitat and condition of the survey area, the project site has low potential to provide habitat for any special status species.

Project Description

The applicant proposes to enlarge their existing, paved parking lot and (contractor's) storage yard (authorized under UP-9-12) by approximately 5,000 square feet for additional laydown and equipment storage space. The expansion would occur on the northern, undeveloped parcel and involves a combined 820 cubic yards of soil cut and fill. New retaining walls are proposed but would not exceed six feet in height. As part of the applicant's request, the three underlying parcels would be merged into a single parcel.

No expansion of the existing structure is proposed. New retaining walls and fencing will match the existing Allen-block retaining wall and brown-slat chain link fence. Additionally, no trees are proposed to be removed as part of this project.

The project plans were transmitted to the Public Works Director/City Engineer, Building Division, and North County Fire Authority, and City Attorney who provided recommended conditions of approval. The biological assessment and draft operating program were transmitted to the HCP

2022-UP-7/2022-EX-5/2022-LLA-3/2022-HCP-1
8/24/2023 Meeting

Plan Operator (San Mateo County Parks Dept.), US Fish and Wildlife Service, and California Dept. of Fish and Wildlife, who concurred with the findings of the biological assessment.

Analysis

Use Permit

In order to approve the Use Permit request, the Planning Commission must:

- A. *Consider and give due regard to the nature and condition of all adjacent uses and structures, and to the General Plan and specific plans for the area in question; and*
- B. *Determine whether or not the establishment, maintenance or operation of the use applied for will, under the circumstances of the particular case, be detrimental to the health, safety, comfort and general welfare of the persons residing or working in the neighborhood of such proposed use, or whether it will be injurious or detrimental to property and improvements in the neighborhood or the general welfare of the city.*

In addition to the findings required for approval of a use permit listed above, no use permit shall be granted for any conditional use in the SCRO-1 Zoning District unless additional, special findings can be made. A summary of the required findings is below; detailed analysis for each finding is provided within Exhibit A of the draft resolution.

The project complies with the findings required under BMC Chapter 17.40 and BMC §17.16.060. The use is consistent with the mixed commercial and residential character of the Southwest Bayshore subarea and SCRO-1 Zoning District and the recent use of the site, since at least 2006, as a contractor's storage yard, and is consistent with General Plan policies and programs pertaining to conservation, community health, and safety.

The proposed expansion of the contractor's storage yard would not be detrimental to the health, safety, comfort, and general welfare of the persons residing or working in the neighborhood, nor be injurious or detrimental to property and improvements in the neighborhood or the general welfare of the city since the expansion would occur to the north, away from the nearest developed parcels and MK Pipelines Inc., has been operating under their current use permit for over nine years with no code enforcement complaints or violations. No additional measures are necessary to protect workers from noise generated by traffic on Bayshore Boulevard and previous modifications were made to address safe ingress and egress from the site under UP-9-12.

Grading Review

The proposed grading is minimized to the footprint of the new paved storage area located on the northern corner of the site. While the overall slope of the site is 46%, the approximate natural slope in the area to be graded is 15% and the new storage area will be at the same level as the existing paved storage area. Additionally, exposed retaining walls are required both below and

2022-UP-7/2022-EX-5/2022-LLA-3/2022-HCP-1
8/24/2023 Meeting

behind the new storage area. The maximum height of all retaining walls would not exceed six feet when measured from grade to the top of the wall. No street trees or protected trees are proposed to be removed, and with adoption of the draft HCP Operating Program, the proposed grading would comply with the terms of the San Bruno Mountain Area Habitat Conservation Plan Agreement and Section 10(a) Permit.

A geotechnical report (Attachment F) for the project site was transmitted along with the project plans for City review and includes a number of recommendations specific to the site. Condition of Approval K requires a licensed soils or geotechnical engineer to submit a Final Grading Observation Report to the City, summarizing conformance of the grading operations to the geotechnical report, prior to construction of the paved yard and retaining walls.

Lot Merger

Contiguous parcels held by the same owner may be merged by recordation of a declaration of lot merger signed by the property owner and acknowledged by the Community Development Director per BMC §16.12.070. The City Attorney has reviewed the proposed lot merger and raised no concerns with the application.

HCP Compliance and Operating Program Analysis

As required by the General Plan and the HCP, a biological resources assessment of the site was conducted consistent with the methodology adopted by the Plan Operator (San Mateo County). An HCP Operating Program was drafted based on the specific findings of the assessment and circulated for review by the US Fish & Wildlife Service and the State Department of Fish & Wildlife. Neither agency raised issues with the conclusions of the biological assessment.


Based on the biological resources assessment's findings of no larval habitat or nectaring plants for the butterflies protected by the HCP, no on-site habitat restoration is proposed for this site. Consistent with the HCP's requirements for Administrative Parcel 2-03, Brisbane Acres, the draft Operating Program requires payment of a fee to fund habitat acquisition elsewhere in the HCP area (Condition of Approval B). This fee will be required prior to building permit issuance for the retaining wall. The property owner must also become signatory to the San Bruno Mountain Area Habitat Conservation Plan Agreement by signing an "Agreement to Comply with Terms and Conditions of the Agreement with Respect to the San Bruno Mountain Area Habitat Conservation Plan and Section 10(a) Permit", including the requirement to participate in the HCP funding program, which must be recorded with the San Mateo County Recorder's office prior to permit final (Condition of Approval F).

ATTACHMENTS

- A. Draft Resolution 2022-UP-7/2022-EX-5/2022-LLA-3/2022-HCP-1
- B. Aerial vicinity map
- C. Applicant's plans

2022-UP-7/2022-EX-5/2022-LLA-3/2022-HCP-1
8/24/2023 Meeting

- D. Assessor Parcel Map
- E. Biological Resources Assessment prepared by Coast Ridge Ecology
- F. Geotechnical Investigation prepared by Divis Consulting, Inc.
- G. Draft Declaration of Lot Merger


Jeremiah Robbins, Associate Planner


John Swiecki, Community Development Director

Attachment A

draft

RESOLUTION 2022-UP-7/2022-EX-5/2022-LLA-3/2022-HCP-1

A RESOLUTION OF THE PLANNING COMMISSION OF BRISBANE
CONDITIONALLY APPROVING USE PERMIT 2022-UP-7, GRADING REVIEW 2022-EX-5, LOT
MERGER 2022-LLA-3, HABITAT CONSERVATION PLAN COMPLIANCE 2022-HCP-1
TO ALLOW AN APPROXIMATELY 5,000 SQUARE FOOT EXPANSION OF THE CURRENT
CONTRACTOR'S STORAGE YARD PREVIOUSLY PERMITTED UNDER UP-9-12
AT 3708 BAYSHORE BOULEVARD

WHEREAS, Sean Brennan, the applicant, applied to the City of Brisbane for approval of a Use Permit, Grading Review, Lot Merger, and San Bruno Mountain Habitat Conservation Plan (HCP) Compliance for an expansion of a contractor's storage yard (previously permitted under UP-9-12, UP-6-11, UP-5-10, UP-5-8, UP-6-07, and UP-3-06) at 3708 Bayshore Boulevard; and

WHEREAS, on August 24, 2023, the Planning Commission conducted a public hearing on the application, publicly noticed in compliance with Brisbane Municipal Code Chapters 1.12 and 17.54, at which time any person interested in the matter was given an opportunity to be heard; and

WHEREAS, the Planning Commission reviewed and considered the staff memorandum relating to said applications, the applicant's plans and supporting materials, and the written and oral evidence presented to the Planning Commission in support of and in opposition to the application; and

WHEREAS, the Planning Commission finds that the proposed project is categorically exempt from the provisions of the California Environmental Quality Act; pursuant to Sections 15301 and 15311 of the State CEQA Guidelines; and

WHEREAS, the Planning Commission of the City of Brisbane hereby makes the findings attached herein as Exhibit A in connection with the application.

NOW THEREFORE, based upon the findings set forth hereinabove, the Planning Commission of the City of Brisbane, at its meeting of August 24, 2023, did resolve as follows:

Use Permit 2022-UP-7, Grading Review 2022-EX-5, Lot Merger 2022-LLA-3, Habitat Conservation Plan Compliance 2022-HCP-1 are approved per the findings and conditions of approval attached herein as Exhibit A.

The Operating Program for Management Unit 2-03-26 is hereby adopted, as attached herein as Exhibit B.

ADOPTED this 24th day of August, 2023, by the following vote:

AYES:

NOES:

ABSENT:

ROEL FUNKE
Chairperson

ATTEST:

JOHN A SWIECKI, Community Development Director

**Draft
EXHIBIT A**

Action Taken: Conditionally approve Use Permit 2022-UP-7, Grading Review 2022-EX-5, Lot Merger 2022-LLA-3, Habitat Conservation Plan Compliance 2022-HCP-1 per the staff memorandum with attachments, via adoption of Resolution 2022-UP-7/2022-EX-5/2022-LLA-3/2022-HCP-1.

Findings:

2022-UP-7

1. *The planning commission shall consider and give due regard to the nature and condition of all adjacent uses and structures, and to general and specific plans for the area in question.*

The proposed commercial use of this property is consistent with the mixed commercial and residential character of the Subregional Commercial/Retail/Office (SCRO) land use designation in the Southwest Bayshore subarea and SCRO-1 District, a mixed-use district with a variety of existing commercial and residential uses. Adjacent development is approximately 470-610 feet away, which includes the mobile home park to the south and single-family residences to the west. Immediately adjacent parcels are undeveloped, but the parcel to the south is entitled for a 30-unit condominium complex. A landscaped yard would separate the two uses with 40 to 60 feet of separation and when approved, MK Pipelines Inc., was an existing commercial use. Furthermore, the proposed expansion would occur on the northern corner of the lot, away from existing and entitled residential uses.

Chapter 12 of the General Plan contains a number of policies and programs that apply specifically to development within the Southwest Bayshore subarea. The proposed use of the property and the applicant's plans are consistent with the applicable General Plan policies and programs, including the Southwest Bayshore subarea policies, including:

- Policy SWB.7 – the proposed expansion will be screened to match the existing yard
 - Policies SWB.3, 119, 123, and Programs 83a 122a, b, & c, and 123a – a biological resources assessment of the site was conducted to comply with the provisions of the San Bruno Mountain Area Habitat Conservation Plan (HCP)
 - SWB.4 – a soils and geotechnical report was required with this application and will be again at building permit application
 - Programs 134a and 228d – Condition of Approval Q, previously adopted and included herein, requires compliance with National Pollutant Discharge Elimination System, to protect stormwater quality.
2. *The planning commission shall determine whether or not the establishment, maintenance or operation of the use applied for will, under the circumstances of the particular case, be detrimental to the health, safety, comfort and general welfare of the persons residing or working in the neighborhood of such proposed use, or whether it will be injurious or*

detrimental to property and improvements in the neighborhood or the general welfare of the city.

MK Pipelines has been operating under their current use permit (UP-9-12) as a contractor's storage yard for over nine years and there have been no code enforcement complaints or violations. Prior to that, the site was approved as a contractor's storage yard under UP-6-11, UP-5-11, UP-5-08, UP-6-07 and UP-3-06. The use is consistent with the mixed commercial and residential character of the Southwest Bayshore subarea and SCRO-1 Zoning District, and the recent use of the site, since at least 2006, has been a contractor's storage yard. The project will require a building permit, and its design and construction shall be subject to compliance with current California Building Code requirements for health and safety.

3. *Adequate measures have been taken to protect workers and residents from the twenty-four (24) hour noise generated by traffic on Bayshore Boulevard.*

The project does not include the construction of any new structures, only the expansion of the existing paved storage yard to accommodate additional construction equipment and temporary storage of surplus material. Of the 27 employees, only four work directly onsite while the remaining 23 employees typically move from job site to job site, and no employees are onsite between 5:30 pm and 7:00 am. No additional measures are necessary to protect workers from noise generated by traffic on Bayshore Boulevard.

4. *The improvements have been designed in a manner that will make adequate provision for on-site parking and traffic circulation and safe ingress to and egress from the site.*

The proposed improvements do not require additional on-site parking and the site is adequately parked per BMC Chapter 17.34. Previous modifications were made to address safe ingress and egress from the site when a 60-foot-long concrete median was constructed on Bayshore Boulevard to prevent illegal turning movements across the southbound traffic lanes as part of the approval of UP-9-12.

5. *The improvements have been designed to be compatible with the topography and soils of the hillside.*

The proposed grading is limited to the area of the proposed paved storage yard and is located on a portion of the site that is relatively level area. The first 65-80 feet of the northeastern corner of the lot, measured from Bayshore Boulevard, has a slope of approximately 15% whereas the entire property has a slope closer to 46%, as measured per BMC Section 17.02.730. The new paved area would also be level with the existing structure and paved yard, approximately 11 feet above Bayshore Boulevard, and not extend any farther than the western limits of the existing paved lot. Proposed retaining walls will not exceed six feet in height and a geotechnical report was submitted for review by City staff and found to be sufficient to support the proposed grading plan. Furthermore, Condition of Approval K requires a licensed soils or geotechnical engineer to submit a Final Grading Observation Report to the City, summarizing conformance of the grading operations to the geotechnical report, prior to construction of the paved yard and retaining walls.

2022-EX-5

6. *The proposed grading is designed to reflect or fit comfortably with the site context and natural topography.*

As discussed in Finding 6 above, the proposed grading is minimized and designed to reflect or fit comfortably with the natural topography of the site.

7. *The proposed grading is designed to ensure that retaining walls visible to the public are designed to be as visually unobtrusive as possible*

As discussed in Finding 6 above, the proposed grading is designed to avoid large exposed retaining walls.

8. *The proposed grading is designed to minimize removal of: (i) existing street trees; (ii) any California Bay Laurel, Coast live Oak or California Buckeye trees; and (iii) three or more trees of any species on the same site having a circumference of at least thirty inches measured twenty-four inches above grade.*

The proposed grading will not require removal of existing street trees or California Bay Laurel, Coast Live Oak, or California Buckeye trees, or any other mature tree on the site.

2022-LLA-3

9. Per BMC §16.12.070, contiguous parcels held by the same owner may be merged by recordation of a declaration of lot merger signed by the property owner and acknowledged by the Community Development Director. The City Attorney has reviewed the proposed lot merger and raised no concerns with this application.

2022-HCP-1

10. The proposed expansion of the contractor's storage yard on the subject property (HCP Management Unit 2-03-26) complies with the terms of the San Bruno Mountain Area Habitat Conservation Plan Agreement and Section 10(a) Permit, given the conditions of approval contained herein and HCP Operating Program contained in Exhibit B this Resolution 2022-UP-7/2022-EX-5/2022-LLA-3/2022-HCP-1.

Conditions of Approval:

Prior to Issuance of a Building Permit:

- A. The applicant shall obtain a building permit and a grading permit prior to proceeding with construction. Plans submitted for the building and grading permits shall substantially conform to plans on file in the City of Brisbane Planning Department, with the following modifications:
1. Plans submitted for grading permit review shall be subject to standard review procedures by the Department of Public Works.

2. Drawings depicting all work completed and proposed shall be provided to the satisfaction of the City. Exposure of covered work may also be required to demonstrate compliance with building code requirements.
 3. Applicant shall submit a new C.3/C.6 Checklist, in conformance with the current Municipal Regional Stormwater Permit (Order No. R2-2022-0018). Should the grading and building permit plans show the project creates and/or replaces 5,000 square feet or more of impervious surface the project would be considered a regulated project under Section C.3 of the Order and shall actively manage stormwater treatment on-site through source control measures.
- B. A one-time habitat conservation fee shall be paid to the City for habitat acquisition in lieu of designation of 40% of the parcel as conserved habitat. This mitigation shall be computed by multiplying the "mitigation fee land area" (40% of the property acreage) by the "mitigation fee market value" (the highest or most recent per square foot sales price, whichever is greater) within Administrative Parcel 2 -03-02 purchased by the City for purposes of open space preservation, as adjusted for inflation. This fee shall be paid prior to issuance of a grading permit from the City of Brisbane.
 - C. The applicant shall obtain an encroachment permit from the Department of Public Works for all proposed construction activity and private improvements within the public right-of-way. Requirements for specific street improvements shall be subject to the discretion of the City Engineer.
 - D. An agreement shall be recorded between the owner and the City whereby the owner waives the right to protest the inclusion of the property within an underground utility district.
 - E. A soils/geotechnical report prepared by an engineer licensed to perform geotechnical analysis shall be submitted for approval by the City Engineer. The report shall provide recommendations for site grading operations, a building foundation analysis, stability of existing on-site ground slopes and calculation of any required pavement sections. The building permit plans shall be approved by the soils engineer consistent with the submitted soils report and shall be subject to the recommendations of the soils report.
 - F. As required by the Plan Operator (San Mateo County), the property owner shall become a signatory to the San Bruno Mountain Area Habitat Conservation Plan Agreement by signing an "Agreement to Comply with Terms and Conditions of the Agreement with Respect to the San Bruno Mountain Area Habitat Conservation Plan and Section 10(a) Permit" and shall record a Declaration of Covenants and Restrictions per Exhibit G of the Agreement with Respect to the San Bruno Mountain Area Habitat Conservation Plan, which shall include the requirement to participate in the HCP funding program.
 - G. The 32 square foot wall sign, approved under SR-2-13, located on the norther façade of the structure, shall be removed, as required per the conditional approval of SR-2-15.

During Construction/Grading:

- H. Consistent with the biological resources assessment prepared by Coast Ridge Ecology, LLC, the following restrictions shall apply to demolition and construction activity on the site:

1. Avoidance of Nesting Birds including Raptors. If feasible, vegetation removal and ground disturbance should be conducted outside of the nesting bird season (February 1 to August 31).
 2. Pre-Construction Nesting Bird Surveys including Raptors. If removal of vegetation is to occur during the nesting season (February 1 to August 31), it is recommended that surveys for nesting birds (including special status raptors) be conducted prior to any vegetation removal by a qualified biologist. Surveys should be conducted no more than one week (seven days) prior to vegetation removal or ground disturbance. If active nests are found, vegetation removal should only be conducted after the young have left the nest and the nest is no longer considered active (i.e. in use).
 3. Implementation of Nesting Bird Buffer Zones. If active nests are found within the survey area, suitable buffer zones should be established in consultation with CDFW to ensure nesting birds are not impacted by project activities. A buffer zone of 250' is recommended for raptors, and a buffer of 100' is recommended for passerines and other nesting birds. Buffer zones should be kept in place until nests are determined inactive by a qualified biologist.
- I. All grading shall be contained on the site and shall comply with the provisions of Brisbane Municipal Code Chapter 15.01, San Mateo Countywide Stormwater Pollution Prevention program best management practices, and the Bay Area Air Quality Management District's standard construction dust control measures.
 - J. If the grading operation takes place during hot and/or windy weather conditions water/fire extinguishers shall be available on site for immediate use.
 - K. Prior to construction of the paved storage yard and retaining walls, the soils engineer shall submit a Final Grading Observation Report to the City summarizing conformance of the grading operations to the geotechnical report required under Condition of Approval E.
 - L. Any prehistoric Native American cultural resources found during the course of construction shall be conserved in accordance with State and Federal requirements (refer to Appendix K of the State CEQA Guidelines and page 248 of Vol. II, 1994 Brisbane General Plan EIR).

Prior to Permit Final:

- M. At time of final inspection, the HCP Plan Operator shall be notified in order to begin the annual assessment. Upon permit final, the Landowner shall pay an annual assessment to the San Bruno Mountain Conservation Fund. The annual assessment shall be as provided in HCP Chapter V-B.

Ongoing/Post Occupancy Conditions:

- N. The Use Permit is for approval of a contractor's storage yard, limited to the existing 18,000 square feet +/- of the property already improved with a building and paved yard and the new 5,000 square feet +/- paved storage area (total 23,000 square feet +/-).
- O. Hours of operation shall be restricted to 7:00 am and 5:30 pm, daily.

- P. No potentially hazardous or flammable materials shall be stored at the site without the approval of the North County Fire Authority (NCFA), and all materials shall be stored in compliance with the California Fire Code, as administered by the NCFA. No pesticides or herbicides shall be stored at the site without the approval of the HCP Plan Operator.
- Q. All Best Management Practice improvements necessary to prevent stormwater pollution per NPDES shall be implemented and maintained to the satisfaction of the Public Works Dept., including, but not limited to, the following:
1. All outdoor equipment and materials storage areas shall be designed to limit potential pollutants to contact runoff. Storage shall occur only on paved and contained areas. The pavement should be checked periodically for cracks and fractures, which should be sealed to prevent leakage.
 2. Any non-hazardous liquids, such as latex-based paint, shall be stored indoors, unless otherwise approved by the Public Works Dept.
 3. Wastewater from any vehicle/equipment washing operations shall not be discharged to the storm drain system. Any wastewater discharges to the sanitary system are subject to approval by the Public Works Dept.
 4. No vehicle/equipment maintenance shall be performed outdoors, but shall be in a protected area that does not allow for ground contamination.
- R. No grading, paving, vegetation removal, or new construction shall be permitted except in compliance with the Brisbane Municipal Code and the San Bruno Mountain Area Habitat Conservation Plan, which is administered through the San Mateo County Parks Department. A San Bruno Mountain Area HCP Site Activity Review shall be obtained from the County prior to any weed removal on undeveloped portions of the property.
- S. Clearance for emergency access shall be provided between the rear fence and the hillside to the satisfaction of the NCFA, subject to approval of a San Bruno Mountain Area HCP Site Activity Review.
- T. No off-site storage or parking is authorized under this Use Permit and these activities shall be on the paved portions of the site.
- U. The site shall be maintained to keep adequate parking open for use by employees and keep emergency vehicle access open.
- V. Access for emergency vehicles shall be maintained for a minimum width of 20 feet from the street to within 50 feet of at least two sides of the building and within 150 feet of the other sides of the building, to the satisfaction of the NCFA.
- W. No signage is approved as part of this permit. Signage may be installed following application and approval of a sign permit, per Brisbane Municipal Code Chapter 17.36. See Condition of Approval G.
- X. The property shall be maintained free of litter.

- Y. The fence shall be maintained so that it is in good repair. If replacement of the existing fence is needed, the fence shall comply with the requirements of Brisbane Municipal Code §17.32.050, which require that chain link fences are to be black or green vinyl coated and that barbed wire or similar materials are not allowed. The slats would also be required to match the replacement fence, subject to Community Development Director approval.

Other Conditions

- Z. The property owner shall abide by the provisions of the adopted Operating Program for HCP Management Unit 2-03-26, the Habitat Conservation Plan, Habitat Conservation Plan Agreement, and Section 10(a) Permit.
- AA. The required off-street parking spaces shall not be used or converted to any other use that would impair their basic use as parking for motor vehicles per Brisbane Municipal Code Chapter 17.34.
- BB. The permittees agree to indemnify, defend and hold the City and its officers, officials, boards, commissions, employees and volunteers harmless from and against any claim, action or proceeding brought by any third party to attack, set aside modify or annul the approval, permit or other entitlement given to the applicant, or any of the proceedings, acts, or determinations taken, done or made prior to the granting of such approval, permit, or entitlement.
- CC. Minor modifications may be approved by the Community Development Director in conformance with all requirements of the Brisbane Municipal Code.
- DD. Pursuant to Brisbane Municipal Code §17.48.010, the Use Permit approval shall become null and void two years from its effective date (at the end of the appeal period) if a Building Permit has not yet been issued for the approved project, or if the Building Permit, once issued, is allowed to expire prior to final inspection.
- EE. Approval of this application is to allow for the project as detailed in the Project Description contained in the Planning Commission staff report dated August 24, 2023, except where project parameters are modified expressly by this Resolution.
- FF. Material violation of any of the conditions, including material deviation from the approved project description, may be cause for revocation of Use Permit 2022-UP-7 and termination of all rights granted there under.

EXHIBIT B: HCP Operating Program

2-03-26. 3708 Bayshore Boulevard (APN 007-350-100, APN 007-350-110, and APN 007-350-120). This management unit is located within the Southeast Ridge (2) Planning Area, Brisbane Acres Administrative Parcel (03). The property is owned by MK Pipelines and consists of a flat, asphalt-paved, construction yard built on APN 007-350-100 and APN 007-350-110, on the east side of the property. A steep, vegetated hillslope rises from the construction yard to the base of San Bruno Mountain on the west side of the property.


The proposed project involves the extension of the construction yard, north into APN 007-350-120, which is currently undeveloped. The project would involve approximately 5000 square feet of grading on the east side of the APN 007-350-120. The majority of the property would remain undeveloped. The project would include the removal of a current Allen-block wall installed between APN 007-350-110 and APN 007-350-120, and the installation of a new Allen-block wall around the west and north edge of the construction yard.

Coast Ridge Ecology, LLC prepared the Biological (Environmental) Assessment Report for the site in July 2022 that concluded that the site did not have any potential to support the Mission blue butterfly or Callippe silverspot butterfly. Several special-status raptor, bat, and insect species have potential to forage or roost on the property, primarily within areas of native habitat.

Obligations: The landowner/developer has the following obligations:

1. **Habitat Conservation Fee.** A one-time habitat conservation fee shall be paid to the City for habitat acquisition in lieu of designation of 40% of the parcel as conserved habitat. This mitigation shall be computed by multiplying the “mitigation fee land area” (40% of the property acreage – approximately 1.5 acres (66,885 square feet) by the “mitigation fee market value” (the highest or most recent per square foot sales price), whichever is greater) within Administrative Parcel 2-03 purchased by the City for purposes of open space preservation, as adjusted for inflation. This fee shall be paid prior to issuance of a grading permit from the City of Brisbane.
2. **HCP Funding Program.** Upon completion of the proposed project, the landowner shall pay an annual assessment to the San Bruno Mountain Conservation Fund consistent with the funding program described in HCP Chapter V-B.
3. **Undeveloped portions of the site are required to have natural vegetation be retained (where applicable).** Planting of invasive species on portions to be developed is prohibited, and aerial or large-scale spraying of pesticides without the prior approval by the Plan Operator is prohibited. Invasive species should be removed as feasible.

Attachment B: Aerial Vicinity Map



**USE PERMIT APPLICATION CHECKLIST
FOR CONDITIONAL USES PER DISTRICT REGULATIONS**

PROJECT DESCRIPTION

MK Pipelines is applying for a Use Permit for expanded operations at our current facility. MK Pipelines was previously issued UP-9-12 as we met the criteria under section 17.16.030, Section 2.

MK Pipelines has purchased the vacant lot directly adjacent to 3708 Bayshore Blvd. Brisbane. Per City request we are in the process of completing a lot merger and we wish to grade and expand our use into the adjacent lot. Plans for both the lot merger and proposed grading are attached to this application.

MK Pipelines is an underground utility contractor that performs primarily public works throughout the peninsula. Since our previous application the company has grown 25 – 30% hence necessitating the additional space. There are currently 27 employees working for MK Pipelines of which only 4 are domiciled/based at the office location. All other staff work on job sites and are only at the facility incrementally or as needed as no dispatch to job sites is taken place from the office location. Crews move from job site to job site along with the equipment. We own approximately 35 pieces of construction equipment i.e., excavators/backhoes/pick-up trucks which move directly from job site to job site 90% of the time. There are however some lags that do occur and equipment needs to come back to the base whilst waiting for another project to begin. MK Pipelines employs one heavy haul driver to bring equipment to and from the shop as required.

MK Pipelines business model is set up that all material delivery is delivered directly to job sites, no delivery of material is transferred through the shop location. We do however at the end of some projects have surplus materials that do come back to the shop for reuse on a future project or to be picked up and returned to the vendor. Special order items that have long lead times may occasionally be delivered to the shop whilst waiting for the project to begin. Minimum fabrication of construction materials is carried out at the shop.

As per our current UP-9-12 storage of pipe materials is predominantly carried out behind the existing shop up to 15' tall and this is reflected on the Site Plan. There are miscellaneous small materials stored outside i.e., excavator buckets/steel plates etc. In our current use the facility is concealed as there was a 6' tall brown slatted fence installed as part of Grading Permit 13-0326-13 and as the current and future yard sits at an elevation approximately 11' higher than the street it means the yard cannot be seen easily from road traffic or foot traffic on Bayshore Blvd.


The proposed future use involves the grading/paving of the vacant lot in order to increase our laydown/equipment storage etc. to support our expanded business growth. No further parking spots will be required as all disabled parking and regular parking spots as detailed in Grading Permit 13-0326-13 will remain untouched and exceed current needs. The future grading will incorporate all of the exact same elements previously approved i.e., same pre-engineered Allen block retaining walls will be used and the same brown slatted fence will be used.

MK Pipelines has been operating under current use permit for over 9 years and to the best of our knowledge there has been zero complaints or zero code violations. We are inspected regularly by a number of different agencies, San Mateo Environmental, San Francisco Water Power Sewer, Brisbane Public Works and North Coast County Fire Department and we are glad to report in 9 plus years we have had zero code

violations with any of the above agencies. In short, we have been a good neighbor and intend to continue operating in the exact same manner.

DEVELOPMENT PLANS


- Site Plan is attached showing existing structures and dimensions
 - Existing Parking Plan is on Site Plan and there will be no changes
 - Conceptual Grading Plan is attached with quantities
 - Conceptual Landscape Plan – TBD – It was discussed at our meeting that a landscape plan may not be required for this project as 75% of the lot is to remain native planting and landscape and will be untouched.
 - Topographic Map – Topo Plan is shown on the Boundary Map as requested.
 - Storm Water Checklist – small projects checklist is attached
1. (a) Hours of operations are between 7AM and 5:30PM for the office/warehouse.
 1. (b & c) MK currently owns 10 excavators, 2 backhoes, 8 skidsteers, 8 Terex Dumpers, 6 Utility Trucks, 1 heavy haul truck, 2 medium light duty trucks. We currently own 2 trailers that are used for transportation of the heavy equipment. Our equipment and trailers rarely come back to the warehouse as the preferred method is to move from project to project. At any one time there may be an average of 4 pieces of equipment in the yard and the additional two trailers. On rare occasions if job site scheduling does not allow that can increase up to 10 pieces of equipment. We cannot breakdown the type specifically of equipment as it changes daily and weekly.
 1. (d) Crews are not dispatched from the warehouse they start their workday on the job sites. A member of the crew may return to the warehouse twice to three times a week to pick up miscellaneous small equipment and/or documentation from the office.
 1. (e) Heavy haul truck can average two trips daily.
 1. (f) In general MK never plans to store surplus materials at the warehouse. Surplus materials from the job sites are generally picked up by vendors directly at the job site. We have occasions when the pipe/pre cast catch basins etc. have been on job sites and the vendor will refuse to accept return and we will bring these back to the warehouse whilst we wait for reuse on an upcoming project. In our 10 years of operations we have never had to store dirt/gravel, we do not ever anticipate a circumstance where would be storing dirt at the facility. There could be in instance where gravel material (3/4" drain rock) may have to be stored on a Friday for an upcoming weekend job (quarries are closed for pickup of materials on Saturdays). MK would classify miscellaneous small materials as catch basins, manhole covers, valves and fittings for water mains.
 1. (g) In 10 years of operation MK has had to fabricate one storm drain pump onsite. Fabrication of any and all materials is normally done on the job site, there is no plan now or at any time in the future to carry out any small or medium scale fabrication, but if the occasion does arise it will occur both outside and inside the warehouse.
 1. (h) MK Pipelines does not handle, store or dispose of any hazardous materials either onsite or offsite.



BENCHMARK STATEMENT:
THE ELEVATIONS SHOWN ARE ON AN
ASSUMED DATUM.

BASIS OF BEARINGS:
THE BEARING OF SOUTH 33 26 19 EAST AS SHOWN ON 28
L.L.S. 69 WAS USED AS THE BASIS OF BEARING FOR THIS
SURVEY.

SURVEYOR'S STATEMENT:
THIS SITE PLAN MAP WAS MADE BY ME OR UNDER MY
DIRECTION ON THE GROUND AND REPRESENTS
MEASUREMENTS MADE SEPTEMBER 2022. A TITLE REPORT
WAS PROVIDED TO THE SURVEYOR BY THE CLIENT. NO
EASEMENTS ARE SHOWN.





SAVIOR P. MICALLEF
LAND SURVEYOR, LS 8289
(805) 709-2423

11-08-22
DATE

SAVIOR P. MICALLEF LAND SURVEYING
421 WILDWOOD DRIVE
SOUTH SAN FRANCISCO, CA 94080
805/709-2423

SITE PLAN
MK YARD, LLC 3708 BAYSHORE BLVD
CITY OF BRISBANE SAN MATEO COUNTY CALIFORNIA

1	Drawing Number:		Date: 11-08-22	No.	Revisions
			Scale 1"=20'		
			Design		
			Drawn SPM		
			Approved SPM		
			Job No.		
OF					
1					



SAVOR P. WICALLEE LAND SURVEYING
421 WILDWOOD DRIVE
SOUTH SAN FRANCISCO, CA 94080
805/709-2423

GRADING PLAN
MK YARD, LLC 3708 BAYSHORE BLVD
CITY OF BRISBANE

CALIFORNIA
SAN MATEO COUNTY

Date	08-14-22	No.	
Scale	1"=10'		
Design	SPM		
Drawn	SPM		
Approved	SPM		
Job No.			
Drawing Number:			
1	of	1	

SUPPORTING STATEMENTS

Findings Required for Approval of All Use Permits

Brisbane Municipal Code §17.40.060

In order to approve any use permit application, the Planning Commission must affirmatively make the findings of approval in BMC Chapter 17.40, which are reproduced below. Supplemental findings may also be required depending on your specific project and the applicable zoning district and are listed in this attachment.

Please respond to each required finding as it relates specifically to your proposal and include a reference to the applicable plan sheet in the development plans. Attach additional pages if necessary, or provide written responses on a separate document.

1. How has the project been designed and operated in order to be compatible with the nature and condition of all adjacent uses and structures, and with general and specific plans for the area in question?

MK already has a use permit granted by Brisbane to operate as a	Plan Sheet Page(s)
contractors and it is on file with the city. The city has mandated MK to merge	
adjacent property & APN into existing APN's at 3708 Bayshore Blvd. so it	
will become one parcel.	

2. How will the propose use be designed and operated in order to not be detrimental to the health, safety, comfort and general welfare of the persons residing or working in the neighborhood?

Proposed use will be consistent with use for last 10 years and business has	Plan Sheet Page(s)
been good neighbor with zero complaints or issues from people residing or	
working in the area	

3. How will the proposed use be designed and operated in order to not be injurious or detrimental to property and improvements in the neighborhood or the general welfare of the city?

Proposed use will be same as existing use that has been granted by city. No	Plan Sheet Page(s)
other improvements or expanding use is planned.	



Existing facility above; proposed expansion lower right






Existing brown-slatted fence and Allen-block retaining wall used throughout the site



Attachment D: Assessor's Parcel Map



Biological Assessment Report for 3708 Bayshore Blvd. Brisbane, CA

Prepared for City of Brisbane

July 2022

Prepared by:
Coast Ridge Ecology, LLC
1410 31st Avenue
San Francisco, 94112
CRecology.com



Biological Assessment for 3708 Bayshore Boulevard

Applicant: MK Pipelines, Inc

Project Lead: City of Brisbane


Total parcel size: 1.0 Acres

Assessor Parcel Numbers: 007-350-110, 007-350-100

Project Proposal Description: This assessment was prepared prior to preparation of plans to develop the subject parcels. The applicant intends to extend their existing contractor's yard north into APN 007-230-120; this work will not impact the footprint of the existing construction yard on the property.

Prepared for the San Mateo County Parks Department and City of Brisbane by:
Coast Ridge Ecology, LLC

As a qualified Biologist, I hereby certify that this Biological Assessment was prepared according to the County Parks' requirements and that the statements furnished in the report and associated maps are true and correct to the best of my knowledge.

Qualified Biologist (signature):		Date: July 1, 2022
		
Suk-Ann Yee	Title: Senior Biologist	Company: Coast Ridge Ecology, LLC
Phone: 415-404-6757	email: syee@crecology.com	
Role: Project Manager and Lead Author		
Other Biologist (signature):		Date:
Name (printed): Greg Pfau	Title: Associate Biologist II	Company: Coast Ridge Ecology, LLC
Phone: 415-404-6757	email: gpfau@crecology.com	
Role: Map Production		

Biological Study Checklist

This Biological Assessment DID provide adequate information to make recommended California Environmental Quality Act (CEQA) findings regarding potentially significant impacts.

	Project Impact Degree of Effect				Cumulative Impact Degree of Effect			
	N	LS	PS-M	PS	N	LS	PS-M	PS
<i>Biological Resources</i>								
<i>Species</i>		X			X			
<i>Ecological Communities</i>	X				X			
<i>Habitat Connectivity</i>	X				X			

N: No impact

LS: Less than significant impact

PS-M: Potentially significant unless mitigation incorporated.

PS: Potentially significant

Contents

SUMMARY	3
SECTION 1. CONSTRUCTION FOOTPRINT DESCRIPTION	4
DEVELOPMENT PROPOSAL DESCRIPTION	4
COASTAL ZONE/OVERLAY ZONES.....	4
ZONING	4
ELEVATION	4
SECTION 2. SURVEY INFORMATION.....	5
2.1 SURVEY PURPOSE	5
2.2 SURVEY AREA.....	5
<i>Location</i>	<i>6</i>
<i>Survey Area Environmental Setting</i>	<i>6</i>
<i>Surrounding Area Environmental Setting</i>	<i>6</i>
<i>Cover</i>	<i>6</i>
2.3 METHODOLOGY.....	9
SECTION 3. THE BIOLOGICAL INVENTORY	10
3.1 ECOLOGICAL COMMUNITIES: PLANT COMMUNITIES, PHYSICAL FEATURES, AND WETLAND	10
<i>Plant Communities</i>	<i>10</i>
<i>Major Plant Communities Summary</i>	<i>10</i>
<i>Physical Features</i>	<i>13</i>
<i>Waters and Wetlands</i>	<i>13</i>
<i>Soils</i>	<i>13</i>
3.2 SPECIES.....	14
<i>Observed Species</i>	<i>14</i>
<i>Special Status Wildlife Species Summary</i>	<i>14</i>
<i>Special Status Plant Species Summary</i>	<i>15</i>
<i>Definitions of Special Status Species</i>	<i>15</i>
<i>Migratory Birds and Nesting Birds</i>	<i>15</i>
<i>Roosting Bats</i>	<i>16</i>
<i>Protected Trees</i>	<i>16</i>
3.3 WILDLIFE MOVEMENT AND CONNECTIVITY	26
SECTION 4: RECOMMENDED IMPACT ASSESSMENT AND CONDITIONS OF APPROVAL.....	28
4.1 SUFFICIENCY OF BIOLOGICAL DATA.....	28
4.2 IMPACTS AND CONDITIONS OF APPROVAL.....	28
<i>Special Status Raptors and Nesting Birds</i>	<i>28</i>
<i>Raptors.....</i>	<i>28</i>
<i>Nesting Birds</i>	<i>28</i>
<i>Special Status Plants</i>	<i>29</i>
<i>Ecological Communities</i>	<i>29</i>
<i>Protected Trees</i>	<i>30</i>
SECTION 5. REFERENCES	31
SECTION 6. PHOTOS	33

Appendices

APPENDIX A: SUMMARY OF BIOLOGICAL RESOURCE REGULATIONS.....A-1

<i>Sensitive Status Species Regulations</i>	<i>A-1</i>
<i>Migratory Bird Regulations</i>	<i>A-3</i>
<i>Plant Community Regulations</i>	<i>A-3</i>
<i>Waters and Wetlands Regulations</i>	<i>A-4</i>
<i>San Bruno Mountain Habitat Conservation Plan (HCP)</i>	<i>A-5</i>
<i>City of Brisbane General Plan.....</i>	<i>A-8</i>
<i>City of Brisbane Municipal Code</i>	<i>A-11</i>

APPENDIX B: POTENTIALLY OCCURRING SPECIAL STATUS SPECIESB-1

List of Tables

<i>Table 1. Survey Details.....</i>	<i>9</i>
<i>Table 2. Plant Communities.....</i>	<i>11</i>
<i>Table 3. Observed Species.....</i>	<i>16</i>

List of Figures

<i>Figure 1. Project Location Map.....</i>	<i>7</i>
<i>Figure 2. Site and Survey Map.....</i>	<i>8</i>
<i>Figure 3. Plant Communities and Photopoints Map.....</i>	<i>12</i>
<i>Figure 4. CNDDDB Occurrence Map - Animals.....</i>	<i>18</i>
<i>Figure 5. CNDDDB Occurrence Map – Plants.....</i>	<i>19</i>

Summary

A Biological Assessment was conducted for 3708 Bayshore Boulevard (comprised of APN 007-350-110, and APN 007-350-100). The property is approximately one acre in size and is located on the east side of San Bruno Mountain. The parcels lie west of Bayshore Boulevard, north of the intersection of Bayshore Blvd and Van Waters and Rodgers Rd. Brisbane Lagoon lies to the east of Bayshore Boulevard. The parcels are rectangular in shape and are bordered by undeveloped lands to the north, south, and west. The parcels are located within the Southwest Bayshore Commercial District, which is a mixed use Subregional Commercial Retail/Office zone (SCRO-1 zoning district; City of Brisbane General Plan, 2022).

There is currently no proposed development for the parcels. Although the applicant plans to extend their existing yard north into APN 007-230-120, this work is not anticipated to impact the footprint of the existing construction yard on the property. The findings of this Assessment will be reviewed upon submittal of project plans to confirm their applicability to the final project scope. A biological resources assessment for APN 007-230-120 was prepared in 2021 by MIG, Inc.

A total of four vegetation communities are found within the study area: French Broom Semi-Natural Shrubland Stands, Developed, Eucalyptus Semi-Natural Woodland Stand and Wild Oats Semi-Natural Herbaceous Stands. Only two of these vegetation communities are found within the project parcels; French Broom Semi-Natural Shrubland Stands and Developed. The eastern portion of the parcel is a developed construction yard owned by MK Pipelines, Inc. The western portion consists of a steep slope vegetated with non-native shrubland species, intermingled with some native shrub species including coyote brush and toyon. The parcels provide some limited wildlife habitat for local wildlife species.

No special status wildlife or plant species were observed on the parcel or the surrounding 60-foot buffer that was included in the survey area. No sensitive plant communities, wildlife connectivity features, or waters or wetlands were observed in the survey area. Based upon the habitat and condition of the survey area, the site has low potential to provide habitat for any special status species. Two special status wildlife species (Cooper's hawk and Northern harrier) were identified as having moderate potential to be found within the study area. Nine special status wildlife species and five special status plant species were identified as having a low potential to occur within the study area.

Section 1. Construction Footprint Description

Construction Footprint Definition (per the San Mateo County Planning & Building): The construction footprint includes the proposed maximum limits of temporary or permanent direct land or vegetation disturbance for a project including such things as the building pad(s), roads/road improvements, grading, septic systems, wells, drainage improvements, fire hazard brush clearance area(s), tennis courts, pools/spas, landscaping, storage/stockpile areas, construction staging areas, fire department turnarounds, utility trenching and other grading areas. The construction footprint on some types of projects, such as mining, oil and gas exploration or agricultural operations, may be quite different than the above.

Development Proposal Description

There is currently no proposed development for the parcels. Although the applicant plans to extend their existing yard north into APN 007-230-120, this work will not impact the footprint of the existing construction yard on the property.

Coastal Zone/Overlay Zones

The parcel is located on the east side of San Bruno Mountain within the City of Brisbane, CA. The parcel is not within the Coastal Zone, Scenic Resources Protection Overlay Zone, Mineral Resources Protection Overlay Zone, or the Scenic Highway Protection Overlay Zone.

Zoning

The parcels are located within the Southwest Bayshore Commercial District, which is a mixed use Subregional Commercial Retail/Office zone (SCRO-1 zoning district; City of Brisbane General Plan, 2022).

Elevation

The parcel rises steeply from east to west. Elevation of the parcel ranges from 30 feet above Mean Sea Level (MSL) at the eastern edge along Bayshore Boulevard to 152 feet above MSL on the western edge of the property, located just downslope of the Stanislaus Walking Trail.

Section 2. Survey Information

2.1 Survey Purpose

Discretionary actions undertaken by public agencies are required to demonstrate compliance with the California Environmental Quality Act (CEQA). The purpose of this Biological Assessment (BA) is to gather enough information about the biological resources associated with the proposed project, and their potential to be impacted by the project, to make a CEQA Initial Study significance finding for biological resources. In general, BAs are intended to:

- Provide an inventory of the biological resources on a project site and the values of those resources.
- Determine if a proposed project has the potential to impact any significant biological resources.
- Recommend project redesign to avoid, minimize or reduce impacts to significant biological resources.
- Recommend additional studies necessary to adequately assess potential impacts and/or to develop adequate mitigation measures.
- Develop mitigation measures, when necessary, in cases where adequate information is available.

2.2 Survey Area

Survey Area Definition (using the SMC Planning & Building definitions): The physical area a biologist evaluates as part of a biological assessment. This includes all areas that could potentially be subject to direct or indirect impacts from the project, including, but not limited to: the construction footprint; areas that would be subject to noise, light, dust or runoff generated by the project; any required buffer areas (e.g., buffers surrounding wetland habitat). The construction footprint plus a 100 to 300-foot buffer— beyond the required fire hazard brush clearance boundary—(or 20-foot from the cut/fill boundary or road fire hazard brush clearance boundary – whichever is greater) is generally the size of a survey area. Required off-site improvements—such as roads or fire hazard brush clearance—are included in the survey area. Survey areas can extend off the project's parcel(s) because indirect impacts may cross property lines. The extent of the survey area shall be determined by the biologist in consultation with County Parks.

The survey area includes the entire 1.0 acre parcels at 3708 Bayshore Boulevard, and a 60-foot buffer surrounding the parcel, as approved by the City and County. The entire survey area was assessed for biological resources during the site visit (Table 1).

Location

The parcels are located at 3708 Bayshore Boulevard and is within the City of Brisbane, along the eastern edge of San Bruno Mountain (Figure 1). The parcels lie west of Bayshore Boulevard, north of the intersection of Bayshore Blvd and Van Waters and Rodgers Rd. Brisbane Lagoon lies to the east of Bayshore Boulevard. The parcels are rectangular in shape are bordered by undeveloped lands to the north, south, and west.

The property lies within the San Bruno Mountain Habitat Conservation Plan (SBM-HCP) area. The SBM-HCP allows development in specific areas on the Mountain, protection of biologically significant habitat areas, and a funding mechanism for managing conserved habitat areas. The closest conserved habitat areas within the SBM-HCP are approximately 0.5 mile to the south of the subject parcels.

Survey Area Environmental Setting

The survey area consists of an asphalt paved construction yard belonging to MK Pipelines, Inc. located on the east side of the property and a relatively steep, vegetated hillslope, rising from the construction yard up into the base of San Bruno Mountain on the west side of the property. The construction yard is completely flat, is asphalt-paved, and contains an office building. It is actively used as an office and for equipment storage by MK Pipelines, Inc. Water drains from west to east on the site, and there are no explicit water bodies, drainages or wetlands present within the survey area. Representative photos of the site and survey area are provided in Section 5.

Surrounding Area Environmental Setting

The survey area is bordered by Bayshore Blvd on the east, with the Brisbane lagoon lying on the other side of Bayshore Blvd, approximately 200' east of the survey area. Immediately to the north, south, and west lie open space parcels. A commercial development lies approximately 700' to the south, and single-family homes lie to the west, beginning as close as 200' from the study area.

Cover

Types of cover of the survey area is quantified as follows:

- 14% non-native vegetation
- 58 % non-native vegetation interspersed with some native vegetation
- 28 % buildings, paved roads, and/or other impervious cover



Figure 1: Project Location Map
3708 Bayshore Boulevard, Brisbane, CA

Service Layer Credits: USGS The National Map: National Boundaries Dataset, National Elevation Dataset, Geographic Names Information System, National Hydrography Dataset, National Land Cover Database, National Structures Dataset, and National

Legend

Project Location





Figure 2: Site and Survey Map
 3708 Bayshore Blvd, Brisbane, CA

Service Layer Credits: Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community



Legend

- ▭ Biological Survey Area
- ▭ Site Parcel Boundary

2.3 Methodology

The California Department of Fish and Wildlife (CDFW) Natural Diversity Database (CNDDB) was consulted for known occurrences of sensitive plant, animal, and natural plant communities of concern found within the San Francisco South and six surrounding 7.5' USGS topographic quadrangles (CNDDB, 2022). Data from CNDDB, California Native Plant Society (CNPS) On-Line Inventory of Rare, Threatened, and Endangered Plants of California (CNPS, 2022), USFWS Critical Habitat maps (USFWS, 2022), knowledge of regional biota, and observations made during the field survey, were used to evaluate on-site habitat suitability for special status plant and wildlife species within the study area.

Table 1. Survey Details

Survey Key ¹	Survey Date	Survey Area Map Keys	Survey Type ²	Time Period	Methods/Constraints	Surveyors
SD1	04/13/2022	SA1	BA	9:00am-1:00 pm	Walking transects. Portions of the site could not be hiked due to steepness; however, the entire site was visible from various vantage points.	Suk-Ann Yee, Ranit Cohen

1. SD= Survey Date

2. BA= Biological Assessment

Section 3. The Biological Inventory

3.1 Ecological Communities: Plant Communities, Physical Features, and Wetland

Background research was conducted prior to conducting the field visits in order to identify expected rare or locally important plant communities, USFWS mapped critical habitat and any mapped wetlands or streams. A 3-mile radius was used in conducting the research.

Plant Communities

Locally important or rare plant communities were not found within the survey area(s).

Major Plant Communities Summary

A total of four vegetation communities are found within the study area: **French Broom Semi-Natural Shrubland Stands, Developed, Eucalyptus Semi-Natural Woodland Stand and Wild Oats Semi-Natural Herbaceous Stands** (CNPS, 2009). Only two of these vegetation communities are found within the project parcels; French Broom Semi-Natural Shrubland Stands and Developed. The location of the plant communities within the survey area are shown in Figure 3.

French Broom Semi-Natural Shrubland Stands are found on the western half of the site and is the dominant plant community on the property. It is located on the steep slopes of the property above the developed construction yard. This vegetation community is dominated by French broom (*Genista monspessulana*), although native shrub species including toyon (*Heteromeles arbutifolia*), coyote brush (*Baccharis pilularis*), and poison oak (*Toxicodendron diversilobum*) are also present and increase in cover farther upslope from the construction yard. Understory species present within this vegetation community included native forbs such as figwort (*Scrophularia californica*), miner's lettuce (*Claytonia perfoliate*) and coastal woodfern (*Dryopteris arguta*). Non-native and invasive species within this habitat type included Italian thistle (*Carduus pycnocephalus*), Himalayan blackberry (*Rubus armeniacus*) and Bermuda buttercup (*Oxalis pes-caprae*)

The Developed portion of the property is located on the eastern flatter portion of the site and is made up of a paved asphalt area that serves as a construction yard for MK Pipelines, Inc. Very little ruderal vegetation is present along the edges of the Developed areas. In addition, a portion of the driveway to the construction yard, and Bayshore Blvd are also designated as Developed.

A small area of Eucalyptus Semi-Natural Woodland Stand is found on the south border of the study area. It is dominated by blue gum eucalyptus (*Eucalyptus globulus*) with an understory of poison oak, and toyon, as well as non-native herbaceous species. Understory herbaceous species include Italian thistle, summer mustard (*Hirschfeldia incana*), panic veldtgrass (*Erharta erecta*), and red valerian (*Centranthus ruber*).

Additionally small areas of Wild Oats Semi-Natural Herbaceous Stands are found within the study area between Bayshore Blvd and the property, as well as on the northern and western corners of the study area. These grassland areas are dominated by non-native grass and forb species such as slender wild oats (*Avena barbata*), bristly ox-tongue (*Helminthotheca echoioides*) and pincushion plant (*Scabious atropurpurea*).

A full list of species observed within the study area is provided in Table 3.

Table 2. Plant Communities

Map Key ¹	MCV Alliance	MCV Association	Misc.	Status	Condition	Acres Total	Acres Impacted	Comments
PC1	Semi-Natural Shrubland Stands	Broom patches	Toyon and coyote brush provide some native cover		Intact	1.42	0	Non-native dominant
PC2	Developed		Developed	None		0.69	0	Generally unvegetated, paved asphalt surface
PC3	Semi-Natural Herbaceous Stands	Wild oats grassland			Intact	0.25	0	Non-native dominant
PC4	Semi-Natural Woodland Stands	Eucalyptus groves		None	Intact	0.10	0	Non-native dominant.
					Totals		0	

¹PC= Plant Community



Figure 3: Plant Communities and Photopoints Map

3708 Bayshore Blvd, Brisbane, CA

Service Layer Credits: Golden Gate National Parks Conservancy and San Mateo County



Legend

- ▬ Site Parcel Boundary
- Biological Survey Area
- Photopoint

Plant Communities

- Avena Semi-Natural Grassland
- Developed
- Eucalyptus Semi-Natural Woodland
- French Broom Semi-Natural Shrubland

Physical Features

No additional physical features that may be important to the site's biological resources were present within the survey area. The office building located in the southern portion of the construction yard was examined for potential bat roosting habitat and signs of roosting bats (e.g. guano). Although corrugated metal sheeting covers the outer walls of the building, the depth of any potential roosting cavities is inadequate to support bat roosts.

Waters and Wetlands

Waters and wetlands were not found within the survey area.

According to the U.S. Fish and Wildlife National Wetlands Inventory (accessed May 26, 2022) the nearest mapped water sources are the Brisbane Lagoon located 250' to the east, and an intermittent stream located a quarter mile to the south.

There are no indications of wetland features on the parcels or within the survey area. There are no visible signs of wetland vegetation, or wetland hydrology (channels, vernal pools, etc.), to indicate a concentration of water collecting on or flowing through or adjacent to the parcels.

Soils

There are three soil types within the survey area boundaries identified by Natural Resource Conservation Science (NRCS 2022): Orthents, cut and fill, 15-75 percent slopes, Candlestick-Kron-Buriburi complex, 30-75 percent slopes, and Urban Land.

Orthents, cut and fill soils are derived from primarily from weathered sandstone and have been cut and filled for urban development. Orthents are generally well-drained soils. This soil type is mapped on the majority of the parcels and survey area.

Candlestick-Kron-Buriburi soils are very shallow to moderately deep, moderately steep to very steep, well drained soils underlain by sandstone, and are found in uplands. Candlestick-Kron-Buriburi soils are well drained and derived from hard fractured sandstone. This soil is mapped on the western edge of the survey area.

Urban land is mapped on the eastern section of the survey area including the developed lands of Bayshore Boulevard, the associated road shoulder, as well as a portion of the construction yard.

There are no serpentine, calcareous or sandy soils that could support special status plant species within the study area.

3.2 Species

Observed Species

During the April 2022 site visit, no special status wildlife or plant species were observed.

The plants and animals identified within the survey area are typical for species that utilize non-native dominant scrub, grassland, and woodland habitats near an urban setting. See Appendix 2 for a list of species observed in the survey area during biological surveys. One mammal species, the brush rabbit (*Sylvilagus bachmani*), was observed within the study area. Bird species observed by sight or sound during the site visit included red-tailed hawk (*Buteo jamaicensis*), California scrub-jay (*Aphelocoma californica*), common raven (*Corvus corax*), California towhee (*Melospiza crissalis*), chestnut-backed chickadee (*Poecile rufescens*), white-crowned sparrow (*Zonotrichia leucophrys*), wrenit (*Chondestes fasciata*), house finch (*Haemorrhous mexicanus*), and cedar waxwing (*Bombicilla cedrorum*). Dozens of variable checkerspot (*Euphydryas chalcedona*) larvae, several pupae, and one adult variable checkerspot butterfly were observed within the study area. Two native bumblebee (*Bombus sp.*) were also observed.

Due to the low density of native species, special status species were not found and are not expected to occur within the survey area.

Special Status Wildlife Species Summary

No special status species were observed within the survey area or in areas directly or indirectly affected by the project. Table 3, below, shows all special status species that have been recorded in the San Francisco South and six surrounding 7.5' USGS topographic quadrangles (CNDDDB 2022). Exclusively aquatic and/or marine species were not included in this table as the study area does not include any fresh or salt waterbodies or water sources. A determination on the potential for each species to occur in the survey area is also provided in Appendix B. Figure 4 shows the mapped locations of special status wildlife within three miles of the property.

Two special status wildlife species were identified as having a moderate potential to occur in the survey area based on habitat types and/or recorded observations near the study area. The Cooper's hawk (*Accipiter cooperii*) and northern harrier (*Circus cyaneus*) have moderate potential to forage on the site, though suitable nesting habitat is not present.

Nine wildlife species were identified as having a low potential for occurrence in the survey area. These include five mammal species, Townsend's big eared bat (*Corynorhinus townsendii*), western red bat (*Lasiurus blossevillei*), pallid bat (*Antrozous pallidus*), hoary bat (*Lasiurus cinereus*), and fringed myotis (*Myotis thysanodes*), three bird species, white-tailed kite (*Elanus leucurus*), merlin (*Falco columbarius*), American peregrine falcon (*Falco peregrinus anatum*), and one invertebrate species, the monarch butterfly (*Danaus plexippus*) has low potential for occurrence

The project site is located approximately a quarter mile north of designated Critical Habitat for the Bay Checkerspot butterfly (*Euphydryas editha bayensis*), (USFWS, 2021). There is no potential habitat on the project site to support this species.

The site visit and biological survey for the parcels and study area was conducted in April 2022, a suitable time for any butterfly host species with potential for presence to be visible during the field survey.

The presence of non-native dominant and disturbed habitats within the study area limits the potential for special status species to be found within the parcels and surrounding area.

Special Status Plant Species Summary

Five special status plant species were determined to have low potential to occur in the survey area. These species include: San Francisco gumplant (*Grindelia hirsutula* var. *maritima*), Diablo helianthella (*Helianthella castanea*), coast iris (*Iris longipetala*), Scouler's catchfly (*Silene scouleri* ssp. *scouleri*), and San Francisco campion (*Silene verecunda* ssp. *verecunda*).

A determination of no potential was given for one or more of the following reasons:

- The species has a perennial life form and was not observed within the study area during the site visits.
- The species is known to occur on San Bruno Mountain, but is associated with different soil types or plant communities than were recorded within the survey area.
- There is a recorded occurrence on San Bruno Mountain or nearby, but all records are historical (over 50 years old), and the species has not been recorded since.

Figure 5 shows the mapped locations of special status plants within three miles of the property. Each of these species were evaluated for their potential to occur within the survey area (Appendix B). The site visit and biological survey for the parcels and study area was conducted in April 2022, a suitable time for the many of the special status plant species with potential for presence to be visible during the field survey.

Definitions of Special Status Species

Appendix 1 provides definitions of the types of special status species that have federal, state or local protection and provides more information on the regulations that protect birds' nests.

Migratory Birds and Nesting Birds

Habitat suitable for nests of birds protected under the Migratory Bird Treaty Act does exist within the survey area. Shrub and woodland habitats within the survey area are appropriate for nesting birds, including corvids and raptors.

If any new disturbance of the site is to occur during the nesting bird season (Feb. 1 – August 31), a nesting bird survey is recommended prior to any disturbance to determine if there is any nesting bird activity within the survey area.

Roosting Bats

While certain bat species have potential to forage within the parcels and study area, these species do not have potential to roost within the parcels (though they could roost in the Eucalyptus trees within the study area, outside of the parcel boundaries). No maternity colonies or roost sites were found, or are expected to be found within the parcel boundaries.

Protected Trees

The City of Brisbane Municipal Code defines protected trees as “any California Bay (*Umbellularia californica*), Coast Live Oak (*Quercus agrifolia*), or California Buckeye (*Aesculus californica*) having a main stem or trunk which measures thirty (30) inches or greater in circumference at a height of twenty-four (24) inches above natural grade (City of Brisbane, 2022).” A circumference of 30 inches translates to approximately 9.5 inches in diameter.

The City of Brisbane Municipal Code further defines protected trees as: “Three (3) or more mature trees of any one or more non-invasive species that are proposed to be removed from the same property or from adjacent property under common ownership.”

No mature trees or trees protected by species are present on the parcels surveyed. There are a number of non-native eucalyptus trees within the survey area adjacent to the property, but they will not be impacted by the proposed project. Appendix 1 provides further background on protected trees.

Table 3: Observed Species Table

Species Observed		
Scientific Name	Common Name	Native
<i>Agapanthus sp.</i>	Lily of the Nile	No
<i>Aira caryophyllaea</i>	Silver hair grass	No
<i>Anthriscus caucalis</i>	Bur-chervil	No
<i>Avena barbata</i>	Slender oat	No
<i>Briza maxima</i>	Rattlesnake grass	No
<i>Briza minor</i>	Little quaking grass	No
<i>Bromus diandrus</i>	Ripgut brome	No
<i>Bromus hordeaceus</i>	Soft chess	No
<i>Cardamine oligosperma</i>	Bitter cress	Yes
<i>Carduus pycnocephalus</i>	Italian thistle	No
<i>Centranthus ruber</i>	Red valerian	No
<i>Claytonia perfoliata</i>	Miner's lettuce	Yes
<i>Dittrichia graveolens</i>	Stinkwort	No
<i>Dryopteris arguta</i>	California wood fern	Yes
<i>Ehrharta erecta</i>	Panic veldtgrass	No
<i>Epilobium brachycarpum</i>	Willow herb	Yes

<i>Epilobium ciliatum</i>	Slender willow herb	Yes
<i>Eschscholzia californica</i>	California poppy	Yes
<i>Festuca bromoides</i>	Brome fescue	No
<i>Foeniculum vulgare</i>	Fennel	No
<i>Fumaria sp.</i>	Fumitory	No
<i>Genista monspessulana</i>	French broom	No
<i>Geranium dissectum</i>	Cutleaf geranium	No
<i>Helminthotheca echioides</i>	Prickly ox-tongue	No
<i>Heteromeles arbutifolia</i>	Toyon	Yes
<i>Hirschfeldia incana</i>	Summer mustard	No
<i>Medicago polymorpha</i>	Bur clover	No
<i>Oxalis pes-caprae</i>	Bermuda buttercup	No
<i>Pentagramma triangularis</i>	Goldenback fern	Yes
<i>Polypodium californicum</i>	California polypody	Yes
<i>Pteridium aquilinum</i>	Bracken fern	Yes
<i>Prunus cerasifera</i>	Cherry plum	No
<i>Rubus armeniacus</i>	Himalayan blackberry	No
<i>Scrophularia californica</i>	California figwort	Yes
<i>Scabiosa atropurpurea</i>	Mourningbride	No
<i>Senecio glomeratus</i>	Cutleaf burnweed	No
<i>Solanum douglasii</i>	Douglas' nightshade	Yes
<i>Sonchus oleraceus</i>	Common sow thistle	No
<i>Stellaria media</i>	Chickweed	No
<i>Toxicodendron diversilobum</i>	Poison oak	Yes
<i>Vicia sativa</i>	Spring vetch	No
ANIMALS		
Birds		
<i>Aphelocoma californica</i>	California scrub-jay	Yes
<i>Bombycilla cedrorum</i>	Cedar waxwing	Yes
<i>Buteo jamaicensis</i>	Red-tailed hawk	Yes
<i>Chanea fasciata</i>	Wrentit	Yes
<i>Corvus corvax</i>	Common raven	Yes
<i>Haemorhous mexicanus</i>	House finch	Yes
<i>Melospiza crissalis</i>	California towhee	Yes
<i>Poecile rufescens</i>	Chestnut-backed chickadee	Yes
<i>Zonotrichia leucophrys</i>	White-crowned sparrow	Yes
Mammals		
<i>Sylvilagus bachmani</i>	Brush rabbit	Yes
Insects		
<i>Euphydryas chalcedona</i>	Variable checkerspot	Yes
<i>Bombus sp.</i>	Bumblebee	Yes





Figure 4: CNDDDB Occurrence Map (Animals)

3708 Bayshore Blvd, Brisbane, CA

Source: CNDDDB, 5/2022

Service Layer Credits: Sources: Esri, HERE, Garmin, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), swisstopo, © OpenStreetMap contributors, and the GIS User Community



*Species with protected records not shown on map





Figure 5: CNDDDB Occurrence Map (Plants)

3708 Bayshore Blvd, Brisbane, CA

Source: CNDDDB, 5/2022

Service Layer Credits: Sources: Esri, HERE, Garmin, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), swisstopo, © OpenStreetMap contributors, and the GIS User Community



Special Status Wildlife Species Accounts

Cooper's Hawk (*Accipiter cooperii*)

The Cooper's hawk is included on the Special Animal List maintained by the California Department of Fish and Wildlife and is included on the Department's Watch List (CDFW, 2020). Their range extends across the contiguous United States into southern Canada and Mexico and is distributed throughout most of California (Curtis et al., 2006). The species inhabits dense stands of oak woodlands, riparian deciduous forests, or other forest habitats often near water and suburban areas (Baicich & Harrison, 2005). This woodland raptor hunts in broken woodlands, along forest edges and suburban areas for medium-sized birds and mammals (Curtis et al., 2006). Typical nest site selection is characterized by mature trees with significant canopy cover; although, species will nest in suburban areas in a variety of trees. Breeding begins in April; the Cooper's hawk is a single-brooded species (Baicich & Harrison, 2005).

While nesting habitat for this species within the study area is marginal, there is appropriate foraging habitat present. There is moderate potential for this species to be found within the study area.

Northern Harrier (*Circus cyaneus*)

The northern harrier is designated as a California Species of Special Concern by CDFW (CDFW 2022). It inhabits both freshwater and saltwater marshes and adjacent upland grasslands and nests on the ground in tall grasses in grasslands and meadows. Breeding begins in March with a single brood produced per nesting season (Baicich & Harrison 2005).

This species has moderate potential to be found in the survey area. Low quality foraging habitat is present within the study area, which is adjacent to the Brisbane lagoon. No nesting habitat for this species is present within the study area.

Pallid bat (*Antrozus pallidus*)

The Pallid bat is a California Species of Special Concern (CDFW, 2022), and a U.S. Forest Service and Bureau of Land Management Sensitive Species. The pallid bat is found in a variety of habitats where suitable roosting sites are available, including oak savanna, grassland, riparian areas and wetlands, orchards, vineyards, and irrigated cropland (WBWG, 2022). A very social bat, the pallid bat occupies a wide variety of habitats throughout California, including grasslands, shrublands, woodlands, and forests. The species is most common in open, dry areas with rocky areas necessary for roosting. It feeds on a variety of insects and arachnids.

The pallid bat has not been observed in the region in several decades. There is low potential for pallid bats to forage within the study area. Roosting habitat is not present.

Hoary bat (*Lasiurus cinereus*)

Hoary bat is considered a bat of medium priority by the Western Bat Working Group (WBWG, 2022). Hoary bats are ubiquitous throughout California. They are solitary foliage roosters that will use evergreen and deciduous trees near the ends of the branches (WBWG, 2022). They may

forage in small to large groups and primarily feed on moths; however, they will eat a variety of insects if available.

There are limited roosting sites and foraging habitat for hoary bat in the survey area. There is low potential for hoary to be present on the parcel. This species does not breed in the San Francisco Bay area.

Fringed myotis (*Myotis thysanodes*)

Fringed myotis is included on the Special Animal List maintained by the California Department of Fish and Wildlife and is included on the Department's Watch list (CDFW, 2022) and is considered a bat of high priority by the Western Bat Group (WBWG, 2022). Fringed myotis range across the western United States, north into British Columbia, Canada and south to Chiapas, Mexico. It is found in a wide variety of habitats from desert scrub, to mesic coniferous forest, grasslands and sage-grass steppe (WBWG, 2021). Fringed myotis roost in building crevices, underground mines, rocks, cliff faces, and bridges, as well in large tree snags. They primarily feed on moths and beetles, but will glean prey such as spiders, harvestmen, and crickets as well.

The survey area provides appropriate foraging habitat for the fringed myotis. There are no potential roosting sites for this species within the survey area. There is low potential for fringed myotis to be found on site.

Townsend's big-eared bat (*Corynorhinus townsendii*)

The Townsend's big-eared bat is listed as high priority by the Western Bat Working Group (WBWG, 2022). It is found throughout California in a wide variety of habitats, although it is most common in mesic sites. The Townsend's big-eared bat is a cave rooster and moth specialist. It inhabits caves and mines, but may also use bridges, buildings, rock crevices and tree hollows in coastal lowlands, cultivated valleys and nearby hills characterized by mixed vegetation throughout California below 3,300 meters. It exhibits high site fidelity and is highly sensitive to disturbance. This species forages along edge habitats near water and may travel long distances during foraging bouts. It is a moth specialist with over 90% of its diet composed of lepidopterans.

The survey area provides marginal foraging habitat for the Townsend's big-eared bat. There are no potential roosting sites for this species within the survey area. It has a low potential to be found within the study area.

Western red bat (*Lasiurus blossevillei*)

The western red bat is listed as high priority by the Western Bat Working Group (WBWG, 2022). It is found throughout California, except the Great Basin region. Primarily a riparian obligate species, it is easily distinguished from other bats by its red fur. Roosting typically occurs individually in dense clumps of tree foliage in riparian areas, especially willows, cottonwoods and sycamores, and within orchards and suburban areas in trees and shrubs. Roosts are often

hidden from view and only access from below). Primarily a moth specialist, but will forage for other insects as well.

There is appropriate roosting and foraging habitat for the western red bat within the study area. It has low potential to be found on the site as there are no riparian habitats within the immediate area.

White-tailed Kite (*Elanus leucurus*)

The white-tailed kite nesting sites are designated as fully protected by §3511 of the California Fish and Game Code. This species receives additional protection under the Migratory Bird Treaty Act (MBTA) and Migratory Bird Treaty Reform Act (MBTRA). White-tailed kites inhabit open grasslands and savannahs. They breed in a variety of habitats including grasslands, cultivated fields, oak woodlands and suburban areas where prey is abundant. Nests are typically built in trees near a water source and may occur in suburban areas with adjacent open areas with abundant prey. Breeding occurs between February and July, and may be double-brooded in some years (Baicich and Harrison 2005). During the non-breeding season, white-tailed kites may hang out communally at roost sites. Species occurs throughout California west of the Sierra Nevada and is more commonly seen in the Central Valley and among the foothills. White-tailed kites prey on small mammals, reptiles and occasionally, birds. This species has moderate potential to be found on site.

The survey area contains marginal foraging habitat for this species. It has low potential to occur on site.

Merlin (*Falco columbarius*)

The merlin is included on the Special Animal List maintained by the California Department of Fish and Wildlife and is included on the Department's Watch List (CDFW 2022). Merlins winter throughout California, breeds in forests and prairies in northern states, Canada and Alaska (Baicich & Harrison 2005, Warkentin et al. 2005). Wintering habitat included open forests, grasslands, agricultural fields, mud flats and urban areas. Prey consists predominantly of small to medium-sized birds, but also known to take dragonflies (Warkentin et al. 2005). Breeding begins in May and is single-brooded (Baicich & Harrison 2005).

Limited foraging habitat exists within the study area. This species is not known to nest in California. The merlin has low potential to be found within the study area.

American Peregrine Falcon (*Falco peregrinus anatum*)

The American peregrine falcon (nesting) is a federally recovered and was delisted in 1999. It is also state listed as Endangered, is a California fully protected species and included on the USFWS Birds of Conservation Concern list (2002). The American peregrine falcon is also protected under the Migratory Bird Treaty Act (16 U.S.C. 703-712; MBTA) and Migratory Bird Treaty Reform Act (Division E, Title I, Section 143 of the Consolidated Appropriations Act, 2005, PL 108-447; MBTRA). Peregrine falcons are a year-round resident in California and are most common along the coast. They inhabit a variety of habitats ranging from wetland, coastal

shorelines and islands to deserts, forests and urban areas (White et al. 2002). American peregrine falcons nest on cliffs, rocky outcrops, bare ground and man-made structures such as bridges, buildings and other tall, prominent structures (Baicich and Harrison 2005). Breeding begins from mid-March to mid-May depending on latitude, is single-brooded and exhibits high site fidelity (Baicich and Harrison 2005). They have a variable diet and feed primarily on birds; however, they may also consume many small mammals including bats and various rodents.

While suitable breeding habitat for this species is not present within the study area, this species may use the study area for foraging. The American peregrine falcon has low potential to be found within the study area.

Monarch butterfly (*Danaus plexippus*)

Monarch butterflies require wind protected tree groves along the California coast for nectaring, migratory roosting, and wintering sites. Roosting sites are also located in isolated locations bordering San Francisco Bay. Blue gum eucalyptus is commonly used by monarch butterflies as nectaring and roosting sites. Monterey pine (*Pinus radiata*) and Monterey cypress (*Cupressus macrocarpa*) groves may also provide roosting habitat for monarch butterflies. They prefer to nectar on *Asclepias* flowers as adults; some species within the aster family (*Asteraceae*) are also used.

There is marginal roosting habitat within the eucalyptus trees in the study area. Coyote brush could be used as a nectar plant.

Mission Blue Butterfly (*Icaricia icarioides missionensis*)

The mission blue butterfly is federally listed as endangered (CDFW, 2022; USFWS, 1999). It is a small butterfly measuring 1 to 1.3 inches across. The larval host plants include three species of lupine (*Lupinus albifrons* var. *collinus*, *L. formosus* var. *formosus* and *L. variicolor*). Adult nectar plants include California Phacelia (*Phacelia californica*), bluedicks (*Dichelostemma capitatum*), golden aster (*Heterotheca villosa*), seaside buckwheat (*Eriogonum latifolium*), and a variety of native and nonnative thistles (TRA, 1982). Mission blue butterflies are found in grassland habitats and utilize roadcuts and rocky outcrops with good sun exposure. Mission blue butterflies are relatively weak flyers and have been recorded to move approximately 0.25 miles between habitat patches. The flight season occurs from March through July. Remaining populations are restricted to the Marin headlands in Marin County, Twin Peaks in San Francisco County, and Milagra Ridge, San Bruno Mountain and Crystal Springs Watershed in San Mateo County.

No host or nectar plants were detected in the survey area during the site visit. This species has no potential to occur within the parcels.

Callippe Silverspot Butterfly (*Speyeria callippe callippe*)

The Callippe silverspot butterfly, also known as the callippe fritillary, is federally listed as endangered (CDFW, 2022). It is a medium-sized butterfly with a wingspan of 2 inches in the Nymphalidae or brush-footed family. The dorsal surface of the wings is brown with black spots

and lines. The Callippe silverspot is found in grasslands in the vicinity of its larval host plant, Johnny-jump-up (*Viola pedunculata*). Hilltops provide important habitat for mate selection. Adult nectar plants include nonnative species such as Italian thistle, pin-cushion plant (*Scabiosa purpurea*), and native species such as California buckeye (*Aesculus californica*). Callippe silverspots are relatively strong flyers that range as far as 0.75 miles between habitat patches (TRA, 1982). The adult flight period occurs from May to July.

No host or nectar plants were detected in the survey area during the site visit. This species has no potential to occur within the parcels.

Bay Checkerspot Butterfly (*Euphydryas editha bayensis*)

The bay checkerspot butterfly is federally listed as threatened (CDFW 2022, USFWS 1999) and is designated as critically imperiled by the Xerces Society's Red List of Pollinator Insects of North America (Shepherd et al. 2005). It is a medium-sized butterfly, *i.e.* 2-inch wingspan, with a brown base color and distinct red, yellow and white checkered pattern forming rows separated by black bands. The bay checkerspot is a member of the Nymphalidae or brush-footed family. It is endemic to California and restricted to serpentinic (or serpentine-derived) soils and similar habitats. Its primary larval host plant is the dwarf plantain (*Plantago erecta*) (Steiner 1990). Secondary host plants include the Indian paintbrush (*Castilleja affinis* ssp. *affinis*) and purple owl's clover (*Castilleja exserta* ssp. *exserta*). The adult flight life stage lasts approximately 10 days and occurs between February and May. Eggs are laid in small masses numbering up to 250, which are deposited at the base *P. erecta* or *C. affinis* (Black and Vaughan 2005). Eggs hatch in approximately ten days and feed on the host plant for a few weeks prior to entering diapause in nearby soil cracks or under rocks until the following spring (Black and Vaughan 2005). Current populations are restricted to five locales in San Mateo (Edgewood County Park & Jasper Ridge) and Santa Clara (Coyote Ridge comprising Kirby, Metcalf, San Felipe and Silver Creek Hills) counties (USFWS 2001b).

Critical Habitat for this species includes San Bruno Mountain. In 2017, this species was reintroduced to San Bruno Mountain. No host or nectar plants were detected in the survey area during the site visit. This species has no potential to occur within the parcels or study area.

Special Status Plants Species Accounts

The following special status plant species accounts are informed largely by the 2015 Rare, Threatened and Endangered Plant Survey: San Bruno Mountain by L. Naumovich, and C. Niederer.

San Francisco gumplant (*Grindelia hirsutula* var. *maritima*) CNPS RPR 3.2, S1, G5T1Q, locally significant rank A1. San Francisco gumplant is a perennial herb belonging to the sunflower family (Asteraceae), endemically restricted to north and central coastal bioregions at elevations 15-400 meters. San Francisco is the type locality for *Grindelia hirsutula*. Plants can grow 8-60" tall (0.2-1.5 m) with the hemispheric and gummy inflorescence and yellow corolla typical of the

genus, sometimes a subshrub. Note that identification is difficult for this taxon currently under taxonomic review. Best diagnostic feature for this species as it differs from *Grindelia camporum* are a notable reddish stem color along entire stem, and lack of both the shiny appearance to leaves and the spiny, glabrous inflorescence head with reflexed phyllaries as are typical of *G. camporum*. Also, best features to discern this species from *G. hirsutula* are erect phyllaries, large involucre, and fruit is generally golden or greyish and deeply ridged. Preferred habitats include coastal bluff, coastal bluff scrub and sea bluffs, but also grasslands and sandy, clay, or serpentine slopes. Blooming period is Jun-Sep, but typically starts to flower in June, which is an important characteristic for identification. Statewide, *G. hirsutula* tends to flower earlier than *G. camporum* at a given location; however, this detail needs review for local accuracy, because the opposite sequence may occur locally to San Bruno Mountain or just for this taxon. This species is threatened by coastal development and non-native plants.

San Francisco gumplant is present in nearby San Bruno Mountain and based on habitat requirements has low potential to be present within the survey area.

Diablo helianthella (*Helianthella castanea*) CNPS RPR 1B.2, G2, S2, locally significant rank A1. Diablo helianthella is a perennial herb in the sunflower family (Asteraceae). Endemic to the northern central coast and northern San Francisco Bay Area bioregions, this taxon can be found in a variety of preferred habitat types at elevations of 25- 1150 meters but is rare and restricted to the East Bay. The geographic exception is this one locally extant occurrence on San Bruno Mountain. Here, its preferred habitat is rocky soils on north-facing slopes or otherwise shady areas within or nearby ecotones between grassland and coastal scrub, chaparral, or oak woodland. Plants grow 3-20" (0.1-0.5 m) with a taproot. Often difficult to distinguish individuals from dense clumps of vegetation. Also, often difficult to distinguish from *Helianthella californica* and *Wyethia* sp. Best discernable features are this taxon's phyllaries of irregular lengths especially at peak bloom, and phyllaries that extend beyond the corolla have a leaf-like appearance. Later, glabrous fruits appear flattened with thick central bulge or ridge, thin edges, and a notch at the apex. Blooming period is Mar-Jun locally. Threatened by urbanization, grazing, and fire suppression, and possibly threatened by road maintenance, recreational activities, and non-native plants.

Diablo helianthella is present in nearby San Bruno Mountain and based on habitat requirements has low potential to be present within the survey area.

Scouler's catchfly (*Silene scouleri* ssp. *scouleri*) CNPS RPR 2B.2, S2S3, G5T5, locally significant rank A2. Scouler's catchfly, also known as simple campion, is a perennial herb in the pink family (Caryophyllaceae). It is endemic and rare in California's coastal range and San Francisco Bay Area bioregions, also found elsewhere and limited to Western North America. Plants grow 5-27 inches (15-70 cm) tall with a distinctive puberulent (wooly) stem. Corolla color varies from white to rose, and the calyx contains 10 veins that are approximately the same width throughout. Preferred habitats include northern coastal scrub, valley and foothill grassland, rocky slopes and coastal bluffs less than 300 meters in elevation. Blooming period can range

from Mar- Sep, but generally blooms in the summer months. Potentially threatened by habitat loss, foot traffic, and recreational activities; possibly threatened by herbivory.

Scouler's catchfly has been previously documented on San Bruno Mountain, was observed in the survey area during 2018 surveys and is present.

San Francisco campion (*Silene verecunda* ssp. *verecunda*) CNPS RPR 1B.2, S1, G5T1, locally significant rank A1. San Francisco campion is a perennial herb in the pink family (Caryophyllaceae), endemically restricted to northern central coast and northern San Francisco Bay Area bioregions at elevations 30-645 meters. San Francisco is the type locality for *Silene verecunda*. Plants can grow 3-22" (0.1-0.6) in height, stem may or may not branch or be glandular, and corolla color varies from white to lavender. Note that identification is difficult for this taxon currently under taxonomic review. Usual blooming period is Mar-Jun and can extend as far as Feb-Aug but typically blooms in summer. At San Bruno Mountain this taxon was found flowering in March and April, possibly an important characteristic versus the larger *Silene scouleri*. Preferred habitat includes chaparral, coastal bluff scrub, coastal prairie, coastal scrub, valley and foothill grassland, mudstone or shale, and sandy or ultramafic soils. This species is threatened by development, recreational activities, and non-native plants.

San Francisco campion is present in nearby San Bruno Mountain and based on habitat requirements has low potential to be present within the survey area.

Coast iris (*Iris longipetala*) CNPS RPR 4.2, S3, G3, locally significant rank B. Coast iris is a perennial rhizomatous monocot herb in the Iris family (Iridaceae) and endemic to the bioregions of the North and Central Coast and San Francisco Bay Area at elevations 0-600 meters. Plants grow 12-24" (30-60cm) tall with funnel-shaped corollas that are blue-lilac-purple in color with dark veins. Blooming period is Mar-May. Best distinguishing characteristics of this taxon are light green leaves that are similar on both sides and generally lacking any difference in hue found in co-occurring *I. douglasiana*. Preferred habitat includes coastal prairie, lower montane coniferous/ mixed evergreen (coastal) forest, and meadows and seeps. Typically occurs in wetter areas although can occur in xeric sites because deep rhizomes can access subsurface water. Coast iris is considered locally abundant on San Bruno Mountain. Considered rare overall although many collections are old thus generally more field surveys are recommended, and it may hybridize with *I. missouriensis*. This species is threatened by development.

Coast iris is present in nearby San Bruno Mountain and based on habitat requirements has low potential to be present within the survey area.

3.3 Wildlife Movement and Connectivity

Wildlife Movement or Connectivity features, or evidence thereof, were not found within the survey area(s).

Wildlife corridors are important for conservation of wildlife in the region. Linkages between habitat types can extend for miles between primary habitat areas and occur on a large scale throughout California. Habitat linkages facilitate movement between populations located in discrete areas and populations located within larger habitat areas. Even where patches of pristine habitat are fragmented, wildlife movement between populations is facilitated through habitat linkages, migration corridors and movement corridors. Wildlife movement includes migration (i.e., usually one direction per season), inter-population movement (i.e., long-term genetic exchange) and small travel pathways (i.e., daily movement within an animal's home range).

The property is situated within an urban-disturbed wildland zone adjacent to existing development along Bayshore Boulevard to the east and limited open space to the north, south, and west. There are likely common and opportunistic wildlife species that are adapted to this urban interface and may be present in the area. These species include raccoon, striped skunk, coyote, eastern fox squirrel, as well as various bat and bird species.

The planned project would not involve any impacts to wildlife habitat within the parcels and is not expected to adversely affect any existing regular movement of wildlife within the parcels. The proposed project will affect the area just north of the parcels via the expansion of the construction lot. This may result in a less than significant loss of habitat within the north portion of the study area and could affect the movement of wildlife species located in the immediate area.

Section 4: Recommended Impact Assessment and Conditions of Approval

4.1 Sufficiency of Biological Data

Surveys for this biological assessment yielded detailed information about natural resources potentially present in the survey area. This documentation revealed that several special status species have low to moderate potential to occur within the survey area. No sensitive natural communities or critical habitats are present within the survey area.

4.2 Impacts and Conditions of Approval

There is no currently proposed project for the parcels being evaluated in this Biological Assessment Report. There is a proposed project for the adjacent parcel to the north being implemented by the same client, MK Pipelines, Inc. No significant impacts to special-status plants and animals, and/or sensitive natural communities are expected within the project parcels, as discussed below.

Conditions of Approval described below (CA-1) include recommendations to avoid impacts to nesting birds including raptors.

Special Status Raptors and Nesting Birds

Raptors

There is low to moderate potential for special status raptors to forage on site such as Cooper's hawk, northern harrier, and white-tailed kite.

Project implementation would not result in any impacts to potential foraging habitat for special status raptor species within the parcels.

Significance Finding – Project Impacts: No Impact.

Significance Finding – Cumulative Impacts: No Impact.

Nesting Birds

Suitable habitat for nesting birds exists within the project site and survey area. There is potential for birds protected by the federal Migratory Bird Treaty Act to nest within the eucalyptus trees and French broom scrub. Project implementation would not result in any impacts to potential foraging or nesting habitat for native bird species protected by the Migratory Bird Treaty Act and CA Fish and Game Code. Since the MK Pipelines, Inc construction yard is currently used by the company for equipment staging and as an office site, anticipated construction in the adjacent lot is unlikely to result in any additional disturbance to nesting

birds within the parcels being evaluated. Should impacts to nesting habitat become necessary, the measures outlined in CA-1 should be implemented.

Significance Finding – Project Impacts: Less than Significant

Significance Finding – Cumulative Impacts: No Impact

Conditions of Approval 1 (CA-1): Protection of Nesting Birds, Including Raptors

CA-1a: Avoidance of Nesting Birds including Raptors. If feasible, vegetation removal and ground disturbance should be conducted outside of the nesting bird season which runs from approximately February 1 to August 31.

CA-1b: Pre-Construction Nesting Bird Surveys including Raptors. If removal of vegetation is to occur during the nesting season (February 1 to August 31), it is recommended that surveys for nesting birds (including special status raptors) be conducted prior to any vegetation removal by a qualified biologist. Surveys should be conducted no more than one week (seven days) prior to vegetation removal or ground disturbance. If active nests are found, vegetation removal should only be conducted after the young have left the nest and the nest is no longer considered active (i.e., in use).

CA-1c: Implementation of Nesting Bird Buffer Zones. If active nests are found within the survey area, suitable buffer zones should be established in consultation with CDFW to ensure nesting birds are not impacted by project activities. A buffer zone of 250' is recommended for raptors, and a buffer of 100' is recommended for passerines and other nesting birds. Buffer zones should be kept in place until nests are determined inactive by a qualified biologist.

Special Status Plants

Significance Finding – Project Impacts: No Impact

Significance Finding – Cumulative Impacts: No Impact

No special status plant species were observed on site or are expected to occur. The project will not cause project-specific or cumulative impacts to special status plant species.

Ecological Communities

Sensitive Plant Communities

Significance Finding – Project Impacts: No Impact

Significance Finding – Cumulative Impacts: No Impact

No sensitive plant communities were observed on site or are expected to occur. The project will not cause project-specific or cumulative impacts to special status plant species.

Waters and Wetlands

Significance Finding – Project Impacts: No Impact

Significance Finding – Cumulative Impacts: No Impact

No state or federal jurisdictional waters or wetlands were observed on site. The project will not cause project-specific or cumulative impacts to waters or wetlands.

Environmentally Sensitive Habitat Areas

Significance Finding – Project Impacts: No Impact

Significance Finding – Cumulative Impacts: No Impact

No Environmentally Sensitive Habitat Areas were observed on site or are expected to occur. The project will not cause project-specific or cumulative impacts to Environmentally Sensitive Habitat Areas.

Habitat Connectivity (Migration Corridors)

Significance Finding – Project Impacts: No Impact

Significance Finding – Cumulative Impacts: No Impact

No migration corridors were observed on site or are expected to occur. The project will not cause project-specific or cumulative impacts to Habitat Connectivity (Migration Corridors).

Protected Trees

Significance Finding – Project Impacts: No Impact

Significance Finding – Cumulative Impacts: No Impact.

No protected trees were observed on site and no trees are expected to be removed as part of the proposed project. If a protected tree as defined by the City of Brisbane Tree Ordinance is to be removed, the applicant must apply for a tree removal permit from the City. Replacement plantings may be required at the discretion of the city.

Section 5. References

Baich, P.J. and C.J.O. Harrison. 2005. Nests, Eggs, and Nestlings of North American Birds. Second Edition. Princeton University Press. Princeton, New Jersey. 347 pp.

Black, S. H., and D. M. Vaughan. 2005. Species Profile: *Euphydryas editha bayensis*. In Shepherd, M. D., D. M. Vaughan, and S. H. Black (Eds).

California Department of Fish and Wildlife (CDFW). 2022. Special Animals. California Natural Diversity Database. Wildlife and Habitat Data Analysis Branch.

<https://nrm.dfg.ca.gov/FileHandler.ashx?DocumentID=109406&inline>

California Department of Fish and Wildlife. 2022. California Natural Diversity Database (CNDDDB) – Government version dated May 2022. Retrieved from <https://map.dfg.ca.gov/rarefind/view/RareFind.aspx>.

California Native Plant Society. Rare Plant Program. 2022. Inventory of Rare and Endangered Plants of California (online edition, v8-03 0.39). Website accessed May 2022. <http://www.rareplants.cnps.org>

California Native Plant Society. 2009. A Manual of California Vegetation.

City of Brisbane. 2020. City of Brisbane General Plan. Updated January 2020. Retrieved May 2022 from <https://www.brisbaneca.org/cd/page/brisbane-general-plan> and <http://planning.smcgov.org/find-my-zoning-parcel-map-and -other-property-info>

City of Brisbane. 2022. City of Brisbane Municipal Code. Updated April 7, 2022. Retrieved May 2022 from https://library.municode.com/ca/brisbane/codes/municipal_code

Curtis, Odette E., R. N. Rosenfield and J. Bielefeldt. 2006. Cooper's Hawk (*Accipiter cooperii*), The Birds of North America Online (A. Poole, Ed.). Ithaca: Cornell Lab of Ornithology; Retrieved from the Birds of North America Online: <http://bna.birds.cornell.edu/bna/species/075>.

Dunk, J. R. 1995. White-tailed Kite (*Elanus leucurus*). In The Birds of North America, No. 178 (A. Poole and F. Gill, eds.). The Academy of Natural Sciences, Philadelphia, and The American Ornithologists' Union, Washington, D.C.

Macwhirter, R. B. and K. L. Bildstein. 1996. Northern Harrier (*Circus cyaneus*). The Birds of North America Online (A. Poole, Ed.). Ithaca: Cornell Lab of Ornithology; Retrieved from the Birds of North America Online: <http://bna.birds.cornell.edu/bna/species/210>.

Naumovich, L. and C. Niederer. 2016. 2015 Rare, Threatened, and Endangered Plant Survey:

San Bruno Mountain. Report for the San Mateo County Parks Department. Creekside Science. Menlo Park, CA

San Mateo County Parks Department, Standards for Biological Studies and Assessments. December 2, 2015.

San Mateo County Parks Department, GIS Biology Map Packet. Hannah Ormshaw. Email communication, December 2, 2020. Consists of mapped resource information for the project site, including: wetlands and waterbodies; wildlife corridors/connectivity areas; vegetation; and high resolution aerial imagery.

Soil Conservation Service, United States Department of Agriculture. 1991. Soil Survey of San Mateo County, Eastern Part, and San Francisco County, California. Retrieved from https://www.nrcs.usda.gov/Internet/FSE_MANUSCRIPTS/california/CA689/0/sanmateo.pdf

Thomas Reid Associates (TRA) 1982. Endangered Species Survey San Bruno Mountain. Biological Study 1980-1981. Prepared for San Mateo County.

U.S. Fish and Wildlife Service (USFWS). 1999. Endangered and Threatened Wildlife and Plants. 50 CFR 17.11 & 17.12. December 31.



U.S. Fish and Wildlife Service. 2022, May. National Wetlands Inventory. Retrieved from <https://www.fws.gov/wetlands/data/Mapper.html>



U.S. Fish and Wildlife Service. 2022. Critical Habitat Online Mapper. Website accessed May 2022. <https://ecos.fws.gov/ecp/report/table/critical-habitat.html>



Warkentin, I. G., N. S. Sodhi, R. H. M. Espie, Alan F. Poole, L. W. Oliphant and P. C. James. 2005. Merlin (*Falco columbarius*), The Birds of North America Online (A. Poole, Ed.). Ithaca: Cornell Lab of Ornithology; Retrieved from the Birds of North America Online: <http://bna.birds.cornell.edu/bna/species/044>.



Western Bat Working Group (WBWG). 2022. Pallid bat (*Antrozous pallidus*), hoary bat (*Lasiurus cinereus*), Townsend's big-eared bat (*Corynorhinus townsendii*), western red bat (*Lasiurus blossevillii*), and fringed myotis (*Myotis thysanodes*). Species Accounts. <http://wbwg.org/western-bat-species/>



Section 6. Photos


Location	
3708 Bayshore Blvd	
Map Key	
P1	
View Direction	
Northeast and downslope.	
Description	
View of parcels from south edge. California figwort, Himalayan blackberry, French broom, and toyon are visible on the hillside. The construction yard and Bayshore Blvd. are in the mid-ground.	
Location	
3708 Bayshore Blvd	
Map Key	
P1	
View Direction	
Northwest	
Description	
View of vegetation on the steep western slopes of the parcel, including Himalayan blackberry, California figwort, French broom, and toyon.	

Location	
3708 Bayshore Blvd	
Map Key	
P2	
View Direction	
West	
Description	
View of the office building and supplies on the construction lot, as well as the steep hillside in the background.	
Location	
3708 Bayshore Blvd	
Map Key	
P2	
View Direction	
North	
Description	
View of the office building on the construction lot, and the paved asphalt parking area.	

Location	
3708 Bayshore Blvd	
Map Key	
P3	
View Direction	
South southeast	
Description	
View of the MK Pipelines, Inc construction lot on the right, and the non-native oat grassland and Bayshore Blvd on the left.	
Location	
3708 Bayshore Blvd	
Map Key	
P3	
View Direction	
Southwest	
Description	
View of the driveway to the parcels/ the MK Pipelines, Inc construction lot in the foreground, with the steep vegetated slope in the background.	

Location	
3708 Bayshore Blvd	
Map Key	
P4	
View Direction	
South southeast	
Description	View of the MK Pipelines, Inc construction lot, and office building, with the vegetated slope in the background, including the eucalyptus grove located within the study area but outside the parcels.
Location	
3708 Bayshore Blvd	
Map Key	
P4	
View Direction	
West southwest	
Description	View of the construction lot, storage materials, and the vegetated slope on the western portion of the parcels. French broom is the dominant vegetation.

Location	
3708 Bayshore Blvd	
Map Key	
P4	
View Direction	
West	
Description	
View of construction lot, and vegetated slope on the west and northwest portions of the parcels and study area.	
Location	
3708 Bayshore Blvd	
Map Key	
P5	
View Direction	
East and downslope.	
Description	
View of the western portion of the study area and site, taken from upslope of the parcels. The Brisbane lagoon and Bayshore Blvd are visible in the background of the photo.	

Location	
3708 Bayshore Blvd	
Map Key	
P5	
View Direction	
Southeast	
Description	
View of the southwestern portion of the study area and site, taken from upslope of the parcels. The Brisbane lagoon and Bayshore Blvd are visible in the background of the photo. Visible vegetation include toyon, coyote brush and French broom.	

P-designation refers to Photopoint locations illustrated on Figure 3. Plant Communities Map.

Appendix A

Summary of Biological Resource Regulations

Sensitive Status Species
Regulations
Migratory Bird Regulations
Plant Community Regulations
Waters and Wetlands Regulations
San Bruno Mountain Habitat Conservation Plan
City of Brisbane General Plan
City of Brisbane Municipal Code

Sensitive Status Species Regulations

Federally Protected Species

San Mateo County is home to several federally listed endangered and threatened plant and wildlife species. The

U.S. Fish and Wildlife Service (USFWS) regulates the protection of federally listed endangered and threatened plant and wildlife species.

FE (Federally Endangered): A species that is in danger of extinction throughout all or a significant portion of its range.

FT (Federally Threatened): A species that is likely to become endangered in the foreseeable future.

FC (Federal Candidate): A species for which USFWS has sufficient information on its biological status and threats to propose it as endangered or threatened under the Endangered Species Act (ESA), but for which development of a proposed listing regulation is precluded by other higher priority listing activities.

FSC (Federal Species of Concern): A species under consideration for listing, for which there is insufficient information to support listing at this time. These species may or may not be listed in the future, and many of these species were formerly recognized as "Category-2 Candidate" species.

The USFWS requires permits for the "take" of any federally listed endangered or threatened species. "Take" is defined by the USFWS as "to harass, harm, pursue, hunt, shoot, wound, kill, trap, capture, or collect, or to attempt to engage in any such conduct; may include significant habitat modification or degradation if it kills or injures wildlife by significantly impairing essential behavioral patterns including breeding, feeding, or sheltering."

The Endangered Species Act (ESA) does not provide statutory protection for candidate species or species of concern, but USFWS encourages conservation efforts to protect these species. USFWS can set up voluntary Candidate Conservation Agreements and Assurances, which provide non-Federal landowners (public and private) with the assurance that if they implement various conservation activities to protect a given candidate species, they will not be subject to additional restrictions if the species becomes listed under the ESA.

State Protected Species

The California Department of Fish and Wildlife (CDFW) regulates the protection of endangered, threatened, and fully protected species listed under the California Endangered Species Act. Some species may be jointly listed under the State and Federal Endangered Species Acts.

SE (California Endangered): A native species or subspecies which is in serious danger of becoming extinct throughout all, or a significant portion, of its range due to one or more causes, including loss of habitat, change in habitat, overexploitation, predation, competition, or disease.

ST (California Threatened): A native species or subspecies that, although not presently threatened with extinction, is likely to become an endangered species in the foreseeable future in the absence of the special protection and management efforts required by this chapter. Any animal determined by the commission as "rare" on or before January 1, 1985, is a "threatened species."

SFP (California Fully Protected Species): This designation originated from the State's initial effort in the 1960's to identify and provide additional protection to those animals that were rare or faced possible extinction. Lists were created for fish, mammals, amphibians, reptiles, and birds. Most fully protected species have also been listed as threatened or endangered species under the more recent endangered species laws and regulations.

SR (California Rare): A species, subspecies, or variety of plant is rare under the Native Plant Protection Act when, although not presently threatened with extinction, it is in such small numbers throughout its range that it may become endangered if its present environment worsens. Animals are no longer listed as rare; all animals listed as rare before 1985 have been listed as threatened.

SSC (California Species of Special Concern): Animals that are not listed under the California Endangered Species Act, but which nonetheless 1) are declining at a rate that could result in listing, or 2) historically occurred in low numbers and known threats to their persistence currently exist.

The CDFW requires permits for the "take" of any State-listed endangered or threatened species. Section 2080 of the Fish and Game Code prohibits "take" of any species that the California Fish and Game Commission determines to be endangered or threatened. "Take" is defined in Section 86 of the Fish and Game Code as "hunt, pursue, catch, capture, or kill, or attempt to hunt, pursue, catch, capture, or kill."

The California Native Plant Protection Act protects endangered and rare plants of California. Section 1908, which regulates plants listed under this act, states: "no person shall import into this state, or take, possess, or sell within this state, except as incident to the possession or sale of the real property on which the plant is growing, any native plant, or any part or product thereof, that the commission determines to be an endangered native plant or rare native plant, except as otherwise provided in this chapter."

Unlike endangered, threatened, and rare species, for which a take permit may be issued, California Fully Protected species may not be taken or possessed at any time and no licenses or permits may be issued for their take except for collecting these species for necessary scientific research and relocation of the bird species for the protection of livestock.

The California Endangered Species Act does not provide statutory protection for California species of special concern, but they should be considered during the environmental review process.

California Rare Plant Ranks (RPR)

Plants with 1A, 1B, 2 or 4 should always be addressed in CEQA documents. Plants with a RPR 3 do not need to be addressed in CEQA documents unless there is sufficient information to demonstrate that a RPR 3 plant meets the criteria to be listed as a RPR 1, 2, or 4.

RPR 1A: Plants presumed to be extinct because they have not been seen or collected in the wild in California for many years. This list includes plants that are both presumed extinct in California, as well as those plants which are presumed extirpated in California. A plant is extinct in California if it no longer occurs in or outside of California. A plant that is extirpated from California has been eliminated from California but may still occur elsewhere in its range.

RPR 1B: Plants that are rare throughout their range with the majority of them endemic to California. Most of the plants of List 1B have declined significantly over the last century.

RPR 2: Plants that are rare throughout their range in California, but are more common beyond the boundaries of California. List 2 recognizes the importance of protecting the geographic range of widespread species.

Plants identified as RPR 1A, 1B, and 2 meet the definitions of Sec. 1901, Chapter 10 (Native Plant Protection Act) or Secs. 2062 and 2067 (California Endangered Species Act) of the California Department of Fish and Game Code, and are eligible for state listing.

RPR 3: A review list for plants for which there is inadequate information to assign them to one of the other lists or to reject them.

RPR 4: A watch list for plants that are of limited distribution in California.

Global and Subnational Rankings

Though not associated directly with legal protections, species have been given a conservation status rank by NatureServe, an international non-profit conservation organization that is the leading source for information about

rare and endangered species and threatened ecosystems. The Ventura County Planning Division considers the following ranks as sensitive for the purposes of CEQA impact assessment (G = Global, S = Subnational or State):

G1 or S1 – Critically Imperiled

G2 or S2 – Imperiled

G3 or S3 - Vulnerable to extirpation or extinction

Migratory Bird Regulations

The Federal Migratory Bird Treaty Act (MBTA) and the California Fish and Game (CFG) Code (3503, 3503.5, 3511, 3513 and 3800) protect most native birds. In addition, the federal and state endangered species acts protect some bird species listed as threatened or endangered. Project-related impacts to birds protected by these regulations would normally occur during the breeding season, because unlike adult birds, eggs and chicks are unable to escape impacts.

The MBTA implements various treaties and conventions between the U.S. and Canada, Japan, Mexico, and Russia for the protection of migratory birds, which occur in two of these countries over the course of one year. The Act maintains that it is unlawful to pursue, hunt, take, capture or kill; attempt to take, capture or kill; possess, offer to or sell, barter, purchase, deliver or cause to be shipped, exported, imported, transported, carried or received any migratory bird, part, nest, egg or product, manufactured or not. Bird species protected under the provisions of the MBTA are identified by the List of Migratory Birds (Title 50 of the Code of Federal Regulations, Section 10.13 as updated by the 1983 American Ornithologists' Union (AOU) Checklist and published supplements through 1995 by the USFWS).

CFG Code 3513 upholds the MBTA by prohibiting any take or possession of birds that are designated by the MBTA as migratory nongame birds except as allowed by federal rules and regulations promulgated pursuant to the MBTA. In addition, there are CFG Codes (3503, 3503.5, 3511, and 3800) which further protect nesting birds and their parts, including passerine birds, raptors, and state "fully protected" birds.

NOTE: These regulations protect almost all *native nesting birds*, not just sensitive status birds.

Plant Community Regulations

Plant communities are provided legal protection when they provide habitat for protected species or when the community is in the coastal zone and qualifies as environmentally sensitive habitat area (ESHA).

Global and Subnational Rankings

Though not associated directly with legal protections, plant communities have been given a conservation status rank by NatureServe, an international non-profit conservation organization that is the leading source for information about rare and endangered species and threatened ecosystems.

The Ventura County Planning Division considers the following ranks as sensitive for the purposes of CEQA impact assessment (G = Global, S = Subnational or State):

- G1 or S1 – Critically Imperiled
- G2 or S2 – Imperiled
- G3 or S3 – Vulnerable to extirpation or extinction

CDFW Rare

Rare natural communities are those communities that are of highly limited distribution. These communities may or may not contain rare, threatened, or endangered species. Though the Native Plant Protection Act and the California Endangered Species Act provide no legal protection to plant communities, CDFW considers plant communities that are ranked G1-G3 or S1-S3 (as defined above) to be rare or sensitive, and therefore these plant communities should be addressed during CEQA review.

Oak Woodlands Protection Act (SB-1334)

The Oak Woodlands Protection Act requires that the County of San Mateo, during the CEQA process, evaluate whether the project will result in the conversion of oak woodlands that will have a significant negative effect on the environment. If the city determines that a significant effect will occur, it will require one or more of the following mitigation measures:

1. Conserve oak woodlands, through the use of conservation easements.
2. Plant an appropriate number of trees, including maintaining plantings and replacing dead or diseased trees.
3. Contribute funds to the Oak Woodlands Conservation Fund, as established under subdivision (a) of Section 1363 of the Fish and Game Code, for the purpose of purchasing oak woodlands conservation easements, as specified under paragraph (1) of subdivision (d) of that section and the guidelines and criteria of the Wildlife Conservation Board. A project applicant that contributes funds under this paragraph shall not receive a grant from the Oak Woodlands Conservation Fund as part of the mitigation for the project.
4. Other mitigation measures developed by the city.

Waters and Wetlands Regulations

Numerous agencies control what can and cannot be done in or around streams and wetlands. If a project affects an area where water flows, ponds or is present even part of the year, it is likely to be regulated by one or more agencies. Many wetland or stream projects will require three main permits or approvals (in addition to CEQA compliance). These are:

- 404 Permit (U.S. Army Corps of Engineers)
- 401 Certification (California Regional Water Quality Control Board)
- Streambed Alteration Agreement (California Department of Fish and Wildlife)

404 Permit (U.S. Army Corps of Engineers)

Most projects that involve streams or wetlands will require a 404 Permit from the U.S. Army Corps of Engineers (USACE). Section 404 of the federal Clean Water Act is the primary federal program regulating activities in wetlands. The Act regulates areas defined as “waters of the United States.” This includes streams, wetlands in or next to streams, areas influenced by tides, navigable waters, lakes, reservoirs and other impoundments. For nontidal waters, USACE jurisdiction extends up to what is referred to as the “ordinary high water mark” as well as to the landward limits of adjacent Corps-defined wetlands, if present. The ordinary high water mark is an identifiable natural line visible on the bank of a

stream or water body that shows the upper limit of typical stream flow or water level. The mark is made from the action of water on the streambank over the course of years.

Permit Triggers: A USACE 404 Permit is triggered by moving (discharging) or placing materials—such as dirt, rock, geotextiles, concrete or culverts—into or within USACE jurisdictional areas. This type of activity is also referred to as a “discharge of dredged or fill material.”

401 Certification (Regional Water Quality Control Board)

If your project requires a USACE 404 Permit, then you will also need a Regional Water Quality Control Board (RWQCB) 401 Certification. The federal Clean Water Act, in Section 401, specifies that states must certify that any activity subject to a permit issued by a federal agency, such as the USACE, meets all state water quality standards. In California, the state and regional water boards are responsible for certification of activities subject to USACE Section 404 Permits.

Permit Trigger: A RWQCB 401 Certification is triggered whenever a USACE 404 Permit is required, or whenever an activity could cause a discharge of dredged or fill material into waters of the U.S. or wetlands.

Streambed Alteration Agreement (California Department of Fish and Wildlife)

If your project includes alteration of the bed, banks or channel of a stream, or the adjacent riparian vegetation, then you may need a Streambed Alteration Agreement from the California Department of Fish and Wildlife (CDFW). The California Fish and Game Code, Sections 1600-1616, regulates activities that would alter the flow, bed, banks, channel or associated riparian areas of a river, stream or lake. The law requires any person, state or local governmental agency or public utility to notify CDFW before beginning an activity that will substantially modify a river, stream or lake.

Permit Triggers: A Streambed Alteration Agreement (SAA) is triggered when a project involves altering a stream or disturbing riparian vegetation, including any of the following activities:

- Substantially obstructing or diverting the natural flow of a river, stream or lake
- Using any material from these areas
- Disposing of waste where it can move into these areas

Some projects that involve routine maintenance may qualify for long-term maintenance agreements from CDFW. Discuss this option with CDFW staff.

San Bruno Mountain Habitat Conservation Plan (HCP)

The project area lies within the Management Unit 2-03-02 of the Brisbane Acres Management Area of the San Bruno Mountain Habitat Conservation Plan. Due to the presence of a number of protected species and habitats, a detailed operating plan exists for the Brisbane Acres area. The entirety of the HCP dealing with the management of Unit 2-03-02 is provided below.

HCP Objectives — Specific Conservation Needs

The HCP objectives for the Brisbane Acres reflects the City's Open Space Plan (OSP) which was drafted by the City of Brisbane Open Space and Ecology Committee and adopted by the Brisbane City Council in 2001. The overall objectives of the OSP are to:

- Identify and prioritize significant natural and open space resource within the City of Brisbane;
- Conduct a thorough inventory of existing open space resources;
- Prepare a map identifying existing open space resources and highlight important resource lands;

- Identify a means for preserving and acquiring open space areas; Develop recommendations for the City Council to adopt and implement an overall open space land preservation program.

The OSP includes the Brisbane Acres as a specific subarea with defined recommendations for preserving open space in the Acres. The following is a list of the recommended selection criteria for acquiring open space parcels in the Brisbane Acres:

- Parcels that are either not adjacent to existing development or are only adjacent on one side of the parcel
- Parcels are contiguous to San Bruno Mountain County Park
- Parcels contain intact native vegetation
- Parcels contain significant watercourses or wetlands
- Parcels contain habitat for the endangered butterflies
- Parcels would be appropriate locations for trail corridor

The OSP includes maps that shows what parcels in the Acres contain one or more of the significant resources identified in the selection criteria. The OSP relies on private property owners:

- 1) Donate land to the City as a tax write-off
- 2) Dedicate land as mitigation for development
- 3) Willingly selling the land to the City at fair market value or at a “bargain sale” which provide the landowners with a tax write-off
- 4) Use the City’s Density Transfer Ordinance to transfer development rights to property owners/parcels in areas of the City that are not constrained for development.

The OSP recommends that the City:

- 1) Review development parcels in the Acres for the presence of significant natural resource and guide development plans to protect the resources;
- 2) Require the dedication of open space easements to protect critical resources on parcels that are granted for development approvals
- 3) Pursue purchasing open space lands from willing sellers
- 4) Accept dedications of open space lands
- 5) Actively seek state, federal and private grants for acquisition of parcels with high resource values
- 6) To work with the HCP operator to preserve butterfly habitat in the Acres.

Operating Program for Management Units 2-03-01 and 2-03-02

2-03-02: This Management Unit is adjacent to county parklands and the South Slope Administrative Parcel. Of the two Brisbane Acres Management Units, this one is utilized by the butterflies of concern to a greater extent and contains the habitat or rare, endemic and range limit plants.

Obligations: Landowners have the following obligations:

1. Unless development is proposed, this area should be left in its natural state and protected from vandalism as necessary.
2. If development is planned for property within this area, a new Management Unit shall be designated, for which a separate Operating Program shall be approved. That Operating Program shall comply with mitigation measures set forth in Section 4, below.
3. As applicable, landowners shall participate in the regulatory provisions and Funding Program of this HCP.

4. Prior to any grading and/or development project and/or the removal or damage of or use of pesticides on vegetation in excess of 500 square feet in any calendar year in the Brisbane Acres:
 - a. An environmental assessment must be prepared. Any such environmental assessment must describe the impacts on habitat of the Mission blue and Callippe Silverspot and must discuss mitigation measures. Notice of development and/or grading proposals and copies of all environmental documents must be sent to the California State Department of Fish and Game, the U.S. Fish and Wildlife Service and the Plan Operator (properties acquired by the City of Brisbane as open space within this management unit may be added to Management Unit 2-03-18 only to the approval of the Plan Operator), and
 - b. The Landowner must demonstrate that approval of the grading and/or development proposal is consistent with protecting 40% of the Brisbane Acres as Conserved Habitat.
- (1) All Landowners shall demonstrate consistency through all of the following mitigation measures:
 - (a) Imposition of landscaping restrictions on undeveloped portions of sites to require removal of invasive species and to retain natural vegetation and to prohibit the planting of invasive species on portions to be developed
 - (b) Reclamation plans for temporarily disturbed areas
 - (c) Payment of a mitigation fee to the City for habitat acquisition. The fee shall be computed by multiplying the "Mitigation Fee Land Area" by the "Mitigation Fee Market Value." As used herein, the "Mitigation Fee Land Area" shall mean 40% of the square footage of the entire property, reduced by the square footage of any land, on or off site, having demonstrated value as habitat for species of concern, which is permanently protected by the Landowner as habitat. Any off site land should be within one of the two management units (2-03-01 and 2-03-02). As used herein, the term "Mitigation Fee Market Value" shall mean the highest or most recent per square foot sales price, whichever is greater, of land within Administrative Parcel 2-03-02 purchased by the City of Brisbane or sold through private transactions, as adjusted for inflation since the date of purchase using the same index applied to the per unit HCP assessment.
- (2) For lands on which endangered species' larval habitat or any rare plant exists, the Landowners shall further demonstrate consistency through the use of the following additional mitigation measures:
 - (a). Dedication of permanent open space easements or transfer of fee title, covering an area not less than 40% of the property, for the purpose of protecting existing habitat.
 - (b). Grading plans designed to minimize habitat destruction to the greatest extent possible, except in no event shall Callippe Silverspot habitat be destroyed unless replacement habitat has first been created elsewhere.
 - (c). Development siting, which may include clustering of development, in order to protect the habitat buffer areas (as defined on page G-1 of the HCP) between habitat and development and to provide broad corridors (as defined on page G-2 of the HCP)
- (3) To further encourage habitat protection, off-site parcels may be acquired for dedication as permanent habitat in order to transfer the allowed density to other parcels in the Brisbane

Acres, consistent with the City of Brisbane's zoning regulations.

5. Require through CC&Rs that future owners observe general provisions regarding protection of Conserved Habitat
6. Submit the final grading plan used to obtain a grading permit and a revegetation plan to the Plan Operator for review. The plan shall provide for temporary fencing to protect all adjacent Conserved Habitat.

The Plan Operator and/or the City of Brisbane have the following obligations:

1. Monitor the effect on adjacent Conserved Habitat of all activities within development areas and provide advice and direction to the Landowners to assist in compliance with the obligations described above.
2. Designate vegetation materials for use in Reclamation Plans and review such Reclamation Plans submitted by Landowners with respect to Administrative Parcel 2-03 in a timely fashion to avoid delays in the implementation of such Plans;
1. Accept dedications of Conserved Habitat within Administrative Parcel 2-03.
2. Prepare a specific habitat management plan for the City-owned open space parcels that is consistent with HCP goals and objectives regarding the protection and maintenance of endangered species habitat. Alternatively, include the City-owned open space parcels in the HCP's Five-year Strategic Plan which is a document prepared by the Habitat Manager which provides strategic implementation guidelines for managing specific conserved habitat areas on the Mountain. The strategic plan must be prepared at five year intervals.

City of Brisbane General Plan

The City of Brisbane General Plan contains various programs and policies regarding natural resource use and conservation within the city's jurisdiction. The plan also contains a detailed section discussing the land use, open space, and conservation programs and policies for the Brisbane Acres area. Below are the portions of the General Plan relevant to this project.

Open Space

Policy 81: The City Shall conduct an on-going effort to identify sites or portions of sites having particular value as open space, wildlife habitat, wetlands, or other environmental qualities that should be preserved and protected. In such cases, the City shall explore the feasibility of acquisition of these areas by the City or by other public or private agencies that are engaged in the ownership and preservation of open space, and, when legally possible, imposing a requirement that such areas be dedicated by the owner to the public for open space purposes.

Policy 81.1: Work to preserve open space lands to protect the natural environment and to provide outdoor educational and recreational opportunities consistent with the sensitivity of the resource.

Policy 82: Encourage the preservation, conservation and restoration of open space to retain existing biotic communities, including rare and endangered species habitat, wetlands, watercourses and woodlands.

Policy 83: Maintain the visual beauty of the Mountain, the ridgelines, hilltops, wildlife and plant habitat including the Brisbane Acres.

Program 83a: In the official actions of the City, including resolutions and ordinances, recognize the importance of maintaining and preserving the natural eco-system and beauty of San Bruno Mountain.

Program 83b: Comply with the provisions of the Habitat Conservation Plan to protect endangered species habitat.

Program 83c: Cooperate with public and private groups involved in rare plant protection, habitat restoration and maintenance of mountain eco-systems to preserve open space on San Bruno Mountain.

Conservation

Policy 118: Preserve areas containing rare and endangered species habitat to the extent allowed by law and available resources.

Policy 119: Comply with the provisions of the Habitat Conservation Plan and the Agreement with respect to the San Bruno Mountain Area Habitat Conservation Plan.

Policy 120: Cooperate with local, State and Federal agencies in conservation efforts for biological resources.

Policy 122: Cooperate with other agencies in conservation efforts.

Program 122a: Work with the Habitat Conservation Plan Operator, the State Department of Fish and Game, the U.S Fish and Wildlife Service, and other agencies as appropriate regarding plans and programs that may affect biological resources in the planning area.

Program 122b: Consult the maps in the technical background reports and information supplied by responsible agencies to determine potential for environmental impacts to biological resources and take appropriate action.

Program 122c: Consult with local, State and Federal agencies to determine when field studies are required to supplement or update existing data.

Program 122e: Encourage applicants to initiate early CEQA consultation on conservation issues.

Policy 123: Conserve important biological communities through sensitive project design.

Program 123a: In land use development applications, consider the siting of structures and utilities so as to conserve identified biological communities.

Program 123b: Request that the HCP Operator study the Brisbane Acres to determine whether there is the potential to meet the 40% requirement for conserved habitat by dedication of large areas of land rather than small portions of parcels.

Policy 129: Require erosion controls to mitigate soil disturbance.

Program 129a: Encourage all property owners, especially of the Quarry, to address erosion on their properties through revegetation or other measures.

Policy 130.1: The City requires restoration of wetland losses. The determination of which land areas are wetlands will be done by those Federal and State agencies having jurisdiction. The City, however, is especially concerned with those wetlands surrounding the perimeter of the Brisbane Lagoon, the Bay shoreline, the Levinson Marsh and the Quarry sediment ponds. The ratios of restoration may exceed the regulatory agencies' mitigation minimums.

Policy 131: Emphasize the conservation of water quality and of riparian and other water-related vegetation, especially that which provides habitat for native species, in planning and maintenance efforts.

Brisbane Acres

Chapter XII.4 of the General Plan outlines specific policies and programs regarding the Brisbane Acres subarea.

Land Use Policy

BA.1: Grading and excavation should be minimized and exposed retaining walls avoided. Landforms should retain the natural topographic character of the Mountain.

Open Space/Conservation Policy

BA.2: Omitted

Program SAB.BA.2.a: In conjunction with any subdivision or other development application, a landscape program and plan shall be submitted to the City and include the following:

- a) Identification and retention of heritage trees
- b) Identification and retention of rare plants
- c) Plant species that are not invasive to the habitat
- d) Water-conserving plants and irrigation systems
- e) Reduced fuels adjacent to the wildland
- f) Screening of structures to blend with the natural landscape
- g) Areas for Conserved Habitat and/or other provisions required by the Habitat Conservation Plan Operator.

Program BA.2.b: Examine ways to improve the existing density transfer program so that a developer/owner can be granted increased density on sites already served by infrastructure in conjunction with the dedication of more remote sites as Open Space.

Program BA.2.c: Retain a trail system through the Brisbane Acres to connect the area to Central Brisbane and the San Bruno Mountain State and County Park.

Program BA.2.d: Map the canyons, intermittent streambeds and banks in the Brisbane Acres and designate such areas for protection.

Program BA.2.e: Develop clear regulations that can be enforced to preserve the natural ecology of the canyons, intermittent streambeds and banks.

Community Health and Safety/Conservation

Policy BA.3: Consider the environmental constraints of the subarea in conjunction with land use development applications.

Program BA.3.a: In conjunction with any subdivision or other development application, the property owner shall be required to supply detailed information on slope, access, water, sanitary sewer and storm drain infrastructure, soils, geology, cultural resources, significant vegetation and endangered species habitat.

Program BA.3.b: Geologic studies for parcels in the Brisbane Acres shall be performed by a licensed engineer and shall pay special attention to slope, landslide and subsurface water. Such studies shall include a detailed evaluation of the stability of the proposed site, the potential effects of construction on the site and adjacent and downslope areas, and the effects of any construction or installation of infrastructure on the site. Specific recommendations for project design to ensure safety and mitigate impacts shall be included in the report and incorporated into construction documents by the project engineer.

Program BA.3.c: Phase grading and construction to coincide with periods of dry weather as set forth in the City's Grading Ordinance.

City of Brisbane Municipal Code

Section 12.12.020 States:

"Protected tree" means each of the following:

1. Any California Bay (*Umbellularia californica*), Coast Live Oak (*Quercus agrifolia*), or California Buckeye (*Aesculus californica*) having a main stem or trunk which measures thirty (30) inches or greater in circumference at a height of twenty-four (24) inches above natural grade.
2. Any species of native or nonnative tree, in addition to those identified in subsection (1) above, designated as a protected tree on recommendation of the parks and recreation commission as adopted by resolution of the city council, based upon its finding and determination that such species uniquely contributes to the scenic beauty of the city or provides special benefits to the natural environment or wildlife.
3. Any tree designated as a protected tree by resolution of the city council.
4. Any tree, regardless of size, originally required by the city to be planted as a condition for the granting of a permit, license, or other approval, or any tree that existed at the time of the granting of such permit, license, or other approval and required by the city to be preserved as part of such approval.
5. Any tree, regardless of size, required by the city to be planted as a replacement for an unlawfully removed tree.
6. Any tree, regardless of size, planted or maintained by the city.
7. Any street tree which is not otherwise described in subsections (1) through (6) above, having a main stem or trunk which measures thirty (30) inches or greater in circumference at a height of twenty-four (24) inches above natural grade.
8. Where three (3) or more trees of any one or more species, each having a main stem or trunk which measures thirty (30) inches or greater in circumference at a height of twenty-four (24) inches above natural grade, are proposed to be removed at the same time from the same property or from contiguous properties under common ownership, such trees shall collectively be regarded as a protected tree.

Pursuant to Section 12.12.040, application and approval of a tree removal permit by the City of Brisbane is required for removal of

3. Any protected tree.
4. Any other tree having a main stem or trunk which measures thirty (30) inches or greater in

circumference at a height of twenty-four (24) inches above natural grade. This requirement shall apply to every owner or occupant of real property within the city, and to every person responsible for destroying, removing, or severely trimming a tree for which a tree removal permit is required under this chapter, regardless of whether such person is engaged in a tree removal business.

Section 17.12.040-I States:

All development within the R-BA District shall comply with the requirements of the San Bruno Mountain Area Habitat Conservation Plan (HCP), including site activity review, environmental assessments, and operating programs for planned management units, consistent with the objectives and obligations set forth in the HCP.

Section 17.12.040-K States:

1. All development proposals shall include a landscape plan to be approved by the planning director in consultation with the HCP plan operator. The plan shall show all proposed landscaping and the location of all protected trees and rare plants. The landscape plan shall be consistent with all of the following objectives:

- a. Preservation of protected trees and rare plants to the greatest extent possible;
- b. Use of plants that are compatible with the natural flora and fauna, and are not invasive to the HCP area;
- c. Use of water conserving plants;
- d. Use of plants that will effectively screen structures and blend with the natural landscape; and
- e. Use of landscaping that is fire resistant.

Section 17.12.040-M States:

Canyon Watercourses and Wetlands. Development of the site, including any temporary disturbance, shall be set back thirty (30) feet in each direction from the center line of any watercourse, and twenty (20) feet from the boundary of any wetlands. The specific location of watercourse center lines and wetland boundaries shall be determined by qualified personnel under the city's direction.

Appendix B
Potentially Occurring Special Status Species

Species Name	Status	Habitat	Potential to Occur Onsite
MAMMALS			
Pallid bat <i>Antrozous pallidus</i>	SSC	Generally found in dry, open habitats including deserts, grasslands, shrublands, woodlands and forests. Roosts in protected structures and rocky outcrops.	Low potential. foraging habitat only. No suitable roosting or breeding habitat present.
Townsend's big-eared bat <i>Corynorhinus townsendii</i>	SSC	Wide variety of habitats, most common in mesic sites. Roosts in the open, hanging from walls & ceilings.	Low potential. Suitable foraging habitat present, however no suitable roosting or breeding habitat present.
Santa Cruz kangaroo rat <i>Dipodomys venustus</i>	G4T1, S1	Requires soft, well-drained sandy soils. Found in manzanita mixed chaparral.	No potential. No suitable habitat or soils present onsite.
Southern sea otter <i>Enhydra lutris nereis</i>	FT, FP, SSC	Near shore, marine environments with canopies of giant kelp and bull kelp and rocky substrates.	No potential. Site is not located near a marine environment.
North American porcupine <i>Erethizon dorsatum</i>	SSC	Wide variety of coniferous and mixed woodland habitats. Generally in the Sierra Nevada, Cascade and Coast Ranges, also occasionally in the transverse ranges.	No potential. Last observed in Pacifica in 1972.
Western red bat <i>Lasiurus blossevillei</i>	SSC	Roosts primarily in trees from sea level up through mixed conifer forests preferring habitat edges.	Low potential. No known breeding colonies within San Francisco County, though species could use trees within the study area during migration in fall.
Hoary bat <i>Lasiurus cinereus</i>	WBWG:M	Roosts in dense foliage of deciduous and evergreen trees, forages over streams and ponds. Prefers habitat edges with access to trees for cover and open areas for feeding.	Low potential. Some suitable roosting sites present in trees on site. This species does not breed in the San Francisco Bay area.
	WBWG:H,		

Species Name	Status	Habitat	Potential to Occur Onsite
Fringed myotis <i>Myotis thysanodes</i>		Found in a wide variety of habitats but prefers dry hardwood woodlands. Roosts in rock crevices, bridges, buildings and tree hollows.	Low potential , foraging habitat only. No roosting habitat present.
San Francisco dusky-footed woodrat <i>Neotoma fuscipes annectens</i>	SSC	Forests with moderate canopies and moderate to dense understory.	No potential . This species not known to occur on San Bruno Mountain. No middens were observed.
Big free-tailed bat <i>Nyctinomops macrotis</i>	SSC	Low-lying arid areas; roosts in high cliffs and rocky outcrops.	No potential . Suitable foraging or roosting habitat not present onsite.
Salt-marsh harvest mouse <i>Reithrodontomys raviventris</i>	FE, SE	Salt and brackish water wetlands in the San Francisco Bay only. Requires pickleweed (<i>Salicornia pacifica</i>) as cover and forage.	No potential . Suitable habitat not present.
Angel Island mole <i>Scapanus latimanus insularis</i>	S1	Known only from Angel Island in San Francisco Bay. Needs friable soils for burrowing.	No potential . Site is not located on Angel Island.
Alameda Island mole <i>Scapanus latimanus parvus</i>	S1	Known only from Alameda Island, habitat variable, usually grasslands. Prefers moist, friable soils, avoids flooded soils.	No potential . Site not located on Alameda Island.
American badger <i>Taxidea taxus</i>	SSC	Most abundant in drier open stages of shrub, forest, and herbaceous habitats, with friable soils.	No potential . Not known to occur in the vicinity of San Bruno Mountain. Last observation in San Francisco from 1947.
Point Reyes jumping mouse <i>Zapus trinotatus orarius</i>	SSC	Primarily in bunch grass marshes on uplands of Point Reyes. Also found in coastal scrub, grassland, and meadows.	No potential . No suitable habitat present.
BIRDS			
Cooper's hawk <i>Accipiter cooperii</i>	WL, S3	Open or interrupted woodlands. Nests in deciduous trees in riparian areas and live oaks.	Moderate potential , foraging only. Nesting habitat not present on site.
Burrowing owl <i>Athene cunicularia</i>	SSC	Grassland, open areas with rodent activity; nest in burrows and is most often associated with the California ground squirrel.	No potential. No suitable habitat . No ground squirrel or other small mammal burrows observed on site.
Marbled murrelet <i>Branchyramphus marmoratus</i>	FT, SE	Occurs year-round in marine subtidal and pelagic habits from Oregon to Point Sal, Santa	No potential . No suitable habitat present.

Species Name	Status	Habitat	Potential to Occur Onsite
		Barbara. Uses stands of mature Douglas fir and redwoods up to 40 miles inland for nesting.	
Western snowy plover <i>Charadrius alexandrinus nivosus</i>	FT, SSC	Sandy beaches, salt pond levees, and alkali lake shores. Requires sandy, gravelly soils for nesting.	No potential. No suitable habitat present.
Northern harrier <i>Circus cyaneus</i>	SSC	Found in coastal salt and fresh-water marshes. Forages over variety of habitats and nests in shrubby vegetation at marsh edge.	Moderate potential, foraging only. Nesting habitat not present on site.
Yellow rail <i>Coturnicops noveboracensis</i>	SSC	Freshwater marshes. Is a summer resident in eastern Sierra Nevada, in Mono county.	No potential. No suitable habitat on site. Last observed in Alameda in 1905.
White-tailed kite <i>Elanus leucurus</i>	S3	Foothills and valley margins with scattered oaks, or in marshes adjacent to deciduous woodlands. Prefers isolated trees for nesting.	Low potential. Foraging only, suitable nest trees not present.
Merlin <i>Falco columbarius</i>	WL	Seacoast, tidal estuaries, open woodlands, savannahs, grassland and desert edges, farms and ranches. Roosts in trees, nests in northern Canada and Alaska.	Low potential, foraging only. Merlins do not nest in California.
American peregrine falcon <i>Falco peregrinus anatum</i>	CFP	Hunts on beaches, mudflats and near water features including wetlands, lakes and rivers. Nests on ledges in cliffs or buildings.	Low potential, foraging only. No suitable nesting habitat present.
Saltmarsh common yellowthroat <i>Geothlypis trichas sinuosa</i>	SSC	Marshy, brushy vegetation in or near water. Requires thick continuous cover of marsh and /or riparian cover down to water surface for foraging. Nests in willow, tall grasses, and tule patches.	No potential. Suitable foraging and nesting habitat not present.
California black rail <i>Laterallus jamaicensis coturniculus</i>	ST, FSC	Freshwater marsh, wet meadows, and margins of saltwater marshes. Requires water depths of approximately one inch for nesting habitat.	No potential. No suitable habitat present.
Alameda song sparrow <i>Melospiza melodia pusillula</i>	SSC	Salt marshes bordering south arm of San Francisco Bay. Inhabits	No potential. No suitable habitat present.

Species Name	Status	Habitat	Potential to Occur Onsite
		<i>Salicornia</i> marshes and nests in <i>Grindelia</i> bushes.	
San Pablo song sparrow <i>Melospiza melodia samuelis</i>	SCC	Salt marshes along the north side of San Francisco and San Pablo Bays. Inhabits <i>Salicornia</i> marshes and nests in <i>Grindelia</i> bushes.	No potential. No suitable habitat present.
Double-crested cormorant <i>Phalacrocorax auritus</i>	WL	Nesting habitat includes coastal cliffs, offshore islands, and along lake margins in inland areas.	No potential. No suitable habitat present.
California Ridgway's rail <i>Rallus obsoletus</i>	FE, SE, FP	Salt-water and brackish marshes in the San Francisco Bay. Associated with pickleweed.	No potential. No suitable habitat present.
Bank swallow <i>Riparia riparia</i>	ST	Riparian ecosystems, forages in a variety of ecosystems, but primarily over water features. Colonial nester in vertical banks/cliffs with fine sandy soils.	No potential. No nesting habitat present.
California least tern <i>Sternula antillarum browni</i>	FE, SE	Migratory. Nests along California coast from San Francisco Bay South to Northern Baja California. Found on bare or sparsely vegetated sandy beaches, alkali flats or landfills. Forage over marine and bay waters and feed on small fish and invertebrates.	No potential. No suitable habitat present.
AMPHIBIANS AND REPTILES			
California tiger salamander <i>Ambystoma californiense</i>	FT, ST	Seasonal wetlands in grassland and oak-savannah. Requires underground refuges for cover and vernal pools or other seasonal water sources for breeding.	No potential. No aquatic or other suitable habitats on or near site.
California giant salamander <i>Dicamptodon ensatus</i>	FT, SSC	Inhabits wet coastal forests near streams from Mendocino Co. south to Monterey Co. and east to Napa Co. Aquatic larvae require cold clear streams, occasionally in lakes or ponds. Adults found in wet forests under rocks and logs near lakes or streams.	No potential. No aquatic or other suitable habitats on or near site.

Species Name	Status	Habitat	Potential to Occur Onsite
Western pond turtle <i>Emys marmorata</i>	SSC	Ponds, creeks in woodland, grassland. Species requires deep water ponds, streams, or marshes with sunny, emergent basking sites and sunny upland habitat for nesting.	No potential. No aquatic or other suitable habitats on or near site.
Foothill yellow-legged frog <i>Rana boylei</i>	SE, SSC	Partly-shaded, shallow streams and riffles with a rocky substrate in a variety of habitats. Needs at least some cobble-sized substrate for egg-laying, and at least 15 weeks to attain metamorphosis.	No potential. No aquatic or other suitable habitats on or near site.
California red-legged frog <i>Rana draytonii</i>	FT, SSC	Lowlands and foothills in or near permanent sources of deep water with dense, shrubby or emergent riparian vegetation.	No potential. No aquatic or other suitable habitats on or near site.
San Francisco garter snake <i>Thamnophis sirtalis tetrataenia</i>	FE, ST	Near freshwater marshes, ponds, and slow moving streams. Prefers dense cover and water depths of at least one foot. Also found in upland habitats adjacent to water sources. Prefers south or west facing slopes with open habitats with occasional shrubs for cover.	No potential. No freshwater aquatic or other suitable habitats on or near site.
INVERTEBRATES			
Opler's longhorn moth <i>Adela opierella</i>	G2, S2	Inner coast ranges. Associated with serpentine grassland. Larvae feed on <i>Platystemon californicus</i> .	No potential. No suitable habitat present, host plant not present.
Incredible harvestman <i>Banksula incredula</i>	G1, S1	Known only from one locality, a Franciscan sandstone talus slope with dense chaparral canopy on San Bruno Mountain, San Mateo County.	No potential. Nearest (and only) recorded occurrence is from 2 miles southwest of survey area. Talus slopes not present on site.
Western bumble bee <i>Bombus occidentalis</i>	G2G3, S1	Open grassy areas, urban parks and gardens, chaparral and shrub areas, and mountain meadows. Host plants include <i>Ceanothus</i> , <i>Centaurea</i> , <i>Chrysothamnus</i> , <i>Cirsium</i> , <i>Geranium</i> , <i>Grindellia</i> , <i>Lupinus</i> , <i>Melilotus</i> , <i>Monardella</i> , <i>Rubus</i> , <i>Solidago</i> , and <i>Trifolium</i> . Once common & widespread, species has declined precipitously from central CA to southern B.C., perhaps from disease. Nests underground.	No potential. Nectar and pollen plants not present.

Species Name	Status	Habitat	Potential to Occur Onsite
Obscure bumble bee <i>Bombus caliginosus</i>	S1S2	Coastal areas from Santa Barbara county to north to Washington state. Grassy coastal prairies and meadows. Nectar and pollen plants include: <i>Ceanothus</i> , <i>Cirsium</i> , <i>Clarkia</i> , <i>Keckiella</i> , <i>Lathyrus</i> , <i>Lotus</i> , <i>Lupinus</i> , <i>Rhododendron</i> , <i>Rubus</i> , <i>Trifolium</i> , and <i>Vaccinium</i>	No potential. Nectar and pollen plants not present.
Crotch bumble bee <i>Bombus crotchii</i>	G2, S1S2	Coastal California east to the Sierra-Cascade Crest. Food plants include: <i>Antirrhinum</i> , <i>Phacelia</i> , <i>Clarkia</i> , <i>Dendromecon</i> , <i>Eschscholzia</i> , and <i>Eriogonum</i> .	No potential. Nectar and pollen plants not present.
Tomales isopod <i>Caecidotea tomalensis</i>	G2, S2	Fresh-water ponds or streams with still or near-still water.	No potential. No suitable habitat present.
Edgewood blind harvestman <i>Calicina minor</i>	G1, S1	Open grassland in areas of serpentine bedrock, found on the underside of serpentine rocks near permanent springs.	No potential. No suitable habitat on site.
San Bruno elfin butterfly <i>Callophrys mossii bayensis</i>	FE	Coastal mountains with grassy ground cover, mainly near San Bruno Mountain. Host plant is <i>Sedum spathulifolium</i> .	No potential. Suitable habitat and host plant not present.
Sandy beach tiger beetle <i>Cicindela hirticollis gravida</i>	S1	Coastal areas adjacent to non-brackish water with dry, light-colored sand.	No potential. No suitable habitat present onsite.
Monarch Butterfly <i>Danaus plexippu</i> ~California overwintering population	S3	Roosts located in wind protected tree groves (eucalyptus, Monterey pine, Monterey cypress) with nectar sources and water nearby. Larvae feed on <i>Asclepias</i> spp. leaves.	Low potential. Limited suitable roosting habitat present within the study area.
Stage's dufourine bee <i>Dufourea stagei</i>	G1G2, S1?	Ground-nesting bee known only from San Bruno Mountain. <i>Dufourea</i> bees are associated with native grassland species.	No potential. Only record is from 1962 from San Bruno Mountain. Native grassland not present.
Bay checkerspot butterfly <i>Euphydryas editha bayensis</i>	FT	Native grasslands on outcrops of serpentine soils. Host plants include <i>Plantago erecta</i> , <i>Orthocarpus (Castilleja) densiflorus</i> and <i>O. purpurascens</i> .	No potential. Species reintroduced to San Bruno Mountain in 2017.
Ricksecker's water scavenger beetle	G2?, S2?		No potential. No aquatic habitat present.

Species Name	Status	Habitat	Potential to Occur Onsite
<i>Hydrochara rickseckeri</i>		Aquatic habitats, weedy shallow open water, and slow moving stream habitats.	
Leech's skyline diving beetle <i>Hydroporus leechi</i>	G1?, S1?	Aquatic beetle. Known from Edgemar district of Pacifica, several miles south of San Francisco County.	No potential. No suitable habitat present on site.
Mission blue butterfly <i>Icaricia icarioides missionensis</i>	FE	Grasslands of the San Francisco Peninsula. Uses three perennial lupines as larval host plants, <i>Lupinus albifrons</i> , <i>L. varicolor</i> , and <i>L. formosus</i> .	No potential. Suitable host plants not present on site.
San Francisco fork-tailed damselfly <i>Ischnura gemina</i>	G2, S2	Freshwater marshes and creeks with emergent and floating aquatic vegetation.	No potential. No suitable habitat present on site.
Bumblebee scarab beetle <i>Lichnanthe ursina</i>	G2, S2	Coastal sand dunes from Sonoma County south to San Mateo County. Usually stays close to sand surface.	No potential. No suitable habitat present.
Callippe silverspot butterfly <i>Speyeria callippe callippe</i>	FE	Northern coastal scrub and grasslands of San Francisco Peninsula. Host plant is <i>Viola pendunculata</i> . Utilizes a variety of native and nonnative plants as nectar sources and hilltops for mate selection.	No potential. Host plants not present within study area.
Myrtle's silverspot butterfly <i>Speyeria zerene myrleae</i>	FE	Coastal habitats with <i>Viola adunca</i> . Restricted to foggy dunes and hills of the Point Reyes peninsula.	No potential. No suitable habitat on site.
San Francisco Bay Area leaf-cutter bee <i>Trachusa gummiifera</i>	G1, S1	Nests in hillside by creating diagonal tunnels in dirt and other substrate. Feeds on flower pollen and nectar.	No potential. Only observation is from 1957 in San Francisco.
Mimic tryonia (=California brackishwater snail) <i>Tryonia imitator</i>	G2, S2	Coastal lagoons, estuaries and salt marshes.	No potential. No suitable habitat present on site.
Marin Hesperian <i>Vespericola marinensis</i>	G2, S2	Found in moist spots in coastal scrub and chaparral vegetation in Marin County. Associated with cow-parsnip spring seeps, leaf-mold along streams, alder woods and mixed evergreen forest.	No potential. No suitable habitat present on site.

Species Name	Status	Habitat	Potential to Occur Onsite
PLANTS			
San Mateo thorn-mint <i>Acanthomintha duttonii</i>	FE, CE, CNPS 1B.1	Chaparral, serpentinite, valley and foothill grasslands. Elevation: 50 - 300 meters. Blooming period: Apr.-June.	No potential. Not known from San Bruno Mountain. Nearest known occurrence is on Pulgas ridge, 11 miles south.
Blasdale's bent grass <i>Agrostis blasdalei</i>	CNPS 1B.2	Coastal bluff scrub, coastal dunes, coastal prairie Elevation: 0 - 150 meters Blooming period: May-July	No potential. No suitable habitat on site.
Franciscan onion <i>Allium peninsulare</i> var. <i>franciscanum</i>	CNPS 1B.2	Cismontane woodland, valley and foothill grassland. clay soils, often on serpentine. Dry hillsides. Elevation: 100-300 m. Blooming: period: May-June.	No potential. No suitable habitat or soils present on site.
Bent- flowered fiddleneck <i>Amsinckia lunaris</i>	CNPS 1B.2 G2?, S2?	Coastal bluff scrub, Cismontane woodland, Valley and foothill grassland, associated with open areas. Elevation: 3 - 500 meters. Blooming period: Mar. – June.	No potential. No suitable habitat on site.
Coast rock cress <i>Arabis blepharophylla</i>	CNPS 4.3	Coastal areas with marine influence. Rocky outcroppings, bluffs, grassy slopes. Elevation: 50-300 meters. Blooming period: May-June.	No potential. No suitable habitat on site.
Franciscan manzanita <i>Arctostaphylos franciscana</i>	FE, CNPS 1B.1	Serpentine outcrops in chaparral. Elevation: 60-300 meters. Blooming period: Feb.- Apr.	No potential. Not observed during site surveys. Suitable soils not present.
San Bruno Mountain manzanita <i>Arctostaphylos imbricata</i>	SE, CNPS 1B.1	Sandstone outcrops in chaparral, also coastal scrub. Elevation: 175-365 meters. Blooming Period: Feb.- May.	No potential. No suitable habitat on site, not observed during the site visit.
Presidio manzanita <i>Arctostaphylos montana</i> ssp. <i>ravenii</i>	FE, SE CNPS 1B.1	Open, rocky serpentine slopes in chaparral, coastal prairie, and coastal scrub. Elevation: 30-90 meters. Blooming period: Feb.- Mar.	No potential. Not observed during site survey. Suitable soils not present.
Montara manzanita <i>Arctostaphylos montaraensis</i>	G1, S1 CNPS 1B.2	Slopes and ridges in chaparral, and coastal scrub, Elevation: 150 - 500 meters. Blooming period: Jan.- Mar.	No potential. Not observed during site survey.
Pacific Manzanita <i>Arctostaphylos pacifica</i>	SE, CNPS 1B.1	Coastal scrub, associated with <i>Arctostaphylos imbricata</i> , <i>A. uva-ursi</i> , and <i>Erysimum franciscanum</i> .	No potential. Not observed during site survey.

Species Name	Status	Habitat	Potential to Occur Onsite
		Elevation: 280-379 meters. Blooming period: Feb.– Apr.	
Kings Mountain manzanita <i>Arctostaphylos regismontana</i>	G2, S2, CNPS 1B.2	Broadleaved upland forest, chaparral, north coast coniferous forest. Elevation: 305 - 730 meters.	No potential. Not observed during site survey.
Marsh sandwort <i>Arenaria paludicola</i>	FE, SE CNPS 1B.1	Freshwater marshes and swamps with dense mats of vegetation. Elevation: 10-170 meters. Blooming period: May- Aug.	No potential. No suitable habitat present on site.
Coastal marsh milk-vetch <i>Astragalus pycnostachyus</i> var. <i>pycnostachyus</i>	G2T2, S2 CNPS 1B.2	Moist dunes, marshes, streamsides, Wetland. Elevation: 0 - 30 meters. Blooming period: Apr.-Oct.	No potential. No suitable habitat on site.
Alkali milk-vetch <i>Astragalus tener</i> var. <i>tener</i>	G2T2, S2 CNPS 1B.2	Alkali playa, valley and foothill grasslands, vernal pools in low, flooded lands. Elevation: 1-170 meters. Blooming period: Mar-June.	No potential. No suitable habitat on site.
Coastal bluff morning-glory <i>Calystegia purpurata</i> ssp. <i>saxicola</i>	CNPS 1B.2	Coastal dunes, coastal scrub, coastal bluff scrub, north coast coniferous forest. Elevation: 5-430 meters. Blooming period: May-Sept.	No potential. No suitable habitat on site.
Bristly sedge <i>Carex comosa</i>	S2, CNPS 2B.1	Freshwater wetlands on lake-margins and edges. 270-1030 meters. Blooming period: May-Sept.	No potential. No suitable habitat on site.
Northern meadow sedge <i>Carex praticola</i>	S2, CNPS 2B.2	Found in moist to wet meadows in coastal prairies and north coastal coniferous forests. Elevation: 15-3200 meters. Blooming period: May- July.	No potential. No suitable habitat on site.
Pappose tarplant <i>Centromadia parryi</i> ssp. <i>parryi</i>	G3T2, S2, CNPS 1B.2	Vernally mesic areas in chaparral, coastal prairie, marsh and swamp, meadow and seep, valley and foothill grassland habitats. Often in alkaline sites. Elevation: 2 - 420 meters. Blooming period: May-Nov.	No potential. No suitable habitat on site.

Species Name	Status	Habitat	Potential to Occur Onsite
Point Reyes bird's-beak <i>Chloropyron maritimum ssp. palustre</i>	S2, CNPS 1B.2	Marsh and swamp, Salt marsh, Elevation: 0 - 10 meters. Blooming period: June- Oct.	No potential. No suitable habitat on site.
San Francisco Bay spineflower <i>Chorizanthe cuspidata var. cuspidata</i>	G2T1, S1, CNPS 1B.2	Coastal bluff scrub, Coastal dunes, Coastal prairie, Coastal scrub, open sandy soils. Elevation: 3 - 215 meters. Blooming period: Apr. - July.	No potential. No suitable habitat on site.
Robust spineflower <i>Chorizanthe robusta var. robusta</i>	FE, CNPS 1B.1	Sandy terraces and bluffs, or loose sand, in cismontane woodland, coastal dunes and coastal scrub. Elevation: 3-1200 meters. Blooming period: Apr.- Sept.	No potential. Suitable soils not present.
Franciscan thistle <i>Cirsium andrewsii</i>	G2, S2.2, CNPS 1B.2	Coastal scrub, Broadleaved upland forest, Coastal bluff scrub, Coastal prairie. Sometimes associated with serpentine seeps. Associated with riparian herb species such as <i>Toxicodendron</i> , <i>Urtica</i> , <i>Baccharis</i> , <i>Conium</i> , <i>Delphinium</i> , etc. Elevation: 0 - 150 meters. Blooming period: Mar. – July.	No potential. No suitable habitat on site.
Crystal Springs fountain thistle <i>Cirsium fontinale var. fontinale</i>	FE, CE, CNPS 1B.1	Chaparral, cismontane woodland, meadow & seep, ultramafic valley & foothill grassland, wetland. Blooming period: (April) May-October.	No potential. No suitable habitat on site.
Mt. Tamalpais thistle <i>Cirsium hydrophilum var. vaseyi</i>	G2T1, S1, CNPS 1B.2	Serpentine seeps and streams in chaparral and woodland. Broadleaved upland forest, chaparral, meadows and seeps. Elevation: 180-610 meters. Blooming period: May- Aug.	No potential. No suitable habitat on site.
Compact cobwebby thistle <i>Cirsium occidentale var. compactum</i>	G3G4T2 CNPS 1B.2	Coastal dunes, prairie and scrub. Also on dunes and clay in chaparral and grassland. Elevation: 5-155 meters. Blooming period: Apr.- June.	No potential. No suitable habitat on site.
Presidio clarkia <i>Clarkia franciscana</i>	G1, S1 CNPS 1B.1	Valley grassland, northern coastal scrub, with affinity for serpentine soils. Elevation: 5- 340 meters. Blooming period: May-July.	No potential. No suitable habitat on site.

Species Name	Status	Habitat	Potential to Occur Onsite
Round-headed Chinese-houses <i>Collinsia corymbosa</i>	G1, S1, CNPS 1B.2	Coastal strand on sand dunes. Elevation: 0-85 meters. Blooming period: Apr.- June.	No potential. No suitable habitat present on site.
San Francisco collinsia <i>Collinsia multicolor</i>	G2, S2.2, CNPS 1B.2	Grows on decomposed shale with decomposed organic material (humus) in closed cone coniferous forest coastal scrub. Elevation: 30 - 250 meters. Blooming period: Mar.-May.	No potential. No suitable habitat on site.
Western leatherwood <i>Dirca occidentalis</i>	CNPS 1B.2	Moist ravines, riparian thickets on slopes, broad leafed upland forest, closed-cone coniferous forest, chaparral, cismontane woodland, north coast coniferous forest. Elevation: 25 - 425 meters.	No potential. Not observed during site survey. No suitable habitat on site.
San Mateo woolly sunflower <i>Eriophyllum latilobum</i>	FE, CE, CNPS 1B.1	Cismontane woodland, ultramafic, Elevation: 45 - 150 meters. Blooming period: May- June.	No potential. No suitable habitat on site.
San Francisco wallflower <i>Erysimum franciscanum</i>	CNPS 4.2	Serpentine outcrops, coastal scrub, or sand dunes, granitic hillsides. Elevation: <500 meters. Blooming period: Jan-Apr.	Low potential. Suitable habitat generally not present.
San Joaquin spearscale <i>Etriplex joaquinana</i>	G2, S2, CNPS 1B.2	Chenopod scrub, alkali wetlands or alkali sink scrub, playas, valley and foothill grasslands. Associated with <i>Distichlis spicata</i> , <i>Frankenia</i> , etc.	No potential. No suitable habitat present on site.
Hillsborough chocolate lily <i>Fritillaria biflora</i> var. <i>ineziana</i>	CNPS 1B.1	Cismontane woodland, ultramafic, valley foothill grassland. Blooming period: Mar. – Apr.	No potential. No suitable habitat on site.
Fragrant fritillary <i>Fritillaria liliacea</i>	G2, S2 CNPS 1B.2	Coastal scrub, Cismontane woodland, Coastal prairie, Valley and foothill grassland, clay or serpentine. Elevation: 3 - 410 meters. Blooming period: Feb.- Apr.	No potential. No suitable habitat on site.
Marin checker lily <i>Fritillaria lanceolata</i> var. <i>tristulis</i>	CNPS 1B.1	Found in coastal bluff scrub, coastal scrub, and coastal prairie, often on serpentine, in canyons, riparian areas, and rock outcrops. Elevation: 15-150 meters. Bloom period: Feb-May.	No potential. No suitable habitat on site.

Species Name	Status	Habitat	Potential to Occur Onsite
Blue coast gilia <i>Gilia capitata</i> ssp. <i>chamissonis</i>	G5T2, S2, CNPS 1B.1	Endemic to sand dunes of the central coast. Elevation: 0- 580 meters. Blooming period: Apr.- July	No potential. No suitable habitat present on site.
Dark-eyed gilia <i>Gilia millefoliata</i>	G2, S2, CNPS 1B.2	Coastal strand. Elevation 0-610 meters. Blooming period: Apr. - July.	No potential. No suitable habitat present on site.
San Francisco gumplant <i>Grindelia hirsutula</i> var. <i>maritima</i>	S1, CNPS 3.2	Coastal bluff, coastal scrub, grasslands. Elevation: 15 - 400 meters. Blooming period: June-Sept.	Low potential. Habitats within the survey area are highly disturbed.
Diablo helianthella <i>Helianthella castanea</i>	G2, S2 CNPS 1B.2	Usually in chaparral and oak woodland interface in rocky soils. Also broadleaved upland forest, coastal scrub, riparian woodland and foothill and valley grassland. Elevation: 25-1150 meters. Blooming period: Mar.-June.	Low potential. Habitats within the survey area are highly disturbed.
White seaside tarplant <i>Hemizonia congesta</i> ssp. <i>congesta</i>	S1S2, CNPS 1B.2	Valley and foothill grasslands and coastal scrub. Elevation: 25-200 meters. Blooming Period: Apr.- Nov.	No potential. Habitats within the survey area are highly disturbed. Records in the San Francisco Peninsula are from the early 1900's.
Short-leaved evax <i>Hesperivax sparsiflora</i> var. <i>brevifolia</i>	S2S3 CNPS 1B.2	Coastal bluff scrub, Coastal dunes, Sandy soils. Elevation: 0 - 215 meters. Blooming period: Mar.-June.	No potential. Suitable habitat not present.
Marin western flax <i>Hesperolinon congestum</i>	FT, ST	In serpentine barrens and in serpentine grassland and chaparral. Elevation: 5 - 370 meters. Blooming period: Apr.- July.	No potential. No suitable soils present.
Water star-grass <i>Heteranthera dubia</i>	S1, CNPS 2B.2	Alkaline water that is still or slow-moving. Found in marshes and swamps. Elevation: 30-1495 meters. Blooming period: July-Aug.	No potential. No suitable habitat present on site.
Santa Cruz tarplant <i>Holocarpus macradenia</i>	FT, SE CNPS 1B.1	Found in clay and sandy soils in coastal prairie, coastal scrub, and valley and foothill grasslands, often with non-native species. Elevation: 10-220 M Blooming period: June- Oct.	No potential. Suitable soils not present.

Species Name	Status	Habitat	Potential to Occur Onsite
Kellogg's horkelia <i>Horkelia cuneata</i> ssp. <i>sericea</i>	S2?, CNPS 1B.1	Closed-cone coniferous forest, Chaparral, Coastal dunes, Coastal scrub in sandy or gravelly, openings. Blooming period: Apr. – Sept.	No potential. Suitable soils and habitat not present.
Point Reyes horkelia <i>Horkelia marinensis</i>	CNPS 1B.2	Sandy coastal dunes, coastal prairie, coastal scrub Elevation: 5 - 755 meters Blooming period: May-Sept	No potential. Suitable soils and habitat not present.
Coast Iris <i>Iris longipetala</i>	CNPS 4.2	Moist coastal prairie, or open coastal forest. Elevation: <600 meters. Blooming period: March-May.	Low potential. Nearest occurrence is ~.5 miles to the south. Suitable habitat generally not present.
Perennial goldfields <i>Lasthenia californica</i> ssp. <i>macrantha</i>	CNPS 1B.2	Coastal bluff scrub, coastal dunes, coastal scrub. Elevation: 5 - 520 meters. Blooming period: Jan.-Nov.	No potential. No suitable habitat present.
Beach layia <i>Layia carnosa</i>	FE, SE	Coastal dunes and coastal scrub. Elevation: 0-550 meters. Blooming period: Mar.- July.	No potential. No suitable habitat present on site.
Coast yellow leptosiphon <i>Leptosiphon croceus</i>	CNPS 1B.1	Coastal bluff scrub, coastal prairie. Elevation: 10 - 150 meters. Blooming period: Apr.-May.	No potential. No suitable habitat on site
Rose leptosiphon <i>Leptosiphon rosaceus</i>	G1, S1 CNPS 1B.1	Coastal bluff scrub. Elevation: 0 - 100 meters. Blooming period: Apr.-July.	No potential. No suitable habitat present on site.
San Francisco lessingia <i>Lessingia germanorum</i>	FE, SE	Coastal scrub on open sandy soils (dunes). Elevation: 5-790 meters. Blooming Period: July- Nov.	No potential. No suitable habitat present on site.
Crystal Springs lessingia <i>Lessingia arachnoidea</i>	CNPS 1B.2	Cismontane woodland, Coastal scrub, valley and foothill grassland. Strong affinity to serpentine soil. Elevation: 60 - 200 meters. Blooming period: July-Oct.	No potential. Not known to occur on San Bruno Mountain. Serpentine soils not present.
Ornduff's meadowfoam <i>Limnanthes douglasii</i> ssp. <i>ornduffii</i>	CNPS 1B.1	Agricultural fields. Meadows and seeps. Elevation: 10 - 20 meters. Blooming period: Nov-May	No potential. No suitable habitat present.
Arcuate bush-mallow <i>Malacothamnus arcuatus</i>	G2, S2, CNPS 1B.2	Chaparral, Cismontane woodland. Elevation: 15 - 355 meters. Blooming period: Apr.- Sept.	No potential. Not observed during site surveys. Nearest known occurrence

Species Name	Status	Habitat	Potential to Occur Onsite
			near San Andreas Reservoir.
Marsh microseris <i>Microseris paludosa</i>	FSC	Moist open woods or grassland; Closed-cone coniferous forest, Cismontane woodland, Coastal scrub, Valley and foothill grassland. Requires vernal moist to saturated soils. Elevation: 5 - 300 meters Blooming period: Apr.- June.	No potential. No suitable habitat present on site.
Northern curly-leaved monardella <i>Monardella sinuate</i> ssp. <i>nigrescens</i>	S2, CNPS 1B.2	Found in sandy soils in coastal dunes, coastal scrub, chaparral, and lower montane coniferous forest. Elevation 0-300 meters. Bloom period: May-July.	No potential. No suitable soils present.
Woodland woollythreads <i>Monolopia gracilens</i>	CNPS 1B.2	Broadleaved upland forest (openings), chaparral, cismontane woodland, north coast coniferous forest (openings), Ultramafic, Valley and foothill grassland, Elevation: 100 - 1200 meters. Blooming period: Mar.-July	No potential. Habitat is highly disturbed.
White-rayed pentachaeta <i>Pentachaeta bellidiflora</i>	FE, SE	Ultramafic grassland. Open dry rocky slopes and grassy areas. Often on soils derived from serpentine bedrock. Elevation: 35 - 620 meters. Blooming period: Mar.-May	No potential. Presumed extirpated, suitable habitat not present.
Choris popcornflower <i>Plagiobothrys chorisianus</i> var. <i>chorisianus</i>	S2.2, CNPS 1B.2	Chaparral, Coastal prairie, Coastal scrub, mesic. Elevation: 15 - 160 meters. Blooming period: Mar. – June.	No potential. No suitable habitat, including mesic conditions present.
San Francisco popcornflower <i>Plagiobothrys diffuses</i>	SE	Coastal prairie, valley grassland. Elevation: 15-260 meters. Blooming period: Mar.- June.	No potential. No suitable habitat present.
Hairless popcornflower <i>Plagiobothrys glaber</i>	CNPS 1A	Coastal salt marsh, in meadows, and wetland-riparian. Elevation 5-180 meters. Blooming Period: Mar.-May.	No potential. No suitable habitat present on site.
Oregon polemonium <i>Polemonium carneum</i>	S1, CNPS 2.2	Coastal prairie, coastal scrub, lower montane coniferous forest. Elevation: 0 - 1830 meters. Blooming period: Apr. – Sept.	No potential. No suitable habitat present. Historical records only.

Species Name	Status	Habitat	Potential to Occur Onsite
Marin knotweed <i>Polygonum marinense</i>	G2Q, S2, CNPS 3.1	Coastal salt marshes and brackish marshes. Elevation: 0-10 meters. Blooming period: May- Aug.	No Potential. No suitable habitat present on site.
Hickman's cinquefoil <i>Potentilla hickmanii</i>	FE, CE, CNPS 1B.1	Freshwater marshes, seeps, and small streams in open or forested areas along the coast. Closed-cone coniferous forest, coastal bluff scrub, freshwater marsh, marsh and swamp, meadow and seep, wetland. Elevation: 10 - 149 meters. Blooming period: Apr.- Aug.	No potential. No suitable habitat present.
Adobe sanicle <i>Sanicula maritima</i>	SR	Meadows, seeps, grassland, chaparral, and coastal prairie in moist clay or ultramafic soils. Elevation: 15-190 meters. Blooming period: Feb.- May.	No potential. No suitable habitat on site.
Chaparral ragwort <i>Senecio aphanactis</i>	CNPS 2B.2	Chaparral, cismontane woodland, and coastal scrub. Associated with drying alkaline flats. Elevation: 20- 855 meters Blooming period: Jan – Apr (May)	No potential. No suitable soils present.
Scouler's catchfly <i>Silene scouleri</i> ssp. <i>scouleri</i>	CNPS 2B.2	Perennial herb found in coastal bluff scrub, coastal prairie, and valley and foothill grassland. Elevation: 0-600 meters. Blooming period: (Mar.) June-Aug. (Sep).	Low potential. Suitable habitat generally not present. Nearest known record is .5 miles to the south.
San Francisco champion <i>Silene verecunda</i> ssp. <i>verecunda</i>	S1, CNPS 1B.2	Chaparral, Coastal bluff scrub, Coastal prairie, Coastal scrub, valley and foothill grassland, often on mudstone or shale, and in sandy soils, Ultramafic. Elevation: 30 - 645 meters. Blooming period: Mar. - Aug.	Low potential. Suitable habitat generally not present. Nearest known record is .5 miles to the south.
Santa Cruz microseris <i>Stebbinsoseris decipiens</i>	G2, S2.2 CNPS 1B.2	Found in open areas in loose or disturbed soils derived from sandstone, shale or serpentine, on seaward slopes. Broadleaf upland forest, conifer forest, chaparral, coastal prairie, coastal scrub. Elevation: 0-510 meters. Blooming period: Apr.-May.	No potential. Suitable habitat generally not present. Records from Angel Island and Marin County only.

Species Name	Status	Habitat	Potential to Occur Onsite
California seablite <i>Suaeda californica</i>	FE	Perennial evergreen shrub found on margins of coastal salt marshes and swamps. Elevation: 0-15 meters. Blooming period: July to Oct.	No Potential. No suitable habitat on site.
Showy rancheria clover <i>Trifolium amoenum</i>	FE, CNPS 1B.1	Coastal bluff scrub, valley and foothill grasslands, sometimes in serpentine substrates. Elevation: 5-415 meters. Blooming period: Apr.- June.	No Potential. No suitable habitat on site.
Saline clover <i>Trifolium hydrophilum</i>	G2, S2 CNPS 1B.2	Mesic and alkaline sites in marshes, swamps, valley and foothill grasslands, and vernal pools. Elevation: 0-300 meters. Blooming period: Apr.- June.	No Potential. No suitable habitat on site.
San Francisco owl's-clover <i>Triphysaria floribunda</i>	G2, S2.2 CNPS 1B.2	Coastal prairie and valley grassland, associated with serpentine soils. Elevation: 10-200 meters. Blooming Period: Apr.-June.	No Potential. Suitable habitat not present.
Coastal triquetrella moss <i>Triquetrella californica</i>	G1, S1, CNPS 1B.2	Coastal bluff scrub, coastal scrub, valley and foothill grassland, rocky slopes. Associated with <i>Pinus contorta</i> , <i>Picea sitchensis</i> , <i>Sequoia sempervirens</i> in north, and dense chaparral in southern range. Elevation: 10- 100 meters.	No Potential. Suitable habitat not present.
Oval-leaved viburnum <i>Viburnum ellipticum</i>	G4G5, S3 CNPS 2B.3	Chaparral, cismontane woodland, lower montane coniferous forest. Elevation: 215-1400 meters. Blooming period:	No potential. Historical records in East Bay only.
Natural Plant Communities			
Northern Maritime Chaparral	G1, S1.2	Shrubland plants with sclerophyllous leaves growing on nutrient poor soils, near the coast in northern and central California. <i>Arctostaphylos</i> , <i>Adenostema</i> , and <i>Ceanothus</i> tend to be dominant species.	Not observed. This habitat type is present further west on San Bruno Mountain.
Valley Needlegrass Grassland	G3, S3.1	Herbaceous layer of perennial grasses where <i>Stipa</i> is characteristically present. Generally intermingling with non-	No Potential. No <i>Stipa</i> or other native perennial grasses were observed on site.

Species Name	Status	Habitat	Potential to Occur Onsite
		native annual grasses including <i>Bromus</i> and <i>Avena</i> species. Found in valley and foothill areas. Soils can have high clay content in inland areas, or be shallow and rocky near the coast.	
Serpentine Bunchgrass	G2, S2.2	Herbaceous grassland dominated by perennial bunchgrasses including <i>Poa secunda</i> , <i>Stipa</i> , or <i>Festuca idahoensis</i> or <i>F. rubra</i> . Found in uplands or freshwater wetlands (<i>Poa</i>), and in all topographic locations.	No Potential. No perennial native grasses were observed on site. There are no serpentine soils mapped within the survey area or observed on site.
Northern Coastal Salt Marsh	G3, S3.2	Salt-tolerate hydrophytes forming dense cover up to one meter tall. Found in sheltered inland margins of bays, lagoons and estuaries. Associated with hydric soils.	No Potential. The study area does not contain salt marsh habitats.
Northern Maritime Chaparral	G1, S1.2	Chaparral habitat associated with various types of manzanita (<i>Arctostaphalos crustacea</i> , <i>A. tomentosa</i>). Soils are derived from various substrates, usually nutrient-poor sandstone, shale, sand deposits, and granitics.	No Potential. Manzanita species were not observed within the study area.
California Buckeye Groves	G3, S3	Woodland habitat where California buckeye (<i>Aesculus californica</i>) is dominant or co-dominant in the canopy.	No potential. California buckeye was not observed within the study area.

**GEOTECHNICAL REPORT
3708 BAYSHORE BOULEVARD
BRISBANE, CALIFORNIA 94005**

Client:

Sean Brennan – MK Pipelines Aura Smithers
3708 Bayshore Blvd.
Brisbane, CA 94005
c/o: caroljones@mkpipelines.com

7 June 2023
23-230301-01.1

Unauthorized use of this document is strictly prohibited by anyone other than the client for the specific project described herein

7 June 2023
23-07020101.1

Sean Brennan – MK Pipelines Aura Smithers
3708 Bayshore Blvd.
Brisbane, CA 94005
c/o: caroljones@mkpipelines.com

Subject: Geotechnical Report
Proposed Storage Yard
3708 Bayshore Boulevard
Brisbane, California 94005
APN 007350120

Dear Mr. Brennan:


This letter transmits the results of our geotechnical studies for the proposed storage yard at the subject site located at 3708 Bayshore Boulevard in Brisbane, California. Plans are preliminary; however, we understand you wish to utilize the site for temporary storage of equipment and supplies. You currently occupy the site immediately to the south. Our services were performed based on our proposal dated 30 March 2023.

Our report contains detailed recommendations that should be reviewed in their entirety. Our continued involvement as geotechnical engineer of record is predicated on our geotechnical review of the project documents, and our geotechnical observations during construction.

A competent and experienced person should be present during the geotechnical aspects of construction to identify any deviations from the conditions described in this report and on the project documents. We should be notified immediately if a changed or unknown condition is encountered.

We appreciate the opportunity to be involved with this project. If you have any questions, please contact the signee of this report.

Yours Sincerely,
DIVIS CONSULTING, INC.


Christian J Divis, GE2694
Principal Engineer

ATTACHMENT

**GEOTECHNICAL REPORT
3708 BAYSHORE BOULEVARD
BRISBANE, CALIFORNIA 94005**

Client:
Sean Brennan – MK Pipelines Aura Smithers
3708 Bayshore Blvd.
Brisbane, CA 94005
c/o: caroljones@mkpipelines.com

7 June 2023
23-230301-01.1

Prepared by:


Christian J Divis, PE, GE
Geotechnical Engineer, GE2694



Unauthorized use of this document is strictly prohibited by anyone other than the client for the specific project described herein

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	SITE DESCRIPTION	1
3.0	PROPOSED IMPROVEMENTS	1
4.0	SCOPE OF WORK	2
5.0	DATA REVIEW	2
5.1	State of California Special Studies Zones	2
5.2	Regional Seismicity	3
5.3	Regional Geology	3
6.0	GEOTECHNICAL FIELD RECONASSAINCE	4
7.0	SUBSURFACE CONDITIONS	4
8.0	CONCLUSIONS	5
8.1	Existing Landslide and Slope Stability	5
9.0	RECOMMENDATIONS	7
9.1	Site Preparation and Grading	7
9.2	Pavement Design	10
9.3	Retaining Wall Design	11
9.4	Surface Drainage	15
9.5	Groundwater and Site Drainage	15
10.0	ADDITIONAL GEOTECHNICAL SERVICES	15
10.1	Consultation During Final Design	15
10.2	Construction Observation and Special Inspection	16
11.0	LIMITATIONS	16
12.0	REFERENCES	16

FIGURES

FIGURE 1	SITE LOCATION MAP
FIGURE 2	SITE PLAN
FIGURE 3	CGS SEISMIC HAZARDS
FIGURE 4	REGIONAL FAULT MAP
FIGURE 5	REGIONAL GEOLOGIC MAP

**GEOTECHNICAL REPORT
 3708 BAYSHORE BOULEVARD
 BRISBANE, CALIFORNIA 94005**

1.0 INTRODUCTION

This report presents the results of our geotechnical for the proposed improvements at the subject site. While plans are preliminary, we understand the intent is to extend the existing storage yard into an adjacent site.

2.0 SITE DESCRIPTION

The subject site is a 5000-square-foot plot of land located on the west side of Bayshore Boulevard, approximately 1500 feet south of the intersection of Brisbane Boulevard and Tunnel Avenue. The site lies within parcel APN 007-350-120, which is bordered by Bayview Boulevard to the northeast, undeveloped lots to the northwest, west and southwest, and the existing MK Pipeline equipment yard to the southeast. A site plan can be found in Figure 2.

The proposed site is located at the eastern end of the parcel. The site has been cleared of heavy brush and debris and is currently vacant. The proposed yard area is mostly level, but the eastern portion slopes towards Bayshore Boulevard at an approximate slope of 3:1-2:1. The approximate location of the proposed site within the parcel is shown on Figure 2.

3.0 PROPOSED IMPROVEMENTS

Our understanding of the proposed improvements was informed by a site walk with you. Based on our observations in the field, we understand that the plans involve extending the existing MK Pipeline equipment yard into the new lot, with the existing driveway and lot serving as the access point from Bayshore Boulevard. To maximize the square footage of the proposed storage yard, we anticipate minor excavation work into the existing hillside and fills along Bayshore Boulevard may be necessary. We anticipate a drilled deepened foundation system to retain proposed cuts along the western and northwest side of the site and a reinforced earth concrete block wall system along Bayshore Boulevard may be required to level the site for the proposed storage yard.

4.0 SCOPE OF WORK

Our services were performed in accordance with our proposal dated 7 February 2023. Our services included a preliminary geotechnical data review, a site-specific field investigation to check for the depth to bearing soils and engineering analyses for foundation support. Based on the results of our studies, we developed geotechnical conclusions and recommendations regarding the following:

- site preparation and grading,
- pavement design based on assumed R-values and traffic indexes,
- lateral earth pressures for site walls,
- interlocking concrete block site walls,
- seismicity and preliminary conclusions regarding geologic hazards, and
- construction considerations.

A review of the existing foundation elements or retaining walls was beyond the scope of our services. The conclusions and recommendations presented herein are strictly intended to underpin the existing foundations to address where the foundations have been undermined. Corrosion studies and waterproofing are beyond our scope of services. The civil aspects of drainage systems are beyond our scope of services. We can provide a separate scope and fee to evaluate additional geotechnical aspects for the proposed development upon request.

5.0 DATA REVIEW

We performed a preliminary geotechnical data review for the site and site vicinity. This included a review of the mapped special studies zones and the seismic hazard zone report for San Mateo County, regional seismicity, previous geotechnical investigations by others, and published geologic maps. Additional references indicated in this section and others are listed in Section 12.

5.1 State of California Special Studies Zones

The State of California has mapped active fault zones, and zones of potential liquefaction and earthquake-induced landslides. These zones are typically referred to as Special Studies Zones. Unless otherwise referenced, we identified whether the site lies within a special studies zone based on the information available at: <https://maps.conservation.ca.gov/cgs/EQZApp/app/>.

A detailed study of seismic hazards is beyond the scope of this report. Figure 3 presents a map of special studies zones mapped within the project vicinity. A summary of our review of the State of California Special Studies Zones is presented below.

5.1.1 State of California Seismic Hazard Zones

The site is not located within a mapped liquefaction zone. The nearest liquefaction zones are roughly 190 feet downslope to the east at the shoreline of Brisbane Lagoon, and roughly 1500 feet upslope to the west at the intersection of San Bruno Avenue and Mendocino Street in a residential neighborhood.

The site is located within a mapped landslide zone. This is likely due to the presence of a historic landslide at the site.

The site is not within a State of California Earthquake Fault Zone, as defined by the Alquist-Priolo Earthquake Fault Zoning Act of 1972. The San Andreas Fault Zone is mapped approximately 4.5 miles to the southwest. A map of faults within the region of the site is presented as Figure 4.

5.2 Regional Seismicity

The major active faults in the area are the San Andreas, San Gregorio, Hayward, Rodgers Creek, and Calaveras Faults. These and other faults in the region are shown in Figure 4. The two closest faults, the San Andreas and Hayward Faults are approximately 4.5 miles and 13.5 miles to the southwest and northeast measured orthogonally to the site, respectively.

The U.S. Geological Survey's Working Group on California Earthquake Probabilities (WGCEP, 2013) has determined that the overall probability of moment magnitude 6.7 or greater earthquake occurring before 2044 is 72 percent. The probability of a moment magnitude 6.0 or greater earthquake occurring during the same period is 98 percent.

5.3 Regional Geology

The site is within the Coast Ranges geomorphic province of California that is characterized by rugged northwest-trending mountain chains, valleys, and ridges. The predominant geologic structure and topographic features are controlled by folds and faults that resulted from the collision of the Farallon tectonic plate and the North American tectonic plate and subsequent right-lateral strike-slip faulting along the San Andreas Fault system (Wagner and others, 1990). The San Andreas Fault is more than 600 miles

long as mapped from Point Arena in the north to the Gulf of California in the south (Jennings and Bryant, 2010). The Coast Ranges province is bounded on the east by the Great Valley and on the west by the Pacific Ocean.

We reviewed published geologic maps for the site vicinity. A representative geologic map (Bonilla, 1998) is presented as Figure 5. The near surface unit is mapped as Landslide Deposits (Ql). The surrounding vicinity is mapped as Sandstone and Shale (KJsk). The relevant geologic unit description for the subject site from published sources is included below:

- Ql, (Landslide Deposits, Quaternary) – Composition and structure depend on the geologic formation involved in type of landslide.
- KJsk, (Sandstone and shale) Sandstone generally containing more than two percent potassium feldspar.

The information regional geology is presented for informational purposes only. The geologic units indicated on published maps are not intended to be used for site specific analyses. Actual conditions can and often do vary from mapped geologic units and contact locations.

6.0 GEOTECHNICAL FIELD RECONASSAINCE

We visited the site on 31 March 2023 to observe the near surface soil conditions within large diameter test holes. A 24-inch solid flight auger was used to excavate potholes across the proposed equipment yard site.

7.0 SUBSURFACE CONDITIONS

We logged the near surface soils to a maximum depth of under 10 feet across the proposed equipment yard site. We found the site to be overlain by native landslide deposits to the maximum depths explored. We found the landslide deposits were consistent with observations made at adjacent sites and they generally consisted of lean clay with sand and gravel; gravel and cobbles with sand; cobbles and boulders.

Free groundwater was not encountered in our borings at any depths explored during our field investigation. Groundwater levels may vary seasonally and depend on a variety of factors, such as

landscaping irrigation upslope of the site, localized dewatering, and seasonal rainfall. Groundwater is typically encountered at the interface between geologic contacts (i.e. soil and bedrock) and within sand lenses in native clays. Perched groundwater and seasonal springs were not observed during this investigation but may be present within the general site vicinity.

8.0 CONCLUSIONS

From a geotechnical and geologic standpoint, we conclude the proposed site may be utilized as an equipment yard for storage. the primary geotechnical considerations for the site with respect to the proposed development are the existing landslide and slope stability.

8.1 Existing Landslide and Slope Stability

The nearest evidence of recent slope failure can be observed directly above and adjacent to the existing MK Pipelines property which sits within the base of a historic large landslide. Evidence of the landslide includes a prominent curvilinear scarp directly above the existing property that trends to the west and the southwest as well as what appears to be a toe or historic debris flow of landslide material protruding from the shore into Brisbane Lagoon to the east of the property across Bayshore Boulevard. Historic aerial photographs indicate a road previously crossed the hillslope from north to south. Approximately 325 feet of this road is missing within the scarp above MK Pipelines; Google Maps shows this missing section of road labeled as: "Washed out Roadway 1936". Aerial photographs dating as early as 1941 show a landslide directly within and surrounding the property currently occupied by MK Pipelines. While little or no vegetation is observable within the landslide scar, the 1941 photo shows at least 4 structures standing within the boundaries of the slide, and what appears to be a recently repaired section of Bayshore Boulevard directly below the landslide, suggesting some time had passed between the slope failure and the 1941 air photo flight. Geotechnical borings conducted by Gilpin Geosciences (2014) and Treadwell and Rollo (2007) within adjoining parcels to the northwest and west were also reviewed for this investigation. The nearest geotechnical boring, boring GGI-5 is located upslope of the MK Pipeline site at an elevation of 125'. Boring log data from GGI-5 shows an approximately 25-foot-thick section of landslide material overlying bedrock at an elevation of approximately 100 feet.

A complete study of the site and potential slope instability is beyond the scope of this report; however, based on our evaluation of the data from adjacent sites, we conclude that there does exist a potential for

future land sliding at the site and vicinity: shallow failures may occur due to the steepness and material strength of the near surface materials on the hillside above and deep seated failures may occur due to discontinuities, shear zones and fracturing of the bedrock below the site. We further conclude that construction of a storage yard consisting of minor cuts and fills should have minimal impact on the overall stability of the hillside provided the recommendations presented herein and the following constraints are adopted. Care should be taken to not undermine the hillside above the storage yard which could result in a greater potential for shallow failures and to maintain the overburden at the site to not reduce the resisting forces at the base of the deep-seated potential landslide. The support of new fill along Bayshore Boulevard should also be considered.

- A buffer zone approximately 8 feet wide should remain in place between the proposed storage yard and the toe of the behind (to the west/northwest of) the storage yard. This toe has been defined on the plans prepared by Savior P. Micallef Land Surveying, titled, "Site Plan MK Yard, LLC 3708 Bayshore Blvd," and dated November 8, 2022. The buffer zone may encroach and new wall cut into a minor portion of the defined toe where the existing slope is shallower than 2:1 (horizontal:vertical) and adjacent to the southwest and northwest parcel boundaries.
- A buffer zone of at least 10 feet in width should remain in place between any fill required for the proposed storage yard and Bayshore Boulevard.
- The volume of materials cut should not exceed that filled across the site (not including new pavement materials) such that the average overburden is not reduced.
- Cuts should be limited to a maximum of about six feet along the western side of the proposed storage yard.
- A permanent retaining structure utilizing deepened foundations should be constructed where cuts are required.
- Fills along Bayshore boulevard are engineered and bear on stable materials or foundations.
- All grading and structural plans are reviewed by the geotechnical engineer.

9.0 RECOMMENDATIONS

This section presents our geotechnical recommendations regarding site preparation and grading, pavement design, design of retaining walls, groundwater and surface drainage, and seismic design parameters.

9.1 Site Preparation and Grading

Areas to be graded should be cleared of vegetation, deleterious materials, existing slabs, pavements and other existing improvements where grading is to be performed. Following site preparation, the geotechnical engineer should check site conditions, any excavations, any soil subgrade and any proposed fill materials. The geotechnical engineer should check for the presence of potentially weak soil. Stripped materials can be stockpiled for future use or disposed of; these materials should be approved for use on a case-by-case basis.

After site preparation, we anticipate the majority of the site grading will consist of cuts and fills to level the proposed storage yard site.

All subgrade should be relatively level, free of any debris or loose/disturbed material, and should be kept moist until covered. Minor grades may be required to facilitate the flow of surface run-off and groundwater.

The contractor should be familiar with the use of standard types of compaction equipment for different soil types and moisture conditioning of soil. We can provide additional recommendations regarding moisture conditioning, if required.

9.1.1 Temporary and Permanent Slopes

We anticipate both temporary and permanent slopes will be required to develop the site as planned. Temporary slopes should not exceed a 1:1 slope (horizontal:vertical). Shallower slopes may be required depending on the materials observed. Minor vertical cuts of less than 5 feet may be utilized without shoring; however, where these cuts are below the existing slope to the west, they should be performed in sections not exceeding about 10 feet in total width unless approved by the geotechnical engineer on-site. Non-sequential sections may be excavated at once as long as there is at least 20 feet between any given section.

Permanent slopes should be no steeper than 2:1 (horizontal:vertical) on average. All temporary and permanent slopes should be reviewed by the geotechnical engineer prior to construction.

9.1.2 Engineered fill

We recommend engineered fill consist of either on-site soil, select fill (imported to the site). Other options may be used in lieu of engineered fill such as lean concrete or geofoam; however, the geotechnical engineer should be consulted prior to the placement of any fill materials. We recommend that the geotechnical engineer be present prior to and during the placement of any fill material.

Prior to the placement of engineered fill, the soil subgrade should be checked and if required, moisture conditioned and compacted to accept new fill materials. Where weak soils are observed, additional methods such as overexcavation and replacement, utilization of a geotextile or geogrid, or the use of admixtures may be required to stabilize a subgrade.

On-site soil should be approved by the geotechnical engineer before use. Any organic or other deleterious materials should be removed. Any chunks of soil, large rock fragments or cobble greater than 4-inches in smallest diameter should be either crushed or removed prior to placement.

Select fill should consist of soil that is non-corrosive, free of organic matter, free of (or tested for) hazardous substances, smaller than d responsibility to check that any fill meets the project requirements and for any potential negative impact it may have on the site. A sample of the proposed fill materials should be submitted to the geotechnical engineer for testing at least three days prior to use at the site. Analytical (environmental) testing is beyond the scope of geotechnical engineering, but we may be able to facilitate testing upon request.

Engineered fill should be moisture-conditioned, placed in horizontal layers (lifts), and compacted. The required lift thickness will depend on the materials and compaction equipment used but should not exceed 12-inches. In most cases, soil lifts should not exceed eight inches where lightweight compaction equipment is used. The compaction equipment selected by the contractor should match the material type and compaction requirements.

Table 1 presents typical compaction and moisture requirements for general cases. Specific compaction requirements should be addressed during final design and in the field. The geotechnical engineer may

utilize different methods to estimate whether compaction has been achieved that may or may not include density testing to determine relative compaction. Compaction requirements are subject to change depending on actual conditions. The requirements presented are only valid where placement of engineered fill is observed by the geotechnical engineer.

TABLE 1
TYPICAL COMPACTION REQUIREMENTS

CASE	RELATIVE COMPACTION ¹ (percent)	MOISTURE CONDITIONING
General Fill	90+	above optimum
Pavement Subgrade	90+	above optimum
Pavement Base	95+	above optimum
Foundation Subgrade	95+	above optimum
Exterior Flatwork	90+	above optimum
Utility Trenches	95+	Above optimum
Fills Greater Than Five Feet Thick	95+	above optimum
Clean sand and gravel	95+	Above optimum
Expansive Soil (all cases)	88 – 93	3 percent above optimum

moisture-conditioned not exceeding eight inches in loose thickness, moisture-conditioned to above the optimum moisture content, and compacted to at least 90 percent relative compaction. Fills deeper than five feet should be compacted to at least 95 percent relative compaction.

¹Relative compaction refers to the in-place dry density of soil expressed as a percentage of the maximum dry density of the same material, as determined by the ASTM D1557-00 laboratory compaction procedure.

9.1.3 Exterior Flatwork and Pavements

Exterior flatwork and pavements within the public right of way (sidewalk and driveway) should be constructed in accordance with local requirements. Exterior flatwork and pavements within the property may either be designed by the engineer of record, installed per the manufacturer's recommendations or per the means and methods of the contractor. The geotechnical engineer should check the subgrade prior to the placement of any materials.

Subgrade for exterior flatwork and pavements should extend at least three feet beyond the edges of the proposed area of improvement where space and site geometry permits. At a minimum, subgrade should be scarified at least 8 inches, moisture conditioned and compacted.

9.1.4 Utility Trench Backfill

Where underground utilities are proposed, utility trenches should conform to the current CAL-OSHA requirements. To provide uniform support, pipes or conduits should be bedded on a minimum of four inches of sand or fine gravel. After the pipes and conduits are tested, inspected (if required) and approved, they should be covered to a depth of six inches with sand or fine gravel, which should be mechanically tamped.

Backfill for utility trenches should be compacted according to the recommendations presented for engineered fill. Jetting of trench backfill should not be permitted. Special care should be taken when backfilling utility trenches beneath exterior flatwork and pavements. Settlement due to improperly placed engineered fill may result in excessive differential settlement and damage.

9.2 **Pavement Design**

The State of California flexible pavement design method was used to develop the recommended asphalt concrete (AC) pavement sections. The final soil subgrade in pavement areas will likely consist of fill. We conservatively assumed a resistance value (R-value) of 10 for pavement design, which is representative of low-plasticity clayey sand and clayey gravel materials. The R-value should be confirmed by further testing once the road subgrade is exposed or the fill source for road subgrade is identified.

Table 2 presents our pavement section recommendations for traffic indices (Tis) of 4.5, 5.0, 6.0, 7.0 and 9.0. Actual TIs should be determined through a traffic engineer's analysis of expected automobile and truck traffic at the site.

TABLE 2
RECOMMENDED ASPHALT PAVEMENT SECTIONS (INCHES)

TI	Asphaltic Concrete (inches)	Class II Aggregate Base (inches)
4.5	2.5	8.5
6.0	3.5	11.5
7.0	4.0	14.5
9.0	5.5	19.0

The soil subgrade beneath AC pavements should be prepared and compacted in accordance with the recommendations presented in this report. In addition, the subgrade should be a firm and non-yielding surface. The subgrade should be proof-rolled to confirm it is non-yielding prior to placing the aggregate base. Care should be taken to properly moisture condition the soil subgrade and not allow the subgrade to dry prior to placement of the aggregate base. If the subgrade is allowed to dry out, it should be ripped, moisture conditioned and recompacted. The Class 2 aggregate base should be moisture-conditioned to near optimum moisture content and compacted to at least 95 percent relative compaction.

For all impermeable pavement types, to prevent irrigation water from entering the pavement sections, curbs adjacent to landscaped areas should extend through the aggregate base and at least three inches into the underlying soil. In addition, permeable pavement sections should incorporate a vertical impermeable barrier where they are immediately adjacent to non-permeable pavements and flatwork.

9.3 Retaining Wall Design

We anticipate a combination of systems will be utilized to level the site for the proposed storage yard: a reinforced earth system or concrete block retaining walls where the first course of concrete blocks acts as the foundation and deepened drilled piers or soldier piles for retention systems where cuts are below the toe of the exiting hillside. Our recommendations for foundations are presented below.

9.3.1 Concrete Block Retaining Walls

Where concrete block retaining walls are constructed, the first course of concrete block should bear on an engineered select fill foundation or levelling pad. Manufacturers specifications should be followed; however, at a minimum, we recommend a 12-inch-thick layer of Class II aggregate base compacted to at least 95 percent be constructed prior to the placement of the first course of concrete block. The first course of concrete block will likely be constructed below final grades per the manufacturer's specifications. A geotextile or soil reinforcement material may be required below the subgrade. We recommend the Class II aggregate base extent at least 1 foot in front of and behind the first course of concrete block where feasible.

Where concrete block walls are greater than about three feet in height above the lowest adjacent grade, they should be mechanically stabilized earth (MSE).

Where concrete block walls bear on an existing slope, it may be required to deepen the first course of concrete block or utilize deepened foundations to support the wall.

9.3.2 Deepened Foundations

Deepened foundations consisting of drilled reinforced cast-in place piers may be required to support new walls. Piers may consist of a soldier pile system where primarily utilized for lateral support. We recommend that piers gain vertical support in friction from the soils and that end bearing be neglected unless specifically approved based on the means and methods of the contractor. We recommend that where piers are utilized for lateral support they extend into the bearing layer at least twice the height of the proposed wall height. For level ground, the bearing layer should be taken as the ground surface. For sloping ground the bearing layer should be taken as the depth where there is at least 10 feet of lateral confinement between the pier face and the slope face.

For piers spaced no closer than three pier diameters, center to center. We recommend designing drilled piers using skin friction values of 500 and 650 psf for dead-plus-live and total loads, respectively, for loads acting in compression. The allowable uplift capacity of the drilled piers may be taken as 80 percent of the capacity in compression.

Drilled piers may utilize passive pressure for lateral resistance below the bottom of the undocumented fill using a lateral earth pressure corresponding to an equivalent fluid weight of 300 pcf up to a maximum uniform pressure of 2,000 psf.

The passive resistance values include a factor of safety of about 1.5 and may be used in combination without reduction.

The bottoms of the pier holes should be free of debris and water before placement of concrete. The drilling contractor should be familiar with difficult drilling conditions as blocks of bedrock may be encountered within the landslide deposit. Casing may be required locally to prevent caving. We do not anticipate groundwater will be encountered during pier drilling. If groundwater is encountered, however, the pier hole should be pumped dry prior to placement of concrete. If the hole cannot be pumped dry prior to placement of concrete, then the concrete should be placed by tremie methods. Concrete should be placed on the same day the holes are drilled.

We should review the final development plans and modify our recommendations regarding drilled piers prior to the final design submission.

9.3.3 Lateral Earth Pressures

Our recommended lateral earth pressures are presented in Table 3 below. Lateral earth pressures are presented for two cases: 1) Where cuts are required into existing grades along the rear of the proposed storage yard and 2) Where fills are required for non-reinforced concrete block walls. A creep force is included for walls which are cut into existing grade. We do not anticipate a seismic increment will be required for design since the walls should be less than six feet in total height. The designer should consider the freeboard in the total wall height for temporary loading due to site erosion. The lateral earth pressures do not include dynamic loading due to rockfalls or instability of the slope above.

Surcharges due to storage of equipment and materials, as well vehicular loading should be evaluated as plans are finalized; however, a 250 pounds per square foot uniform loading on the back of site walls may be used for preliminary design and should be confirmed by the designer.

TABLE 3
LATERAL EARTH PRESSURES FOR RETAINING WALLS

Design Pressure	Walls Supporting Cuts	Walls Supporting Engineered Fill
ACTIVE	90 pcf	40 pcf

The equivalent lateral earth pressures presented above are for walls less than about six feet in height and which are back drained such that groundwater pressures will not build up behind these walls. Drainage may consist of premanufactured panels, French drains, or walls which allow the flow of water through them (lagged walls). Where walls are not backdrained, we should be consulted to provide revised lateral earth pressures.

Where fills are required behind retaining walls, select fill should be used. Lightweight compaction equipment should be used to reduce stresses induced on the retaining walls during fill placement unless the walls are appropriately braced. Retaining walls should be backfilled before framing or subsequent construction to minimize effects of initial wall deflections due to backfill placement.

9.3.4 MSE Retaining Wall Design and Construction Considerations

For static loading, MSE walls required a minimum reinforcement length of 0.7 times the height of the wall. MSE walls constructed within seismically active areas may require a minimum reinforcement length of up to 1.1 times the height of the proposed wall.

For an MSE wall with a minimum reinforcement length of 0.7 time the height of the wall, a lateral displacement at the top of the wall between about 1 inch and 2.5 inches should be anticipated. For new engineered fills greater than five feet in thickness, settlements on the order of ½ inch for every five feet of new fill thickness should be anticipated. Differential settlement between different fill thicknesses should be anticipated. Therefore, any flatwork should be flexible and maintenance may be required to maintain final grades for surface run-off.

MSE walls should be designed per the manufacturer's specifications. We can provide additional geotechnical design parameters upon request. We should review the MSE retaining wall design prior to construction.

9.4 Surface Drainage

Positive surface drainage should be provided to direct surface water away from new foundation elements and the top of any wall or slopes. Under no circumstances should any surface run-off be re-directed to any slope on-site. Any collected runoff, including water from downspouts should be discharged into the sewer system or a containment system.

9.5 Groundwater and Site Drainage

The proposed site excavations may encounter seasonal springs at the interface between geologic contacts. Furthermore, groundwater seepage may occur in the future even if seepage is not observed during construction. Where groundwater or evidence of groundwater is encountered during construction, we should be notified to evaluate if additional measures are required to control the flow of groundwater at the site.

The final design should include measures to intercept groundwater where it may impact the proposed construction. Where collected, groundwater should be discharged to a suitable collection point.

10.0 ADDITIONAL GEOTECHNICAL SERVICES

Our report is based on a limited data review, widely spaced exploration points and preliminary development plans. Future geotechnical services should include: consultation during final design, plan and calculation review and construction observation.

10.1 Consultation During Final Design

We can consult with the design team during the development of the structural plans, civil plans, and selection of the contractor. We should review the geotechnical aspects of the project documents prior to construction. Our role as geotechnical engineer is contingent on this review.

10.2 Construction Observation and Special Inspection

During construction, our staff can provide on-site observation and testing during site preparation, temporary excavations, engineered fill placement, foundation installation, and other geotechnical aspects of the project.

Our observations will allow us to compare actual with anticipated subsurface conditions and to verify that the contractor's work conforms to the geotechnical aspects of the plans and specifications.

Our role as geotechnical engineer of record is contingent on performing geotechnical construction observations. Our scope during construction can be provided once final plans have been developed and approved.

11.0 LIMITATIONS

This geotechnical and geologic hazard study has been conducted in accordance with the standard of care commonly used as state-of-practice in the profession. No other warranties are either expressed or implied.

The recommendations made in this report are intended to protect the life and safety of occupants within the structure during a major seismic event on a nearby fault; damage to the structure and other improvements may still occur due to seismic forces on the proposed improvements. The recommendations made in this report are based on a limited subsurface investigation. If the subsurface conditions or the scope of the proposed improvements deviate from those described in this report, we should be notified immediately to provide supplemental recommendations as required as required by the actual conditions.

The conclusions and recommendations presented herein are subject to change based on our observations during construction. It is the responsibility of the contractor to notify us at least 48 hours in advance to request construction observation and/or special inspection. The design and implementation of any waterproofing or subsurface drainage system is beyond the scope of our services. Corrosivity analysis of the near-surface soils is beyond the scope of this report.

12.0 REFERENCES

Bonilla, M.G., (1998). Preliminary geologic map of the San Francisco South 7.5' quadrangle and part of the Hunters Point 7.5' quadrangle, San Francisco Bay area, California.


California Geological Survey, (2000). Seismic Hazard Report for the City and County of San Francisco, California, Seismic Hazard Zone Report 043.

Jennings, C.W., and Bryant, W.A., (2010). Fault Activity Map of California. California Geological Survey Geologic Data Map No. 6.

Wagner, D.L., Bortugno, E.J., and McJunkin, R.D., (1990). Geologic map of the San Francisco-San Jose quadrangle: California Division of Mines and Geology Regional Geologic Map No. 5A, scale 1: 250,000.

Working Group on California Earthquake Probabilities (WGCEP), (2013). The Uniform California Earthquake Rupture Forecast, Version 3 (UCERF 3), USGS Open File Report 2013-1165, CGS Special Report 228.

FIGURES



0 0.1 0.2 mi



Approximate scale

Base map: (c) 2023 California Earthquake Hazard Zone Application

divis
CONSULTING, INC.
GEOTECHNICAL ENGINEERING


3708 BAYSHORE BLVD
Brisbane, California


SITE LOCATION MAP

06/07/23

23-230301-01

Figure 1





EXPLANATION



Liquefaction: Areas where historic occurrence of liquefaction, or local topographic, geological, geotechnical, and subsurface water conditions indicate a potential for permanent ground displacements.



Earthquake-Induced Landslides: Areas where previous occurrence of landslide movement, or local topographic, geological, geotechnical, and subsurface water conditions indicate a potential for permanent ground displacements.



0 1000 2000 Feet



Approximate scale

Base map: State of California, Seismic Hazard Zones City and County of San Francisco, Official Map, Released November 17, 2001.

divis
CONSULTING, INC.
GEOTECHNICAL ENGINEERING

3708 BAYSHORE BLVD
Brisbane, California

CGS SEISMIC HARZARDS


06/07/23

23-230301-01

Figure 3



UCERF3 Fault Model
Slip Rates (mm/yr)



Approximate scale

divis
CONSULTING, INC.
GEOTECHNICAL ENGINEERING


3708 BAYSHORE BLVD,
Brisbane, California

REGIONAL FAULT MAP

06/07/23

23-230301-01

Figure 4

**EXPLANATION**

	Artificial Fill
	Landslide Deposits (Quaternary)
	Slope Debris and Ravine Fill (Quaternary)
	Sheared Rocks (Franciscan Formation)
	Bay Mud
	Sandstone and Shale
	Geologic contact: dashed where approximate and dotted where concealed, queried where uncertain



0 500 ft
Approximate scale

Preliminary geologic map of the San Francisco South 7.5' quadrangle and part of the Hunters Point 7.5' quadrangle, San Francisco Bay area, California: A digital database By: M.G. Bonilla, 1998

divis
CONSULTING, INC.
GEOTECHNICAL ENGINEERING

3708 BAYSHORE BLVD
Brisbane, California

REGIONAL GEOLOGIC MAP

06/07/23

23-230301-01

Figure 5

Recording requested by:
CITY OF BRISBANE

After recordation, return to:
CITY CLERK/CITY OF BRISBANE
50 PARK PLACE
BRISBANE, CA 94005

EXEMPT FROM RECORDING FEES
PURSUANT TO GOVERNMENT CODE
SECTION 6103

DECLARATION OF LOT MERGER

WHEREAS, MK YARD LLC, a California limited liability company, ("MK Yard") is the owner of certain real property situated in the City of Brisbane, County of San Mateo, State of California as described (i) in Exhibit A of this Declaration, (the Exhibit A real property being designated for San Mateo County property tax purposes as APN 007-350-100), (ii) in Exhibit B of this Declaration, (the Exhibit B real property being designated for San Mateo County property tax purposes as APN 007-350-110), and (iii) in Exhibit C of this Declaration, (the Exhibit C real property being designated for San Mateo County property tax purposes as APN 007-350-120); Collectively, the Exhibits A, B, and C real properties are commonly known as 3708 Bayshore Boulevard, Brisbane, CA 94005.

WHEREAS, MK Yard desires to merge the Exhibit A, B, and C real properties to form a separate parcel of land as described in Exhibit D and depicted in Exhibit E of this Declaration; and

THEREFORE, MK Yard HEREBY DECLARES merger of the Exhibits A, B, and C real properties as follows:

The properties described in Exhibits A, B, and C are merged and combined as one separate and complete parcel of land described in Exhibit D "Merged Parcel" and depicted in Exhibit E.

MK YARD LLC
By Sean Brennan, President
3708 Bayshore Blvd., Brisbane, CA, 94005-1400

DATE

The foregoing Declaration of Lot Merger is hereby approved by the City of Brisbane.

JOHN SWIECKI
Community Development Director
City of Brisbane

DATE

(GENERAL ACKNOWLEDGMENT BY NOTARY PUBLIC MUST BE ATTACHED)

EXHIBIT 'A'
APN 007-350-100
LEGAL DESCRIPTION OF EXISTING PARCEL
FOR PURPOSES LOT MERGER
BRISBANE, SAN MATEO COUNTY, CALIFORNIA

The land referred to herein below is situated in the City of Brisbane, County of San Mateo, State of California and is a portion of Rancho Canada De Guadalupe La Visitacion Y Rodeo Viego, more particularly described as follows:

Beginning at a point on the westerly line of Bayshore Highway, 779.86 feet due South and 1979.77 due East of the North corner of Block 3, as designated on the map entitled, "AMENDED MAP OF SUBDIVISION NO. 1, 2 AND 3 OF CITY OF VISITACION, SAN MATEO COUNTY, CALIFORNIA", which map was filed in the Office of the Recorder of the County of San Mateo, State of California, on October 14, 1908 in Book 6 of Maps at Page 45, said POINT OF BEGINNING being opposite Station 107+63.26 of said highway;

Thence southerly along curve line, being the westerly line of said highway, 105.48 feet;

Thence South 60° 28' 15" West, 226.00 feet;

Thence northerly along a curve line concentric with and 226.00 feet radially from the westerly line of Bayshore Highway 88.89 feet;

Thence North 56° 16' East, 226.00 feet to the POINT OF BEGINNING

Description prepared by Savior P. Micallef Land Surveying


 Savior P. Micallef L.S. 8289

01-12-23
 Date



EXHIBIT 'B'
APN 007-350-110
LEGAL DESCRIPTION OF EXISTING PARCEL
FOR PURPOSES LOT MERGER
BRISBANE, SAN MATEO COUNTY, CALIFORNIA

The land referred to herein below is situated in the City of Brisbane, County of San Mateo, State of California and is a portion of Rancho Canada De Guadalupe La Visitacion Y Rodeo Viego, more particularly described as follows:

Beginning at a point on the westerly line of Bayshore Highway, 779.86 feet due South and 1979.77 due East of the North corner of Block 3, as designated on the map entitled, "AMENDED MAP OF SUBDIVISION NO. 1, 2 AND 3 OF CITY OF VISITACION, SAN MATEO COUNTY, CALIFORNIA", which map was filed in the Office of the Recorder of the County of San Mateo, State of California, on October 14, 1908 in Book 6 of Maps at Page 45, said POINT OF BEGINNING being opposite Station 107+63.26 of said highway;


Thence along the westerly line of said highway, North 33° 44' 00" West, 100.00 feet;

Thence South 56° 16' 00" West, 226.00 feet;

Thence South 33° 44' 00" East, 100.00 feet;

Thence North 56° 16' 00" East, 226.00 feet to the POINT OF BEGINNING.

Description prepared by Savior P. Micallef Land Surveying


Savior P. Micallef L.S. 8289

01-12-23
Date



EXHIBIT 'C'
APN 007-350-120
LEGAL DESCRIPTION OF EXISTING PARCEL
FOR PURPOSES LOT MERGER
BRISBANE, SAN MATEO COUNTY, CALIFORNIA

The land referred to herein below is situated in the City of Brisbane, County of San Mateo, State of California and is described as follows:

Assessor's Highway Lot 4, Beginning at a point on the westerly line of Bayshore Highway known as State Highway IV-San Mateo-68-A, said point of beginning being South 56°16' 00" West, 62.50 feet and North 33° 44'00" West 100.00 feet from Station 107+63.26 B.C. of the Official Survey of the centerline of said highway;

Thence along said westerly line of said highway North 33° 44' 00" West, 100.00 feet;

Thence South 56° 16' 00" West, 226.00 feet;

Thence South 33° 44' 00" East, 100.00 feet;

Thence North 56° 16' 00" East, 226.00 feet to the Point of Beginning.

Description prepared by Savior P. Micallef Land Surveying


Savior P. Micallef

L.S. 8289

01-12-23

Date



EXHIBIT 'D'
APN 007-350-_____
LEGAL DESCRIPTION OF MERGED PARCEL
FOR PURPOSES LOT MERGER
BRISBANE, SAN MATEO COUNTY, CALIFORNIA

The land referred to herein below is situated in the City of Brisbane, County of San Mateo, State of California and is described as follows:

POINT OF COMMENCEMENT being Station 107+63.26 B.C. on the centerline of the Bayshore Highway known as State Highway IV-San Mateo-68-A;

Thence South 56°16' 00" West, 62.50 feet to a point on the westerly line of said highway right-of-way and the POINT OF BEGINNING;

Thence along the westerly line of said highway right-of-way, North 33°44'00" West, 198.76 feet;

Thence leaving said line of said highway, South 56°16'00" West, 226.00 feet;

Thence South 33°44'00" East, 198.76 feet to the beginning of a tangent curve concave right, having a radius of 1211.52 feet;

Thence along said curve through a central angle of 4°12'15" for a arc length of 88.90 feet;

Thence North 60°28'15" East, 226.00 feet to a point said westerly highway right-of-way to the beginning of a non-tangent curve concave left, having a tangent bearing of North 29° 31' 45" West and having a radius of 1,437.52 feet;


Thence along said curve highway right-of-way through a central angle 4°12'15" for an arc length of 105.48 feet to the POINT OF BEGINNING.

Containing an area of 66,885 sq ft, more or less.

END OF DESCRIPTION



A plat, entitled Exhibit "E", is attached hereto and by this reference made a part hereof.

Prepared by or under supervision of:

 01/12/23
 Savior Micallef, LS 8289 Date



Sheet 1 of 1



PLAT TO ACCOMPANY LEGAL DESCRIPTION

SCALE ; 1" = 40'
DATE: JANUARY 2023

PARCEL 1
3708 BAYSHORE BLVD,
BRISBANE, CALIFORNIA

SAVOR P. MICALLEF, L.S.8289
LAND SURVEYING
(805) 709-2423