

PLANNING AND ZONING COMMISSION Tuesday, January 28, 2025, 4:30 PM 191 5th Street West, Ketchum, Idaho 83340

AGENDA

PUBLIC PARTICIPATION INFORMATION

Public information on this meeting is posted outside City Hall.

We welcome you to watch Commission Meetings via live stream.

You will find this option on our website at www.ketchumidaho.org/meetings.

If you would like to comment on a public hearing agenda item, please select the best option for your participation:

- Join us via Zoom (please mute your device until called upon).
 Join the Webinar: https://ketchumidaho-org.zoom.us/j/89430882103
 Webinar ID: 894 3088 2103
- 2. Address the Commission in person at City Hall.
- 3. Submit your comments in writing at participate@ketchumidaho.org (by noon the day of the meeting)

This agenda is subject to revisions. All revisions will be underlined.

CALL TO ORDER:

ROLL CALL: Pursuant to Idaho Code 74-204(4), all agenda items are action items, and a vote may be taken on these items.

COMMUNICATIONS FROM COMMISSIONERS:

CONSENT AGENDA:

ALL ACTION ITEMS - The Commission is asked to approve the following listed items by a single vote, except for any items that a commissioner asks to be removed from the Consent Agenda and considered separately.

<u>1.</u> ACTION ITEM: Approval of the January 14, 2025 minutes from the Planning and Zoning Commission

PUBLIC HEARING:

2. ACTION: Recommendation to approved Warm Springs Preserve Floodplain Development Permit 24-002, as conditioned, and direct staff to return with findings of fact.

```
NEW BUSINESS:
EXECUTIVE SESSION:
ADJOURNMENT:
```



CALL TO ORDER: (00:00:24 in video)

Neil Morrow called the meeting of the Ketchum Planning and Zoning Commission to order at 4:30 p.m.

ROLL CALL:

Neil Morrow Susan Passovoy Brenda Moczygemba Tim Carter Matthew McGraw

ALSO PRESENT:

Morgan Landers – Director of Planning & Building Abby Rivin – Senior Planner Paige Nied – Associate Planner

COMMUNICATIONS FROM COMMISSIONERS: (00:00:40 in video)

None

CONSENT AGENDA: (00:00:40 in video)

None

NEW BUSINESS: (00:00:45 in video)

- 1. ACTION: Recommendation to remand the 121 Badger Lane Floodplain Development permit to the Planning and Building Department for further analysis. (00:00:50 in video)
 - Commissioner comments re 121 Badger Lane decision to remand: Brenda Moczygemba (00:01:00 in video)

Motion to Remand at 4:34 p.m. (00:04:15 in video)

MOVER: Matthew McGraw

SECONDER: Susan Passovoy

AYES: Susan Passovoy, Matthew McGraw, Tim Carter, & Neil Morrow

NAYS: Brenda Moczygemba

RESULT: ADOPTED

2. Update on the Cohesive Ketchum Comprehensive Plan and Code Update project (00:04:45 in video)

- Staff Presentation, update on status of draft Comprehensive Plan, Public Comments, upcoming Community Open House; Abby Rivin (00:04:50 in video)
- Staff Presentation on usability features, specifically the adjustable slider for the proposed Future Land Use Map; Abby Rivin. (00:07:25 in video)
- Commission questions for Staff and Staff responses regarding Public Comment, and extending the public comment period; Susan Passovoy, Morgan Landers, Matthew McGraw. (00:10:10 in video)
- Commission questions for Staff and Staff responses regarding housing density; Brenda Moczygemba, Morgan Landers. (00:17:30 in video)
- Commission questions for Staff and Staff responses regarding the next steps of the adoption draft, potential changes after the public comment period, and extending the public comment period; Brenda Moczygemba, Morgan Landers, Tim Carter, Neil Morrow, Susan Passovoy, Matthew McGraw. (00:19:10 in video)
- Commission questions for Staff and Staff responses regarding the Comprehensive Plan's overlaps/interactions with zoning ordinance & Ketchum Municipal Code; Susan Passovoy, Morgan Landers. (00:28:20 in video)
- Commission comments and Staff responses regarding public outreach for draft Comprehensive Plan; Morgan Landers, Matthew McGraw, Neil Morrow, (00:30:20 in video)

PUBLIC COMMENT: (00:37:00 in video)

- 3. Public comments
 - Tori Canfield commented on public feedback, accuracy of the future land use map with zoning changes; Tori Canfield. (00:37:20 in video)
 - Michelle Stannet commented on comparisons between current neighborhoods and potential future neighborhoods, Michelle Stannet. (00:41:10 in video)
 - Perry Boyle commented, suggesting time for public comment at every Planning & Zoning Commission meeting, commenting on adding language addressing interplay of City Council with the Comp Plan, and commenting on having a 3D model of Ketchum constructed for public use showing how Ketchum would look if entirely built to code; Perry Boyle. (00:44:40 in video)
 - Staff response to public comments; Morgan Landers. (00:46:50 in video)

NEW BUSINESS (CONT.): (00:49:30 in video)

- 4. Update of Ketchum Code Update
 - Staff presentation on update of Ketchum Development Code, compilation of Titles 16 and 17 into one combined chapter, increased usability and comprehensibility; Morgan Landers. (00:49:50 in video)
 - Commission questions and Staff responses regarding transfer of language from old Ketchum Code, and the replacement process; Tim Carter; Morgan Landers. (00:53:50 in video)
 - Commission questions and Staff responses regarding codification of changed interpretations in the code over the last 3-4 years; Brenda Moczygemba, Morgan Landers. (00:58:40 in video)

5. Staff comment on hiring of Senior Planner, and continued staffing issues; Morgan Landers (00:59:45 in video)

ADJOURNMENT:

Motion to adjourn at 5:30 p.m. (01:00:30 in video) MOVER: Susan Passovoy SECONDER: Brenda Moczygemba AYES: Brenda Moczygemba, Susan Passovoy, Matthew McGraw, Tim Carter, & Neil Morrow NAYS: RESULT: UNANIMOUSLY ADOPTED

Neil Morrow – P & Z Commissioner

Morgan Landers – Director of Planning & Building



City of Ketchum Planning & Building

STAFF REPORT KETCHUM PLANNING AND ZONING COMMISSION JANUARY 28, 2025 MEETING

PROJECT: Warm Springs Preserve

FILE NUMBER: P24-002

- **REPRESENTATIVE:**Ben Whipple, City of KetchumStacy Passmore, Superbloom, Landscape ArchitectureRob, Rio Applied Science and Engineering (ASE)
- **OWNER:** City of Ketchum
- **REQUEST:** Floodplain Development Permit for restoration activities related to the river and floodplain function, rehabilitation of riparian areas, and enhancement of fish habitat.
- LOCATION: 201-311 Bald Mountain Rd (Warm Springs Ranch Resort)
- **ZONING:** Tourist (T) and Recreation Use (RU)
- **OVERLAY:** Floodplain Management Overlay and Avalanche Overlay
- NOTICE: A public meeting notice for the project was mailed to all owners of property within 300 feet of the project site and all political subdivisions on January 8, 2025. The notice was published in the Idaho Mountain Express on January 8, 2025. A notice was posted on the project site and the city's website on January 8, 2025.

REVIEWER: Morgan Landers, AICP – Director of Planning and Building Jen Zung – Harmony Engineering

EXECUTIVE SUMMARY

The City of Ketchum acquired the 65-acre Warm Springs Preserve property in 2022 and spent the past few years developing the Warm Springs Preserve Master Plan (adopted in 2023) and a restoration plan to achieve the vision of the plan. The vision states "Warm Springs Preserve offers a unique opportunity for large-scale, community-supported creek restoration and passive recreation near the confluence of the Big Wood River and Warm Springs Creek." The plan seeks to achieve the vision through six principles including:

- Create a Preserve that is connected and accessible to all
- Design for success over time
- Support all-season multi-functional use
- Demonstrate leadership through regeneration of kealthy ecosystems for people, plants, and animals
- Restore the creek and floodplain
- Celebrate and educate about the past, present, and future of the preserve

The full master plan can be found by <u>clicking HERE</u>.

The property generally consists of seven zones which are shown and illustrated in the master plan and in the application materials included as Attachment 3. The proposed project includes a significant amount of work within and outside the floodplain. As this is a floodplain development permit, the Commission is reviewing the proposed work within the established floodplain and riparian areas which consists of restoration efforts focused on restoring the river, floodplain and riparian zones with the majority of work taking place in the creek, the lower creek edge, and southern floodplain.

The work will includes stream alterations in the form of pool and channel excavations, installation of large woody debris, and installation of a constructed riffle. These items are designed to improve the longevity and stability of the creek during flood events, minimizing degradation of the creek during high water periods. The work is also designed to increase the efficiency of the flood carrying capacity of the larger area during flood events to allow for safe and efficient movement of water through the reach with minimal damage. Finally, the restoration work that will occur, once the grading work has been completed, focuses on the stabilization of river/floodplain function and enhancement of fish habitats through an extensive and thoughtful planting plan by zone with specific plant lists for areas identified as wet and dry floodplain, near-stream riparian, in-stream aquatic, wet meadows, and wetlands. The goal of the planting plan is to create a bio-diverse ecosystem of plants to ensure the long term success and resilience of the area.

Due to the scope of the project, staff determined the complex stream alterations projects warrant review by the Planning & Zoning Commission. The project is subject to all floodplain development review criteria and standards specified in KMC §17.88.050 & 17.88.060.

Upon review of the proposed project, staff finds the project to not reduce floodwater carrying capacity, preserves the inherent natural characteristics of the floodplain, mitigates wetland impacts effectively with new wetlands, as well as meets all other applicable floodplain development criteria. A full review of all floodplain criteria can be found in Attachment 4.

BACKGROUND

The Warm Springs Preserve property has seen many transformations since the 1800s. As outlined on page 8 of the Warm Springs Preserve Master Plan, the area was a thriving ecosystem with an active floodplain with multiple meanderings streams and areas able to convey flood waters. In the 1800s and into the mid 1900s, increased human activity resulted in channelization of the stream and much of the areas able to convey flood waters were filled. As development continued within the floodplain up and down the reach, Warm Springs Creek continued to become confined and is now at high risk of stream bank erosion, channel incision, and downstream flooding. As noted above, the City of Ketchum purchased the property in 2022 and adopted the Warm Springs Preserve Master Plan in 2023.

A floodplain development permit application was received on January 9, 2024, and routed to all staff departments and Harmony Engineering and Design for review. Two rounds of review and revisions were conducted prior to scheduling the application for review by the Planning and Zoning Commission. As of the date of this report, all comments have been addressed satisfactorily through revisions to the proposed plans or though conditions of approval.

CONFORMANCE WITH FLOODPLAIN DEVELOPMENT STANDARDS:

As the project occurs within the Floodplain Management Overlay District, the project is subject to criteria and standards listed in KMC 17.88.050. Please see attachment XX for a full detailed analysis of all applicable standards. Staff finds the project to be in conformance with all standards and have highlighted a few below that result in proposed conditions of approval.

Permits from Regulatory Agencies

Ketchum requires that all permits required by outside agencies must be obtained prior to submittal of a floodplain development permit. The Administrator has the ability to waive or amend this requirement. Due to the size and complexity of the project and the many agencies that require permits, staff recommends condition of approval #1 allowing submittal of the approved permits prior to start of construction. Below is a list of required permits:

- FEMA Conditional Letter of Map Revision (CLOMR)
- Idaho Department of Water Resources Stream Alteration Permit
- Idaho Department of Environmental Quality general construction permit due to the size of project
- US Army Corps of Engineers (ACE) (authorized on February 26, 2024)

As of the date of this report, the USACE issued a letter of authorization for the project on February 26, 2024 (Attachment 1).

Comments from City Engineer

There is one access to the Warm Springs Preserve property and that is Lopey Lane. Lopey Lane is an existing road with a bridge that crosses Warm Springs Creek. Currently, the bridge is elevated as such that floodwaters pass under the bridge, not over. The bridge is not proposed to be altered as part of the project. The project does propose to improve the road once it crosses onto the Warm Springs Preserve property. As shown on Sheet C2.0 the road includes a set of two 36" culverts closer to the existing bridge and one additional bridge structure closer to the parking area. The existing driveway/road and proposed bridge/culverts are located outside of published FEMA 100-year floodplain extents and are designed to convey only a portion of Warm Springs Creek flood flows. Both facilities are designed to have a minimum of 1-foot of freeboard at the 100-year flow. The existing driveway/road does not become inundated at the 100- year flow under proposed conditions. Additionally, the bridge is designed to carry those flows with or without the culverts in place.

The city engineer did provide some minor comments related to the finished condition of the road included crowning, amount of gravel shoulder, details of drywells, and a few others that will be addressed with issuance of the final construction plans. These items will not impact the ability of the culverts or bridge to effectively convey flood waters. Condition of approval #2 addresses these items.

Bridge Stability

The existing condition of the property and stream create a high-risk environment during flood events, risking public safety and damage to properties. The channelization of Warm Springs Creek and adjacent development have made it difficult for water to move at reasonable velocities throughout the area. The proposed project includes re-grading to create additional side channels and removes historically placed fill to recreate a functioning river and floodplain that reduces the danger to the public and property. Additionally, the project proposes to address existing exposure issues related to water/sewer mains and bridges. Finally, the study conducted by the applicant and reviewed by third party engineers seeks to ensure the long-term stability of the construction. Condition of Approval 3 requires an additional scour analysis be conducted for the materials proposed within the stream near the bridge to ensure that the materials can withstand higher flows during more significant flood events.

STAFF RECOMMENDATION:

Staff recommends **approval** of the Floodplain Development Permit application (File No. P24-002) subject to the following conditions:

 A Conditional Letter of Map Revision (CLOMR) approved by FEMA and other jurisdictional permits are required for the project. Work shall not commence until all required permits from third party agencies including USACE, IDWR, IDEQ, and FEMA have been issued and provided to the Planning and Building Department.

- Prior to commencement of construction, no later than September 15, a revised civil plan set shall be submitted to the Planning and Building Department addressing all comments from the city engineer regarding reconstruction of Lopey Lane and adjacent parking areas. Civil plans shall be reviewed and approved by the City Engineer prior to construction of all items under the scope of work associated with Lopey Lane and the parking.
- 3. An additional scour analysis pertaining to materials placed in the stream near the existing Lopey Lane bridge shall be conducted to ensure the materials can withstand higher flows. The design of these materials should be designed for a 200-yr event and checked against a 500-yr event. The scour analysis shall be provided to the Planning and Building Department for review and approval prior to installation of materials.
- 4. A Construction Management Plan shall be submitted by the contractor prior to start of construction.
- 5. This approval is subject to the scope of work described in the documents shown in Attachments 1-3.
- 6. Any modification to approved plans as referenced in this approval shall be subject to a written amendment to this permit approval. If construction or improvements differ from the approved plans, such work may be subject to removal at the applicant's expense.
- 7. Following project completion, upon an annual inspection, if 80% or fewer of the plants indicated on Landscape Plan have not survived, the property owner shall re-install new plantings.
- 8. The Administrator shall conduct site inspections of work in progress. The Administrator shall make as many inspections of the work as may be necessary to ensure that the work is being done according to the terms of this permit, approved plans, and KMC 17.88. In exercising this power, the Administrator has a right, upon presentation of proper credentials, to enter the property at any reasonable hour for the purposes of inspection or other enforcement action.
- 9. Floodplain Development Permit approval shall be valid for a period of 1 year the date of signing Findings of Fact. If construction has not commenced within that time, the permit shall become null and void unless an extension is requested and granted pursuant to KMC 17.88.050.G.
- 10. No use of restricted use chemicals or soil sterilants will be allowed within one hundred feet (100') of the mean high-water mark on any property within the city limits at any time (KMC 17.88.040.C.3).
- 11. All applications of herbicides and/or pesticides within one hundred feet (100') of the mean high water mark, but not within twenty five feet (25') of the mean high water mark, must be done by a licensed applicator and applied at the minimum application rates (KMC 17.88.040.C.4).
- 12. Application times for herbicides and/or pesticides will be limited to two (2) times a year; once in the spring and once in the fall unless otherwise approved by the City Arborist (KMC 17.88.040.C.5).
- 13. It shall be unlawful to dump, deposit or otherwise cause any trash, landscape debris or other material to be placed in any stream, channel, ditch, pond or basin that regularly or periodically carries or stores water.

RECOMMENDED MOTION:

"I move to approve the Warm Springs Preserve Floodplain Development Permit application, as conditioned, and direct staff to return with the findings of fact."

ATTACHMENTS:

- 1. Application and Supplemental Documents
- 2. Warm Springs Preserve Basis of Design Report
- 3. Project Plans (landscape, irrigation, civil, stream alteration)
- 4. Floodplain Development Criteria Analysis



City of Ketchum

ATTACHMENT 1:

Application and Supporting Documents

| OFFICIAL USE ONLY |
|-----------------------|
| File Number: P24-002 |
| Date Received: 1/9/24 |
| By: HLN |
| Fee Paid: |
| Approved Date: |
| Denied Date: |
| 8y: |

Floodplain Development Permit Application

Submit completed application and documentation to planningandzoning@ketchumidaho.org Or hand deliver to Ketchum City Hall, 191 5th St. W. Ketchum, ID If you have questions, please contact the Planning and Building Department at (208) 726-7801. To view the Development Standards, visit the City website at: www.ketchumidaho.org and click on Municipal Code. You will be contacted and invoiced once your application package is complete.

When is a Floodplain Development Permit Application required?

The Floodplain Management Overlay Zoning District boundaries are represented on the official zoning map of the City.

All land within the external boundary of the special flood hazard area (SFHA) and all parcels with any portion thereof affected by said SFHA shall be considered to be within the Floodplain Management Overlay Zoning district.

All land areas within the external boundary of the SFHA shall be considered to be within the floodplain subdistrict of the Floodplain Management Overlay Zoning District. The City may make necessary interpretations of the boundary based upon the recommendation of the City Engineer or other expert.

All land areas within the external boundary of the regulatory floodway shall be considered to be within the floodway subdistrict of the Floodplain Management Overlay Zoning District. The City may make necessary interpretations of the boundary based upon the recommendation of the City Engineer or other expert.

NOTE: This permit is required for all properties containing 100 year floodplain area and Riparian Setbacks

| PROPERTY OWNER INFORMATION | |
|---|------|
| Property Owner Name(s): City of Ketchum | |
| Property Owner's Mailing Address: P.O. Box 2315 - 191 5th St., West Ketchum, ID 83340 | |
| Phone: (208)726.4228 | |
| Email: Ben Whipple (Owner's Contact + PM) bwhipple@ketchumidaho.org | |
| PROJECT INFORMATION | |
| Project Name: Warm Springs Preserve | |
| Project Representative's Name (main point of contact for project): Stacy Passmore | |
| Project Representative's Phone: 214-288-1517 | |
| Project Representative's Mailing Address: 750 Pennsylvania Ave, Denver, CO 80203 | |
| Project Representative's Email: stacy@superbloom.net | |
| Architect's name, phone number, e-mail: Michael Doty Architects | |
| Landscape Architect's name, phone number, e-mail: see above project representative | |
| Environmental consultant's name, phone number, e-mail: Rio Applied Science & Engineering | |
| Engineer's name, phone number, e-mail: Joe Young joe@rioase.com | |
| Project Address: 201-311 Bald Mountain Rd, Ketchum, ID 83340 | |
| Legal Description of parcel: WARM SPRINGS RANCH RESORT PUD BLK 2 IN CODE AREA 003002 | |
| Lot Size: 23.46 acres | |
| Zoning District: T, RU | _ |
| Overlay Zones – indicate all that apply: 🔯 Floodplain 🕱 Floodway 🗶 Riparian Zone 🖄 Avalanche 🗆 Mountain | |
| Brief description of project scope: | |
| The proposed design seeks to restore the stated characteristics of the river, floodplain, and Riparian Zone. Numerous in-channel alterations are proposed to include pool and channel excavation, installation of large woody debris, and installation of constructed riffles to achieve the project goals and objectives. The restoration plan integrates elements of limiting disturbance to areas identifies by the landowner (City of Ketchum), improving irrigation, restoring processes for improved river-floodplain function, and rehabilitation and enhancement of fish habitats. The project is part of the larger Warm Springs Preserve project, which is detailed in the Warm Springs Preserve Master Plan, approved by Ketchum City Council In 2023. A parallel application has been submitted for the proposed driveway alterations and new restroom and maintenance building, which is not in the floodplain zone. | ied |
| Value of Project: \$ Floodplain improvements are estimated to be \$2,254,000. Total project cost is estimated to be \$5.5 M including non-floodplain improvements. | |
| TYPE OF PROJECT – indicate all that apply: | |
| | 1 10 |

| New Building in Floodplain | Building Addition in Floodplain | Emergency Streambank | I Other. Please describe: |
|--------------------------------------|---|------------------------|----------------------------|
| Floodplain Development | 🛛 Streambank Stabilization / | Stabilization / Stream | Floodplain restoration and |
| | Stream Alteration | Alteration | open space trails |
| PROPOSED SETBACKS – if projec | t is a new building or an addition to a | n existing building | |
| Front: | Side: | Side: | Rear: |
| ADDITIONAL INFORMATION | | | |
| Will fill or excavation be required | in floodplain, floodway or riparian zo | ne? Yes 🖄 No | |
| If Yes, Amount in Cubic Yards: | Fill: 2,334CY Excavation: | 10,064 CY | |
| Will Existing Trees or Vegetation | be Removed? ¥es 🛛 | No 🗆 | |
| Will new trees or vegetation be p | lanted? Yes 🛛 🛛 N | o 🗆 | |

Applicant agrees in the event of a dispute concerning the interpretation or enforcement of the Floodplain Management Overlay Application, in which the City of Ketchum is the prevailing party, to pay reasonable attorney fees, including attorney fees on appeal, and expenses of the City of Ketchum. I, the undersigned, certify that all information submitted with and upon this application form is true and accurate to the best of my knowledge and belief.

Signature of Owner Representative

1/2/24 Date



Ecosystem Sciences | 202 N 9th Street, Suite 400 Boise, ID 83702 | Phone 208.383.0226 | Fax 208.368.0184 | ecosystemsciences.com

Warm Springs Preserve Project Floodplain Development Permit Application

Floodplain Management Overlay Evaluation Standards Narrative

1. The proposal preserves or restores the inherent natural characteristics of the river, floodplain, and Riparian Zone, including riparian vegetation and wildlife habitat. Development does not alter river channel unless all stream alteration criteria for evaluation are also met.

Yes, the proposed project seeks to restore the stated characteristics of the river, floodplain, and riparian zone. Numerous in-channel alterations are proposed to achieve the project goals and objectives. These include—pool and channel excavation, and installation of large woody debris and constructed riffles. The plan integrates elements of restoration—restoring processes for improved river-floodplain function, and rehabilitation and enhancement of fish habitats—while limiting disturbance to areas identified by the landowner (City of Ketchum), and improving irrigation. Applying this strategy is intended to improve habitat complexity, floodplain connectivity, and increased riparian tree- and shrub-dominated habitat to provide long-term structure and cover. The following restoration concepts are being proposed as specific actions for the project:

- i) Restore process and habitat by distributing flow and energy laterally through enabling channel migration to the extent practical, floodplain reconnection, and/or reconstructing appropriate primary and secondary channel planforms.
- ii) Restore process and reconnect habitat by increasing side channel abundance and diversity with proximal access to the primary channel.
- iii) Restore hydraulic processes, floodplain reconnection, and habitat by providing a greater diversity of channel forms. Channel geometry and planform restoration will focus on reducing channel confinement and increasing geomorphic complexity. Secondary channels will be incorporated where possible.
- iv) Protect existing areas of dense woody riparian vegetation where hydraulic complexity and habitat conditions are already favorable.
- v) Restore riparian processes by planting woody vegetation (especially cottonwood) with greater plant density along the outside of bends and in floodplain areas susceptible to channel migration and/or avulsion to ensure future channel evolution results in favorable conditions.
- vi) Restore process and habitat by increasing the abundance of instream structure (e.g., large woody debris and boulders), creating hydraulic diversity and habitat complexity while promoting more floodplain inundation and side channel development.
- vii) Restore localized hydraulic processes and habitat by modifying primary channels to result in diverse habitat units, including greater frequency of pools and greater overall range of channel geometry.

2. No temporary construction activities, encroachment, or other disturbance into the twentyfive foot (25') Riparian Zone, including encroachment of below grade structures, shall be permitted, except for approved stream stabilization work and restoration work associated with a riparian zone that is degraded.

Temporary construction activities (e.g., temporary construction access routes) and river/floodplain restoration-related disturbances as described in the response to question #1 above are being proposed within the riparian zone in numerous locations. The extent of the disturbances is specified in the Design Drawings that accompany the application. It should be noted that Rio Applied Science and Engineering (Rio ASE) considered all appropriate General Aquatic Conservation Measures when completing the design. These Conservation Measures specify how all work (within and outside of sensitive areas) shall be conducted. The Conservation Measures are included in the Design Drawings for ease of reference by the selected construction contractor and are considered requirements (not optional or mere suggestions).

- 3. No permanent development shall occur within the twenty-five foot (25') Riparian Zone, except for approved stream stabilization work and restoration work associated with permit issued under this title, or exceptions as described below:
 - a) Access to a property where no other primary access is available.
 - b) Emergency access required by the Fire Department.
 - c) A single defined pathways or staircases for the purpose of providing access to the river channel and in order to mitigate multiple undefined social paths.
 - d) Development by the City of Ketchum.

See above responses regarding proposed restoration grading and planting improvements within the 25' riparian zone. The design plans do not include building development in the 25' riparian zone. To provide ADA access to the restored floodplain area and to Warm Springs Creek, the design includes several small low-profile footbridges that cross the new pilot channels, rustic benches for seating and minimal directional signage. These are detailed in the drawings and were selected/designed to be durable to inundation and will minimally impact any hydrological flows.

4. New or replacement planting and vegetation in the Riparian Zone shall include plantings that are low growing and have dense root systems for the purpose of stabilizing stream banks and repairing damage previously done to riparian vegetation. Examples of such plantings most commonly include red osier dogwood, common chokecherry, serviceberry, elderberry, river birch, skunk bush sumac, Beb's willow, Drummond's willow, little wild rose, gooseberry, and honeysuckle. However, in rare instances the distance from the top-of-bank to the mean highwater mark is significant and the native vegetation appropriate for the Riparian Zone are low growing, drought resistant grasses and shrubs. Replacement planting and vegetation shall be appropriate for the specific site conditions. Proposal does not include vegetation within the twenty-five foot (25') Riparian Zone that is degraded, not natural, or which does not promote bank stability.

Per the attached landscape plans, the design proposes extensive revegetation of the floodplain and fill areas using site specific native species that are planted by hydrological zone. The restoration plantings include trees, shrubs and seeded grasses and perennials

that would have historically been found in this riparian floodplain area. These are defined in several zones and are based on slope and access to annual water flows.

5. Landscaping and driveway plans to accommodate the function of the floodplain allow for sheet flooding. Surface drainage is controlled and shall not adversely impact adjacent properties including driveways drained away from paved roadways. Culvert(s) under driveways may be required. Landscaping berms shall be designed to not dam or otherwise obstruct floodwaters or divert same onto roads or other public pathways.

A significant amount of re-grading of existing high terraces located adjacent to Warm Springs Creek is being proposed thereby converting these disconnected areas to active riverine floodplains capable of activating/inundating on a near annual basis. These areas are designed to look and function as natural floodplains and are designed to accommodate sheet flooding from Warm Springs Creek. Any/all storm drainage generated onsite and from off-site (run-on) locations will be retained onsite or drain back to Warm Springs Creek within the project extents and will have no change in impacts to adjacent properties. Landscaping berms in the form of spoil piles generated from project excavations are located outside of existing 100-year floodplain extents and drainage from these features will not impact existing or proposed roads or public pathways. Storm drainage within proposed parking areas is designed to be contained/infiltrated onsite. Two new bridge/culverts are proposed within the new floodplain intended to convey floodplain flows through the project site and back to Warm Springs Creek. These hydraulic structures are designed to convey only a portion of flood flows and will be designed to have a minimum of 1-foot of freeboard at the 100-year flow.

6. Floodwater carrying capacity is not diminished by the proposal.

Rio ASE is currently coordinating with City of Ketchum's floodplain administrator to complete a Conditional Letter of Map Revision (CLOMR). Preliminary hydraulic modeling/analyses indicate that base flood elevations (BFE's) will be reduced or stay the same (compared to FEMA published values) as a result of proposed project activities.

7. Impacts of the development on aquatic life, recreation, or water quality upstream, downstream or across the stream are not negative.

This project seeks to improve aquatic habitats as described in the responses to questions #1 and #18. Proposed new recreation access and opportunities are described in the responses to questions #8 and #17. Proposed water quality improvements are described in the responses to questions #8 and #18 (e.g., fine sediment storage on the floodplain, stabilization of banks through riparian planting and bank stability provided by wood habitat structures, and thermal buffering provided by shading and a more robust riparian corridor).

8. Building setback in excess of the minimum required along waterways is encouraged. An additional ten-foot (10') building setback beyond the required twenty-five foot (25') Riparian Zone is encouraged to provide for yards, decks and patios outside the twenty five foot (25') Riparian Zone.

The design plans do not include building development in the floodplain or within 35' of the riparian areas. The proposed restroom and maintenance building is over 35' from the closest edge of the new proposed floodplain area and is over 200' from the closest point on the Creek. There are several small low-profile footbridges and benches within the new

floodplain area to provide ADA access to the Creek.

- 9) The top of the lowest floor of a building located in, or partially within, the SFHA shall be at or above the Flood Protection Elevation (FPE). A building is considered to be partially within the SFHA if any portion of the building or appendage of the building, such as footings, attached decks, posts for upper story decks, are located within the SFHA. See section 17.88.060, figures 1 and 2 of this chapter to reference construction details. See Chapter 17.08 of this title for definition of "lowest floor."
 - a) In the SFHA where Base Flood Elevations (BFEs) have been determined, the FPE shall be twenty-four inches (24") above the BFE for the subject property; twenty-four inches (24") or two (2) feet is the required freeboard in Ketchum city limits.
 - b) In the SFHA where no BFE has been established, the FPE shall be at least two (2) feet above the highest adjacent grade.

The design plans do not include buildings or development in the floodplain or SFHA.

- 10. The backfill used around the foundation in the SFHA floodplain shall provide a reasonable transition to existing grade but shall not be used to fill the parcel to any greater extent.
 - a) Compensatory storage shall be required for any fill placed within the floodplain.
 - b) A CLOMR-F shall be obtained prior to placement of any additional fill in the floodplain.

There are no structures proposed within SFHA's.

11. All new buildings located partially or wholly within the SFHA shall be constructed on foundations that are designed by a licensed professional engineer.

There are no structures proposed within SFHA's..

12. Driveways shall comply with City of Ketchum street standards; access for emergency vehicles has been adequately provided for by limiting flood depths in all roadways to one foot (1-ft) or less during the 1% annual chance event.

The design plans do not include new driveways in the floodplain or SFHA. However, the design includes two new bridge/culverts under the existing driveway/road into the project site. The existing driveway/road originates from Bald Mountain Road, crosses Warm Springs Creek to the south via an existing bridge (which this project does not intend to modify/impact), and continues to a proposed parking area. The existing driveway/road and proposed bridge/culverts are located outside of published FEMA 100-year floodplain extents. These hydraulic structures are designed to convey only a portion of Warm Springs Creek flood flows and will be designed to have a minimum of 1-foot of freeboard at the 100-year flow. The existing driveway/road does not become inundated at the 100-year flow under proposed conditions.

13. Landscaping or revegetation shall conceal cuts and fills required for driveways and other elements of the development.

The entire restoration area will be extensively revegetated per the landscaping plans to restore the native planting regime adjacent to Warm Springs Creek. Grading and topography have been carefully designed to be as natural as possible and to minimize steep slopes.

14. (Stream alteration.) The proposal is shown to be a permanent solution and creates a stable situation.

All proposed stream alteration design elements are intended to be permanent solutions addressing existing limiting factors to in-stream habitat and river and floodplain processes. However, post-construction adaptive management may be needed (pending an evaluation from all stakeholders) to address unintended responses (if any) which is common in restoration projects of this scope. All wood structures are designed to withstand estimated hydraulic conditions at the 100-year flow. Engineered riffle materials for constructed riffles in the mainstem Warm Springs Creek and at bridge/culvert locations were sized based on the 100-year flow. Constructed riffles within the Baldy Side Channel are sized to withstand hydraulic conditions at the 1.5-year flow. Limiting factors, design criteria, methods, and approaches are discussed in more detail in the basis of design report.

15. (Stream alteration.) No increase to the one percent (1%) annual chance flood elevation at any location in the community, based on hydrologic and hydraulic analysis performed in accordance with standard engineering practice and has been certified and submitted with supporting calculations and a No Rise Certificate, by a registered Idaho engineer.

Rio ASE is currently coordinating with City of Ketchum's floodplain administrator to complete a Conditional Letter of Map Revision (CLOMR).

16. (Stream alteration.) The project has demonstrated No Adverse Impact or has demonstrated all impacts will be mitigated.

Rio ASE is currently coordinating with City of Ketchum's floodplain administrator to complete a Conditional Letter of Map Revision (CLOMR). Preliminary hydraulic modeling/analyses indicate that base flood elevations (BFE's) will be reduced or stay the same (compared to FEMA published values) as a result of proposed project activities. A CLOMR is FEMA's comment on a proposed project that would result in a modification of the existing regulatory floodway or effective BFEs.

17. (Stream alteration.) The recreational use of the stream including access along any and all public pedestrian/fisher's easements and the aesthetic beauty shall not be obstructed or interfered with by the proposed work.

This project seeks to increase access to Warm Springs Creek and floodplain areas within the entire project reach by all recreational users and will not obstruct or restrict access at any location. Access to Warm Springs Creek will be enhanced by the addition of a pedestrian trail network with some portions of the trail being ADA compliant. Users of the proposed Warm Springs Preserve will be allowed to explore freely and are encouraged to utilize proposed access points with direct access to the Warm Springs Creek channel and other features including a new pond and new side channels.

18. (Stream alteration.) Fish habitat shall be maintained or improved as a result of the work proposed.

Within the project area, Warm Springs Creek flows through and over relic glacial outwash and alluvium. Over the past several thousand years, the modern Warm Springs Creek has slowly incised through this material, leaving behind sets of terraces. More recently,

the terraces within the project area have been mechanically altered to accommodate land use and development, including a golf course. Similarly, the stream channel has been artificially confined, concentrating flow and creating further incision and floodplain abandonment. There is virtually no floodplain connectivity within the northern half of the project reach, even at the 100-year recurrence interval flow. The southern half of the project has marginally better floodplain connectivity, activating at around the 5-year recurrence interval flow. Channel incision is expected to continue where flood flows lack the ability to spread out and dissipate energy on the floodplain, and instead are concentrated on the bed and banks. As a result of incision and concentrated stream flow, much of the fine sediment has been scoured from the streambed, leaving behind a relatively uniform layer of coarse cobble bed armor. This condition has created a channel morphology that is predominantly plane-bed with only occasional pools formed by large flow constrictions caused by boulders, logs, tree roots and/or human infrastructure such as bridge abutments. Fine sediment introduced to the system tends to fill interstitial spaces between the armor causing severe embedment, further reducing pool formation and spawning habitat quality. Most of the Warm Springs Creek banks within the project area are stable; many are also armored with riprap. Bank erosion is only prevalent where there is a lack of bank material stability including tree roots and riprap. Much of the abandoned floodplain vegetation has been cleared or converted to non-native species. The incised stream channel has likely lowered the groundwater table and has certainly reduced the frequency and magnitude of groundwater recharge via the floodplain. Past geotechnical explorations on the site reveal the late-summer groundwater table is over 10 feet below the floodplain surface in many areas. Few riparian species can survive on the abandoned floodplain. Cottonwood trees and willow shrubs persist only along the nearbank riparian area where water is accessible. At the downstream end of the reach, where Warm Springs Creek approaches the Big Wood River, less incision has occurred, the floodplain is more accessible, the groundwater table is presumably higher (relative to the floodplain elevation), and healthy, native riparian vegetation is much more prevalent. This project seeks to restore river and floodplain processes to improve the quantity, quality, and diversity of aquatic habitats. Fish habitat is expected to be improved as discussed in the response to question #1a.

19. (Stream alteration.) The proposed work shall not be in conflict with the local public interest, including, but not limited to, property values, fish and wildlife habitat, aquatic life, recreation and access to public lands and waters, aesthetic beauty of the stream and water quality.

This project does not seek to conflict with local public interest and much public outreach and coordination performed by the City of Ketchum and stakeholders has already occurred and will continue as the design progresses. This project does not seek to reduce the value of adjacent properties but does seek to improve aquatic and terrestrial habitats, recreation and access, water quality, and riparian and upland plant communities.

20. (Stream alteration.) The work proposed is for the protection of the public health, safety and/or welfare such as public schools, sewage treatment plant, water and sewer distribution lines and bridges providing particularly limited or sole access to areas of habitation.

Rio ASE analyzed perceived risk associated with large woody material using the Large Woody Materials–Risk Based Design Guidelines (Knutson and Fealko, 2014). Based on the analysis (Appendix B of the Basis of Design Report), the estimated risk to public safety and property damage are both high primarily due to the numerous residential

houses immediately adjacent to Warm Springs Creek and existing bridge used to access the site within the project reach. Based on the risk-based design guidelines, a design flow event equal to or greater than the 100-year peak flood is recommended. Rio ASE has selected the 100-year flow as the design flow for all wood structures, project wide. This project also does not seek to impact the existing bridge on Warm Springs Creek and includes wood habitat structures (for improved habitat and bank stability) and a new side channel (for added conveyance capacity) in the lower portion of the project reach to address existing bank instabilities in the near vicinity of an existing sewer line.

21. (Wetlands) Where development is proposed that impacts any wetland the first priority shall be to move development from the wetland area. Mitigation strategies shall be proposed at time of application that replace the impacted wetland area with an equal amount and quality of new wetland area or riparian habitat improvement.

A formal wetland delineation has not been performed within the Warm Springs Preserve project area. Ecological units (e.g., riverine, riparian, and aspen/cottonwood communities), which contain likely WOTUS/associated wetlands have been mapped within the project area. All proposed actions for the project have been overlaid by the mapped ecological units (see Warm Springs Preserve Stream and Enhancement Design Set—60% Design Drawings). Most of the proposed actions that intersect possible wetlands are within Warm Springs Creek's active riverine channel. There is a limited extent of vegetated wetlands that occur within the riparian or aspen/cottonwood community ecological units. The proposed actions largely avoid areas where vegetated wetlands possibly occur. Where proposed actions to likely WOTUS/associated wetlands or riparian areas are unavoidable, a mitigation ratio of 1:1 or greater has been applied. The post implementation project condition is expected to result in a net gain in the quantity and quality of aquatic stream habitat, including off-channel wetland/riparian areas.

Supporting Information and Attachments

- Attachment A: Site Survey Drawings
- Attachment B1: 60% Design Drawings Stream and Floodplain Enhancement
- Attachment B2: 60% Design Drawings Landscape, Parking, and Irrigation
- Attachment C: Stream and Floodplain Enhancement 60% Basis of Design Report



Acknowledgement of Floodplain Affidavit

Pursuant to Ketchum Municipal Code §17.88.040 D1, prior to the issuance of any floodplain development permit for development within the Floodplain Management Overlay District and the Waterways Review District as defined under to Ketchum Municipal Code §17.08, the property owner shall submit to the Planning and Building Department a written affidavit on a form provided by the City, signed by the property owner under seal of a notary public, of the property owner's actual knowledge that the property is located within the Floodplain Management Overlay District or the Waterways Review District. The property owner will also acknowledge that he or she is aware of the flood hazard potential for the property and is aware of the regulations the Floodplain Management Overlay Zoning District and Waterways Review District no work shall occur in these areas without city permits and approvals

Instructions

- 1. Property owner shall complete the attached affidavit.
- 2. Property Owner shall sign before a notary public and have the affidavit notarized.

3. Property Owner shall return original notarized affidavit to the City of Ketchum Planning & Building Department.

4. The Planning & Building Department shall have the notarized affidavit recorded in the records of Blaine County for the property.

5. A copy of the recorded document will be delivered to the Property Owner and filed in the City records with the building permit documents.



100000333

RECORDING REQUESTED BY AND WHEN RECORDED RETURN TO:

City Clerk, City of Ketchum PO Box 2315 Ketchum Idaho, 83340

(Space Above Line For Recorder's Use)

Acknowledgement of Floodplain Management Overlay District and Waterways Design Review District Affidavit

| Property Owner: City of Ketchum - Jade Riley (City Administrator) |
|--|
| Building Permit Number or Land Use Permit Number: |
| Property Address: 201-311 Bald Mountain Rd, Ketchum, ID 83340 |
| Legal Description: WARM SPRINGS RANCH RESORT PUD BLK 2 IN CODE AREA 003002 |
| Parcel Number: RPK |
| Scope of Work: Warm Springs Preserve Floodplain Restoration |

Please initial and fill below:

X____I acknowledge that this development and the parcel of land, or portion thereof, on which the development will be situated are within the Floodplain Management Overlay District.

___ I acknowledge this property is within the Waterways Review District.

х I have thoroughly read and fully understand Ketchum Municipal Code Title 17, Chapter 17.88 "Floodplain Management Overlay District", to include regulations for the Waterways Design Review District including regulations on activities within 100 feet of the mean high-water mark.

_! fully understand and agree to comply with Ketchum Municipal Code Title 17, Chapter 17.88.040 C.

Х _l, on behalf of myself, my personal representatives and my heirs, successors, and assignees, acknowledge by this written affidavit that said property is located within the one percent annual chance floodplain (SFHA) as defined herein, and/or said property is within the Waterways Design Review District and that a violation of the terms of Ketchum Municipal Code 17.88 shall cause the City to seek legal remedies.

X I acknowledge that the City of Ketchum Planning & Building Department shall have the notarized affidavit recorded in the records of Blaine County for the property.

Property Owner Signature

STATE OF 10440, County of 6LANDE

_____, before me, the undersigned, a Notar day of said State, personally appeared _____, known or identified to me to be the name is subscribed to the within instrument.

WITNESS my hand and seal the day and year in this certificate first above written.

Notary Public for IDALO (State)

On this

_____ Residing at: _____ KERCHUM

City of Ketchum accepts this Affidavit from (insert owner's name).

ATTEST, CITYECI JBLAIT COUNT "Presentation" 20



DEPARTMENT OF THE ARMY

U.S. ARMY CORPS OF ENGINEERS IDAHO FALLS REGULATORY OFFICE 900 NORTH SKYLINE DRIVE, SUITE A IDAHO FALLS, IDAHO 83402-1700

February 26, 2024

WALLA WALLA DISTRICT REGULATORY DIVISION

SUBJECT: NWW-2024-00033, Warm Springs Preserve

Ben Whipple City of Ketchum 191 Fifth St Ketchum, ID 83340

Dear Mr. Whipple:

We have determined that your proposed project is authorized in accordance with Department of the Army (DA) **Nationwide Permit (NWP) No. 27: Aquatic Habitat Restoration, Establishment, and Enhancement Activities**. This project is located at Warm Springs Preserve, 201-311 Bald Mountain Rd, Ketchum, Blaine County, Idaho, within Sections 11, 12, and 13 of Township 03 North, Range 17 East, near Latitude 43.6895408 and Longitude -114.3848390. Please refer to File Number NWW-2024-00033 in all future correspondence with our office regarding this project.

Project activities include the discharge of approximately 1,953 cubic yards of dirt, rocks, and woody material below the Ordinary High-Water Mark (OHWM) along a 4,800-ft reach of Warm Springs Creek, for the purpose of improving fish habitat, restoring riparian and hydraulic processes, reconnecting floodplain, and increasing groundwater recharge. The work will entail the grading of creekbanks, excavation of adjacent land to restore flood plain, the creation of creek side channels, the installation of a headgate to control water level of side channels, the creation of riffle complexes and pools within the creek, the placement of boulders and logs as habitat features within the creek and along its banks, and the planting of native vegetation. Additional work includes temporary partial-dewatering of work areas via coffer dam. All work shall be done in accordance with the submitted drawings, titled:

"Appendix_A_WSP_60pct_Design_Stream_Floodplain_Drawings_20240105"

DA permit authorization is necessary because your project may involve the discharge of fill material into waters of the U.S. This authorization is outlined in Section 404 of the Clean Water Act (33 U.S.C. 1344).

You must comply with all general and regional conditions for this verification letter to remain valid and to avoid possible enforcement actions. The general and regional permit conditions for *NWP No. 27: Aquatic Habitat Restoration, Establishment, and Enhancement Activities* are attached and also available online¹.

You must also comply with the conditions detailed in the attached Section 401 Water Quality Certification (WQC) issued by the Idaho Department of Environmental Quality (IDEQ) on December 4, 2020. If you have any questions regarding the conditions set forth in the WQC, please contact IDEQ directly at 208-736-2190, Twin Falls Regional Office.

Nationwide Permit General Condition 30 (Compliance Certification) requires that every permittee who has received NWP verification must submit a signed certification regarding the completed work and any required mitigation. This Compliance Certification form is enclosed for your convenience and must be completed and returned to us within 30 days of your project's completion.

This letter of authorization does not convey any property rights, or any exclusive privileges and does not authorize any injury to property or excuse you from compliance with other Federal, State, or local statutes, ordinances, regulations, or requirements which may affect this work.

This verification is valid until **March 14, 2026**, unless the NWP is modified, suspended, or revoked. If your project, as permitted under this NWP verification, is modified in any way you must contact our office prior to commencing any work activities. If you will not complete construction of your project by March 14, 2026, please contact us at least 60-days prior to this date. A new application and verification may be required.

We actively use feedback to improve our delivery and provide you with the best possible service. If you would like to provide feedback, please take our online survey². If you have questions or if you would like a paper copy of the survey, please contact the Walla Walla District Regulatory. For more information about the Walla Walla District Regulatory program, you can visit us online³.

¹ <u>http://www.nww.usace.army.mil/Business-With-Us/Regulatory-Division/Nationwide-Permits/</u>

² https://regulatory.ops.usace.army.mil/customer-service-survey/

³ <u>http://www.nww.usace.army.mil/Business-With-Us/Regulatory-Division/</u>

If you have any questions or need additional information about this permit authorization, you can contact Cabel Patterson by phone at 208-541-2991, by mail at the address in the letterhead, or email at cabel.c.patterson@usace.army.mil. For informational purposes, a copy of this letter has been sent to: Bradley Dawson (IDFG), Sean Woodhead (IDEQ), and Mandy Pomeroy (Blaine County Administrator).

Sincerely,

James M. Joyner

James Joyner Chief, Upper Snake/Idaho Panhandle Branch, Regulatory Division

Encls

Transfer of Nationwide Permit Form Compliance Certification Form Joint Application for Permit NWP27 Permit Conditions Section 401 Water Quality Certification (WQC)

TRANSFER OF NATIONWIDE PERMIT

When the structures or work authorized by this Nationwide Permit, NWW-2024-00033, Warm Springs Preserve, are still in existence at the time the property is transferred. The terms and conditions of this Nationwide Permit, including any special conditions, will continue to be binding on the new owner(s) of the property. To validate the transfer of this Nationwide Permit, the associated liabilities and compliance with the terms and conditions the transferee must sign and date below.

Name of New Owner:

Street Address:

Mailing Address:

City, State, Zip:

Phone Number:

Signature of TRANSFEREE

DATE

COMPLIANCE CERTIFICATION



US Army Corps of Engineers Walla Walla District



Permit Number: NWW- NWW-2024-00033

Name of Permittee: Ben Whipple, City of Ketchum

Date of Issuance: February 26, 2024

Upon completion of the activity authorized by this permit and any mitigation required by the permit, please sign this certification and return it to the following address:

U.S. Army Corps of Engineers Walla Walla District Idaho Falls Regulatory Office 900 North Skyline Rd., Suite A Idaho Falls, Idaho 83402-1718

Please note that your permitted activity is subject to a compliance inspection by a U.S. Army Corps of Engineers representative. If you fail to comply with all terms and conditions of this permit, the permit is subject to suspension, modification, or revocation and you are subject to an enforcement action by this office.

I hereby certify that the work authorized by the above-referenced permit has been completed in accordance with the terms and conditions of the said permit. The required mitigation was also completed in accordance with the permit conditions.

Signature of PERMITEE

DATE



City of Ketchum

ATTACHMENT 2:

Warm Springs Preserve Basis of Design Report



Warm Springs Preserve Basis of Design Report (90% Design)

For Wood River Land Trust August 19, 2024



Prepared by Rio ASE | <u>Joe@RioASE.com</u> RioASE.com | Boise, ID | <u>Admin@RioASE.com</u>

AUTHORS AND CONTRIBUTORS

Authors: Rob Richardson (Rio ASE), Mark Pacold (Rio ASE), Joe Young (Rio ASE), Zach Sudman (Rio ASE)

Contributors: Erin Murray (Rio ASE)

ACKNOWLEDGMENTS

The authors and contributors of this report gratefully acknowledge the citizens of the Wood River Valley for their cooperation and involvement throughout the project. Funding for this project was provided by the City of Ketchum and the Wood River Land Trust. Lastly, we thank the Friends of the Warm Springs Preserve for their support throughout the project.

CONTENTS

| Authors a | ind Contributorsi |
|-------------|--|
| Acknowle | dgmentsii |
| Contents | |
| List of Fig | uresv |
| List of Tal | olesvi |
| List of Ac | ronymsvii |
| 1 Intro | duction1 |
| 1.1 | Project Responsible Parties1 |
| 1.2 | Site Location1 |
| 2 Proje | ect Background2 |
| 2.1 | Environmental Setting2 |
| 2.2 | Project Goals and Objectives2 |
| 3 Exist | ing Conditions4 |
| 3.1 | Hydrology4 |
| 3.2 | Geomorphology4 |
| 3.3 | Fish Use and Habitat Availability5 |
| 3.4 | Riparian Conditions and Wetlands7 |
| 3.5 | Bridges |
| 3.6 | Irrigation Diversion |
| 3.7 | Utilities |
| 4 Desi | gn Development |
| 4.1 | Proposed Project Elements |
| 4.2 | Channel Design 15 |
| 4.2.1 | Side Channel Length and Salmonid Utilization |
| 4.2.2 | 2 Flow Distribution and Channel Section15 |
| 4.3 | Bridge Design |
| 4.4 | Cost Estimates |
| 4.5 | Project Impacts |
| 5 Hydr | raulic Modeling and Analysis |
| 5.1 | Existing Conditions Model Results |
| 5.2 | Proposed Conditions Model Results 17 |
| 6 Stab | ility Analysis |

| | 6.1 | Large Woody Material Risk Assessment and Design Factors of Safety 2 | 0 |
|---|---------|---|---|
| | 6.2 | Large Wood Stability Analysis 2 | 0 |
| | 6.3 | Scour Analysis 2 | 1 |
| | 6.4 | Constructed Riffle Stability 2 | 1 |
| 7 | Const | ruction 2 | 3 |
| | 7.1 | General Aquatic and Construction Conservation Measures 2 | 3 |
| 8 | Limit | ations 2 | 5 |
| | 8.1 | Design Purposes, Persons, and Projects 2 | 5 |
| | 8.2 | Design Factors 2 | 5 |
| | 8.3 | Conditions Can Change 2 | 5 |
| | 8.4 | Report Misinterpretation 2 | 6 |
| | 8.5 | Hazards of Instream Habitat Structures 2 | 6 |
| | 8.6 | Channel Response is Unpredictable | 7 |
| | 8.7 | Monitoring and Maintenance 2 | 7 |
| | 8.8 | Construction Site Safety 2 | 7 |
| 9 | Refer | ences 2 | 8 |
| A | opendix | A 90% Design Drawings | |
| A | ppendix | B Hydraulic Model Development Technical Memo | |
| A | ppendix | C Adaptive Management Plan | |
| A | ppendix | D Construction Quantities and Cost Estimate | |
| A | opendix | E Large Wood Risk Matrix and Stability Calculations | |
| A | opendix | F Design Review Comment Tracking | |

LIST OF FIGURES

| Figure 1-1. Project vicinity | 1 |
|--|------|
| Figure 3-1. Life stages of trout and relevance to the project site. | 6 |
| Figure 3-2. Summary of health riparian conditions targeted for the project area | 8 |
| Figure 3-3. Existing wetlands (National Wetlands Inventory database, accessed December 2023) | 9 |
| Figure 3-4. Pipe exposed in the creek bed adjacent to the existing irrigation diversion. | . 11 |
| Figure 5-1. Proposed conditions inundation extent (depth) at low flow. | . 18 |
| Figure 6-1. Risk evaluations for public safety and property damage | . 20 |

LIST OF TABLES

| Table 3-1. Selected Peak Discharges (cubic ft per second [cfs]) | 4 |
|--|----|
| Table 3-2. Annual Daily Exceedance Discharges (cfs) for the USGS Gage Locations and Project Area | 4 |
| Table 4-1. Performance and Sustainability Criteria for Each Proposed Action | 13 |
| Table 4-2. Materials Discharged below OHWM or Wetlands | 16 |
| Table 4-3. Summary of Impacts to Waters of the U.S. or Wetlands | 16 |
| Table 5-1. Proposed Conditions Flow Split at Low Flow (95% exceedance flow) | 18 |
| Table 5-2. Modeled Flow Distributions and Percentages of Total Flow at Upstream End of Channels | 18 |
| Table 6-1. Large Woody Material Stability | 21 |
| Table 6-2. Constructed Riffle Material Gradations | 22 |

LIST OF ACRONYMS

| 1D – one-dimensional |
|--|
| 2D – two-dimensional |
| BMP – best management practice |
| cfs – cubic feet per second |
| CLOMR – Conditional Letter of Map Revision |
| Drawings – 90% Design Drawings |
| FEMA – Federal Emergency Management Agency |
| FHWA – Federal Highway Administration |
| ft – feet |
| FWSP – Friends of the Warm Springs Preserve |
| HEC-RAS – Hydraulic Engineering Center's River Analysis System |
| IDWR – Idaho Department of Water Resources |
| NOAA – National Oceanic and Atmospheric Administration |
| NWI – National Wetlands Inventory |
| OHWM – ordinary high-water mark |
| OSC – Idaho Governor's Office of Species Conservation |
| Report – 90 Percent Basis of Design Report |
| |
| Rio ASE – Rio Applied Science & Engineering |
| |
| Rio ASE – Rio Applied Science & Engineering |
| Rio ASE – Rio Applied Science & Engineering STA – station |
| Rio ASE – Rio Applied Science & Engineering STA – station SWPPP – storm water pollution prevention plan |
| Rio ASE – Rio Applied Science & Engineering STA – station SWPPP – storm water pollution prevention plan USACE – U.S. Army Corps of Engineers |
| Rio ASE – Rio Applied Science & Engineering STA – station SWPPP – storm water pollution prevention plan USACE – U.S. Army Corps of Engineers USBR – U.S. Bureau of Reclamation |
| Rio ASE – Rio Applied Science & Engineering STA – station SWPPP – storm water pollution prevention plan USACE – U.S. Army Corps of Engineers USBR – U.S. Bureau of Reclamation USFS – U.S. Forest Service |

1 INTRODUCTION

Rio Applied Science & Engineering (Rio ASE) has prepared this 90 Percent Basis of Design report (report) for the Wood River Land Trust (WRLT). This report provides a summary of our findings pertaining to the existing conditions of the Warm Springs Preserve project reach on Warm Springs Creek near Ketchum, Idaho, and an explanation of the design process, analyses, and outcomes for the proposed enhancement design.

Rio ASE organized the following sections of this report to describe the project scope and design approach. This report is submitted to satisfy a 90 Percent Design review by WRLT, City of Ketchum, and regulatory/permitting agencies. The conditions of the project reach are described in terms of processes that shaped the stream and associated ecosystem. This includes discussions on hydrology, hydraulics, habitat, and geomorphology. The evaluation and consideration of the site conditions provide the basis for the project stream and floodplain restoration design.

1.1 Project Responsible Parties

- The project sponsor is the Wood River Land Trust and the project manager is Cory McCaffrey, 208-788-3947.
- The design consultant for all proposed work within Warm Springs Creek and grading within the floodplain is Rio ASE and the engineer of record is Joe Young, 208-484-4700. Proposed site civil work (to include proposed parking lots, utilities, pump stations and pressurized irrigation systems, trails, and structures) is being designed by others (Superbloom and Benchmark Associates).

1.2 Site Location

The Warm Springs Preserve project reach is located on Warm Springs Creek just upstream of its confluence with the Big Wood River. The reach is about 4,800 feet (ft) long and is located about two miles west of downtown Ketchum, Idaho, on 65 acres of land owned by the City of Ketchum. Additional mapping is provided in the 90% Design Drawings (Drawings) in Appendix A.



Figure 1-1. Project vicinity.

2 PROJECT BACKGROUND

In 2022, the City of Ketchum took possession of 65 acres of the Warm Springs Ranch property and established the Warm Springs Preserve for public use. The City of Ketchum has partnered with the WRLT and various stakeholders, including the Friends of the Warm Springs Preserve (FWSP) to create a renewed landscape to enhance the streamside park. The enhancement of the Warm Springs Preserve property includes a wide range of objectives related to recreation and restoration. The scope of this piece of the larger project is only concerning the restoration and enhancement of Warm Springs Creek and the adjacent floodplain and does not include park amenities. Some of the main components of this project include restoration of aquatic habitat within the existing creek, creation of side channels, enhancement of floodplain connectivity, flood conveyance improvements, and establishment of native plant communities.

2.1 Environmental Setting

The Warm Springs Preserve project site is located just upstream from its confluence with the Big Wood River, which joins the Malad River just before the Malad flows into the Snake River. The project reach runs along the base of Bald Mountain and the adjacent land includes a former golf course, riparian zone, and steep, densely forested areas. The nearby Warm Springs Creek canyon drains a mountainous and forested area to the west, but is densely developed with residential homes within the direct vicinity of the project area. Warm Springs Road is the major arterial providing access to residential areas and recreation, including Sun Valley Ski Resort on Bald Mountain. Elevations within the project reach range from 5,800 to 6,200 ft above sea level.

Warm Springs Creek has historically meandered through a narrow river valley, changing its course due to flooding and waterway developments, but has been stabilized into its current channel with riprap and fill to protect residential developments and historical land uses. In the southeast portion, the channel moves along the former golf course and through land previously used for ranching. This area contains topsoil and gravel that previous landowners removed from the stream channel. The historical golf course abuts the steep face of Bald Mountain, which is heavily forested with Douglas fir trees and riparian understory (Walsworth, 2009).

2.2 Project Goals and Objectives

The WRLT and City of Ketchum are committed to the following priorities for the Warm Springs Preserve. Items in bold represent aspects that are addressed in this piece of the design.

- A passive park for open space in perpetuity
- Off-leash dog access
- Nordic ski trails
- Public restrooms
- New irrigation system
- Restoration of the riparian zone adjacent to Warm Springs Creek and its floodplain

The primary stream and floodplain restoration goals include:

- Enhance and increase the natural channel function of Warm Springs Creek and geomorphic processes that improve habitat suitability for trout
- Create a pond that can be used for irrigation, fishing, and dogs
- Increase floodplain inundation and floodway conveyance
- Create side channels through the floodplain to provide more diverse aquatic and riparian habitat
- Create a wetland to help mitigate loading of pollutants

Stream and floodplain restoration objectives were developed to address the primary limiting factors:

- Increase the number of large wood pieces in Warm Springs Creek
- Increase the quantity and quality of habitat diversity (aquatic, riparian, and upland)
- Increase stem density (number per area) of native shrubs and trees
- Improve site-appropriate native vegetation
- Increase floodplain connectivity
- Increase number and depth of pools

3 EXISTING CONDITIONS

3.1 Hydrology

Flow frequency analyses were performed using data from four U.S. Geological Survey (USGS) gaging stations (#13137000 Warm Springs Creek, ID; #13135500 Big Wood River NR Ketchum ID; and #13139510 Big Wood River at Hailey, ID) to estimate peak flows for input into hydraulic models discussed in this section. A detailed description of the hydrologic analyses is described in Appendix B. As part of the hydrologic analyses, basin area regressions were developed to estimate discharge values at inflow locations within each of the hydraulic models. A summary of peak flows at inflow locations is shown in Table 3-1; Table 3-2 includes a low flow (95% exceedance flow) estimated to be representative of base flow conditions in the summertime, as discussed in Appendix B. The estimated drainage area of Warm Springs Creek at the upstream limit of the project site is 96 square miles (USGS, 2023).

| Exceedance Probability | Recurrence Interval | Warm Springs Creek | Big Wood River Upstream | Big Wood River Downstream | | |
|-------------------------------|------------------------|--------------------------|-------------------------------|---------------------------------|--|--|
| 0.667 | 1.5-year | 330 | 809 | 1,139 | | |
| 0.5 | 2-year | 432 | 1,014 | 1,446 | | |
| 0.2 | 5-year | 723 | 1,548 | 2,271 | | |
| 0.1 | 10-year | 867* | 2543* | 3410* | | |
| 0.04 | 25-year | 1081* | 3402* | 4483* | | |
| 0.02 | 50-year | 1399* | 3981* | 5380* | | |
| 0.01 | 100-year | 1673* | 4690* | 6363* | | |
| *FENAL draft model discharges | | | | | | |

Table 3-1. Selected Peak Discharges (cubic ft per second [cfs])

*FEMA draft model discharges

Table 3-2. Annual Daily Exceedance Discharges (cfs) for the USGS Gage Locations and Project Area

| Annual Daily | Warm Springs Creek, | Big Wood River | Big Wood River |
|--------------|---------------------|----------------|----------------|
| Exceedance | USGS Gage 13137000 | Upstream | Downstream |
| 95% | 29 | 69 | 40 |

3.2 Geomorphology

Within the project area, Warm Springs Creek flows through and over relic glacial outwash and alluvium. As with many drainages in the region, Warm Springs Creek exhibited much greater discharge during the last ice age, generating large volumes of sediment (glacial outwash) that filled the valley (Pierce & Scott, 1982). Over the past several thousand years, Warm Springs Creek has slowly incised through this material, leaving behind sets of terraces. More recently, the terraces within the project area have been mechanically altered to accommodate land use and development, including a golf course. Similarly, the stream channel has been artificially confined, concentrating flow and creating further incision and floodplain abandonment. There is virtually no floodplain connectivity within the northern half of the project reach, even at the 100-year recurrence interval flow (see Hydraulic Modeling Maps in Appendix B). The southern half of the project has marginally better floodplain connectivity, activating at around the 5-year recurrence interval flow. Channel incision is expected to continue

where flood flows lack the ability to spread out and dissipate energy on the floodplain, and instead are concentrated on the bed and banks.

As a result of incision and concentrated stream flow, much of the fine sediment has been scoured from the streambed, leaving behind a relatively uniform layer of coarse cobble bed armor. This condition has created a channel morphology that is predominantly plane-bed with only occasional pools formed by large flow constrictions caused by boulders, logs, tree roots, and/or human infrastructure such as bridge abutments. Fine sediment introduced to the system tends to fill interstitial spaces between the armor, causing severe embedment and further reducing pool formation and spawning habitat quality. The project reach has an average bed slope of 0.83% with sub-reaches that vary from 0.4% to a constructed boulder riffle at 6.4%. Most of the Warm Springs Creek banks within the project area are stable; many are also armored with riprap. Bank erosion is only prevalent where there is a lack of bank material stability, including tree roots and riprap.

Much of the abandoned floodplain vegetation has been cleared or converted to non-native species. The incised stream channel has likely lowered the groundwater table and has certainly reduced the frequency and magnitude of groundwater recharge via the floodplain. Past geotechnical explorations on the site reveal the late-summer groundwater table is over 10 ft below the floodplain surface in many areas. Few riparian species can survive on the abandoned floodplain. Cottonwood trees and willow shrubs persist only along the near-bank riparian area where water is accessible. At the downstream end of the reach, where Warm Springs Creek approaches the Big Wood River, less incision has occurred, the floodplain is more accessible, the groundwater table is presumably higher (relative to the floodplain elevation), and healthy, native riparian vegetation is much more prevalent.

3.3 Fish Use and Habitat Availability

According to project stakeholders and reporting from the Wood River Atlas (Cardno and Ecosystem Sciences, 2020), trout abundance and size is less than desired. Current habitat limitations include:

- Lack of pool quantity and depth for overwintering and cover from predators
- Lack of instream wood for cover from predators
- Armored large bed material that results in lack of spawning gravel

Additional information regarding the life cycles of trout and the relevance to the project site is provided in Figure 3-1.

Trout Life Stages and Preferred Habitat

Trout need cool, clear water and plenty of food to eat. They also need cover from predators and room to travel upstream and down at different times of the year when feeding, overwintering and spawning.



Spawning Female trout dig a nest or redd in clean gravel shallows. As she releases her eggs, they are fertilized by the male and then covered with gravel. The gravels must be 10-40mm in size, loose and free of silt with plenty of oxygen rich water flowing through them. Spawning occurs in the spring.

> Eggs At 2-5mm in diameter, eggs incubate in clean gravels and hatch into alevins. Female rainbow trout usually produce 2000 to 3000 eggs. The eggs usually hatch in about four to seven weeks, depending on stream temperature.

Adults

Adult trout have a territory that gives them a good supply of food and a place to hide from predators, preferring deeper pools. In winter, they migrate, perhaps miles upriver, to spawn in early to late spring.

Alevins Newly hatched trout are called sac fry or alevin. Alevins stay in the gravel, living off the yolk sac. In approximately two weeks, the yolk sac is completely consumed, and fry commence feeding mainly on zooplankton. They then emerge as fry, set up territories and grow into parr. Alevins develop into parr in early summer, depnding on stream conditions.

Parr Fry and parr are territorial and solitary. They need plenty of cover in the stream from rocks, emergent and trailing bankside plants, and shallow water that is not too fast flowing. Side channels are incredibly important for native trout. They provide vital habitat and often allow these juveniles to escape high velocity flows during flood events, escape predators and offer a food resource.



Insects + Plants = Fish Food Aquatic invertebrates like insects, are integral to the trout food web. Insects feed on aquatic plants, decaying matter and microscopic animals. In turn, they become food for fish.



Riparian Vegetation

in side channels.

banks while providing shade and cover

for fish. Juvenile fish need slow water

and cover generally near the bank and



Deep Pools and Cover Adult fish need deep pools and cover often associated with instream wood and boulders.

Figure 3-1. Life stages of trout and relevance to the project site.

3.4 Riparian Conditions and Wetlands

Due to the incised/entrenched nature of the existing Warm Springs Channel there is a narrow riparian fringe and few wetlands. The northern half of the project reach has a narrow riparian corridor that exists on the channel margins. Both right and left banks through this reach are steep (2:1 or greater), which means that vegetation must be within a few feet laterally of the channel to access the adjacent groundwater associated with the channel. This reach also is considered a losing reach, meaning that groundwater elevations drop moving away from the channel, making the transition from riparian to upland even more abrupt.

The left bank through this reach is on private property, resulting in a patchwork of riparian conditions. Some landowners have left mature trees and a small riparian buffer, while others have converted their bank to mowed lawns, poured concrete, or placed riprap to protect the bank. The river right bank is within the Warm Springs Preserve property and has a fairly consistent corridor of mature trees and brush, but all contained within a narrow margin due to the steep and tall nature of the bank. There are no wetlands within the north half of the project other than the immediate channel margins and an artificial pond used for pumping water to irrigate the upland lawn.

The southern half of the project has better floodplain connectivity on the river right side. The southern floodplain is mostly grasses with stands of quaking aspen and cottonwood, as well as some wetlands along the toe of the hillslope. The river right bank is lower and more gradual than upstream, which allows for a wider riparian corridor. The river left bank through this reach is all private property as well, with a similar assortment of riparian conditions as the northern reach. A summary of healthy riparian conditions targeted for the project site is provided in Figure 3-2.

According to the National Wetlands Inventory (NWI) database managed by the U.S. Fish and Wildlife Service (USFWS), the wetlands types consist of forested/shrub and emergent in the downstream portion of the project reach. NWI wetlands are shown in Figure 3-3. A formal wetland delineation has not been completed but may be at a later time, if needed.

Riparian Stream Edge

Riparian zones are the areas bordering the stream channel and provide many environmental and recreational benefits. The Warm Springs Preserve Master Plan includes natural space near the creek for riparian forest, and meadows that transition to more manicured and park like upland terraces. The most sensitive riparian areas of the Preserve are being restored to a natural condition.

> Stream Channel

Meadow

Cottonwod - Willow

Riparian Forest This community occurs at low elevations, along the stream channel, where the water table is high and/or there is year-round water flow. Frequent spring flows provide areas of scour and sedimentation within the channel; this dynamic hydrologic regime contributes to the habitat's structural diversity and high wildlife value.

Botanical Resources

Vegetation within this community is predominantly composed of deciduous species. The tall riparian trees and dense understory result in almost full canopy cover. Typical tree species include cottonwood, willow, bittercherry, rosewood, dogwood, herbaceous shrubs and grasses.

Wildlife Resources This habitat type is noted for its very high bird species diversity and abundance. Deciduous trees and shrubs are used by nesting migrants for foraging during migration. Mature trees provide numerous cavities for cavity-dependent wildlife such as woodpeckers. Tall trees are used by nesting raptors; stream banks provide nesting for belted kingfishers. A variety of mammals utilize the dense forest for cover, shade and food.

Side Channels Side channel habitats (built specifically for aquatic species and juvenile fish) and riparian habitat are small watered remnants of major river meanders across the floodplain. On the Preserve these sites are constructed channels connecting ponds built specifically for aquatic habitat. These areas provide off-channel habitat for aquatic species and riparian habitat for terrestrial species and increases the diversity of habitat available within the stream corridor.

Fisheries Resources Vegetation rooted

at the water's edge provides cover, shade and food for fish. This is especially critical along intermittent streams where remnant summer pools provide refugia for fish. Large wood embedded in the stream bank provides cover and refuge for fish.



Dynamic + Continually Changing Riparian forests grow within an alluvial environment that is continually changing due to the ebb and flow of the stream. Riparian vegetation is constantly being reset by flooding disturbance. Mature cottonwood stands do not regenerate in place, but regenerate by "moving" up and down a river reach. Over time, a healthy riparian area supports all stages of cottonwood communities. Periodic flooding events are needed for Cottonwood seedlings to germinate and become established on newly-deposited, moist sand and gravel bars. This cottonwood community can grow into a mature riparian forest.

Figure 3-2. Summary of health riparian conditions targeted for the project area.

Side Channel



Figure 3-3. Existing wetlands (National Wetlands Inventory database, accessed December 2023).

3.5 Bridges

Currently, one single span, two-lane bridge provides access to the Warm Springs Preserve and is located approximately at the midpoint of the project reach. Concrete abutments with piles provide a bearing surface. Based on the hydraulic model results (discussed in Section 5), the bridge structure appears to adequately convey the 100-year flow.

3.6 Irrigation Diversion

Within the project reach, the Warm Springs Preserve irrigation diversion serves the Warm Springs Preserve parcel. Three water rights are stacked and have a combined use limitation of 27.9 acres and a combined diversion rate of 1.12 cfs. The primary water right, 37-212A, has a priority date of June 23, 1888, and authorizes diversion of 1.12 cfs for irrigation of 27.9 acres between April 15 and October 31. The other two water rights, 37-2621 and 37-20381, are supplemental water rights for irrigation at the same place of use. Water right 37-2621 has a priority date of August 6, 1959, and a diversion rate of 0.48 cfs. Water right 37-20381 has a priority date of November 12, 1936, and a diversion rate of 0.50 cfs. These three water rights are stacked and have a combined use limitation of 27.9 acres and a combined diversion rate of 1.12 cfs.

3.7 Utilities

As shown in the Drawings (Appendix A; Drawing C2), two known pipe crossings exist on Warm Springs Creek, both exposed in the channel bed (Figure 3-4). The design team has been engaging with the City of Ketchum to determine the use of these pipes. The pipe at station (STA) 2+50 is an active water line. A valve for this water pipe is located on the south side of Warm Springs Creek and will be preserved and protected during construction. The pipe crossing is in an area of the channel that will not be disturbed during construction. The second pipe crossing located at approximately STA 9+00 is suspected of being a part of the existing irrigation system and will also be left undisturbed during construction. The proposed design does not seek to stabilize or provide protection for these pipe crossings. Additional utilities may exist at approximately STA 24+00, where relic bridge abutments are located, as well as in other unknown locations. Rio ASE was not provide all utility linework/mapping.



Figure 3-4. Pipe exposed in the creek bed adjacent to the existing irrigation diversion.

An existing sanitary sewer is located adjacent to Warm Springs Creek near STA 48+00. As part of restoration activities, the project will stabilize the existing riprapped bank by incorporating wood habitat structures at this location. Refer to the Drawings (Appendix A) for more details on the proposed treatment.

4 DESIGN DEVELOPMENT

The restoration plan for the project reach integrates elements of limiting disturbance to areas identified by the landowner, improving irrigation, restoring processes for improved river-floodplain function, and rehabilitation and enhancement of fish habitats. The project is intended to improve habitat complexity, floodplain connectivity, and riparian tree- and shrub-dominated habitat to provide long-term structure and cover. The following restoration concepts are specific actions developed for the project reach:

- Restore process and habitat by distributing flow and energy laterally through enabling channel migration to the extent practical, floodplain reconnection, and/or reconstructing appropriate primary and secondary channel planforms.
- Restore process and reconnect habitat by increasing side channel abundance and diversity with proximal access to the primary channel.
- Restore hydraulic processes, floodplain reconnection, and habitat by providing a greater diversity of channel forms. Channel geometry and planform restoration should focus on reducing channel confinement and increasing geomorphic complexity. Secondary channels should be incorporated where possible.
- Protect existing areas of dense woody riparian vegetation where hydraulic complexity and habitat conditions are already favorable.
- Restore riparian processes by planting woody vegetation (especially cottonwood and willow) with greater plant density along the outside of bends and in floodplain areas susceptible to channel migration and/or avulsion to ensure future channel evolution results in favorable conditions.
- Restore process and habitat by increasing the abundance of instream structure (e.g., large woody debris and boulders), creating hydraulic diversity and habitat complexity while promoting more floodplain inundation and side channel development.
- Restore localized hydraulic processes and habitat by modifying primary channels to result in diverse habitat units, including greater frequency of pools and greater overall range of channel geometry.

4.1 Proposed Project Elements

The design team collaborations and interpretations of the current environmental setting have helped identify specific restoration actions for the Project Reach. These actions are listed below and depicted in the 60% Design Drawings (Appendix A):

- Improvement of the Warm Springs Preserve diversion by creating a constructed riffle and removing the
 existing concrete headworks. The existing headworks will be replaced with a natural channel that is
 designed to divert perennial flow into the proposed side channel ("Baldy Channel"). The inlet of the
 Baldy Channel will mimic a natural side channel inlet composed of soil, rock, and logs to provide
 structure and to prevent excessive erosion.
- Instream earthwork (excavation and fill) within the existing mainstem channel to create pools, point bars, and constructed riffles to develop an overall more complex riverine network.
- Installation of large and small woody debris structures to promote in-channel complexity, force hydraulic response (scour, deposition, split flow, floodplain connection, sediment sorting, and overall hydraulic diversity), and provide concealment cover for juvenile trout.
- Floodplain earthwork (excavation) to lower the floodplain to allow for more frequent activation on a semi-annual basis (2-year recurrence interval flood or greater) and to create off-channel habitat, including multiple perennial side channels and a small irrigation pond. The static volume of the proposed irrigation pond is approximately 0.6 acre ft, which is less than 2.22 acre ft, which is the 24 hour volume of the irrigation water right of 1.12 cfs.

- Installation of one 30-ft span rolled steel girder bridge and two 36-inch corrugated metal relief culverts where the parking lot access road crosses the proposed Baldy Channel and proposed floodplain swale, respectively.
- Revegetation by means of planting native species within the riparian zone and transplanting local vegetation harvested near the project site, as available. Existing mature vegetation will be preserved to the extent possible and used as floodplain roughness and/or bank roughness, where available and appropriate. Existing, mature riparian vegetation is extremely limited within the project area.

The proposed channel alignments and geometry are designed to be highly functional from baseflow through bankfull flow. The performance and sustainability criteria vary based on each proposed action summarized in Table 4-1.

| Work Element | Performance/Sustainability Criteria | | |
|---------------------------------|--|--|--|
| Headcut and Grade Stabilization | Performance: 1) Standard riffle to provide localized grade control for bankfull conditions within constructed side channels. 2) Structural control riffles to prevent headcuts and provide project-scale grade control under 100-year discharge conditions at the bridge, side-channel inlet (Baldy Channel), and the reconstructed riffle immediately upstream of the existing bridge. Develop appropriate riffle/streambed material gradation based on estimated hydraulics from the two-dimensional (2D) hydraulic model to be stable during design discharges. Sustainability: Utilize native material for riffle construction. The reduced channel slope will reduce shear stresses throughout the project area, lessening potential for incipient motion of materials. The long-term plan allows for some movement of the channel plan forms; attempting to utilize existing gravels as riffle matrix should allow riffle performance over time. Risk: The riffles become unstable and hydraulic forces lower riffle elevations, causing a reduction in floodplain activation. The risk is being countered by designing riffles to be stable up to the 100-year discharge. | | |
| Improve Floodplain Connectivity | Performance: Develop vertical profile to activate the floodplain at a more frequent (1.5- to 2-year discharge) interval primarily via floodplain excavation. Excavate, develop, and promote complex floodplain features (side channels, oxbow [irrigation] pond, high-flow swales, topographic variability) to diversify floodplain conditions at all active flows and increase floodplain connectivity. Removal of existing berms/levees will also increase floodplain connectivity. Sustainability: Initial vegetated floodplain roughness features need to survive and grow to prevent overbank erosion. Bank stability, large woody material structures, and constructed riffles will maintain channel geometry to ensure floodplain connectivity. Risk: Channel incision or channel erosion that increases channel capacity and reduces floodplain connectivity. This risk is being reduced by strategic placement of floodplain roughness, riffle stability, large woody material, and riparian revegetation to promote stability. | | |
| Protect Streambanks Using | Performance: Provide short-term stability (5 years) at strategic locations | | |
| Bioengineering Methods | by roughening banks using large woody debris or other natural materials | | |

Table 4-1. Performance and Sustainability Criteria for Each Proposed Action

Table 4-1. Performance and Sustainability Criteria for Each Proposed Action

| Work Element | Performance/Sustainability Criteria |
|--|---|
| | and planting with native riparian vegetation. Sustainability: The near-bank revegetation plan should provide rapid development of a riparian zone that will increase bank stability in the long term (+5 years). Risk: Increased erosion and channel widening reduce floodplain connectivity. This risk is being mitigated by redundancy in structures, revegetation treatments, and current activation levels of floodplain, which will all reduce energy at higher discharge events. |
| Install Habitat-Forming Natural Material Instream Structures | Performance: Large woody debris structures will be designed to withstand estimated hydraulic conditions associated with a minimum 100-year flow event. Structures will be strategically located to stabilize banks and/or to scour and/or maintain pools and provide fish cover habitat. Sustainability: The volume of wood structures installed will mitigate the short-term lack of natural large woody recruitment through the project reach. Revegetation strategy should provide future large wood recruitment once the system matures (+20 years). Risk: The loss of structures could reduce wood loading metrics below desired levels. This is mitigated through the volume of wood initially placed. The loss of structures poses risks to the Warm Springs Preserve bridge and residential dwellings by causing blockages and/or associated scour. This is mitigated by specifying a maximum log length and designing to the 100-year discharge. |
| Riparian Vegetation Planting | Performance: The planting plan utilizes local native species and a range of stock types, likely including live stakes, plugs, and containerized plants. A detailed planting plan will be developed in future design phases. Sustainability: There are cottonwood trees and willows in and around the project area, including seed sources further upstream. The proposed grading plan takes into consideration native recruitment and it is expected that native cottonwood, willow, and other plants will naturally recruit within the project area, further bolstering the plant cover. The riparian community should be naturally sustainable over time following project completion. Risk: Plants not surviving or performing poorly increases the potential for encroachment by weeds and reduced stability of graded surfaces over time due to reduced root mass and associated soil binding. This risk is being mitigated by requiring a specialized contractor to acquire and install plant materials, and by providing irrigation until plants are established. Revegetation will also be scheduled for spring to maximize the probability of success. |
| Performance: Create side channels and add instream structur diversify instream hydraulics, improve fish habitat, and increa floodplain connectivity. The floodplain will be activated at a m | |

Table 4-1. Performance and Sustainability Criteria for Each Proposed Action

| Work Element | Performance/Sustainability Criteria |
|--------------|--|
| | frequent (1.5- to 2-year) interval. Channel profile and cross sections |
| | should have less than a 10% adjustment within the first five years to |
| | promote short-term stability as vegetation becomes established. |
| | Sustainability: Long-term goals for the project are to maintain restored |
| | floodplain connection, reduce the potential for future channel incision, |
| | and maintain restored habitat complexity. |
| | Risk: In early years, prior to establishment of a robust riparian corridor that will provide dominant hydraulic control, there is risk of increased deformation. This rick is being mitigated by placement of bank. |
| | deformation. This risk is being mitigated by placement of bank roughness, large woody material structures, and constructed riffles to maintain plan form and profile in the short term. |

4.2 Channel Design

4.2.1 Side Channel Length and Salmonid Utilization

Recent biological studies of salmonids in the Upper Salmon Basin (Idaho Governor's Office of Species Conservation [OSC Team], 2019) suggest that juvenile fish utilize side channels heavily, but tend to occupy areas near inlets or outlets. Telemetry studies indicated the maximum daily movement of a juvenile salmonid is approximately 415 ft. Therefore, the proposed design incorporates multiple shorter-length side channels to maximize the number of flow convergences and divergences and connection opportunities to the primary Warm Springs Creek channel. The Baldy Channel is a long side channel bordering the upland terrace proposed to facilitate floodplain groundwater recharge and for upland irrigation needs. This long side channel has been divided into segments by including an inline oxbow (irrigation) pond and wetland. This diversity of habitat was selected to increase complexity and provide shorter stream lengths between various habitat types.

4.2.2 Flow Distribution and Channel Section

Design channel dimensions were selected based on target flow splits at the 1.5-year discharge and at low flow (selected as 29 cfs, which is the 95% exceedance flow during the summer season). Channel dimensions were initially estimated based on average reach slopes and calculations for normal depth at riffle locations. Obtaining low-flow perennial discharge was the primary factor in determining channel inverts at side channels leaving Warm Springs Creek. Channel width was largely driven by the desired flow during the 1.5-year discharge. The combination of these two controls required side channels to have a lower width-to-depth ratio than the main channel.

4.3 Bridge Design

The existing parking lot access road (Lopey Lane) will follow the existing road alignment; however, there are two proposed crossings. One crossing includes installation of two 36-inch corrugated metal flood relief culverts where Lopey Lane crosses a flood swale designed to convey floodplain flows that begin flowing at the 1.5-year discharge. This is referred to in the design drawings (Appendix A) as the Floodplain Swale. The other crossing is a 30-ft rolled steel girder bridge where Lopey Lane crosses the proposed perennial Baldy Channel.

The bridge span (width perpendicular to stream flow) was determined by multiplying the width of the channel at the 1.5-year discharge (bankfull width) by 1.5. This is the minimum width as specified by the National Oceanic and Atmospheric Administration (NOAA) to allow for fish passage and natural stream processes (NOAA, 2023). This calculation resulted in a 30-ft span for the Baldy Channel.

The crossings were incorporated into the 2D hydraulic models by grading the crossings into the Proposed Conditions terrain. Hydraulic analysis was conducted for the bridge with the assumption of no conveyance in the flood relief culverts to reflect the worst-case scenario. The bridge elevation was set such that the low chord of the bridge was 1.2-ft above the modeled 100-year discharge Proposed Conditions water surface elevation to satisfy the Idaho Department of Water Resources (IDWR) requirement of 1-ft of freeboard above the 100-year discharge. See the design drawings in Appendix A for profile views of the bridge and culverts, Section 5 for hydraulic model results, and Appendix B for discussion of model development.

4.4 Cost Estimates

Refer to Appendix D for estimated quantities and associated construction costs.

4.5 Project Impacts

Construction is planned for fall 2025; the in-water work window is July 15 to March 15. The spatial extent of disturbance is shown in the Drawings (Appendix A). Table 4-2 summarizes materials discharged below the ordinary high-water mark (OHWM) or wetlands. Although a formal wetland delineation has not been completed, ecological units for the project have been mapped. All impacts were calculated for the Active Riverine and Lacustrine zones. It is assumed that all wetlands within the project area are contained in this zone, based on the absence of observable wetlands outside of the margins of these zones (see further discussion in Section 3.4). Table 4-3 summarizes impacts to waters of the United States, including wetlands.

| Type or Material | Quantity (cubic yard) |
|--|--------------------------|
| Class 1, 2, and 3 Riffle Material for Constructed Riffles (gravel, rock, or stone) | 840 |
| Boulders (gravel, rock, or stone) | 84 |
| General Fill for Filling Existing Pond (dirt or topsoil) | 298 |
| Woody Material for Habitat Structures | 731 |
| Total | 1,953 |

Table 4-3. Summary of Impacts to Waters of the U.S. or Wetlands

| Туре | Area (acres) | Area (sq. ft) | Quantity (cubic yard) | Material |
|--|-----------------|------------------|--------------------------|---|
| Channel Fill (filling) | 0.41 | 18,010 | 1,222 | Riffle Material |
| Channel and Pool Excavation (excavation) | 0.65 | 28,417 | 978 | Native alluvium |
| Wood Material (filling) | 0.19 | 8,155 | 731 | Woody Material (for habitat structures) |
| Total | 1.25 | 54,582 | 2,931 | |

5 HYDRAULIC MODELING AND ANALYSIS

The purpose of the existing conditions hydraulic model is to determine the hydraulic conditions (depth, velocity, shear stress, and water surface elevation) for existing conditions in order to evaluate existing floodplain connectivity, in-channel and floodplain habitat conditions at high and low flows, and provide the basis for comparison with proposed conditions hydraulic modeling (to ensure project objectives are being met). The 2D hydraulic model was developed using the U.S. Army Corps of Engineers (USACE) Hydraulic Engineering Center's River Analysis System (HEC-RAS), version 6.3.1. Development of any HEC-RAS 2D hydraulic model requires delineation of the model domain, a terrain surface, designation of hydraulic roughness (Manning's n values), creation of the model mesh, and designation of boundary conditions specifying the inflow(s) hydrology and conditions for outflow(s). Each of these major components of the hydraulic model are discussed in greater detail in Appendix B.

5.1 Existing Conditions Model Results

Appendix B includes model results (depth, velocity, and shear stress) for the low flow and various recurrence interval flows for existing conditions. Interpretations of the results are summarized as follows:

- Inundation extent (and water surface elevations relative to existing bank heights) indicate the channel is disconnected from the floodplain throughout the upper project reach above the 100-year flow event and the lower project reach above the 5-year flow event.
- Lack of floodplain engagement limits riparian vegetation to a narrow vegetated riparian corridor along the left and right banks. Limited width provides little low-velocity refuge for aquatic species, such as fish, during high-flow events.
- Depth, velocity, and shear stress results indicate a substantial lack of hydraulic variability throughout the project reach.
- Difference maps illustrate the relative difference in water surface elevations, velocities, and shear stress comparing existing vs. proposed conditions.
 - These difference maps were generated from 2D hydraulic model results, which calculate hydraulic metrics longitudinally and laterally across a detailed 2D mesh (grid) rather than using depth-averaged results from individual cross sections in a one-dimensional (1D) model. A Conditional Letter of Map Revision (CLOMR) has also been submitted for this project, which uses the Federal Emergency Management Agency (FEMA) standard 1D modeling results developed from multiple cross sections. The two different modeling approaches (1D vs 2D) produce slightly different results; however, regulatory compliance will be based on the CLOMR 1D model, which does not show a rise in base flood elevations in the Warm Springs Ranch Subdivision.

The project reach is severely confined, resulting in a lack of floodplain connectivity. Combined with a homogenous channel, the project reach provides little quantity or quality aquatic habitat value.

5.2 Proposed Conditions Model Results

Appendix B includes 2D hydraulic model results (depth, velocity, and shear stress) for proposed conditions for various recurrence interval flows. Interpretations of the results are summarized as follows:

- Improved floodplain connectivity and inundation frequency throughout the upper project reach at and above the 1.5-year flow. Additionally, the lower river right floodplain is activated at 5-year flow.
- Shear and velocity remain unchanged on river left of Warm Spring Creek adjacent to existing infrastructure and residential dwellings. Additional floodplain connectivity on river right provides

increased flood conveyance and relief. These components working in concert indicate no harm or significant change in hydraulic conditions are expected to occur on river left.

- Flow splits provide perennial side channel activation; however, the design will be refined in a future phase to ensure adequate perennial water delivery to the relocated irrigation pump station. Table 5-1 summarizes proposed channel flow splits and Figure 5-1 illustrates inundation extents at low flow.
- Table 5-2 summarizes flow splits for each channel segment for various modeled proposed condition flows. The flows in the main channel and side channels past the first segments are mathematical subtractions and additions, which cause some inaccuracies at higher flows when overland flow is entering or exiting a channel.

| Channel | Flow (cfs) |
|----------------|------------|
| Baldy Channel | 5.3 |
| Dollar Channel | 1.9 |
| Sunny Channel | 0.3 |

Table 5-1. Proposed Conditions Flow Split at Low Flow (95% exceedance flow)




Figure 5-1. Proposed conditions inundation extent (depth) at low flow.

| Channel Segment | Channel Discharge (cfs) | | Percent of Total Discharge | |
|---|-------------------------|--------|----------------------------|--------|
| | Low Flow | 1.5-yr | Low Flow | 1.5-yr |
| Main Channel – Upstream of Baldy Channel | 29 | 330 | 100% | 100% |
| Main Channel – Downstream of Baldy Channel | 23.8 | 272 | 82% | 82% |
| Main Channel – Downstream of Dollar Channel | 21.9 | 246 | 75% | 74% |
| Main Channel – Downstream of Sunny Channel | 23.4 | 262 | 81% | 79% |
| Baldy Channel | 5.3 | 58 | 18% | 18% |
| Dollar Channel | 1.9 | 28 | 7% | 9% |
| Sunny Channel | 0.3 | 14 | 1% | 4% |

| Table 5-2. Modeled Flow Distributions | and Percentages of Tot | al Flow at Upstream En | d of Channels |
|---------------------------------------|------------------------|------------------------|---------------|

The bridge span for Lopey Lane was designed to be 1.5 times the bankfull width of the channel. This design width and flood relief culverts help to mitigate high shears and velocities associated with contractions and expansions at the bridge. The highest velocities and shear stresses modeled at the bridge contraction were at the 100-year discharge, having a maximum velocity of 8.3 ft/s and a maximum shear stress of 1.9 lb/ft². These results were used to design the riffle material that will compose the channel bed material through the bridge crossings to mitigate the risks of erosion and incision. See Section 6.4 for further discussion.

6 STABILITY ANALYSIS

6.1 Large Woody Material Risk Assessment and Design Factors of Safety

Large woody material structures are proposed in the main channel and side channels to provide roughness and habitat throughout the project area. There are approximately 10 different types of proposed structures. These structures will consist of key log members that act as the frame of the structure and may include wood piles. Wood structures will also include numerous racking logs and slash material. These structures are intended to emulate natural log jams.

Rio ASE analyzed the perceived risk associated with large woody material using the Large Woody Materials–Risk Based Design Guidelines (Knutson & Fealko, 2014). Based on the analysis (Appendix E), the estimated risk to public safety and property damage are both high, due primarily to the numerous residential houses immediately adjacent to Warm Springs Creek and the fact that the public park will be used by recreationalists with varying degrees of knowledge and experience with rivers and their associated hazards. The risk matrix scorings in Figure 6-1 are intended to be representative of all structures proposed within the project reach.




Figure 6-1. Risk evaluations for public safety and property damage.

These guidelines recommend a design flow event equal to or greater than the 100-year peak flood and factors of safety of 2.0 for buoyancy and 1.75 for sliding and rotation.

6.2 Large Wood Stability Analysis

Rio ASE evaluated all proposed wood structure types at the 100-year peak flood (Appendix E). A summary of the stability analyses for each structure type are shown below in Table 6-1. One structure location was analyzed for each structure type, representing critical hydraulic conditions experienced by that structure type. Factors of safety have been included in the stability analysis, which are achieved in part by incorporating existing riprap boulders where present into the design to supplement the support provided by the wood alone. For example, log structures are proposed adjacent to the City of Ketchum sewer line that is currently protected with rock riprap. During construction, the existing riprap is proposed to be removed, the wood structures installed, and the existing riprap replaced as backfill to provide ballast over the woody materials and scour countermeasures. Coarse alluvium will also be used as backfill to achieve the necessary quantity of backfill material. The top

elevation of the wood structure and backfill in this location will be near or at the 100-year base flood elevation. Wood material longevity when fully submerged below water is expected to persist for several decades (U.S. Forest Service [USFS] 1967; Bilby et al., 1999). At such time that the wood does decay, the additional rock will provide bank stability comparable to the existing condition. Also, additional wood is expected to be racked (accumulate) onto the proposed structure, which is desirable because it will provide improved habitat. The proposed wood structures will result in a modest amount of fill within the ordinary high-water extents, thereby reducing the conveyance capacity of the mainstem Warm Springs Creek channel. The proposed side channel on the opposite bank is expected to offset that lost conveyance capacity in order to retain (or lower) existing base flood elevations.

| | Factor of Safety | | |
|----------------------------|------------------|---------|--|
| Structure | Buoyancy | Sliding | |
| Minimum Requirement | 2.0 | 1.75 | |
| HS-1: Six-Log Structure | 2.2 | 2.1 | |
| HS-2: Nine-Log Structure | 2.1 | 2.1 | |
| HS-3: Single-Log Structure | 2.1 | 2.7 | |
| HS-4: Whole-Tree Structure | 2.1 | 3.0 | |
| HS-5: Constriction Jam | 2.3 | 1.9 | |
| HS-6: Small Apex Jam | 2.4 | 2.6 | |
| HS-7: Bleeder Jam | 2.1 | 3.0 | |

Table 6-1. Large Woody Material Stability

6.3 Scour Analysis

Scour analyses for each wood structure were estimated using the standard HEC-18—single-pile equation, HEC-18—effective pier width method assuming debris loading, and Froehlich's abutment scour equation. Results from the three methods were averaged to estimate scour depths at each structure.

Bridge scour was evaluated for the proposed bridge crossing on Lopey Lane. Details of this analysis are provided in Appendix B. The total potential scour of 7-ft below the design channel elevations was estimated for this structure by summing the results of contraction and abutment scour at the 500-year flow event. It is important to note that the analysis assumes native alluvium material composed of primarily sandy-gravelly material. The proposed engineered riffle material (specified in the Drawings [Appendix A] and discussed in Section 6.4 for the channel bed through the bridge opening) was sized to withstand the expected hydraulic conditions at the 100year flow.

6.4 Constructed Riffle Stability

Based on hydraulic model results for the 100-, 5-, and 1.5-year discharges, it was determined that three riffle gradation classes would be necessary to satisfy the desired stability requirements for the proposed constructed riffles. The following standard methods were used to calculate design riffle gradations:

- HEC 11 Design of Riprap Revetment Method (Federal Highway Administration [FHWA], 1989)
- EM 1601 (USACE, 1994)
- Rock Ramp Design Guidelines (U.S. Bureau of Reclamation [USBR], 2007)

Class-1: Class-1 Riffle Material is designed for the two constructed riffles on Warm Springs Creek (see Appendix A). One of these riffles (Mainstem Riffle 1) is located at the inlet to the Baldy Channel. The intent of this riffle is to reduce the risk of incision on Warm Springs Creek, which would result in reduced flows within the Baldy Channel. The other Class-1 Riffle (Mainstem Riffle 2) is located immediately upstream of the existing bridge on Lopey Lane. The intent of this riffle is to create a more stable riffle than the current configuration of boulders

that is actively eroding at this site. The hydraulic model showed that both of these riffles had worst case hydraulic conditions at the 100-year discharge, and shear stresses and velocities were similar enough that the same gradation could be used for both riffles. The highest velocities and shears were located at Mainstem Riffle 1. The maximum shear stress was modeled at 4.5 lb/ft² and the maximum velocity was modeled at 11.0 ft/s with a depth at max velocity of 5 ft. The gradation shown in Table 6-2 was developed using these hydraulic model results with the listed analysis methods, and according to incipient motion calculations (Julien, 2010), the gradation material size of D30 and larger is calculated to be stable at the 100-year discharge.

Class-2: Class-2 Riffle Material is designed primarily for the constructed riffle that will pass below the proposed bridge on Lopey Lane, the riffles downstream of the bridge, and at the inlet to the Baldy Side Channel. The hydraulic conditions were different enough from the Class-1 Riffles that it was determined that a smaller gradation would achieve stability at the 100-year design flow. The intent of the riffles is to mitigate the risk of scour through the bridge crossing, which would risk compromising the bridge sills through the downstream riffles near the confluence with Warm Springs Creek, potentially resulting in the formation of a headcut that could compromise the bridge, and through the inlet of the Baldy Side Channel, which could compromise the ability of the inlet to convey the design irrigation flow. The hydraulic model showed that these areas had worst-case hydraulic conditions at the 100-year discharge. The hydraulic conditions at the downstream riffles and the upstream inlet locations were not as erosive as the bridge crossing; however, these were identified as hydraulic controls where incision would be undesirable. The maximum shear stress at the bridge crossing was modeled at 2.0 lb/ft² and the maximum velocity was modeled at 8.0 ft/s with a depth at maximum velocity of 1.9 ft. The gradation shown in Table 6-2 was developed using these hydraulic model results with the listed analysis methods. According to incipient motion calculations (Julien, 2010), the gradation material size of D50 and larger is calculated to be stable at the 100-year discharge.

Class-3: Class-3 Riffle Material is designed for grade control with the Baldy Channel at the 1.5-year discharge, which is assumed to be the channel-forming discharge. It is anticipated that some of the native in-situ glacial outwash and alluvium that will be excavated to create the proposed floodplain and Baldy Channel will meet this gradation criteria. The contracting officer or design engineer will be on-site and responsible for determining if the in-situ materials are suitable during construction. If the material is not suitable, the contractor shall over-excavate the native material and replace it with material that meets the gradation requirements. The 1.5-year discharge model results were analyzed to determine the worst-case hydraulic conditions along the Baldy Channel. The maximum shear stress was modeled at 1.2 lb/ft² and the maximum velocity was modeled at 5 ft/s with a depth at maximum velocity of 1.8 ft. Using these hydraulic model results with the listed analysis methods, the gradation shown in Table 6-2 was developed. According to incipient motion calculations (Julien, 2010), the gradation material of D50 and larger is calculated to be stable at the 1.5-year discharge.

| Percent Passing | Class-1 Riffle Material (in.) | Class-2 Riffle Material (in.) | Class-3 Riffle Material (in.) |
|-----------------|----------------------------------|----------------------------------|----------------------------------|
| 100% (D100) | 32 | 18 | 8 |
| 84% (D84) | 26 | 14 | 6 |
| 50% (D50) | 16 | 9 | 4 |
| 30% (D30) | 12 | 7 | 3 |
| 16% (D16) | 8 | 4.5 | 2 |
| 10% (D10) | < 0.8 | < 0.5 | < 0.2 |

7 CONSTRUCTION

Construction is expected to begin in the summer and fall of 2025 and completed prior to 2026 spring high-flows.

Rio ASE considered General Aquatic Conservation Measures when completing the design. These Conservation Measures are included in the Drawings attached in Appendix A for ease of reference by the construction contractor. The following is a summary of the project's compliance with the general conservation measures.

7.1 General Aquatic and Construction Conservation Measures

- Climate change: Climate change was considered in the design. Primary features that address climate change scenarios (runoff timing, lower flows, increased temperature) include side channels, wetlands, and shallow groundwater storage. In addition to these, there will be increased floodplain connectivity and wetland habitat, which should also enhance shallow groundwater storage and subsequent surface water/groundwater connectivity in warmer months and low-flow conditions.
- **Timing of in-water work**: The approved in-water work window for the Warm Springs Creek is currently July 15th through March 15th of the following year.
- **Temporary Cofferdams**: Temporary cofferdam locations proposed for active channel work are in the design drawings (Appendix A). It is ultimately up to the contractor to determine the configuration of the cofferdams, but the contractor will be held to the requirement that any work in the active channel must be completely isolated using cofferdams and dewatered. This work is only to occur during the in-water work window.
- **Site layout and flagging**: The construction contractor will be required to stake all major project elements for approval by the contracting officer or engineer prior to construction and adhere to vertical and horizontal tolerances in accordance with the Specifications (to be developed in a future design phase).
- **Temporary access roads and paths**: Temporary access routes are shown in the Drawings (Appendix A). The construction contractor will not be allowed to deviate from the designated routes unless approved by the contracting officer or engineer.
- **Temporary stream crossings**: There are no temporary stream crossings planned. All construction access is planned to utilize temporary bridges.
- **Staging, storage, and stockpile areas**: Proposed staging and stockpile areas throughout the project area are shown in the Drawings (Appendix A). The construction contractor will not be allowed to deviate from these areas unless approved by the contracting officer or engineer.
- **Equipment**: Equipment necessary to complete the project likely will include dozers, excavators, loaders, and a variety of service vehicles. We included General Conservation and Implementation Measures as notes in the Drawings (Appendix A), and those notes indicate biodegradable lubricants are required for work below the ordinary high-water mark (OHWM).
- **Erosion control**: General Aquatic Conservation Measures in the Drawings (Appendix A) along with suggested placement of stormwater best management practices (BMP). Those include erosion control measures for temporary erosion controls, sediment barriers restricting loads to the stream, soil stabilization measures, and emergency erosion controls. Our scope does not include preparation of a project-specific storm water pollution prevention plan (SWPPP).
- **Dust abatement**: General Conservation and Implementation Measures are included in the Drawings (Appendix A). Those include recommendations regarding work scheduling, dust stabilization measures (water only), spill containment, and a restriction on petroleum-based stabilization products.
- **Spill prevention, control, and counter measures**: General Conservation and Implementation Measures are included in the Drawings (Appendix A). Those include directing the contractor to keep a list of

hazardous materials, written procedures for notification of environmental response, spill containment kits, worker training, and storage of waste liquids. Our scope does not include preparation of a SWPPP.

• **Invasive species control**: General Conservation and Implementation Measures are included in the Drawings (Appendix A). Those include directing the contractor to power wash all vehicles, inspecting inwater equipment, and a restriction on felt-soled wading boots. Our scope does not include preparation of a project-specific invasive species control plan.

8 LIMITATIONS

Some clients, design professionals, and contractors may not recognize that stream and river engineering analysis and design practices are less exact than other engineering and natural science disciplines. Such misunderstandings can create unrealistic expectations, sometimes leading to disappointments, claims, and disputes. Rio ASE includes these explanatory "limitations" provisions in our reports to help reduce such risks. Please confer with Rio ASE if you are unclear how these "Report Limitations and Guidelines" apply to your project or site.

8.1 Design Purposes, Persons, and Projects

This report has been prepared for the Client and their authorized agents and regulatory agencies for use on the Project(s) specifically designed in the report. The information contained herein is not applicable to other sites or projects.

Rio ASE structures its services to meet the specific needs of its clients. No party other than the Client may rely on the product of our services unless we agree to such reliance in advance and in writing. Within the limitations of the agreed scope of services for the Project and its schedule and budget, our services have been executed in accordance with our Agreement and generally accepted practices in this area at the time this report was prepared. We do not authorize, and will not be responsible for, the use of this report for any purposes or projects other than those identified in the report.

8.2 Design Factors

This report has been prepared solely for this Project and Client. Rio ASE considered a number of unique, projectspecific factors when establishing the scope of services for this project and report. Unless Rio ASE specifically indicates otherwise, it is important not to rely on this report if it was:

- Not prepared for you,
- Not prepared for your project,
- Not prepared for the specific site, or
- Completed before project changes were made.

For example, changes that can affect the applicability of this report include those that affect:

- The function of the proposed design and/or structure
- Elevation, configuration, location, or orientation of the proposed structures
- Composition of the design team, or
- Project ownership.

If changes occur after the date of this report, Rio ASE cannot be responsible for any consequences of such changes in relation to this report unless we have been given the opportunity to review our interpretations and recommendations in the context of such changes. Based on that review, we can provide written modifications or confirmation, as appropriate.

8.3 Conditions Can Change

This report is based on conditions that existed at the time the study/design was performed. The findings and conclusions of this report may be affected by the passage of time, by man-made events such as construction on or adjacent to the site, new information or technology that becomes available subsequent to the report date, or by natural evens such as floods, earthquakes, slope instability, stream flow fluctuations or stream channel fluctuations. If more than a few months have passed since issuance of our report or work product, or if any of

the described events may have occurred, please contact Rio ASE before applying this report for its intended purpose so that we may evaluate whether changed conditions affect the continued reliability or applicability of our conclusions and recommendations.

Any designs associated with this report may need to be adjusted in the field during construction in order to meet the specific-site conditions and intended function. Rio ASE cannot assume responsibility for the recommendations in this report if unexpected conditions are encountered during construction. We recommend that you allow sufficient monitoring and consultation by Rio ASE during construction to confirm that the conditions encountered are consistent with those indicated in the report, to provide recommendations for design changes if the conditions revealed during the work differ from those anticipated, and to evaluate whether construction activities are completed in accordance with our recommendations.

8.4 Report Misinterpretation

Misinterpretation of this report can result in costly problems. Rio ASE can help reduce the risks of misinterpretation by conferring with appropriate stakeholders after submitting the report, participating in prebid and preconstruction conferences, and providing construction observation.

To help reduce the risk of problems, we recommend giving contractors the complete report, including these "Report Limitations and Guidelines." When providing the report, we recommend that you preface it with a clearly written letter of transmittal that:

- Advises contractors that the report was not prepared for purposes of bid development and that its accuracy is limited, and
- Encourages contractors to confer with Rio ASE and/or to conduct additional study to obtain the specific types of information they need or prefer.

8.5 Hazards of Instream Habitat Structures

Instream habitat structures ("Structures") create potential hazards, including, but not limited to:

- Persons falling from the Structures and associated injury or death,
- Collisions of recreational users and their watercraft with the Structures, and associated risk of injury, and damage of the watercraft,
- Mobilization of a portion or all of the Structures during high water flow conditions and related damage to downstream persons and property,
- Flooding,
- Erosion, and
- Channel avulsion.

In some cases, instream habitat structures are only intended to be temporary, providing temporary stabilization while riparian vegetation becomes established or while stream/river processes stabilize. This gradual deterioration with age and vulnerability to major flood events make the risks with temporary Structures inherently greater with their increasing age.

Rio ASE strongly recommends that the Client appropriately address safety concerns, including but not limited to warning construction workers of hazards associated with working in or near deep and fast-moving water and on steep, slippery, and unstable slopes. In addition, signs should be placed along the enhanced stream reaches in prominent locations to warn third parties, such as nearby residents and recreational users, of the potential hazards noted above.

8.6 Channel Response is Unpredictable

In general, rivers and streams are dynamic and unpredictable. Any predictions regarding future channel evolution and/or response either stated or implied in this report or associated design(s) shall be considered an estimate based on professional judgment given the data available and conditions that existed at the time the study/design was performed. Channel evolution and/or response may include but is not limited to erosion, deposition, channel migration, avulsion, flooding, and sediment and debris transport. Channel evolution and/or response is inevitable, and it should not be assumed that any condition whether natural or constructed will persist unchanged indefinitely in a riverine environment.

8.7 Monitoring and Maintenance

In some designs, Rio ASE may have excluded piles, anchors, chains, cables, reinforcing bars, bolts and similar fasteners from woody habitat structures with the intent of mimicking naturally occurring instream wood structures. In other designs Rio ASE may have included such fasteners in woody habitat structures, if considered appropriate. While Rio ASE designs structures to be relatively stable during flood events, some movement of these structures is expected. We recommend that the Client implement appropriate monitoring and maintenance procedures to minimize potential adverse impacts at or near areas of concern, and consider replacing, adjusting and/or removing damaged, malfunctioning, or deteriorated components of structures.

8.8 Construction Site Safety

Our recommendations are not intended to direct the construction contractor's procedures, means, methods, schedule, or management of the work site during construction of any project associated with this report. The construction contractor is solely responsible for job site safety and for managing construction operations to minimize risks to on-site personnel and adjacent properties.

9 **REFERENCES**

- Bilby, R., Heffner, J. T., Fransen, B. R., Ward, J. W., & Bisson, P. A. (1999). Effects of Immersion in Water on Deterioration of Wood from Five Species of Trees Used for Habitat Enhancement Projects. North American Journal of Fisheries Management, 19(3).
- Cardno, Inc. and Ecosystem Sciences. (2020). *Big Wood River Atlas. Prepared for Blaine County, ID*. https://www.co.blaine.id.us/509/Big-Wood-River-Atlas-2020
- Federal Highway Administration (FHWA). (1989). Design of Riprap Revetment HEC 11.
- Idaho Governor's Office of Species Conservation Team (OSC Team). (2019). Upper Salmon Subbasin Habitat Integrated Rehabilitation Assessment (pp. 1–303). <u>https://modelwatershed.idaho.gov/wp-</u> <u>content/uploads/2019/12/Upper_Salmon_IRA_20190620.pd_.pdf</u>
- Julien, P. Y. (2010). Erosion and Sedimentation (2nd ed.). Cambridge University Press.
- Knutson, M., & Fealko, J. (2014). Pacific Northwest Region Resource & Technical Services Large Woody Material—Risk Based Design Guidelines (pp. 1–89). U.S. Department of the Interior Bureau of Reclamation. <u>https://www.usbr.gov/pn/fcrps/documents/lwm.pdf</u>
- National Oceanic and Atmospheric Administration (NOAA). (2023). NOAA Fisheries WCR Guidance to Improve the Resilience of Fish Passage Facilities to Climate Change (p. 151).
- Pierce, K. L., & Scott, W. E. (1982). Pleistocene episodes of alluvial-gravel deposition, southeastern Idaho. In *Cenozoic geology of Idaho* (Vol. 26, pp. 685–702). Idaho Bureau of Mines and Geology.
- U.S. Army Corps of Engineers (USACE). (1994). *Engineering and Design: Hydraulic Design of Flood Control Channels* (Engineer Manual 1110-2–1601). <u>https://www.publications.usace.army.mil/portals/76/publications/engineermanuals/em_1110-2-1601.pdf</u>
- U.S. Army Corps of Engineers (USACE). (2022). *Hydrologic Engineering Center River Analysis System (HEC-RAS)* (Version 6.3.1) [Computer software]. U.S. Army Corps of Engineers. https://www.hec.usace.army.mil/software/hec-ras/
- U.S. Bureau of Reclamation (USBR). (2007). Rock Ramp Design Guidelines (p. 102). <u>https://www.usbr.gov/tsc/techreferences/mands-pdfs/RockRampDesignGuidelines_09-</u> <u>2007_508.pdf</u>
- U.S. Forest Service (USFS). (1967). *Factors Influencing Decay of Untreated Wood* (U.S. Forest Service Research Note FPL-0154).
- U.S. Geological Survey (USGS). (2023). StreamStats. https://streamstats.usgs.gov/ss/
- Walsworth, C. T. (2009). Warm Springs Ranch: A historic context narrative 1880 to 2000. Prepared for MPE, Inc. & DDRM.

APPENDIX A 90% DESIGN DRAWINGS

APPENDIX B HYDRAULIC MODEL DEVELOPMENT TECHNICAL MEMO

APPENDIX C ADAPTIVE MANAGEMENT PLAN

APPENDIX D CONSTRUCTION QUANTITIES AND COST ESTIMATE

APPENDIX E LARGE WOOD RISK MATRIX AND STABILITY CALCULATIONS

APPENDIX F DESIGN REVIEW COMMENT TRACKING



City of Ketchum

ATTACHMENT 3:

Project Plans (landscape, irrigation, civil, stream alteration)

PROJECT NARRATIVE

A FORMER GOLF COURSE SAVED BY THE COMMUNITY, WARM SPRINGS PRESERVE IS AN EXTRAORDINARY OPPORTUNITY TO ENHANCE A WELL-LOVED LANDSCAPE AND IMPORTANT ECOSYSTEM IN THE KETCHUM COMMUNITY. IN 2022-2023 THE CITY OF KETCHUM CONDUCTED EXTENSIVE COMMUNITY OUTREACH TO DEVELOP A VISION PLAN FOR THE FUTURE OF THE PRESERVE, INCLUDING 10-ACRES OF CREEK AND FLOODPLAIN RESTORATION, UNIVERSALLY ACCESSIBLE (ADA) TRAIL IMPROVEMENTS, NEW IRRIGATION AND IMPROVED ACCESS AND PARKING. THESE ITEMS WERE OUTLINED AND REQUIRED THROUGH THE DEED OF TRANSFER WHEN THE CITY ACQUIRED THE PROPERTY, AND THE VISION PLAN WAS APPROVED BY KETCHUM CITY COUNCIL IN APRIL 2023. DUE TO THE SCALE OF THE PROJECT, THE IMPROVEMENTS INCLUDED IN THE VISION PLAN THE PROJECT MAY BE DEVELOPED IN PHASES.

AREA B: FLOODPLAIN AND MIDDLE TERRACE RESTORATION: THIS DESIGN PACKAGE INCLUDES RESTORATION DESIGN WITHIN THE FLOODPLAIN ZONE ADJACENT TO WARM SPRINGS CREEK. THE PROPOSED DESIGN SEEKS TO RESTORE THE STATED CHARACTERISTICS OF THE RIVER, FLOODPLAIN, AND RIPARIAN ZONE. NUMEROUS **IN-CHANNEL ALTERATIONS ARE PROPOSED TO INCLUDE POOL AND CHANNEL** EXCAVATION, INSTALLATION OF LARGE WOODY DEBRIS, AND INSTALLATION OF CONSTRUCTED RIFFLES TO ACHIEVE THE PROJECT GOALS AND OBJECTIVES. THE **RESTORATION PLAN INTEGRATES ELEMENTS OF LIMITING DISTURBANCE TO AREAS** IDENTIFIED BY THE LANDOWNER (CITY OF KETCHUM), IMPROVING IRRIGATION **RESTORING PROCESSES FOR IMPROVED RIVER-FLOODPLAIN FUNCTION, AND** REHABILITATION AND ENHANCEMENT OF FISH HABITATS. THE PROJECT IS PART OF THE LARGER WARM SPRINGS PRESERVE PROJECT. WHICH IS DETAILED IN THE WARM SPRINGS PRESERVE MASTER PLAN, APPROVED BY KETCHUM CITY COUNCIL IN 2023, A PARALLEL APPLICATION HAS BEEN SUBMITTED FOR THE PROPOSED DRIVEWAY ALTERATIONS AND NEW RESTROOM AND MAINTENANCE BUILDING, WHICH IS NOT IN THE FLOODPLAIN ZONE.

LEGAL DESCRIPTION

WARM SPRINGS RANCH RESORT PUD BLK 2 IN CODE AREA 003002 ADDRESS: 201-311 BALD MOUNTAIN ROAD, KETCHUM, ID 83340



VICINITY MAP

PROJECT LOT COVERAGE

TOTAL SQUARE FOOTAGE – BLOCK 6 = 195,647 SF (LOT COVERAGE OF BUILDING AND PARKING = 7.8%) TOTAL SQUARE FOOTAGE – ENTIRE WARM SPRINGS PRESERVE = 5,623,930 (LOT COVERAGE OF BUILDING AND PARKING 0.2 %)

TEAM NAMES + CONTACTS

OWNER CITY OF KETCHUM, IDAHO

ADDRESS: CITY OF KETCHUM PO BOX 2315 191 5TH ST KETCHUM, IDAHO 83340

CONTACT | BEN WHIPPLE EMAIL | BWHIPPLE@KETCHUMIDAHO.ORG

LANDSCAPE ARCHITECTURE SUPERBLOOM

ADDRESS: 750 PENNSYLVANIA AVE. DENVER, COLORADO 80203 WWW.SUPERBLOOM.NET

CONTACT | STACY PASSMORE EMAIL | STACY@SUPERBLOOM.NET PHONE | 720.310.0255 ARCHITECTURE MICHAEL DOTY ASSOCIATES, ARCHITECTS PC

ADDRESS: 371 WASHINGTON AVE NORTH KETCHUM, ID 83340

CONTACT | MICHAEL DOTY, AIA PHONE | 208.726.4228

IRRIGATION BAER DEESIGN GROUP, LLC

ADDRESS: 10674 N SAGE HOLLOW WAY BOISE, ID 83714


CONTACT | GREG BAER EMAIL | GREG@BAERDG.COM PHONE | 208.859.1980 APPLIED SCIENCE & ENGINEERING RIO APPLIED SCIENCE & ENGINEERING

ADDRESS: 3380 WEST AMERICANA TERRACE, SUITE 390, BOISE, ID 83706

CONTACT | ROB RICHARDSON PHONE | 208.559.4615

RESTORATION ENGINEER & GEOMORPHOLOGY MORELL ENGINEERING

CONTACT | MATT MORELL PHONE | 208.726.2844



WARNSPRINGS PRESERVE FLOODPLAIN DEVELOPMENT PERMIT LANDSCAPE & REVEGETATION PLANS

Issued: 12/10/24

ILLUSTRATIVE RENDERING

| | SHEET INDEX | | |
|---|--------------|--|--|
| | SHEET NUMBER | SHEET TITLE | |
| | L0.00 | COVER SHEET | |
| | L0.01 | ILLUSTRATIVE RENDERINGS | |
| | C1.0 | SITE GEOMETRY PLAN - PARKING | |
| | C2.0 | ROAD PLAN AND PROFILE | |
| CIVIL ENGINEERING | C2.1 | PARKING LOT GRADING | |
| BENCHMARK ASSOCIATES | C3.0 | UTILITY PLAN | |
| ADDRESS: | L1.00 | OVERALL PLAN | |
| , 3380 WEST AMERICANA TERRACE, SUITE 390, BOISE. ID 83706 | L1.01 | LANDSCAPE PLAN | |
| , | L1.02 | LANDSCAPE PLAN | |
| CONTACT PHOEBE JOHANNESSEN P.E. EMAIL PHOEBE@GALENA-BENCHMARK.COM | L1.03 | LANDSCAPE PLAN | |
| PHONE 208.726.9516 EXT.116 | L1.04 | LANDSCAPE PLAN | |
| RESTORATION PLANTING | L2.00 | LANDSCAPE DETAILS & PLANTING SCHEDULES | |
| INTERMOUNTAIN AQUATICS | IR1.0 | IRRIGATION - PLUMBING PLAN | |
| ADDRESS: | IR1.1 | IRRIGATION - ELECTRICAL PLAN | |
| 1499 S 600 W | IR1.2 | IRRIGATION - DETAILS | |
| REXBURG, ID 83401 | IR1.3 | IRRIGATION - DETAILS | |
| CONTACT JEFF KLAUSSMAN | IR1.4 | IRRIGATION PUMP STATION DETAILS | |
| EMAIL JEFF@NORTHFORKNATIVEPLANTS.COM PHONE 208.354.3691 | IR1.5 | PUMP PAD & WET WELL LAYOUT | |

SUPERBLOOM

 ALL EXISTING GRADING, CURB LAYOUT, EASEMENTS AND UTILITIES ARE BASED ON SURVEY INFORMATION PREPARED BY MARK PHILLIPS (2023) AND RIO APPLIED SCIENCE & ENGINEERING (2023) AND ARE SHOWN FOR INFORMATION ONLY.
 ALL PROPOSED UTILITIES, STREET LAYOUT, AND STREET & ROAD GRADING INFORMATION WAS PREPARED BY BENCHMARK ASSOCIATES ENGINEERING AND ARE SHOWN FOR INFORMATION ONLY. REFER TO CIVIL CONSTRUCTION DRAWING PACKAGE FOR FURTHER INFORMATION. NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES.

CONTRACTOR TO VERIFY LOCATION OF ALL UTILITIES ABOVE AND BELOW GRADE PRIOR TO CONSTRUCTION.

4. FINAL LIGHTING LOCATIONS TO BE STAKED AND CONFIRMED WITH LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. STREET LIGHTING WILL BE PROVIDED ON SITE PER CIVIL CONSTRUCTION

DRAWINGS. CONTRACTOR TO VERIFY LOCATIONS IN FIELD PRIOR TO COMMENCING WORK. CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT AND ENGINEER OF ANY DISCREPANCIES.

ALL ARCHITECTURAL ELEMENTS ARE SHOWN ON LANDSCAPE PLANS FOR REFERENCE ONLY. DEMOLITION AND PROPOSED ARCHITECTURAL BUILDING DOCUMENTATION SHALL BE PROVIDED UNDER SEPARATE COVER BY ARCHITECT OR MICHAEL DOTY ARCHITECTS.

THESE DRAWINGS USE A SYSTEM OF KEYNOTES FOR MATERIAL DESIGNATIONS AND SPECIFIC SITUATION NOTES. CONTRACTOR TO BE FAMILIAR WITH SYSTEM PRIOR TO COMMENCING WORK. CONTACT LANDSCAPE ARCHITECT IF CONFLICTS ARE FOUND OR SYSTEM IS NOT CLEAR.

7. WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.

ALL LAYOUT DIMENSIONS ARE FROM PLAN VIEW CALCULATIONS. FIELD DIMENSIONS MAY VARY FROM PLAN DUE TO ACTUAL LENGTHS ALONG SLOPED SURFACES.

 ALL LAYOUT DIMENSIONS ARE TO BACK OF CURB, FACE OF WALL, CENTERLINE OF ARCHITECTURAL COLUMN, AND/OR FACE OF BUILDING UNLESS OTHERWISE NOTED.

10. DIMENSIONS MARKED "VERIFY" ARE TO BE FIELD MEASURED. ANY DISCREPANCIES FROM THE NOTED DIMENSIONS ARE TO BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO CONTINUING WORK.

11. COORDINATE PROPOSED WALKS AND RAMPS WITH EXISTING CONDITIONS. LAYOUT OF ARCS TO BE SMOOTH AND CONTINUOUS. STAKE PROPOSED WALKS AND REVIEW IN FIELD WITH ARCHITECT PRIOR TO FORMING.

12. UNLESS OTHERWISE NOTED, FOR ALL ATTACHED AND DETACHED CITY SIDEWALKS, ACCESSIBLE RAMPS AND CURB & GUTTER WITHIN RIGHT-OF-WAY, REFER TO CIVIL DRAWINGS.

 CONTRACTOR SHALL VERIFY ALL WALK WIDTHS, GRADES AND ADJACENT CONDITIONS PRIOR TO STARTING WORK AND SHALL NOTIFY LANDSCAPE ARCHITECT OF ANY AND ALL DISCREPANCIES.
 ALL UTILITY EASEMENTS AS NOTED HEREIN SHALL REMAIN UNOBSTRUCTED AND FULLY ACCESSIBLE ALONG THEIR ENTIRE LENGTH FOR MAINTENANCE EQUIPMENT ENTRY.

 LIMIT OF WORK LINE FOR CONSTRUCTION IS SHOWN DIAGRAMMATICALLY AND OCCURS AT BACK OF CURB, FACE OF BUILDING OR PROPERTY LINE UNLESS OTHERWISE NOTED.
 DRAWING AND PLAN NOTES REPRESENT FINISHED, BUILT CONDITIONS. ALL BRACING, TEMPORARY SUPPORTS AND SHORING NECESSARY FOR CONSTRUCTION ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

17. ALL SYMBOLS ARE SHOWN DIAGRAMMATICALLY ILLUSTRATING APPROXIMATE LOCATION OF EXISTING AND PROPOSED MATERIALS. ANY DISCREPANCIES OR CONFLICTS BETWEEN EXISTING AND PROPOSED CONDITIONS SHALL BE REPORTED TO THE ARCHITECT PRIOR TO CONSTRUCTION.

18. ALL FENCING SHALL BE IN ACCORDANCE WITH THE CITY OF AURORA FENCE, WALL, AND AWNING STANDARDS CHAPTER 146-4.7.9, EXCEPT WHERE OTHERWISE NOTED AND ACCEPTED BY THE CITY OF AURORA.

19. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION PERTAINING TO THE PROJECT MATERIALS, PROCEDURES AND INSTALLATION.

750 PENNSYLVANIA ST, **DENVER, CO 80203** 720.440.2668 **S** $(\cap$ Σ 4 * R SO WORKING DRAFT CONSTRUCTION 12/10/2024 DATE:_ DESIGNED: SP, DL, HC, MP APPROVED: DRAWING NAME **COVER SHEET** DRAWING NO. L0.00



| 0 | Fairway - 9 acres | 3 |
|---|--------------------------------|---------------------|
| 2 | Middle Terrace - 4 acres | Ħ |
| 3 | Lower Creek Edge - 9 acres | Ŧ |
| 4 | Southern Floodplain - 15 acres | - |
| 5 | The Woods - 22 acres | † † |
| 6 | The Creek - 5.5 acres | ರೆ |
| 9 | Parking & Facilities - 1 acre | 稟 |

ILLUSTRATIVE IMAGE OF OVERALL MASTER PLAN



NEW POND | ILLUSTRATIVE RENDERING




FLOODPLAIN AND NEW PILOT CHANNEL | ILLUSTRATIVE RENDERING





INFORMATION.

GENERAL DESIGN AESTHETIC. THESE ARE NOT FOR CONSTRUCTION PURPOSES. PLEASE REFER TO HARDLINED DRAWINGS AND DETAILS FOR THIS

L0.01








----- FP ----- 100-YEAR FLOODPLAIN ----- MODERATE RISK AVALANCHE ZONE - RA ----- HIGH RISK AVALANCHE ZONE – — LIMIT OF WORK ----- TREE PROTECTION ZONE 29 CFS "LOW FLOW" INUNDATION EXTENTS

SEED MIX LEGEND

| SYMBOL | KEY | PLANT MIX TYPE |
|------------|-----------|--|
| | MIX A | UPLAND MEADOW MIX |
| | MIX B | XERIC (DRY) FLOODPLAIN |
| | MIX C | MESIC (WET) FLOODPLAIN |
| | MIX D | NEAR STREAM RIPARIAN |
| | MIX E,F,G | IN STREAM AQUATIC, SHALLOW EMERGENT WETLAND, & DEEP EMERGENT WETLAND |
| | MIX H | ASPEN GROVE |
| ¥ ¥ ¥ ¥ | SOD | RESTORED LAWN |



DATE: DESIGNED: APPROVED:

DRAWING NAME

DRAWING NO.


KEY MAP

ш S

Ζ

 \mathbf{O}

 \geq



73


12/10/2024 SP, DL, HC, MP

LANDSCAPE

PLANS

L1.01





----- FP ----- 100-YEAR FLOODPLAIN - MODERATE RISK AVALANCHE ZONE - RA ----- HIGH RISK AVALANCHE ZONE LIMIT OF WORK ----- TREE PROTECTION ZONE 29 CFS "LOW FLOW" INUNDATION EXTENTS


SEED MIX LEGEND

| SYMBOL | KEY | PLANT MIX TYPE |
|------------|-----------|--|
| | MIX A | UPLAND MEADOW MIX |
| | MIX B | XERIC (DRY) FLOODPLAIN |
| | MIX C | MESIC (WET) FLOODPLAIN |
| | MIX D | NEAR STREAM RIPARIAN |
| | MIX E,F,G | IN STREAM AQUATIC, SHALLOW EMERGENT WETLAND, & DEEP EMERGENT WETLAND |
| | MIX H | ASPEN GROVE |
| ¥ ¥ ¥ ¥ | SOD | RESTORED LAWN |



<mark>|</mark>₹

KEY MAP





 \square

74

DRAWING NO.

L1.02







----- FP ----- 100-YEAR FLOODPLAIN BA ----- BA ----- MODERATE RISK AVALANCHE ZONE ----- TREE PROTECTION ZONE 29 CFS "LOW FLOW" INUNDATION EXTENTS


SEED MIX LEGEND


| SYMBOL | KEY | PLANT MIX TYPE |
|------------|-----------|--|
| | MIX A | UPLAND MEADOW MIX |
| | MIX B | XERIC (DRY) FLOODPLAIN |
| | MIX C | MESIC (WET) FLOODPLAIN |
| | MIX D | NEAR STREAM RIPARIAN |
| | MIX E,F,G | IN STREAM AQUATIC, SHALLOW EMERGENT WETLAND, & DEEP EMERGENT WETLAND |
| | MIX H | ASPEN GROVE |
| ¥ ¥ ¥ ¥ | SOD | RESTORED LAWN |



KEY MAP







----- FP ----- 100-YEAR FLOODPLAIN BA BA MODERATE RISK AVALANCHE ZONE ----- RA ------ HIGH RISK AVALANCHE ZONE ----- TREE PROTECTION ZONE 29 CFS "LOW FLOW" INUNDATION EXTENTS

SEED MIX LEGEND

| SYMBOL | KEY | PLANT MIX TYPE |
|--------------------------------|-----------|--|
| (), (), (), 3 (), (), (), 3 | MIX A | UPLAND MEADOW MIX |
| | MIX B | XERIC (DRY) FLOODPLAIN |
| | MIX C | MESIC (WET) FLOODPLAIN |
| | MIX D | NEAR STREAM RIPARIAN |
| | MIX E,F,G | IN STREAM AQUATIC, SHALLOW EMERGENT WETLAND, & DEEP EMERGENT WETLAND |
| | MIX H | ASPEN GROVE |
| ¥ ¥ , ¥ ¥ | SOD | RESTORED LAWN |



Щ

5

BMI

5

S

IN

J

DPL

Õ Õ

F

SE SE

D N

SERV

AN

ENH,

SPRING. AIN ENH

ARM SODPL

0

S

N


RVE


R


KETCHL IDAHO WOOD RIVER LAND WARM SPRINGS CREEK, H BLAINE COUNTY, I

IJ


KEY MAP
















4 Floodplain ADA Overlook Scale: NTS







3 Pedestrian Footbridge Scale: NTS



| NT MIX A - UPLAND | | | | | - | 1 | | | | |
|-----------------------------|----------------------|--|---|--------------------------|-------------------|--------------------------------|------------------------|----------------|-----------------|---|
| KEY Ibs (Patches): 15% (| QTY of Total Hate | BOTANICAL NAME h Area (49.600 sf) | COMMON NAME | PLANT TYPE | SIZE | ROOT | % OF HATCH AREA 15% | % OF PATCH | O.C. SPACING | NOTES |
| - | 3180 | Artemisia tridentata var. vaseyana | Mountain Big Sagebrush | Shrub | 10 ci | Tube Seedling | | 50% | 3' | Plant in patches in favorable microsites, Shrubs to be Field Located by Landscape Architect. |
| - | 955 | Chrysothamnus viscidiflorus | Douglas Rabbitbrush | Shrub | 10 ci | Tube Seedling | | 15% | 3' | Shrubs to be Field Located by Landscape Architect. |
| - | 955 1270 | Ericameria nauseosa Purshia tridentata | Rubber Rabbitbrush Antelope Bitterbrush | Shrub Shrub | 10 ci 10 ci | Tube Seedling Tube Seedling | | 15% 20% | 3' 3' | Shrubs to be Field Located by Landscape Architect. Plant in patches in favorable microsites, Shrubs to be Field Located by Landscape Architect. |
| ses (Seed to Cover | | | | Onido | 10 01 | Tube Coouning | 4 4 | 20/0 | Ŭ | |
| | | | | | | | | | | Grasses = 80% of Seed Mix. Individual Species Percentages to be Supplied to Contractor Duri |
| - | - | Bromus ciliatus | Fringed Brome | Grass | | Seed | - | - | - | Construction Phase |
| - | - | Bromus ciliatus Bromus marginatus | Fringed Brome Mountain Brome | Grass Grass | - | Seed Seed | - | - | - | |
| | - | Bromus marginatus | Mountain Brome | Grass | - | Seed | - | - | - | |
| - | | Elymus elymoides | Squirreltail Grass | Grass | - | Seed | - | - | - | |
| : | - | Elymus elymoides | Squirreltail Grass | Grass | - | Seed | - | - | - | |
| - | - | Elymus glaucus Elymus glaucus | Blue Wildrye Blue Wildrye | Grass Grass | - | Seed Seed | - | - | - | |
| | - | Elymus lanceolatus ssp. lanceolatus | Thickspike Wheatgrass | Grass | - | Seed | - | - | - | |
| | - | Elymus lanceolatus ssp. lanceolatus | Thickspike Wheatgrass | Grass | - | Seed | | - | - | |
| - | - | Elymus trachycaulus Elymus trachycaulus | Slender Wheatgrass Slender Wheatgrass | Grass Grass | - | Seed Seed | - | - | - | |
| 0- | - | Festuca idahoensis | Idaho Fescue | Grass | - | Seed | - | - | - | |
| | | Festuca thurberi | Thurber's Fescue | Grass | - | Seed | | | | |
| - | - | Hesperostipa comata | Needle and Thread Bunchgrass | Grass | | Seed | - | - | - | |
| - | - | Koeleria macrantha Leymus cinereus | Prairie Junegrass Great Basin Wildrye | Grass Grass | - | Seed Seed | - | - | - | |
| - | - | Poa secunda sandbergii | Sandberg Bluegrass | Grass | - | Seed | - | - | - | |
| | - | Pseudoroegneria spicata | Bluebunch Wheatgrass | Grass | - | Seed | - | - | - | |
| (Seed to Cover 1 | 00% of Hatch | Area) | | | | 1 | | - | | |
| - | - | Achillea millefolium occidentalis | Western Common Yarrow | Forb | _ | Seed | - | _ | - | Forbs = 20% of Seed Mix. Individual Species Percentages to be Supplied to Contractor During Construction Phase |
| | - | Eriogonum umbellatum | Sulfurflower Buckwheat | Forb | - | Seed | - | - | | |
| | - | Linum lewisii | Blue Flax | Forb | - | Seed | - | - | - | |
| 3 - | - | Lupinus sericeus | Silky Lupine | Forb | - | Seed | - | - | - | |
| - | - | Penstemon eatonii Penstemon strictus | Firecracker Penstemon Rocky Mountain Penstemon | Forb Forb | - | Seed Seed | - | - | - | |
| | - | Sphaeralcea sp. | Globemallow | Forb | - | Seed | - | - | - | Species dependent on availability |
| | - | | | | | | | | | |
| | | | | | | | | | | |
| T MIX B - XERIC (D KEY | QTY | BOTANICAL NAME | COMMON NAME | PLANT TYPE | SIZE | ROOT | % OF HATCH AREA | % OF PATCH | O.C. SPACING | NOTES |
| | | h Area (25,000 sf) | | | | | 20% | <i>x</i> ••••• | | |
| 12 | 80 | Amelanchier alnifolia | Western Serviceberry | Shrub | #5 | Cont. | | 2.5% | 3' | Plant in microsites that retain more moisture, Shrubs to be Field Located by Landscape Archited |
| - | 1600 | Artemisia tridentata | Big Sagebrush | Shrub | 10 ci | Tube Seedling | | 50% | 3' | Consider Establishing in island patches, Shrubs to be Field Located by Landscape Architect. |
| | 480 | Chrysothamnus viscidiflorus | Douglas Rabbitbrush | Shrub | 10 ci | Tube Seedling | | 15% | 3' | Shrubs to be Field Located by Landscape Architect. |
| - | 480 80 | Ericameria nauseosa Prunus virginiana | Rubber Rabbitbrush Chokecherry | Shrub Shrub | 10 ci #5 | Tube Seedling Cont. | | 15% 2.5% | 3' 3' | Shrubs to be Field Located by Landscape Architect. Plant in microsites that retain more moisture, Shrubs to be Field Located by Landscape Archited |
| - | 320 | Purshia tridentata | Antelope Bitterbrush | Shrub | 10 ci | Tube Seedling | | 10% | 3' | Plant in patches in favorable microsites, Shrubs to be Field Located by Landscape Architect. |
| - | 160 | Rosa woodsii | Wood's Rose | Shrub | #5 | Cont. | | 5% | 3' | Shrubs to be Field Located by Landscape Architect. |
| es (Seed to Cover | 100% of Hat | ch Area) | | | 1 | 1 | | | | Owners - 75% of Sound Ning Ladicidual Onesian Demonstrates to the Owner South of the Owner |
| - | - | Festuca idahoensis | Idaho Fescue | Grass | - | Seed | - | - | - | Grasses = 75% of Seed Mix. Individual Species Percentages to be Supplied to Contractor Duri Construction Phase |
| - | - | Leymus cinereus | Great Basin Wildrye | Grass | - | Seed | - | - | - | |
| ; - | - | Poa secunda sandbergii | Sandberg Bluegrass | Grass | - | Seed | - | | - | |
| - (Seed to Cover 1 | - MW of Hatch | Pseudoroegneria spicata | Bluebunch Wheatgrass | Grass | - | Seed | .= | - | - | |
| - | - vv % 01 match | Achillea millefolium | Common Yarrow | Forb | - | Seed | - | - | - | |
| | | | | | | | | | | Forbs = 25% of Seed Mix. Individual Species Percentages to be Supplied to Contractor During |
| - | - | Artemisia ludoviciana | White Sagebrush | Forb | - | Seed | - | - | - | Construction Phase |
| - | - | Eriogonum umbellatum | Sulfurflower Buckwheat | Forb | - | Seed | | | | |
| - | - | Linum lewisii Lupinus argenteus | Blue Flax Silvery Lupine | Forb Forb | - | Seed Seed | - | - | - | |
| | - | Penstemon sp. | Penstemon species | Forb | - | Seed | | | | Species dependent on availability |
| - | - | Sphaeralcea sp. | Globemallow | Forb | - | Seed | - | - | - | Species dependent on availability |
| | | | | | | | | | | |
| MIX C - MESIC (V | | AIN (68-953 SF) | | | | | | | | |
| KEY | QTY | BOTANICAL NAME | COMMON NAME | PLANT TYPE | SIZE | ROOT | % OF HATCH AREA | % OF PATCH | O.C. SPACING | NOTES |
| (Patches): 10% of | Total Hatch | | | | | | 10% | | | |
| <u>j</u> (1993) | 55 | Populus angustifolia | Narrow-leaf Cottonwood | Tree | #5 | Cont. | - | 45% | 8' | Install Wildlife Exclusion Fence Around Trees |
| - | 12 55 | Populus tremuloides Populus trichocama | Quaking Aspen Black Cottonwood | Tree Tree | #5 | Cont. Cont. | - | 10% 45% | <u>8'</u> 8' | Install Wildlife Exclusion Fence Around Trees Install Wildlife Exclusion Fence Around Trees |
| - 5 (Patches): 10% / | | Populus tricnocarpa h Area (6,895 sf) | Black Collonwood | ILEE | #9 | Cont. | - 10% | 40% | 0 | |
| - | 25 | Alnus incana | Thin-leaf Alder | Shrub | #5 | Cont. | | 5% | 6' | Plant in microsites that retain more moisture, Shrubs to be Field Located by Landscape Archited |
| - | 25 | Betula occidentalis | Water Birch | Shrub | #5 | Cont. | | 5% | 6' | Shrubs to be Field Located by Landscape Architect. |
| | 150 | Ribes aureum | Golden Currant | Shrub | #5 | Cont. | | 35% | 6' | Shrubs to be Field Located by Landscape Architect. |
| - | 150 90 | Rosa woodsii Symphoricarpos sp. | Wood's Rose Snowberry | Shrub Shrub | #5 | Cont. Cont. | | 35% 20% | <u>6'</u> 6' | Shrubs to be Field Located by Landscape Architect. Shrubs to be Field Located by Landscape Architect. |
| es (Seed to Cover | | | | OTILO | <i>#</i> U | - Conc. | | 2070 | | |
| | | | | | | | | | | Grasses = 60% of Seed Mix. Individual Species Percentages to be Supplied to Contractor Dur |
| - | - | Elymus glaucus | Blue Wildrye | Grass | - | Seed | - | - | - | Construction Phase |
| - | - | Leymus cinereus Pascopyrum smithii | Great Basin Wildrye Western Wheatgrass | Grass Grass | - | Seed Seed | - | - | - | |
| - | - | Pseudoroegneria spicata | Bluebunch Wheatgrass | Grass | - | Seed | - | - | - | |
| (Seed to Cover 1 | 00% of Hatch | Area) | | | | · · · · · · | | 1 | | - |
| - | - | Achillea millefolium | Common Yarrow | Forb | - | Seed | - | - | | |
| | - | Linum lewisii | Blue Flax | Forb | _ | Seed | - | - | - | Forbs = 40% of Seed Mix. Individual Species Percentages to be Supplied to Contractor During Construction Phase |
| | - | Lupinus sp. | Lupine Species | Forb | - | Seed | - | - | - | Species dependent on availability |
| - | | Lupinus SD. | | | | | | | | |
| | - | Penstemon sp. | Penstemon species | Forb | | Seed | | - | | Species dependent on availability |
| | | | | 1. William (1999) (1997) | - | Seed Seed Seed | - | - | - | Species dependent on availability |

NOTES

- 1. All species cross-referenced to Blaine County Riparian and Wetland List
- 2. All species listed are generally available commercially; Wild collections may be needed to increase diversity or aesthetics
- 3. Recommend wild collections of cottonwood, willow, dogwood species, sagebrush, rabbitbrush, and antelope bitterbrush
- 4. No formal on-site plant investigations have been completed by IMA
- 5. Species present taken from geoengineers investigation and other professional plant surveys of the Wood River Watershed
- 6. Consider using pre-vegetated coir mats (wetland sod) for aesthetic impact and erosion protection in place of herbaceous wetland seedings



NOTE: The Following Live Plants in the Plant Mixes are being Contract Grown under a separate Contract and will be provided to the installing Contractor. The Installing Contractor is to coordinate with Owner's Representative and Landscape Architect for integration of Contract Grown species into plantings.

| PLANT MIX D - NEAR | STREAM RIPA | RIAN (26,985 SF) | | | | | | | | |
|--------------------|---------------|--|--|-----------------------------|------|----------------|------------------|------------|--------------|---|
| KEY | QTY | BOTANICAL NAME | COMMON NAME | PLANT TYPE | SIZE | ROOT | % OF HATCH AREA | % OF PATCH | O.C. SPACING | NOTES |
| ees (Patches): 10% | of Total Hato | h Area (6,746 sf) | | · | · | | 25% | | | |
| 10 | 50 | Populus angustifolia | Narrow-leaf Cottonwood | Tree | #5 | Cont. | | 40% | 8' | Tree Forming, Install Wildlife Exclusion Fence Around Trees |
| - | 50 | Populus trichocarpa | Black Cottonwood | Tree | #5 | Cont. | -1 | 40% | 8' | Install Wildlife Exclusion Fence Around Trees |
| | 15 | Salix amygdaloides | Peachleaf Willow | Tree | #5 | Cont. | - | 10% | 8' | Install Wildlife Exclusion Fence Around Trees |
| | 15 | Salix lasiandra var. caudata | Whiplash Willow | Tree | #5 | Cont. | -1 | 10% | 8' | Tree Forming, Install Wildlife Exclusion Fence Around Trees |
| ubs (Patches): 50 | % of Total Ha | tch Area (13,490 sf) | | | | | 50% | 20 | | |
| | 110 | Cornus sericea | Redosier Dogwood | Shrub | #5 | Cont. | | 25% | 6' | Very Palatable to Moose, Shrubs to be Field Located by Landscape Architect. |
| 3 - 1 | 110 | Salix boothii | Booth's Willow | Shrub | #5 | Cont. | | 25% | 6' | Clump Forming, Shrubs to be Field Located by Landscape Architect. |
| 3. | 110 | Salix exigua | Golden Currant | Shrub | #5 | Cont. | | 25% | 6' | Mat Forming, Shrubs to be Field Located by Landscape Architect. |
| 3 - 1 | 110 | Salix lutea | Wood's Rose | Shrub | #5 | Cont. | | 25% | 6' | Clump Forming, Shrubs to be Field Located by Landscape Architect. |
| asses (Seed to Cov | ver 100% of H | atch Area) | · | · | | | | | | |
| | | | | | | | | | | Grasses = 100% of Seed Mix. Individual Species Percentages to be Supplied to Contractor Durin |
| - | - | Calamagrostis canadensis | Bluejoint Reedgrass | Grass | | Seed | - | - | - | Construction Phase, Saturated but not inundated soils |
| 1 - 1 | - | Deschampsia cespitosa | Tufted Hairgrass | Grass | | Seed | - | - | - | Saturated but not inundated soils |
| | - | Elymus glaucus | Blue Wildrye | Grass | 0.00 | Seed | • | - | | Moist Soils |
| | | | | | | | | | | |
| ANT MIX E - IN STR | REAM AQUATIO | ; (2,055 SF, 33.33% of Total Hatch A | rea Indicated in Plans as Mix E, F, G) | | | | | | | |
| KEY | QTY | BOTANICAL NAME | COMMON NAME | PLANT TYPE | SIZE | ROOT | % OF PLANT MIX E | % OF PATCH | O.C. SPACING | NOTES |
| rbaceous Live Pla | nts: 25% of M | ix E | | | | | 25% | | | To be located along stream channels on inundated and saturated soils |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores a |
| | 005 | O and the second s | Mater Oadaa | I facilitation and a second | | Take Ocealling | 050/ | | 0" | atvaave shannal vesusina |

| KEY | QTY | BOTANICAL NAME | COMMON NAME | PLANT TYPE | SIZE | ROOT | % OF PLANT MIX E | % OF PATCH | O.C. SPACING | NOTES |
|----------------------------|---------------|--------------------------|-----------------------|------------|---------------|---------------|------------------|------------|---|---|
| Herbaceous Live Plants | 5: 25% of Mix | xE | | | | | 25% | | | To be located along stream channels on inundated and saturated soils |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| - | 265 | Carex aquatilis | Water Sedge | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| | 265 | Carex utriculata | Beaked Sedge | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| - 265 Eleocharis palustris | | Great Spike Rush | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. | |
| | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and | |
| - | 265 | Juncus articus | Arctic Rush | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| Seed Mix: Seed to Cove | er 100% of P | lant Mix E (2,055 SF) | | | | - | % OF PLANT MIX E | | | |
| 127 | | Beckmannia syzigachne | American Slough Grass | Herbaceous | - | Seed | 100% | | | Saturated but not inundated soils |
| u n . | | Calamagrostis canadensis | Bluejoint Grass | Herbaceous | - | Seed | | | | Saturated but not inundated soils |
| u . . | | Deschampsia cespitosa | Tufted Hair Grass | Herbaceous | - | Seed | | | | Saturated but not inundated soils |
| - | | Pascopyrum smithii | Western Wheatgrass | Herbaceous | - | Seed | | | | Saturated but not inundated soils |
| | | | * | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

| KEY | QTY | BOTANICAL NAME | COMMON NAME | PLANT TYPE | SIZE | ROOT | % OF PLANT MIX F | % OF PATCH | O.C. SPACING | NOTES |
|---------------------|---------------|--------------------------|-----------------------|------------|--------|---------------|------------------|------------|--------------|---|
| | t | | | · | | | | | | To be located along pond edges with zones of permanent inundation and frequent soil |
| erbaceous Live Pla | nts: 25% of M | ix F | | | | | 25% | | | saturation |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| 1.5 | 265 | Carex nebrascensis | Nebraska Sedge | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| 1 . | 265 | Carex pellita | Wooly Sedge | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| | 265 | Carex utriculata | Beaked Sedge | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| (=) | 265 | Juncus articus | Arctic Rush | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| eed Mix: Seed to Co | ver 100% of | Plant Mix F (2,055 SF) | | | | | % OF PLANT MIX F | | | |
| 157 | | Beckmannia syzigachne | American Slough Grass | Herbaceous | - | Seed | 100% | | | Saturated but not inundated soils |
| 1. . . | | Calamagrostis canadensis | Bluejoint Grass | Herbaceous | - | Seed | | | | Saturated but not inundated soils |
| U . | | Deschampsia cespitosa | Tufted Hair Grass | Herbaceous | - | Seed | | | | Saturated but not inundated soils |
| U. . . | | Pascopyrum smithii | Western Wheatgrass | Herbaceous | - | Seed | | | | Saturated but not inundated soils |

| KEY | QTY | BOTANICAL NAME | COMMON NAME | PLANT TYPE | SIZE | ROOT | % OF PLANT MIX F | % OF PATCH | O.C. SPACING | NOTES |
|---------------------|----------------|--------------------------|-----------------------|------------|--------|---------------|------------------|------------|--------------|---|
| | | L | | L | | | | 1 | | To be located along pond edges with zones of permanent inundation and frequent so |
| Herbaceous Live Pla | ants: 25% of M | ix F | | | | | 25% | | | saturation |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| 127 | 265 | Carex nebrascensis | Nebraska Sedge | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| 1.0 | 265 | Carex pellita | Wooly Sedge | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| | 265 | Carex utriculata | Beaked Sedge | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| | | | | | | | | | | Alternatively could be wetland sod mix of sedges and rushes at water's edge along pond shores and |
| | 265 | Juncus articus | Arctic Rush | Herbaceous | 5.5 ci | Tube Seedling | 25% | | 9" | stream channel margins. |
| Seed Mix: Seed to C | over 100% of | Plant Mix F (2,055 SF) | | | | | % OF PLANT MIX F | | | |
| 67 | | Beckmannia syzigachne | American Slough Grass | Herbaceous | - | Seed | 100% | | | Saturated but not inundated soils |
| - | | Calamagrostis canadensis | Bluejoint Grass | Herbaceous | - | Seed | | | | Saturated but not inundated soils |
| - | | Deschampsia cespitosa | Tufted Hair Grass | Herbaceous | - | Seed | | | | Saturated but not inundated soils |
| - | | Pascopyrum smithii | Western Wheatgrass | Herbaceous | - | Seed | | | | Saturated but not inundated soils |
| | | | | | | | | | | |
| | | | | | | | | | | |


| PLANT MIX G - DEEP EM | ERGENT WET | LAND (2,055 SF, 33.33% of Tota | Hatch Area Indicated in Plans as Mix E, | F, G) | | | | | | | | | | |
|------------------------|--|--------------------------------|---|------------|----|-------|-----|--|--|---|--|--|--|--|
| KEY | KEY QTY BOTANICAL NAME COMMON NAME PLANT TYPE SIZE ROOT % OF PLANT MIX G % OF PATCH O.C. SPACING NOTES | | | | | | | | | | | | | |
| Herbaceous Live Plants | : 100% of Mi | ix G | | | | 100% | | | To be located within pond on permanently inundated soils | | | | | |
| - | 1185 | Schoenoplectus acutus | Hardstem Bulrush | Herbaceous | #1 | Cont. | 50% | | 12" | Alternatively could be wetland sod mix of these species | | | | |
| - | 1185 | Scirpus microcarpus | Small-Fruited Bulrush | Herbaceous | #1 | Cont. | 50% | | 12" | Alternatively could be wetland sod mix of these species | | | | |
| | | | | | | | | | | | | | | |

| KEY | QTY | BOTANICAL NAME | COMMON NAME | PLANT TYPE | SIZE | ROOT | % OF PLANT MIX G | % OF PATCH | O.C. SPACING | NOTES |
|------------------------|-------------|------------------------|--------------------------|------------|--------|---------------|------------------|---------------|-------------------|--|
| rbaceous Live Plants | : 100% of N | lix G | | | | | 100% | | | To be located within pond on permanently inundated soils |
| 57 | 1185 | Schoenoplectus acutus | Hardstem Bulrush | Herbaceous | #1 | Cont. | 50% | | 12" | Alternatively could be wetland sod mix of these species |
| - | 1185 | Scirpus microcarpus | Small-Fruited Bulrush | Herbaceous | #1 | Cont. | 50% | | 12" | Alternatively could be wetland sod mix of these species |
| | | | | | | | | | | |
| ANT MIX H - ASPEN GI | ROVE (2473 | 1 SF) | | | | | | | | |
| KEY | QTY | BOTANICAL NAME | COMMON NAME | PLANT TYPE | SIZE | ROOT | % OF HATCH AREA | % OF PATCH | O.C. SPACING | NOTES |
| rbs: 40% of Total Hate | ch Area (98 | 92.4 sf) | | | • | | 40% | | | |
| 19 <u>1</u> | 360 | Achillea millefolium | Common Yarrow | Forb | 4" | Pot | | 14 2 (| 18" | |
| | 360 | Aquilegia coerulea | Blue Columbine | Forb | #1 | Cont. | | k⊑ i | 18" | |
| 17 <u>1</u> | 360 | Delphinium occidentale | Duncecap Larkspur | Forb | #1 | Cont. | | 14 2 (| 18" | |
| 12 | 360 | Erigeron speciosus | Showy Fleabane | Forb | 4" | Pot | | 14 2 (| <mark>18"</mark> | |
| | 360 | Eriogonum umbellatum | Sulfurflower Buckwheat | Forb | 4" | Pot | | 1 | 18" | |
| | 360 | Gaillardia aristata | Blanket Flower | Forb | 4" | Pot | - | 1 -2 1 | <mark>18</mark> " | |
| | 360 | Geranium viscosissimum | Sticky Geranium | Forb | #1 | Pot | - | 1 <u>4</u> 1 | <mark>18</mark> " | |
| | 360 | Heliomeris multiflora | Showy Goldeneye | Forb | #1 | Cont. | - | - | 18" | |
| - | 360 | Hymenoxys hoopesii | Meadow Fire | Forb | #1 | Cont. | - | | 18" | |
| | 360 | Linum lewisii | Blue Flax | Forb | 4" | Cont. | - | | 18" | |
| | 360 | Penstemon rydbergii | Rydberg's Penstemon | Forb | 4" | Cont. | - | | 18" | |
| | 360 | Penstemon strictus | Rocky Mountain Penstemon | Forb | #1 | Cont. | - | | 18" | |
| | 360 | Rudbeckia occidentalis | Western Coneflower | Forb | #1 | Cont. | - | | 18" | |
| | 360 | Solidago missouriensis | Missouri Goldenrod | Forb | #1 | Cont. | - | | 18" | |
| (- | 360 | Symphyotrichum laeve | Smooth Aster | Forb | #1 | Cont. | - | | 18" | |
| asses: 60% of Hatch / | Area (14838 | 3 sf) | | | | · | · | | | |
| - | 1630 | Bouteloua curtipendula | Side Oats Gram | Grass | 5.5 ci | Tube Seedling | | | 18" | |
| | 1630 | Bouteloua gracilis | Blue Grama | Grass | 5.5 ci | Tube Seedling | | | 18" | |
| 3 . | 1630 | Festuca idahoensis | Idaho Blue Fescue | Grass | 5.5 ci | Tube Seedling | | | 18" | |
| | 1630 | Hesperostipa comata | Needle and Thread Grass | Grass | 5.5 ci | Tube Seedling | | | 18" | |
| 36 | 1630 | Oryzopsis hymenoides | Indian Ricegrass | Grass | 5.5 ci | Tube Seedling | | | 18" | |
| D (54,410 SF) | | | | | | | | | | |
| KEY | QTY | BOTANICAL NAME | NOTES | | | | | | | |

NOTES

- 1. All species cross-referenced to Blaine County Riparian and Wetland List
- 2. All species listed are generally available commercially; Wild collections may be needed to increase diversity or aesthetics
- 3. Recommend wild collections of cottonwood, willow, dogwood species, sagebrush, rabbitbrush, and antelope bitterbrush
- 4. No formal on-site plant investigations have been completed by IMA
- 5. Species present taken from geoengineers investigation and other professional plant surveys of the Wood River Watershed
- 6. Consider using pre-vegetated coir mats (wetland sod) for aesthetic impact and erosion protection in place of herbaceous wetland seedings





DRIP IRRIGATION NOTES

- ALL PLANTER BEDS ARE TO BE IRRIGATED WITH A NETAFIM TLCV4-12## DRIP IRRIGATION LINE. THE CONTRACTOR IS RESPONSIBLE TO INSTALL THE DRIP SYSTEM AS PER MANUFACTURER'S RECOMMENDATIONS AND THE FOLLOWING REQUIREMENTS:
- A. <u>SHRUBS</u>: DETAIL 19/IR302
- <u>TREES:</u> DETAILS 20 & 21/IR302 В.
- RIPAIRIAN: DETAIL 18/IR302 ALL ZONES 15 G.P.M. AND <u>UNDER</u> SHALL BE INSTALLED WITH A RAIN BIRD XCZ-100-FLOW DRIP CONTROL ZONE KIT. ENSURE THAT KIT INCLUDES PRESSURE D. REGULATION AND DIAPHRAGM SCREEN CLEANING SYSTEM. FILTER SHALL BE 150
- MESH STAINLESS STEEL SCREEN. INSTALL PER DETAIL 15/IR301. E. ALL ZONES 16-50 G.P.M. SHALL BE INSTALLED WITH A RAIN BIRD XCZ-150-LCS DRIP CONTROL ZONE KIT. ENSURE THAT KIT INCLUDES PRESSURE REGULATION AND DIAPHRAGM SCREEN CLEANING SYSTEM. FILTER SHALL BE 120 MESH STAINLESS STEEL SCREEN. INSTALL PER DETAIL 15/IR301.
- F. ALL ZONES SHALL HAVE A MANUAL DRAIN VALVE AT THE END OF EACH SUPPLY/EXHAUST LATERAL, AS NEEDED, TO ALLOW FOR ADEQUATE DRAINAGE FOR WINTERIZATION.
- G. ALL ZONES SHALL INCLUDE AN AIR/VAC RELIEF VALVE AT ALL HIGH POINTS H. ALL TUBING IS TO BE STAKED DOWN WITH TLS6 SIX INCH (6") SOIL STAPLES TO
- PREVENT EXPOSURE OF PIPE THROUGH MULCH. I. CONTRACTOR SHALL INSTALL CHECK VALVES ON LATERAL HEADERS EVERY 8' IN ELEVATION CHANGE.
- 2. THE CONTRACTOR IS RESPONSIBLE TO INSTALL THE DRIP SYSTEM SO THAT THE OPTIMUM AMOUNT OF WATER IS APPLIED TO INSURE THE HEALTH OF ALL PLANT MATERIAL.
- 3. THE CONTRACTOR IS RESPONSIBLE TO SCHEDULE A MEETING WITH THE LANDSCAPE ARCHITECT, IRRIGATION CONSULTANT AND THE OWNER'S REPRESENTATIVE BEFORE PROCEEDING WITH ANY IRRIGATION INSTALLATION IN ORDER TO REVIEW WORK TO BE DONE. ALL LATERAL LINES FROM VALVES TO HEADERS ARE TO BE BURIED AT MINIMUM DEPTH OF TWELVE INCHES (12"). SIZE AS NECESSARY.
- 4. ALL DRIP TUBING OUTSIDE OF THE 100 100 YR FLOOD LIMIT SHALL BE BURIED AT A DEPTH OF 3".
- 5. ALL DRIP TUBING INSTALLED WITHIN THE 100 YR FLOOD ZONE SHALL BE BURIED AT A DEPTH OF 6". 6. AFTER INSTALLATION OF THE IRRIGATION SYSTEM THE CONTRACTOR IS RESPONSIBLE
- TO PROVIDE THE OWNER WITH AS-BUILT DRAWINGS AND INSTRUCTIONS FOR MAINTENANCE OF THE DRIP SYSTEM.
- 7. CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT AND IRRIGATION CONSULTANT AFTER INSTALLING DRIP IRRIGATION AND PRIOR TO PLACING MULCH/TOPSOIL FOR INSPECTION.

DRIP LAYOUT SCHEMATIC



_____ TREE AND SHRUB DRIP RING, Details 19, 20 & 21/IR3.02 LATERAL SERVICE WITH HEADER TO SHRUB DRIP ZONES

RIPARIAN DRIP OUTLINE, Detail 18/IR3.02 LATERAL SERVICE WITH HEADER TO RIPARIAN DRIP ZONES

GENERAL NOTES

- 1. EXISTING SITE PLAN WAS CREATED BY SUPERBLOOM.
- 2. DESIGN IS BASED ON 500 GPM @ 105 PSI.
- 3. ALL NEW IRRIGATION MATERIAL NOTED ON THIS PLAN IS TO BE CONTRACTOR PROVIDED, CONTRACTOR INSTALLED.
- 4. ALL VIH ROTORS WILL BE GPS'D BY BAER DESIGN GROUP (BDG). BDG MAY ADJUST LOCATION OF MATERIALS IN THE FIELD AS NECESSARY TO FIT SITE CONDITIONS. CONTRACTOR SHALL SCHEDULE STAKING A MINIMUM OF 10 DAYS IN ADVANCE. MINIMUM OF THREE HOLES SHALL BE STAKED PER VISIT.
- 5. CONTRACTOR SHALL VERIFY LOCATION OF ALL UTILITIES (PRIVATE AND PUBLIC) PRIOR TO CONSTRUCTION. ANY DAMAGE TO MARKED UTILITIES SHALL BE REPAIRED AT NO COST TO THE OWNER. 6. COORDINATE WITH ALL OTHER PLAN SHEETS PRIOR TO AND DURING CONSTRUCTION.
- 7. CONTRACTOR WILL PAY FOR AND ACQUIRE ALL PERMITS REQUIRED AS PART OF THIS PROJECT. 8. ALL ROCK OR DEBRIS LARGER THAN 2" BROUGHT TO THE SURFACE FROM TRENCHING SHALL BE REMOVED FROM THE BACKFILL.
- 9. ALL SPLICES TO BE INSTALLED IN 10" ROUND VALVE BOX WITH BLACK FLUSH LID MARKED "ELEC".
- 10. ALL COMMUNICATION WIRE SHALL BE 12-2 OR 14-2 MAXI CABLE PER ELECTRICAL PLAN.
- 11. ALL ELECTRICAL WIRE ABOVE FINISH GRADE SHALL BE INSTALLED IN RIGID SCH 40 PVC CONDUIT. 12. ALL MULTI-STRAND ELECTRICAL WIRES SHALL BE TAPPED TOGETHER IN TEN FOOT INTERVALS OR LESS.
- 13. ALL INSTALLATION SHALL MEET OR EXCEED NATIONAL, STATE AND LOCAL CODES.
- 14. CONTRACTOR SHALL MAINTAIN DAILY RECORDS AND MODIFICATIONS OF WORK NOTED ON AN IRRIGATION AS–BUILT.
- 15. CONTRACTOR SHALL ACCOMPANY CURRENT IRRIGATION AS-BUILT WITH EACH PAYMENT APPLICATION MONTHLY. 16. THE ENTIRE INSTALLED SYSTEM SHALL INCLUDE MINIMUM A ONE YEAR WARRANTY FROM THE DATE OF FINAL ACCEPTANCE. ALL DEFECTS IN MATERIAL OR LABOR SHALL BE REPAIRED BY THE CONTRACTOR IN A TIMELY MANNER AND AT NO COST TO THE OWNER. PLANT MATERIAL LOST DUE TO LACK OF URGENCY ON A WARRANTY ITEM SHALL BE REPLACED TO EQUAL OR GREATER VALUE AT NO COST TO THE OWNER.
- 17. ALL MATERIALS SHALL BE THOSE SPECIFIED NEW IN BOX AND WITHOUT FLAWS OR DEFECTS OF ANY KIND.
- 18. NO SUBSTITUTIONS WILL BE ALLOWED WITHOUT WRITTEN APPROVAL PRIOR TO BID.
- 19. THE IRRIGATION SYSTEM IS DESIGNED TO PROVIDE MAXIMUM EFFICIENCY AND DISTRIBUTION UNIFORMITY. IF THE CONTRACTOR IS REQUIRED TO MAKE FIELD ADJUSTMENTS, NOTIFY THE IRRIGATION CONSULTANT IMMEDIATELY FOR FURTHER EVALUATION.

| 11.11 | | | | | LJ | \subseteq | / | | | |
|-------|---------|------------|------|---------|----------|-------------|----------|-------|-------|------|
| 1. | INSTALL | IRRIGATION | PUMP | STATION | ADJACENT | TO | EXISTING | POND. | EXACT | LOCA |
| | | | | | | - D C | | | | |

- 2. INSTALL TWO IRRIGATION CONTROLLERS ON PEDESTAL NEAR IRRIGATION PUMP STATION AND MAINLINE.
- CONNECT TO 120V GFCI POWER SUPPLY PROVIDED BY ELECTRICAL.
- 4. BRIDGE CROSSING.
- 5. INSTALL DRAIN VALVE AT LOW POINT. PLUMB DISCHARGE TO CREEK. PROVIDE RIP RAP TO PREVENT
- EROSION IF REQUIRED.
- 7. CREEK CROSSING SEE DETAIL 13/IR301.
- 8. RIPARIAN DRIP ZONE INSTALL ELECTRIC VALVE, HEADER/LATERAL PIPING AND DRIP TUBING TO PROVIDE UNIFORM IRRIGATION APPLICATION TO PLANTINGS WITHIN THE RIPARIAN ZONES.

- CATION TO BE DETERMINED ON SITE. COORDINATE WITH ELECTRICAL FOR POWER SERVICE.
- 3. EXTEND MAINLINE TO FUTURE POND AND IRRIGATION PUMP STATION LOCATION.

- 6. INSTALL AIR RELIEF VALVE AT HIGH POINT. FIELD ADJUST EXACT LOCATION AS REQUIRED.

 $\land \rightarrow$

•

8

 \bigcirc

 $\mathbb{P}^{\mathbb{P}}$

SAT

_____6"_____ ______8" _____

_____ _____

| | ON LEGEND | | OR DISCREPANCIES PRIOR TO ANY FABRICATION OF ANY WORK OR FIELD WORK BEING DONE, IN ACCORDANCE WITH AIA DOCUMENT A201. DO NOT |
|---|---|--|---|
| | 75' VIH ADJ. ROTOR: (DETAIL 7 & 8/IR300) | RAIN BIRD A-952-E-70-48; 75' SPACING, 29.7 GPM @ 70 PSI WITH BASELINE BL5201 SINGLE STATION DECODER | SCALE THESE DRAWINGS. 2. THE DRAWINGS, SPECIFICATIONS AND OTHER DOCUMENTS PREPARED BY THE ARCHITECTS FOR THIS PROJECT ARE |
| | 65' VIH ROTOR: (DETAIL 7 & 8/IR300) | RAIN BIRD A-702-E-70-32; 65' SPACING, 23.3 GPM @ 70 PSI WITH BASELINE BL5201 SINGLE STATION DECODER | INSTRUMENTS OF THE ARCHITECTS SERVICE FOR USE SOLELY WITH RESPECT TO THIS PROJECT AND UNLESS OTHERWISE PROVIDED THE ARCHITECT SHALL BE DEEMED THE AUTHOR OF THESE |
| | 65' VIH ADJ. ROTOR: (DETAIL 7 & 8/IR300) | RAIN BIRD A—752—E—70—36; 65' SPACING, 23.2 GPM @ 70 PSI WITH BASELINE BL5201 SINGLE STATION DECODER | DOCUMENTS AND SHALL RETAIN ALL COMMON LAW STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT. REPRODUCTION IS PROHIBITED. COPYRIGHT 2022. STUDIO |
| | 50' VIH ADJ. ROTOR: (DETAIL 7 & 8/IR300) | RAIN BIRD A-752-E-70-26; 51' SPACING, 10.9 GPM @ 70 PSI WITH BASELINE BL5201 SINGLE STATION DECODER | |
| | 50' LANDSCAPE ROTOR: (DETAIL 9/IR300) | RAIN BIRD 5012+PCSAMR, #6 NOZZLE; 50' R, 6.63 GPM @ 55 PSI | WARM SPRINGS PRESERVE |
| | 25' LANDSCAPE ROTOR: (DETAIL 9/IR300) | RAIN BIRD 5012+SAMSS-MPR-25; 25' R, 45 PSI (90°:1.0 GPM) (180°:1.98 GPM) (360°: 3.82 GPM) | ### BALD MOUNTAIN RD. KETCHUM, ID CITY OF KETCHUM |
| | 30' LANDSCAPE ROTOR: (DETAIL 9/IR300) | RAIN BIRD 5012+SAMSS-MPR-30; 30' R, 45 PSI (90°:1.4 GPM) (180°:2.96 GPM) (360°: 5.78 GPM) | AND WRLT |
| | 35' LANDSCAPE ROTOR: (DETAIL 9/IR300) | RAIN BIRD 5012+SAMSS-MPR-35; 35' R, 45 PSI (90°:192 GPM) (180°:3.81 GPM) (360°: 7.58 GPM) | Z |
| | QUICK COUPLER VALVE: (DETAIL 5/IR300) | RAIN BIRD 5RC | PLAN |
| | 2" ELEC. CONTROL VALVE: (DETAIL 16/IR301) | RAIN BIRD 200-PESB-PRS-D WITH BASELINE BL5201 SINGLE STATION DECODER | MBING |
| | 1.5" DRIP CONTROL VALVE: (DETAIL 17/IR301) | RAIN BIRD XCZ-150-LCS WITH BASELINE BL5201 SINGLE STATION DECODER | MB |
| | 1" DRIP CONTROL VALVE: (DETAIL 17/IR301) | RAIN BIRD XCZ-100-FLOW WITH BASELINE BL5201 SINGLE STATION DECODER | PLU |
| | LATERAL ISOLATION VALVE (DETAIL 2/IR300) | | 1 |
| | MAINLINE ISOLATION VALVE (DETAIL 1/IR300) | | RRIGATION |
| | AIR RELIEF VALVE: (DETAIL 4/IR300) | CRISPIN PL10A | IGA |
| | DRAIN VALVE (DETAIL 3/IR300) | | IRR |
| | BASELINE BL5315 SOIL MOIS | STURE SENSOR | |
| | BASELINE 3200 BASELINE B | L-3200PSS-CM W/BL-CLOUD-LTE-VZ-P & BL-CM-OMNI | TATE OF IDAK |
| | 2" HDPE 4710 DR13.5 | | CREG P. BARR |
| | 6" HDPE 4710 DR13.5 | | 11/26/2024 LA-16635 |
| | 8" HDPE 4710 DR13.5 | | 11/26/2024 LA-16635 |
| _ | HDPE DR13.5 SLEEVING – II COMMUNICATION/ELECTRICAL | NCLUDE TWO (2) 2" CONDUITS AT ALL SLEEVING LOCATIONS FOR | ANDSCAPE ANI |
| | | in GROUP, L | SCALE: AS NOTED |
| | | | |
| | | | IR100 |

Scale 1" = 20'-0"



DRAWN BY: CHECKED BY:

SUPERBLOOM

750 PENNSYLVANIA ST, **DENVER, CO 80203** 720.440.2668

DATE: November 17, 2023


PROJECT NO.

NOTES:

1. CONTRACTORS AND

SUBCONTRACTORS SHALL VERIFY AL GURED DIMENSIONS AND DITIONS AT THE JOBSITE, REVIEW D COMPARE ALL CHAPTERS AN ERDISCIPLINARY DRAWINGS, AN TIFY THE ARCHITECT OF ANY MENSIONAL ERRORS, OMISSION OR DISCREPANCIES PRIOR TO AN

SUBMITTALS 1 DESIGN REVIEW





- ELECTRICIAN.

| IRRIGATION CONTROLLER : | BASELINE BL-3200PSS-CM BL-CLOUD-LTE-VZ-P & BL-CM-OMN |
|--|---|
| 12-2 COMMUNICATION WIRE | PATH – GROUP A (GREEN) |
| 14-2 COMMUNICATION WIRE | PATH – GROUP A (GREEN) |
| 12-2 COMMUNICATION WIRE | PATH – GROUP A (BLUE) |
| 14-2 COMMUNICATION WIRE | PATH – GROUP A (BLUE) |
| GROUNDING/ARRESTOR – CO (DETAIL 17/IR301) | DMMUNICATION WIRE PATH |

2. COORDINATE AND PROVIDE FOR A 120V POWER, 20 AMP GFCI POWER SERVICE FOR TWO IRRIGATION CONTROLLERS NEAR PUMP STATION. 3. IRRIGATION PUMP STATION (FINAL LOCATION) - CONNECT 480V POWER SUPPLY TO PUMP STATION DISCONNECT. COORDINATE WITH ELECTRICAL FOR SERVICE. ALL WORK SHALL BE DONE BY A LICENSED

4. INSTALL MOISTURE SENSOR IN LOCATION THAT BEST REPRESENTS THE OVERALL MICRO CLIMATE OF EACH SPECIFIC PLANTING ZONE. EXACT LOCATION TO BE DETERMINED BY DESIGN TEAM AND CLIENT. 5. EXTEND IRRIGATION COMMUNICATION WIRE TO PROPOSED BUILDING FOR FUTURE.







81


GBT


DRAWN BY: CHECKED BY:

















NOTES: 1. CONTRACTORS AND SUBCONTRACTORS SHALL VERIFY ALL FIGURED DIMENSIONS AND CONDITIONS AT THE JOBSITE, REVIEW AND COMPARE ALL CHAPTERS AND INTERDISCIPLINARY DRAWINGS, AND NOTIFY THE ARCHITECT OF ANY DIMENSIONAL ERRORS, OMISSIONS OR DISCREPANCIES PRIOR TO ANY FABRICATION OF ANY WORK OR FIELD WORK BEING DONE, IN ACCORDANCE WITH AIA DOCUMENT A201. DO NOT SCALE THESE DRAWINGS. THE DRAWINGS, SPECIFICATIONS AND OTHER DOCUMENTS PREPARED BY THE ARCHITECTS FOR THIS PROJECT ARE INSTRUMENTS OF THE ARCHITECTS SERVICE FOR USE SOLELY WITH RESPECT TO THIS PROJECT AND UNLESS OTHERWISE PROVIDED THE ARCHITECT SHALL BE DEEMED THE AUTHOR OF THESE DOCUMENTS AND SHALL RETAIN ALL COMMON LAW STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT. REPRODUCTION IS PROHIBITED. COPYRIGHT 2022. STUDIO SUPERBLOOM, LLC. PROJECT WARM SPRINGS PRESERVE ### BALD MOUNTAIN RD. KETCHUM, ID CITY OF KETCHUM AND WRLT ETAILS \Box 1 IRRIGATION \dots E AS NOTED SCALE: IR301 83 DRAWN BY: GBT CHECKED BY:

SUPERBLOOM

750 PENNSYLVANIA

ST, DENVER, CO 80203

720.440.2668


DATE: November 17, 2023

SUBMITTALS DATE 1 DESIGN REVIEW 11/17/23

WSP


PROJECT NO.





Rectangular Valve Box Spacing $(24)\frac{Re}{NTS}$


RECOMMENDATION, BACKFILL, AND SPREAD SURFACE TREATMENT AS DIRECTED BY OTHERS.



21 Tree Drip Plumbing Detail



| T50 PENNSYLVANIA | |
|--|--|
| ST, DENVER, CO 80203 720.440.2668 | |
| DATE: November 17, 2023 PROJECT NO. WSP SUBMITTALS DATE 1 DESIGN REVIEW 11/17/23 2 3 4 5 6 | |
| NOTES: 1. CONTRACTORS AND SUBCONTRACTORS SHALL VERIFY ALL FIGURED DIMENSIONS AND CONDITIONS AT THE JOBSITE, REVIEW AND COMPARE ALL CHAPTERS AND INTERDISCIPLINARY DRAWINGS, AND NOTIFY THE ARCHITECT OF ANY DIMENSIONAL ERRORS, OMISSIONS OR DISCREPANCIES PRIOR TO ANY FABRICATION OF ANY WORK OR FIELD WORK BEING DONE, IN ACCORDANCE WITH AIA DOCUMENT A201. DO NOT SCALE THESE DRAWINGS. 2. THE DRAWINGS, SPECIFICATIONS AND OTHER DOCLIMENTS PREPARED BY THE ARCHITECTS FOR THIS PROJECT ARE INSTRUMENTS OF THE ARCHITECTS SERVICE FOR USE SOLELY WITH RESPECT TO THIS PROJECT AND UNLESS OTHERWISE PROVIDED THE ARCHITECT SHALL BE DEEMED THE AUTHOR OF THESE DOCUMENTS AND SHALL RETAIN ALL COMMON LAW STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT. REPRODUCTION IS PROHIBITED. COPYRIGHT 2022. STUDIO SUPERBLOOM, LLC. | |
| PROJECT WARM SPRINGS | |
| PRESERVE ### BALD MOUNTAIN RD. KETCHUM, ID CITY OF KETCHUM AND WRLT | |
| IRRIGATION - DETAILS | |
| CREG P. BAR | |
| SCALE: AS NOTED | |
| DRAWN BY: CHECKED BY: B | |



| | DESIGN SPECIFICATIONS | | |
|-------------|---|-------------|-----|
| Design f | | 5 PSI | |
| Duty Pu | mp Details: 25 HP/Pump 270 | GPM @ 240 | TDH |
| | Pump Details: 5 HP/Pump 55 | GPM @ 240 | TDH |
| Minimum | Power: 480 Volt / 3 Phase | 1 | |
| item No. | DESCRIPTION | Size | QTY |
| 1 | AC UNIT, N28, HOFFMAN | | 1 |
| 2 | CONTROL PANEL | | 1 |
| 3 | ENCLOSURE, MARINE GRADE ALUMINUM, 4–DOOR | 48x96x66 | 1 |
| 4 | FILTER | 6" | 1 |
| 5 | FLOW METER, BADGER | 6" | 1 |
| 6 | HARMONICS PANEL | 24"x20"x10" | 1 |
| 7 | HIGH PRESSURE SWITCH | 1/4" | 1 |
| 8 | HOSE BIB | 3/4" | 1 |
| 9 | LEVEL SENSOR/FLOAT SWITCH CAP | | 1 |
| 10 | MODEM | | 1 |
| 11 | MOTOR | | 2 |
| 12 | PRESSURE GAUGE | 2-1/2" | 2 |
| 13 | PRESSURE TRANSDUCER | 1/4" | 2 |
| 14 | PUMP, SUBMERSIBLE | | 1 |
| 15 | PUMP, TURBINE, DI HEAD | 4" | 2 |
| 16 | SKID, BENT | 48"x96" | 1 |
| 17 | TRANSFORMER | 3kVA | 1 |
| 18 | VALVE, AIR RELIEF | 3/4" | 1 |
| 19 | VALVE, AIR RELIEF, FV-4 | 1/2" | 1 |
| 20 | VALVE, BALL | 3/4" | 1 |
| 21 | VALVE, BALL | 1" | 1 |
| 22 | VALVE, BALL | 1-1/2" | 1 |
| 23 | VALVE, BUTTERFLY, GROOVE, LEVER | 2" | 1 |
| 24 | VALVE, BUTTERFLY, GROOVE, LEVER | 4" | 2 |
| 25 | VALVE, BUTTERFLY, GROOVE, LEVER | 6" | 1 |
| 26 | VALVE, BUTTERFLY, LUG, LEVER, 175 PSI | 2" | 1 |
| 27 | VALVE, BUTTERFLY, WAFER, GEAR- OP, NBE | 6" | 2 |
| 28 | VALVE, CHECK, GROOVED | 2" | 1 |
| 29 | VALVE, CHECK, NBE | 6" | 1 |
| 30 | VALVE, CHECK, SILENT | 4" | 2 |
| 31 | VALVE, FILTER FLUSH | 1-1/2" | 1 |
| 32 | VALVE, LAKE SCREEN SUPPLY | 1" | 1 |
| 33 | VALVE, PRESSURE RELIEF, ANGLED | 2" | 1 |

SCOPE OF WORK

Packaged Pump Station supplier shall provide a variable speed vertical turbine pump station complete with pump, piping, valves, sensors, variable frequency drive (VFD), programmable logic controller (PLC), UL 508A listed control panel, and all appurtenances necessary for a complete and functioning pumping system. The station shall be mounted to press brake formed steel base and enclosed in a powder-coated marine grade aluminum enclosure. The pump station shall be manufactured by a <u>UL QCZJ and ISO 9001</u> certified pump station manufacturer.

<u>Technical Service and Support</u>. The manufacturer shall provide access 24/7 phone support with a factory certified technician. The technician shall have access to all relevant data specific to the pump station, including specifications, submittal, shop drawings, programming, and detailed photos of the system.

Factory Testing. The pump station shall undergo and pass all of the following system performance tests: Hydrostatic testing that meets ANSI/HI specifications and standards; Flow testing that meets ANSI/HI 14.6 specifications and standards; and Vibration testing that meets ANSI/HI 9.6.4 Vibration Measurement and Allowable Values specifications and standards. The pumping system shall be flow tested as a complete unit, which shall include function testing of pumps, motors, instrumentation, appurtenances, and control panel. The results of all tests shall be available to the owner.

PRODUCTS

Piping, Valves, Skid Base, & Station Enclosure.

Piping. The station piping shall be standard wall pipe with grooved connections. Flanged or welded connections shall not be acceptable. Threaded connections between the main piping sections other than at the pump volute shall not be acceptable.

Valves. Butterfly style isolation valves——with grooved connections--shall be included on station suction and discharge piping. Flanged or threaded connections shall not be accepted. A non-slam check valve shall be included on the discharge of each pump. An air release valve shall be included, located immediately after the pump check valve.

Skid. The pump skid shall be made of 1/4" press broke A36 steel. No welded bases or open rail systems shall be acceptable. Corrosion Protection. The pump skid and appurtenances shall be cleaned to bare steel and coated with a baked on powder coating, all piping including elbows shall be coated inside and out. The pump station shall be pressure tested prior to coating. No welding shall be

performed after the pump station is powder coated. Station Enclosure. The pump station enclosure shall be constructed of marine grade aluminum modular panels to allow access to all pumps and components by simply removing any panel. The entire front of the enclosure shall consist of hinged doors. The enclosure shall be powder coated. The roof of the enclosure shall be easily displaced and replaced by one person for the purpose of servicing the pump station. The station enclosure shall include a ventilation fan (or fans) appropriately sized to adequately cool the enclosed equipment.

Automatic Filter: The pump station shall include an automatic screen filter. The filter shall use suction scanning devices to automatically remove debris from the filter element. The filter shall be VAF or approved equal. Control logic for filter flush shall be included as part of the main control panel PLC programming.

Pump Control System

NEMA Rating. The VFD, PLC, and associated electrical equipment shall be mounted in a NEMA 12 enclosure rated for indoor installation. To avoid potential water or rodent damage, VFD's mounted outside the main control panel are not acceptable.

Control Panel Manufacturing & Testing. The pump control panel shall be manufactured and listed by a UL508A Panel Shop. The panel shall be UL labeled as an "Enclosed Industrial Control Panel". The pump control panel shall be completely manufactured, tested and programmed prior to delivery to the job site.

Documentation. A color wiring schematic and pump nameplate information shall be permanently affixed to the inside of the control enclosure. All field terminal connections shall be numbered and labeled.

Cooling System. The control panel cooling system shall be appropriately sized for the ambient conditions. The cooling system shall not allow dust, insects or rodents inside the pump control panel. Two sets of spare filters shall be included with the pumping system.

Main Disconnect. A service-entrance rated, non-fused disconnect shall be mounted in the pump control panel and shall isolate all power to the control panel. The disconnect shall include an operating handle mounted on the control panel enclosure door that is mechanically interlocked to prevent entry while the disconnect is in the ON position. To prevent damage from vandalism, a disconnect external to the pump station enclosure shall not be accepted. Overcurrent Protection. The VFD bridge rectifiers shall be protected from over current by an appropriately sized circuit breaker. Fuses are not acceptable.

Lightning & Surge Protection. The Pump Control Panel shall be equipped with transient voltage and surge arrestors.

Variable Frequency Drive (VFD). The VFD shall be appropriately sized to meet the FLA (full load amps) required by the pump motor, as stated on the motor nameplate. The VFD shall be manufactured by ABB Industrial Systems, Mitsubishi, or approved equal. Initial start-up and calibration shall be performed by a factory certified technician, which shall extend the warranty on the control panel to a total of three (3) years.

Programmable Logic Controller (PLC). The PLC shall be fully programmed prior to pump panel installation. The technician installing and programming the PLC is to be factory trained and certified by the PLC manufacturer. The PLC programming shall be non-proprietary, and the complete station programming shall be made available to the owner via a USB drive included with the station control panel.

PLC Operator Interface. The PLC shall be equipped with a 5.7" LCD color touchscreen. The operator interface shall allow the user to make adjustments to the PLC program locally without requiring any additional equipment such as a laptop computer. A VFD control keypad is not an acceptable substitution for the digital operator interface. The PLC shall have an Ethernet port to enable remote access.

PLC Control Functions:

- 1. User settable Local or Remote control.
- 2. System Pressure Setpoint
- 3. Pump Sleep Settings, with two threshold modes: Sleep by Flow or Sleep by Frequency
- 4. System Protection Settings, including fault and warning parameters for low flow, high flow, low pressure, high pressure, restart trials and restart delay time.
- 5. Load Factory Default Settings, User Saved Default Settings.
- 6. Pre-Programmed Start-Up Routines to limit and/or delay starting and acceleration of the pump to eliminate excessive velocity and pressure. It shall also include initial start-up, mainline fill, power outage and automatic re-starts.

PLC Monitoring Functions

1. Pump operating status, total pump run hours, motor frequency, motor amperage

- 2. System pressure, flow rate
- 3. Fault Log with time stamps and diagnostic utility.
- 4. Trend Data, with graphic display of system pressure, flow, motor frequency and amperage. Data shall be exportable to MS Excel.


5. USB port to upload, download of program, and data storage. Instrumentation.

Pressure Gauges shall have a 304 stainless steel case, with bezel construction. Gauges shall have a 2.5" diameter and be liquid filled. Pressure Transmitter(s) shall be constructed of stainless steel and rated for the pump station discharge pressure.

Flow Meter. The station shall include a magnetic flow meter. The flow meter shall have flange connections. The flow meter shall be capable of pulse and analog output. Current and totalized flow shall be read at the pump control panel HMI. Inserion flow meters and sensors shall not be accepted.


Submersible Pump Protection Shrouds

Each pump and motor shall be completely encased in a slotted PVC well casing. Both ends of the shall be thoroughly sealed to ensure that no water can enter at either end. Water shall only enter the casing through precision laser cut slots, which will not allow debris larger than can be passed entirely through the pump. All water entering the casing shall pass over, and cool the motor, prior to entering the pump.




Ph. 208.859.1980 DRAWN BY: CHECKED BY:

GB



PLAN VIEW



PLANT SCHEDULE L6.15

FINISH GRADE TO SLOPE AWAY —

FROM PUMP PAD ON ALL SIDES.

– 2"HDPE SCREEN RETURN LINE.

CONNECT TO PUMP STATION AND

SELF CLEANING SCREEN IN POND.

STRAP TO INTAKE PIPE EVERY 10'

LF 12" SDR32.5 PVC INTAKE PIPE CONTINUOUS SLOPE FROM WET WELL TO POND.

##" TO NORMAL

HIGH WATER

PREFABRICATED PUMP STATION. SEE —

DETAIL SHEET IR401.

12" CLEARANCE

ALL DE CONTRACTOR OF THE OWNER OWNE

40

WATER EL.: ####'


12" INTAKE INVERT EL.: ####'

WET WELL SUMP EL.: ####'

DENSITIES.

WALLS.

SECTION VIEW PLANT SCHEDULE L6.16



PUMP PAD EL.: +0.25' FINISH GRADE EL.: 0.00'

30" COVER 8" FLA DISCHARGE

6" 4000 PSI CONCRETE SLAB.


- COMPACTED STRUCTURAL BASE. MIN 6" DEPTH OVER UNDISTURBED SOILS.


- REINFORCED 12"X12" CONCRETE FOOTING AROUND WET WELL.

— KOR–N–SEAL RUBBER BOOT

-48" DIA. x ##' DEEP CONCRETE WET WELL WITH CONCRETE BASE. PRECAST RINGS WITH WATER TIGHT SEAL AT ALL JOINTS. MINIMUM 6"

-12" DEPTH 3/4" CRUSHED ROAD MIX OVER UNDISTURBED SOILS, COMPACTED TO 95% MAXIMUM DRY





| | Curve Table | | | | | |
|-------|-------------|--------|--------|------------|-----------------|--------------|
| ion | Curve # | Length | Radius | Delta | Chord Direction | Chord Length |
| 48"W | C1 | 95.67' | 78.23' | 70°03'57" | S48° 17' 47"W | 89.82' |
| 45"W | C2 | 71.55' | 38.60' | 106°12'24" | S30° 13' 33"W | 61.74' |
| '19"E | C3 | 69.69' | 39.00' | 102°23'02" | S73° 46' 10"E | 60.78' |
| '47"E | C4 | 24.98' | 38.00' | 37°39'32" | N36° 12' 33"E | 24.53' |


SCALE IN FEET


Rep.


STA: 11+84.

Cx6>.3c

LOPELINE








DRAINAGE UTILITY KEY N U01 INSTALL 30" CATCH BASINS. SEE D a. CB #1 RIM = 5827.75' 12" INV OUT = 5823.75' b. CB #2 RIM = 5827.4' 12" INV OUT = 5823.4' U02 INSTALL DRY WELL LENGTH, WIDTH VARY. SEE DETAIL 1 / C2.2. a. DW #1 6' L X 6' W X 6' DEPTH O RIM = 5827.5' 12" INV IN = 5823.3' b. DW #2 8' L X 8' W X 8' DEPTH RIM = 5826.75' 12" INV IN = 5822.6' c. DW #3 6' L X 6' W X 6' DEPTH RIM = 5826.2' d. DW #4 8' L X 8' W X 8' DEPTH RIM = 5826.8' -SD-U03 INSTALL 12" STORM DRAIN LINE SLO SEE DETAIL X1 / X2. U04 INSTALL LANDSCAPE DRYWELL FO DOWNSPOUTS. SEE DETAIL X1 / X2 $\mathbf{\Phi}^{\mathcal{W}}$

CONSTRUCTION NOTES


- 1. ALL CONSTRUCTION SHALL BE IN CONFORI CONSTRUCTION" (ISPWC) AND CITY OF KET COPY OF THE ISPWC AND CITY OF KETCHU
- 2. THE LOCATION OF EXISTING UNDERGROUN RESPONSIBLE FOR LOCATING EXISTING UT FULLY RESPONSIBLE FOR ANY AND ALL DA UNDERGROUND UTILITIES. CONTRACTOR S OF 48 HOURS IN ADVANCE OF EXCAVATION
- 3. CONTRACTOR SHALL COORDINATE LOCAT FRANCHISE.
- 4. THE CONTRACTOR SHALL CLEAN UP THE S EXISTED PRIOR TO CONSTRUCTION.
- 5. THE CONTRACTOR SHALL OBTAIN ALL NEC NATIONAL POLLUTANT DISCHARGE ELIMINA
- 6. ALL CLEARING & GRUBBING SHALL CONFO
- ALL EXCAVATION & EMBANKMENT SHALL C AND CROSS-SECTION SHOWN ON THE PLAI D-698. THE CONTRACTOR SHALL WATER O MEASUREMENTS, THE SUBGRADE MAY BE
- PROOF-ROLLING: AFTER EXCAVATION TO T PROOF ROLL THE SUBGRADE WITH A 5-T ENGINEER. THE CONTRACTOR SHALL IN CAPABLE OF COMPACTION ACCORDING AND/OR DISPLACES UNDER ANY TYPE O
- IF, IN THE OPINION OF THE ENGINEER, THE CONTRACTOR SHALL, AT HIS OWN EXPE SUBSOIL, LINE EXCAVATION WITH GEOT
- 8. ALL 2" MINUS GRAVEL SHALL CONFORM TO SECTION 801 AND COMPACTED PER SECTION DENSITY AS DETERMINED BY AASHTO T-99.
- 9. ALL 3/4" MINUS CRUSHED GRAVEL SHALL C WITH ISPWC SECTION 802 AND COMPACTE LABORATORY DENSITY AS DETERMINED BY
- 10. ALL ASPHALTIC CONCRETE PAVEMENT WO AGGREGATE SHALL BE 1/2" (13MM) NOMINA CONFORMING TO TABLE A-1 IN ISPWC SECT
- 11. ASPHALT SAWCUTS SHALL BE AS INDICATE OTHERWISE SO AS TO PROVIDE A CLEAN F
- 12. ALL CONCRETE WORK SHALL CONFORM TO IN ISPWC SECTION 703, TABLE 1. IMMEDIAT COMPOUND, TYPE 2, CLASS A PER ASTM C
- 13. ALL TRENCHING SHALL CONFORM TO ISPW 95% OF MAXIMUM DENSITY AS DETERMINED
- 14.PER IDAHO CODE § 55-1613, THE CONTRACT POINTS SET IN CONTROL SURVEYS; ALL MO ARE LOST OR DISTURBED BY CONSTRUCTIO CAUSING THEIR LOSS OR DISTURBANCE AT REPLACEMENT BENCHMARK OR CONTROL I

| ISSUED FOR PERMIT ON | ILY |
|---|--|
| NOTES DETAIL X1 / X2. | |
| | OH |
| TH AND DEPTH | S PRESERVE • GRADING CITY OF KETCHUM, BLAINE COUNTY, IDAHO OF KETCHUM, BLAINE COUNTY, IDAHO |
| | |
| | PRESERV GRADING PY OF KETCHUM, BLAIN FKETCHUM, BLAIN |
| LOPE AT 2%. | PRE GRA |
| OR BUILDING 2. | |
| | LOJ FOR: CIT |
| | SPRIN(SPRIN(SPRIN(10-03.dwg 11/06/24.4: |
| | ARKING LOT PREPARED FOR: CITY OLI 12024-10-03.dwg 11/06/24 4:27:42 PM |
| | ARA PARK I SECTION 118 L |
| | P/AF |
| | |
| RMANCE WITH THE MOST CURRENT EDITION OF THE "IDAHO STANDARDS FOR PUBLIC WORKS TCHUM STANDARDS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING AND KEEPING A JM STANDARDS ON SITE DURING CONSTRUCTION. | |
| ND UTILITIES ARE SHOWN ON THE PLANS IN AN APPROXIMATE WAY. THE CONTRACTOR SHALL BE TILITIES PRIOR TO COMMENCING AND DURING THE CONSTRUCTION. THE CONTRACTOR AGREES TO BE AMAGES WHICH RESULT FROM HIS FAILURE TO ACCURATELY LOCATE AND PRESERVE ANY AND ALL SHALL CALL DIGLINE (1-800-342-1585) TO LOCATE ALL EXISTING UNDERGROUND UTILITIES A MINIMUM N. | PROJECT INFORMATION |
| TIONS OF DRY UTILITY FACILITIES (POWER, CABLE, PHONE, TV) WITH THE APPROPRIATE UTILITY | PROJECT |
| SITE AFTER CONSTRUCTION SO THAT IT IS IN A CONDITION EQUAL TO OR BETTER THAN THAT WHICH | |
| CESSARY PERMITS PRIOR TO CONSTRUCTION (THIS MAY INCLUDE ENCROACHMENT PERMITS AND IATION SYSTEM (NPDES) CONSTRUCTION GENERAL PERMIT (CGP) PERMIT COVERAGE). | MINARTION |
| DRM TO ISPWC SECTION 201. | PRENOTRUS |
| CONFORM TO ISPWC SECTION 202. SUBGRADE SHALL BE EXCAVATED AND SHAPED TO LINE, GRADE, ANS. THE SUBGRADE SHALL BE COMPACTED TO 95% OF MAXIMUM DENSITY AS DETERMINED BY ASTM OR AERATE SUBGRADE AS NECESSARY TO OBTAIN OPTIMUM MOISTURE CONTENT. IN-LIEU OF DENSITY PROOF-ROLLED TO THE APPROVAL OF THE ENGINEER. | COME |
| THE SUBGRADE ELEVATION AND PRIOR TO PLACING COURSE GRAVEL, THE CONTRACTOR SHALL TON SMOOTH DRUM ROLLER, LOADED WATER TRUCK, OR LOADED DUMP TRUCK, AS ACCEPTED BY THE MMEDIATELY NOTIFY THE ENGINEER OF UNSUITABLE SUBGRADE MATERIAL AREAS, AND/OR AREAS NOT & TO THESE SPECIFICATIONS. UNSUITABLE OR DAMAGED SUBGRADE IS WHEN THE SOIL MOVES, PUMPS OF PRESSURE INCLUDING FOOT TRAFFIC LOADS. | DESIGNED BY: PLJ DRAWN BY: PLJ CHECKED BY: SURVEY DATE: |
| E CONTRACTOR'S OPERATIONS RESULT IN DAMAGE TO, OR PROTECTION OF, THE SUBGRADE, THE ENSE, REPAIR THE DAMAGED SUBGRADE BY OVER-EXCAVATION OF UNSUITABLE MATERIAL TO FIRM FEXTILE FABRIC, AND BACKFILL WITH PIT RUN GRAVEL. | |
| O ISPWC 802, TYPE II (ITD STANDARD 703.04, 2"), SHALL BE PLACED IN CONFORMANCE WITH ISPWC ION 202. MINIMUM COMPACTION OF PLACED MATERIAL SHALL BE 90% OF MAXIMUM LABORATORY 9. | Prive Prive Drive C6-9512 Protemark |
| CONFORM TO ISPWC 802, TYPE I (ITD STANDARD 703.04, 3/4" B), SHALL BE PLACED IN CONFORMANCE ED PER SECTION 202. MINIMUM COMPACTION OF PLACED MATERIAL SHALL BE 95% OF MAXIMUM Y AASHTO T-99 OR ITD T-91. | ENCE ENCE |
| DRK SHALL CONFORM TO ISPWC SECTION(S) 805, 810, AND 811 FOR CLASS II PAVEMENT. ASPHALT AL SIZE CONFORMING TO TABLE 803B IN ISPWC SECTION 803. ASPHALT BINDER SHALL BE PG 58-28 TION 805. | GALENA BLEVATION BLE |
| ED ON THE DRAWINGS, OR 24" INCHES FROM EDGE OF EXISTING ASPHALT, IF NOT INDICATED PAVEMENT EDGE FOR MATCHING. NO WHEEL CUTTING SHALL BE ALLOWED. | EACH WAR |
| O ISPWC SECTIONS 701, 703, AND 705. ALL CONCRETE SHALL BE 3,000 PSI MINIMUM, 28 DAY, AS DEFINED TELY AFTER PLACEMENT PROTECT CONCRETE BY APPLYING MEMBRANE-FORMING CURING C 309-94. APPLY CURING COMPOUND PER MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS. | |
| WC STANDARD DRAWING SD-301. TRENCHES SHALL BE BACKFILLED AND COMPACTED TO A MINIMUM OF ED BY AASHTO T-99. | |
| CTOR SHALL RETAIN AND PROTECT ALL MONUMENTS, ACCESSORIES TO CORNERS, BENCHMARKS AND ONUMENTS, ACCESSORIES TO CORNERS, BENCHMARKS AND POINTS SET IN CONTROL SURVEYS THAT ION SHALL BE REESTABLISHED AND RE-MONUMENTED, AT THE EXPENSE OF THE AGENCY OR PERSON IT THEIR ORIGINAL LOCATION OR BY SETTING OF A WITNESS CORNER OR REFERENCE POINT OR A | |
| POINT, BY OR UNDER THE DIRECTION OF A PROFESSIONAL LAND SURVEYOR. | |
| | NISIONS |
| | REVISI |


ш







C2.2




LEGEND


| s | SANITARY SEWER MAIN LINE (NOT SURVEYED) |
|----|---|
| SS | SANITARY SEWER SERVICE (NOT SURVEYED) |
| | WATER MAIN LINE (NOT SURVEYED) |
| WS | WATER SERVICE LINE (NOT SURVEYED) |
| WS | WATER SERVICE PROPOSED |
| | SEWER SERVICE PROPOSED |
| | UNDERGROUND POWER LINE PROPOSED |
| S | SEWER MANHOLE (NOT SURVEYED) |


UTILITY GENERAL NOTES

- 1. UTILITIES SHALL BE CONSTRUCTED PER THE CITY OF KETCHUM'S STANDARDS; THE MOST CURRENT VERSION OF THE IDAHO STANDARDS FOR PUBLIC WORKS CONSTRUCTION (ISPWC); AND DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ) STANDARDS.
- 2. WATER LINES SHALL HAVE A MINIMUM OF 10 FEET OF HORIZONTAL SEPARATION AND 18" VERTICAL SEPARATION FROM SEWER LINES AND STORM DRAIN PIPES, MEASURED FROM OUTSIDE OF PIPE TO OUTSIDE OF PIPE.
- 3. ELECTRICAL SERVICE LINE MAY BE IN THE SAME TRENCH AS THE WATER SERVICE LINE. ONCE THE WATER LINE IS INSTALLED, THE TRENCH SHALL BE BACK FILLED TO 42" IN DEPTH AND THE POWER INSTALLED WITH A MINIMUM OF 1-FOOT HORIZONTAL SEPARATION FROM THE WATER LINE.
- 4. UTILITY TRENCHES SHALL BE CONSTRUCTED PER DETAILS 1 & 2. TRENCHES SHALL BE BACKFILLED WITH IMPORTED STRUCTURAL BACKFILL.
- 5. CONTRACTOR SHALL CONTACT CITY OF KETCHUM WATER AND SEWER PRIOR TO ANY WATER AND SEWER SERVICE CONSTRUCTION.





C3.0






SECTION A





- STRUCTURAL DESIGN OF ABUTMENTS AND FOOTINGS BY BRIDGE MANUFACTURER




BRIDGE ABUTMENT #2 PROFILE (2 EACH)

SCALE: 1"=20' H; 1"=4' V


C4.0

OR

ISSUE



| n your final scope of work and specifications. | NOT FOR CONSTRUCTION | |
|--|---------------------------|---------------------|
| H Stringer 36' Span x 36' Width | PROJECT NUMBER: 223313 | DATE: 10/23/2024 |
| Warm Springs Preserve | DESIGNED: DYOB | DRAWN: DYOB |
| Vehicular Bridge | CHECKED: | APPROVED: |
| Ketchum, Idaho | SHEET NO .: 1 | OF 4 |



WARM SPRINGS PRESERVE STREAM & FLOODPLAIN ENHANCEMENT DESIGN SET WARM SPRINGS CREEK, KETCHUM, ID 95% DESIGN DRAWINGS



WOOD RIVER LAND TRUST CORY MCCAFFREY 119 E BULLION STREET HAILEY, ID 83333 (208) 788-3947

PREPARED BY:

UNITED

MA

MOSCOW

LEWISTON

OREGC

95

NEW MEADOWS

MOUNTAI

HOM

NEVADA


RIO APPLIED SCIENCE & ENGINEERING, LLC ATTN: JOE YOUNG, PE 3380 WEST AMERICANA TERRACE, SUITE 390 BOISE, ID 83706 (208) 484-4700

CANADA


95 STATES

OEUR D'ALENE

CASCADE



| SHEET COUNT | DRAWING NUMBER | SHEET TITLE |
|----------------|-------------------|---|
| 1 | G1 | COVER SHEET |
| 2 | G2 | GENERALS - 1 |
| 3 | G3 | GENERALS - 2 |
| 4 | G4 | CONSERVATION MEASURES - 1 |
| 5 | G5 | CONSERVATION MEASURES - 2 |
| 6 | G6 | QUANTITIES |
| 7 | C1 | EXISTING CONDITIONS OVERVIEW |
| 8 | C2 | EXISTING CONDITIONS PLAN 1 |
| 9 | C3 | EXISTING CONDITIONS PLAN 2 |
| 10 | C4 | EXISTING CONDITIONS PLAN 3 |
| 11 | C5 | EXISTING CONDITIONS PLAN 4 |
| 12 | C6 | PROPOSED CONDITIONS OVERVIEW |
| 13 | C7 | PROPOSED CONDITIONS PLAN - 1 |
| 14 | C8 | PROPOSED CONDITIONS PLAN - 2 |
| 15 | C9 | PROPOSED CONDITIONS PLAN - 3 |
| 16 | C10 | PROPOSED CONDITIONS PLAN - 4 |
| 17 | C11 | PROPOSED CONDITIONS DEMO OVERVIEW |
| 18 | C12 | PROPOSED CONDITIONS ACCESS, STAGING, & EROSION CONTRO |
| 19 | C13 | PROPOSED CONDITIONS ACCESS, STAGING, & EROSION CONTRO |
| 20 | C14 | MAINSTEM PLAN & PROFILE RIFFLE 1 - STA 10+39 TO 12+01 |
| 21 | C15 | MAINSTEM PLAN & PROFILE RIFFLE 2 - STA 26+17 TO 27+77 |
| 22 | C16 | BALDY CHANNEL PLAN & PROFILE STA 0+00 TO 6+00 |
| 23 | C17 | BALDY CHANNEL PLAN & PROFILE STA 6+00 TO 14+00 |
| 24 | C18 | BALDY CHANNEL PLAN & PROFILE STA 14+00 TO 20+92 |
| 25 | C19 | BALDY CHANNEL PLAN & PROFILE STA 20+92 TO 24+22 |
| 26 | C20 | DOLLAR CHANNEL PLAN & PROFILE STA 0+00 TO 3+47 |
| 27 | C21 | SUNNY CHANNEL PLAN & PROFILE STA 0+00 TO 3+38 |
| 28 | C22 | CHALLENGER CHANNEL PLAN & PROFILE STA 0+36 TO 3+32 |
| 29 | C23 | ROUNDHOUSE CHANNEL PLAN & PROFILE STA 0+03 TO 2+15 |
| 30 | C24 | VALLEY SECTION OVERVIEW |
| 31 | C25 | VALLEY SECTIONS |
| 32 | D1 | ACCESS AND ISOLATION DETAILS |
| 33 | D2 | DETAIL CONSTRUCTED RIFFLE |
| 34 | D3 | DETAIL CONSTRUCTED RIFFLE MATERIALS AND SCHEDULES |
| 35 | D4 | DETAIL SHORT ROUGHENED EDGE |
| 36 | D5 | DETAIL HABITAT STRUCTURE 1 |
| 37 | D6 | DETAIL HABITAT STRUCTURE 2 |
| 38 | D7 | DETAIL HABITAT STRUCTURE 3 |
| 39 | D8 | DETAIL HABITAT STRUCTURE 4 |
| 40 | D9 | DETAIL HABITAT STRUCTURE 5 |
| 41 | D10 | DETAIL HABITAT STRUCTURE 6 |
| 42 | D11 | DETAIL HABITAT STRUCTURE 7 |
| 43 | D12 | DETAIL HABITAT STRUCTURE 8 |
| 44 | D13 | DETAIL BALDY CHANNEL INLET |



GENERAL NOTES

- A. PROJECT COORDINATE SYSTEM IS NAD83 IDAHO STATE PLANE, CENTRAL ZONE, US FOOT.
- B. THE IDAHO STATE PUBLIC WORKS CONSTRUCTION (ISPWC) STANDARDS FOR CONSTRUCTION SHALL APPLY UNLESS OTHERWISE NOTED IN THE PLANS OR PROJECT SPECIAL PROVISIONS.
- C. TOPOGRAPHIC MAPPING WITHIN THE PROJECT AREA IS BASED ON A COMBINATION OF 2017 LIDAR DATA SUPPLEMENTED WITH TOPOGRAPHIC AND BATHYMETRIC DATA COLLECTED BY RIO ASE IN SEPTEMBER 2022 AND 2023 AND PHILLIPS LAND SURVEYING IN OCTOBER 2023. TOPOGRAPHIC MAPPING IS ASSUMED TO BE ACCURATE AND REPRESENTATIVE OF EXISTING CONDITIONS.
- D. EXISTING UNDERGROUND UTILITY LOCATIONS HAVE NOT BEEN IDENTIFIED AND ARE NOT SHOWN ON THESE PLANS. CONTRACTOR IS RESPONSIBLE TO LOCATE UTILITIES PRIOR TO CONSTRUCTION AND SHALL PROTECT EXISTING UTILITIES DURING CONSTRUCTION.

GENERAL REQUIREMENTS

1. DESCRIPTION OF WORK

- A. EXCAVATION OF FLOODPLAIN TO INCREASE SEASONAL FLOODPLAIN INUNDATION.
- B. ADDITION OF WOOD STRUCTURES ON WARM SPRINGS CREEK TO ENHANCE HABITAT.
- C. EXCAVATION OF POOLS WITHIN WARM SPRINGS CREEK TO ENHANCE HABITAT.
- D. CREATION OF A SIDE CHANNEL TO CONVEY FLOW INTO AND OUT OF A POND TO BE USED FOR IRRIGATION AND RECREATION.
- E. CREATION OF TWO SHORTER SIDE CHANNELS FOR HABITAT.
- F. INCORPORATION OF RIFFLES, POOLS, AND GLIDE HABITAT UNITS AND BANK AND FLOODPLAIN ROUGHNESS TREATMENTS AND WOOD HABITAT STRUCTURES WITHIN SIDE CHANNELS.
- G. REVEGETATION THROUGH PLANTING AND SEEDING OF NATIVE SPECIES WITHIN RIPARIAN, WETLAND, AND UPLAND ZONES.

2. PROJECT ROLES

- A. THE ABOVE WORK IS TO BE PERFORMED FOR THE CITY OF KETCHUM, HEREAFTER REFERRED TO AS THE "SPONSOR". THE SPONSOR WILL APPOINT A PROJECT STAFF MEMBER, HEREAFTER REFERRED TO AS "CONTRACTING OFFICER", WHO WILL HAVE THE RESPONSIBILITY TO ISSUE A CONTRACT TO CONSTRUCT THE ABOVE WORK AND WILL ADMINISTER THE CONTRACT AND FUNDS FOR THE PROJECT. ONLY THE SPONSOR MAY APPROVE CHANGES TO THE CONTRACT AMOUNT AND THE CONTRACT REQUIREMENTS.
- B. RIO ASE, HEREAFTER REFERRED TO AS THE "ENGINEER," IS THE SPONSOR'S REPRESENTATIVE WHO HAS DESIGNED THE PROJECT, THE ENGINEER PROVIDES CLARIFICATION TO THE CONTRACTING OFFICER REGARDING THE INTENT OF THE DRAWINGS AND SPECIFICATIONS AND WHETHER ALL THE PROPOSED OR COMPLETED WORK IS IN COMPLIANCE WITH THE CONSTRUCTION SPECIFICATIONS. THE ENGINEER ALSO REVIEWS ALL PROPOSED CHANGES AND MAKES RECOMMENDATIONS TO THE CONTRACTING OFFICER PRIOR TO THE CONTRACTING OFFICER'S APPROVAL OF THE CHANGES.
- C. THE OWNER OF THE PROPERTY WHERE CONSTRUCTION WILL OCCUR IS THE CITY OF KETCHUM, HEREIN REFERRED TO AS THE "PROPERTY OWNER."
- D. CONSTRUCTION OBSERVATION WILL BE PROVIDED BY THE SPONSOR AND/OR THE ENGINEER. CONSTRUCTION OBSERVERS WILL NOT DIRECT THE CONTRACTOR IN ANY WAY BUT WILL ADVISE THE CONTRACTING OFFICER REGARDING THE TECHNICAL REQUIREMENTS OF THE DRAWINGS AND SPECIFICATIONS, AND WHETHER THE ONGOING WORK IS IN COMPLIANCE OR IF THERE ARE DISCREPANCIES. THE CONSTRUCTION OBSERVERS ARE NOT RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIOUES, PROCEDURES AND/OR SAFETY OF THE CONTRACTOR.

3. GENERAL CONSTRUCTION SEQUENCE

- A. CONSTRUCTION STAKING
- B. SITE PREPARATION, INSTALL EROSION & SEDIMENT CONTROL MEASURES
- C. EARTHWORK AND GRADING INCLUDING EXCAVATION OF NEW CHANNELS, ALCOVES, AND FLOODPLAIN FEATURES, INSTALLATION OF BOULDERS AND LARGE WOOD HABITAT STRUCTURES
- D. CHECK GRADES, PREWASH CHANNELS, ACTIVATE CHANNELS
- E. RECLAIM TEMPORARY CONSTRUCTION ACCESS AND STAGING AREAS TO PRE-EXISTING CONDITIONS
- F. PLANTING AND SEEDING
- G. FINAL INSPECTION, SITE CLEANUP, AND DEMOBILIZATION

4. WORK SCHEDULE

- A. THE APPROVED WORK WINDOW FOR THIS PROJECT IS JULY 8 TO MARCH 15 THE FOLLOWING YEAR. WORK REQUIRING EQUIPMENT TO OPERATE PARTLY, OR WHOLLY, BELOW THE ORDINARY HIGH WATER LINE SHALL BE COMPLETED DURING THE IN-WATER WORK WINDOW.
- B. ALL OTHER WORK LOCATED OUTSIDE OF THE ORDINARY HIGH WATER LINE SHALL BE ACCOMPLISHED BY_
- C. THE CONTRACTOR MAY NOT LEAVE THE WORK SITE OR SUSPEND ACTIVITY FOR MORE THAN FIVE (5) CONSECUTIVE DAYS AFTER MOBILIZING TO THE SITE AND PRIOR TO REACHING SUBSTANTIAL COMPLETION UNLESS OTHERWISE APPROVED BY THE CONTRACTING OFFICER.

5. LOCATION

- A. ALL WORK IS ON WARM SPRINGS CREEK, ITS FLOODPLAIN, AND THE PROPERTY BELONGING TO THE PROPERTY OWNER.
- B. SITE IMPROVEMENTS WILL BE REQUIRED TO CREATE ACCESS POINTS SUITABLE FOR MOBILIZATION OF CONSTRUCTION EQUIPMENT AND DELIVERY OF PROJECT MATERIALS.

USE OF SITE

1. CONTRACTORS USE OF PREMISES

- A. PRIOR TO PERFORMING WORK, THE CONTRACTOR SHALL BECOME THOROUGHLY FAMILIAR WITH THE PROJECT SITE, PROJECT SITE CONDITIONS, AND ALL PORTIONS OF THE WORK.
- B. CONTRACTOR MUST COORDINATE ALL WORK AND ACCESS TO THE SITE WITH THE CONTRACTING OFFICER. THE CONTRACTING OFFICER WILL BE RESPONSIBLE FOR COORDINATION WITH THE PROPERTY OWNER.
- C. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING PUBLIC SAFETY IN AND AROUND THE PROJECT SITE, AND WILL PROVIDE ANY SAFETY PRECAUTIONS SUCH AS TEMPORARY FENCING OR OTHER METHODS AT THE CONTRACTOR'S DISCRETION WHERE DEEMED NECESSARY. THE CONTRACTOR SHALL BE SOLELY AND COMPLETELY RESPONSIBLE FOR COMPLIANCE WITH ALL APPLICABLE OSHA AND NRS CHAPTER 618 STANDARDS, IN THE CONSTRUCTION PRACTICES FOR ALL EMPLOYEES DIRECTLY ENGAGED IN THE CONSTRUCTION OF THIS PROJECT.
- D. THE CONTRACTOR IS RESPONSIBLE FOR THE SECURITY OF PROPERTY AT THE PROJECT SITE AND WILL PROVIDE REASONABLE PROTECTION TO PREVENT DAMAGE OR LOSS TO EQUIPMENT, MATERIALS, AND SUPPLIES INCORPORATED IN THE PROJECT AND TO THE PROPERTY OWNER.

- E. THE CONTRACTOR SHALL ONLY ACCESS THE PROJECT SITE AS SHOWN ON THE DRAWINGS. ALTERNATE GATE ACCESS POINTS SHALL NOT BE USED, UNLESS AUTHORIZED BY THE CONTRACTING OFFICER.
- F. CONTRACTOR SHALL ONLY USE DESIGNATED ACCESS ROUTES AND STREAM CROSSING LOCATIONS AS INDICATED ON THE DRAWINGS.
- G. THE CONTRACTOR SHALL CAUSE NOTICE TO BE GIVEN TO THE APPROPRIATE STATE UNDERGROUND UTILITIES LOCATION CENTER AND TO ANY UNDERGROUND UTILITY FACILITIES WHO ARE NOT MEMBERS OF THE REGISTERED PROTECTION SERVICE. THE CONTRACTOR MUST TAKE ALL REASONABLE MEASURES TO PROTECT EXISTING UTILITIES AND ALL NOTICES SHALL BE GIVEN AT LEAST 72 HOURS PRIOR TO THE START OF CONSTRUCTION. ALL WORK PERFORMED ADJACENT TO UTILITIES SHALL BE IN ACCORDANCE WITH PROCEDURES OUTLINED BY THE UTILITY COMPANY. THE CONTRACTOR SHALL IMMEDIATELY REPORT ANY DAMAGE TO UTILITIES TO THE SPONSOR AND THE UTILITY COMPANY.
- H. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE INCURRED TO ANY UTILITY LINES AT NO COST OR OBLIGATION TO THE SPONSOR OR THE PROPERTY OWNER
- I. MOVEMENT OF CONSTRUCTION EQUIPMENT OVER PIPES, BRIDGES, UTILITIES OR INFRASTRUCTURE DURING CONSTRUCTION SHALL BE AT THE CONTRACTOR'S RISK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE INCURRED TO INFRASTRUCTURE AT NO COST OR OBLIGATION TO THE SPONSOR OR THE PROPERTY OWNER
- J. CONTRACTOR IS EXPECTED TO KEEP A NEAT AND TIDY CONSTRUCTION SITE, FREE OF ACCUMULATED WASTE MATERIALS AND TRASH.
- K. CONTRACTOR SHALL TAKE ALL MEASURES NECESSARY TO MINIMIZE DAMAGE TO EXISTING VEGETATION DURING CONSTRUCTION ACTIVITIES.
- L. THE CONTRACTOR SHALL ONLY REMOVE TREES AND SHRUBS THAT ARE ABSOLUTELY NECESSARY FOR THE EXECUTION OF THE WORK AND SHALL MAKE ALL FEFORTS TO MINIMIZE TREE AND SHRIJB REMOVAL. IN THE EVENT THAT A TREE OR SHRIJB OUTSIDE THE IMMEDIATE WORK AREAS MUST BE REMOVED OR DAMAGED, THE CONTRACTOR SHALL OBTAIN PRIOR APPROVAL FROM THE CONTRACTING OFFICER. ANY TREE OR SHRUB UNNECESSARILY REMOVED FROM THE WORK SITE SHALL BE REPLACED BY A NEW TREE OR SHRUB OF EQUAL OR GREATER VALUE AT THE SOLE EXPENSE OF THE CONTRACTOR AS APPROVED BY THE CONTRACTING OFFICER.
- M. THE CONTRACTOR SHALL REMOVE ALL TEMPORARY EQUIPMENT AND FACILITIES UPON COMPLETION OF WORK UNDER THIS CONTRACT.

2. EQUIPMENT

- A. CONTRACTOR IS REQUIRED TO PRESSURE WASH AND REMOVE ALL DIRT, GREASE, OIL, FUEL, VEGETATION AND WEED SEEDS BEFORE BRINGING EQUIPMENT ON SITE TO LIMIT INTRODUCTION OF NOXIOUS WEEDS, AQUATIC INVASIVES AND POLLUTANTS TO THE SITE.
- B. COMPLETE VEHICLE AND EQUIPMENT STAGING, CLEANING, MAINTENANCE, REFUELING, AND FUEL STORAGE IN THE DESIGNATED CONSTRUCTION STAGING AND MATERIAL STORAGE AREA 150' AWAY FROM ANY NATURAL WATER BODY.
- C. INSPECT ALL VEHICLES AND EQUIPMENT OPERATED WITHIN 150 FEET OF SURFACE WATERS DAILY FOR FLUID LEAKS BEFORE LEAVING THE CONSTRUCTION STAGING AND MATERIAL STORAGE AREA. REPAIR ANY LEAKS DETECTED IN THE CONSTRUCTION STAGING AND MATERIAL STORAGE AREA BEFORE RESUMING OPERATION. DOCUMENT INSPECTIONS IN A RECORD THAT IS AVAILABLE FOR REVIEW ON REQUEST BY THE CONTRACTING OFFICER AND REGULATORY AGENCIES.
- D. USE OF EQUIPMENT IN FLOWING WATER IS LIMITED BY APPLICABLE PERMITS. EQUIPMENT MUST BE THOROUGHLY CLEANED BEFORE ENTERING THE WATER. CONTRACTOR IS RESPONSIBLE FOR COMPLIANCE WITH APPLICABLE REGULATIONS FOR IN-WATER EQUIPMENT USE.
- E. HYDRAULICS FLUIDS ALL EQUIPMENT THAT ARE DOING WORK IN ACTIVE STREAM CHANNELS, OR PERMANENT WATER BODIES DURING PROJECT CONSTRUCTION MUST USE HYDRAULIC OIL THAT MEETS OR EXCEEDS ENVIRONMENTALLY ACCEPTABLE LUBRICANTS BY THE U.S. EPA (2011); E.G., MINERAL OIL, POLYGLYCOL, VEGETABLE OIL, SYNTHETIC ESTER; MOBIL® BIODEGRADABLE HYDRAULIC OILS, TOTAL® HYDRAULIC FLUID, TERRESOLVE TECHNOLOGIES LTD.® BIOBASED BIODEGRADABLE LUBRICANTS, COUGAR LUBRICATION® 2XT BIO ENGINE OIL, SERIES 4300 SYNTHETIC BIO-DEGRADABLE HYDRAULIC OIL, 8060-2 SYNTHETIC BIO-DEGRADABLE GREASE NO. 2, ETC. OR MEET STRINGENT ACUTE AQUATIC TOXICITY (L-50), WHICH IS INHERENTLY BIODEGRADABLE. THIS DOES NOT INCLUDE TRUCKS, DOZERS, FRONT END LOADERS, ETC., THAT ARE OPERATED ON THE FLOOD PLAIN OR INVOLVED IN THE CONSTRUCTION OF NEW CHANNELS PRIOR TO ADDING WATER FLOW OR FILLING ABANDONED CHANNELS AFTER DE-WATERING. ALL PRODUCTS SHALL BE API CERTIFIED AND THE VENDOR SHALL FURNISH DOCUMENTATION OF THE CERTIFICATION UPON REQUEST. PRODUCTS MUST MEET THE PERFORMANCE AND WARRANTY REQUIREMENTS OF THE MANUFACTURERS LISTED IN THE SPECIFICATIONS.
- F. ABSORBENT PADS TO SOAK UP LEAKS AND A FUEL SPILL RESPONSE KIT (INCLUDING RAG PADS AND BOOMS) OF APPROPRIATE SIZE FOR THE EQUIPMENT USED SHALL BE ON SITE AT ALL TIMES AND READILY AVAILABLE THROUGHOUT THE CONSTRUCTION PERIOD.

3. HOURS OF WORK

A. THE NORMAL WORK HOURS SHALL BE 7:00 AM TO 7:00 PM, MONDAY THROUGH FRIDAY. NO WORK SHALL BE PERFORMED OUTSIDE THE NORMAL WORK HOURS, OR ON SATURDAYS, SUNDAYS, OR HOLIDAYS UNLESS AUTHORIZED BY THE CONTRACTING OFFICER. THE CONTRACTOR SHALL REQUEST WORK HOUR VARIATIONS IN WRITING VIA EMAIL AND OBTAIN WRITTEN APPROVAL FROM THE CONTRACTING OFFICER PRIOR TO WORKING OUTSIDE NORMAL WORK HOURS.

SPECIAL PROCEDURES

1. IN-STREAM WORK

- A. IN-STREAM WORK IS ALLOWED AS SPECIFIED IN THE PERMIT DOCUMENTS.
- B. TURBIDITY CRITERIA SHALL BE STRICTLY ADHERED TO WHILE COMPLETING ALL INSTREAM WORK. COFFERDAMS, FLOW DIVERSION STRUCTURES AND BYPASS CHANNELS SHALL BE INSTALLED AT ALL LOCATIONS INDICATED ON THE DRAWINGS OR AT LOCATIONS SHOWN ON AN APPROVED "COFFERDAM AND FLOW DIVERSION PLAN" (SEE SPECIFICATIONS). SOME ASPECTS OF THE PROJECT MAY NOT REQUIRE THE USE OF A COFFERDAM TO COMPLETE THE WORK.
- C. DEWATERING WITHIN COFFERDAMS SHALL BE PERFORMED TO THE EXTENT NECESSARY TO CONSTRUCT THE PROJECT AS SHOWN ON THESE PLANS AS FOLLOWS: DEWATERING AT WOOD STRUCTURE LOCATIONS SHALL BE CONDUCTED SUCH THAT WATER IS NO DEEPER THAN THE DIAMETER OF THE LOG(S) ON THE LOWEST LAYER OF THE STRUCTURE, AND WITHIN CONSTRUCTION EXCAVATIONS SUCH THAT WATER IS SHALLOW ENOUGH TO ALLOW THE CONTRACTING OFFICER TO EASILY INSPECT FINISHED ELEVATIONS OF THE WORK. DISCHARGE FROM PUMPING SHALL BE ROUTED TO THE FLOODPLAIN AREAS SO AS TO ALLOW THE REMOVAL OF FINE SEDIMENTS PRIOR TO REENTERING SURFACE WATERS OR WETLANDS. ALL PUMPS USED BY THE CONTRACTOR FOR DEWATERING SHALL HAVE SCREENED INTAKES THAT MEET WASHINGTON DEPARTMENT OF FISH AND WILDLIFE SPECIFICATIONS AND NATIONAL MARINE FISHERIES SERVICE ANADROMOUS SALMONID PASSAGE FACILITY DESIGN CRITERIA (NMFS, 2011).
- D. CONTRACTOR SHALL RETAIN EXISTING VEGETATION AND VARY CHANNEL WIDTH (±0.5 FEET) AND DEPTH (+0.2 TO -0.5 FEET) OF SIDE CHANNEL EXCAVATION AS DIRECTED BY THE CONTRACTING OFFICER.

| Applied Science & Engineering WOOD RIVER LAND TRUST | | | | |
|---|---------------------|--|--|--|
| WARM SPRINGS PRESERVE STREAM & FLOODPLAIN ENHANCEMENT DESIGN SET | 95% DESIGN DRAWINGS | WOOD RIVER LAND TRUST WARM SPRINGS CREEK, KETCHUM, ID BLAINE COUNTY, IDAHO | | |
| DESIGNED: APPROVED: DRAWING N | ENERAL | | | |

SPECIAL PROCEDURES CONTINUED

2. TURBIDITY MONITORING

- A. TURBIDITY MONITORING IS REQUIRED AS PART OF THIS PROJECT AND SHALL BE COMPLETED BY THE CONTRACTOR IN ACCORDANCE WITH THE CONSERVATION MEASURES. THE CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS FOR TURBIDITY AS SET FORTH IN THE PERMIT DOCUMENTS AND FOLLOW THE PROTOCOLS OUTLINED BELOW
 - 1. TAKE A BACKGROUND TURBIDITY SAMPLE USING A RECENTLY-CALIBRATED TURBIDIMETER IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS, OR MEASURE TURBIDITY WITH A VISUAL TURBIDITY OBSERVATION. TURBIDITY SHOULD BE MEASURED EVERY 2 HOURS WHILE IN-WATER WORK IS BEING IMPLEMENTED OR MORE OFTEN IF SEDIMENT DISTURBANCE VARIES GREATLY. TURBIDITY DOES NOT NEED TO BE MONITORED WHEN WORKING IN THE DEWATERED SECTIONS UNLESS A VISIBLE PLUME IS EVIDENT. THE BACKGROUND SAMPLES SHOULD BE TAKEN AT A RELATIVELY UNDISTURBED LOCATION APPROXIMATELY 100 FEET UPSTREAM FROM THE PROJECT AREA, RECORD THE OBSERVATION, LOCATION (LATITUDE/LONGITUDE), AND TIME BEFORE MONITORING AT THE DOWNSTREAM POINT, KNOWN AS THE MEASUREMENT COMPLIANCE POINT.
 - 2. TAKE A SECOND SAMPLE, IMMEDIATELY AFTER EACH UPSTREAM SAMPLE, AT THE MEASUREMENT COMPLIANCE POINT, APPROXIMATELY 100 FEET DOWNSTREAM FROM THE PROJECT AREA. RECORD THE DOWNSTREAM OBSERVATION, LOCATION, AND TIME.
 - 3. COMPARE THE UPSTREAM AND DOWNSTREAM SAMPLES. IF OBSERVED OR MEASURED TURBIDITY DOWNSTREAM IS MORE THAN UPSTREAM OBSERVATION OR MEASUREMENT (> 10%), THE ACTIVITY MUST BE MODIFIED TO REDUCE TURBIDITY. IF VISUAL ESTIMATES ARE USED, AN OBVIOUS DIFFERENCE BETWEEN UPSTREAM AND DOWNSTREAM OBSERVATIONS SHALL BEAR THE ASSUMPTION OF A (> 10%) DIFFERENCE (FIGURE 1). MARK "YES" OR "NO" ON YOUR DATASHEET. CONTINUE TO MONITOR EVERY 2 HOURS AS LONG AS INSTREAM ACTIVITY CONTINUES.
 - 4. IF EXCEEDANCES OCCUR FOR MORE THAN TWO CONSECUTIVE MONITORING INTERVALS (AFTER 4 HOURS), THE ACTIVITY MUST STOP UNTIL THE TURBIDITY LEVEL RETURNS TO BACKGROUND, AND THE EC LEAD MUST BE NOTIFIED WITHIN 48 HOURS. THE EC LEAD SHALL DOCUMENT THE REASONS FOR THE EXCEEDANCE AND CORRECTIVE MEASURES TAKEN THEN NOTIFY THE LOCAL NMFS BRANCH CHIEF AND/OR USFWS FIELD SUPERVISOR AND SEEK RECOMMENDATIONS
 - 5. IF AT ANY TIME, MONITORING, INSPECTIONS, OR OBSERVATIONS SHOW THAT THE TURBIDITY CONTROLS ARE INEFFECTIVE, IMMEDIATELY MOBILIZE WORK CREWS TO REPAIR, REPLACE, OR REINFORCE CONTROLS AS NECESSARY.
 - 6. ANY EXCEEDANCE OF THE TURBIDITY STANDARD MUST BE REPORTED TO THE DEQ REGIONAL OFFICE WITHIN 24 HOURS. COPIES OF TURBIDITY MONITORING RECORDS OR LOGS MUST BE AVAILABLE TO DEQ UPON REQUEST. THE LOG MUST INCLUDE BACKGROUND MEASUREMENTS (IN NTUS); DOWN-CURRENT MEASUREMENTS, COMPARISON OF BACKGROUND AND DOWN-CURRENT MONITORING AS A NUMERIC VALUE (IN NTUS), AND LATITUDE/LONGITUDE, TIME AND DATE FOR EACH SAMPLING EVENT. MONITORING RECORDS OR LOGS MUST DESCRIBE ALL EXCEEDANCES AND SUBSEQUENT ACTIONS TAKEN TO CORRECT THE VIOLATIONS, INCLUDING MONITORING AND THE EFFECTIVENESS OF THE ACTION(S) TAKEN.

WOOD STRUCTURES

1. WOOD STRUCTURES

- A. SEE SPECIFICATIONS FOR LOG, RACKING, AND SLASH MATERIAL REQUIREMENTS.
- B. CONTRACTOR SHALL PROCURE ALL WOOD MATERIALS REOUIRED FOR THIS CONTRACT THROUGH LEGAL MEANS AND HAS SOLE RESPONSIBILITY TO SECURE ANY AND ALL NECESSARY PERMITS TO DO SUCH.

TEMPORARY UTILITIES

1. TEMPORARY ELECTRIC

- A. ELECTRIC POWER IS NOT AVAILABLE AT THE SITE.
- B. IF TEMPORARY POWER IS NECESSARY TO OPERATE PUMPS, CONTRACTOR SHALL PROVIDE ALL GENERATORS, AND OTHER ELECTRICAL EQUIPMENT AND FACILITIES FOR OBTAINING AND DISTRIBUTING POWER ON THE SITE.
- C. ALL GENERATORS SHALL BE PLACED OUTSIDE OF THE ORDINARY HIGH WATER LINE WITH APPROPRIATE SPILL PREVENTION AND CONTAINMENT MEASURES.

2. TEMPORARY WATER

A. POTABLE WATER IS NOT AVAILABLE TO THE CONTRACTOR AT THE SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUPPLYING POTABLE WATER FOR ALL EMPLOYEES AT THE SITE.

3. TEMPORARY SANITATION FACILITIES

A. CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY SANITATION FACILITIES (E.G., "PORT-A-POTTIES") FOR USE BY THE CONSTRUCTION AND OBSERVATION CREWS FOR THE DURATION OF THE CONSTRUCTION AND REVEGETATION ACTIVITIES.

4. TEMPORARY FIRST AID FACILITIES

- A. CONTRACTOR SHALL PROVIDE FIRST AID EQUIPMENT AND SUPPLIES ONSITE FOR EMPLOYEES.
- B. CONTRACTOR SHALL HAVE AN EMERGENCY ACTION PLAN AND INSTRUCT EMPLOYEES WHAT TO DO IN CASE OF A WORKPLACE INJURY.
- C. CONTRACTOR SHALL REVIEW THE PLAN WITH EACH EMPLOYEE AND HAVE THE PLAN AVAILABLE ONSITE AT ALL TIMES.

5. TEMPORARY FIRE PROTECTION

- A. THE CONTRACTOR SHALL CONDUCT OPERATIONS IN A MANNER THAT IS FIRE-SAFE FOR THE WORK AREA AND ADJACENT AREAS. PROPER FIRE EXTINGUISHERS SHALL BE INSTALLED ON ALL EQUIPMENT AND MAINTAINED BY THE CONTRACTOR. THE PREMISE SHALL BE MAINTAINED CLEAR OF RUBBISH, DEBRIS, OR OTHER MATERIAL CONSTITUTING A POTENTIAL FIRE HAZARD.
- WHERE SIGNIFICANT OR CONTINUED NONCOMPLIANCE WITH FIRE SAFETY IS NOTED, THE CONTRACTING OFFICER RESERVES THE RIGHT TO STOP THE WORK AT NO EXTRA COST DUE TO EXTENSION OF TIME PENDING REMEDIAL ACTION. FURTHERMORE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR, AND REIMBURSE THE SPONSOR AS APPROPRIATE, ANY FINES OR PENALTIES LEVIED BY THE FIRE DEPARTMENT.

6. TEMPORARY FUEL STORAGE

- A. ALL STATIONARY TEMPORARY FUEL STORAGE SHALL BE LOCATED IN CONSTRUCTION STAGING AREAS OR OTHERWISE APPROVED LOCATIONS.
- B. FUEL STORAGE VESSELS SHALL BE INSPECTED PRIOR TO SITE DELIVERY FOR LEAKS OR DAMAGE. LEAKY STORAGE TANKS WILL NOT BE PERMITTED ON SITE.
- C. SECONDARY CONTAINMENT WILL BE REQUIRED FOR ALL ON SITE FUEL STORAGE VESSELS. SECONDARY CONTAINMENT STRUCTURES WILL PROVIDE STORAGE CAPACITY IN THE AMOUNT OF 110% OF THE VOLUME OF THE LARGEST PRIMARY CONTAINER STORED WITHIN.
- D. AT THE CONCLUSION OF PROJECT CONSTRUCTION, ANY LEAKED FUEL OR CONTAMINATED RAINWATER WITHIN THE SECONDARY CONTAINMENT STRUCTURE WILL BE PROPERLY COLLECTED AND LEGALLY DISPOSED OF AT AN OFFSITE LOCATION.

TEMPORARY ENVIRONMENTAL CONTROLS

1. REGULATORY REQUIREMENTS

A. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL FEDERAL, STATE, AND LOCAL LAWS AND REGULATIONS AND SHALL BE EXPECTED TO MAINTAIN COPIES OF ALL REQUIRED PERMITS ON SITE FOR INSPECTION AND REVIEW.

- B. CONTRACTOR SHALL CONFORM TO MOST STRINGENT REQUIREMENT IN CASES OF CONFLICT BETWEEN SPECIFICATIONS AND REGULATORY REQUIREMENTS.
- C. CONTRACTING OFFICER MAY STOP ANY CONSTRUCTION ACTIVITY IN VIOLATION OF FEDERAL, STATE, OR LOCAL LAWS AND ADDITIONAL EXPENSES RESULTING FROM WORK STOPPAGE WILL BE RESPONSIBILITY OF CONTRACTOR
- D. CONTRACTOR WILL BE RESPONSIBLE FOR PRODUCING IMPLEMENTING, ADHERING TO, AND MAINTAINING A STORMWATER POLLUTION PREVENTION PLAN (SWPPP) OR EQUIVALENT PLAN IN ACCORDANCE WITH THE REGULATIONS AND GUIDELINES SET FORTH AND SUBJECT TO APPROVAL BY THE STATE IN WHICH THE PROJECT IS LOCATED.

2. DUST CONTROL

- A. CONTRACTOR SHALL TRUCK WATER TO THE SITE TO USE FOR DUST ABATEMENT. WATER SHALL BE OBTAINED THROUGH LEGAL MEANS.
- B. CONTRACTOR SHALL PROVIDE ALL LABOR, EQUIPMENT, AND MATERIALS TO CONTROL DUST ON ALL ACCESS ROADS SEVERAL TIMES PER DAY TO PREVENT DUST NUISANCE OR DAMAGE TO PERSONS, PROPERTY, OR ACTIVITIES, INCLUDING, BUT NOT LIMITED TO CROPS, ORCHARDS, CULTIVATED FIELDS, WILDLIFE HABITATS, DWELLINGS AND RESIDENCES, AGRICULTURAL ACTIVITIES, RECREATIONAL ACTIVITIES, TRAFFIC, AND SIMILAR CONDITIONS.
- C. CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGES RESULTING FROM DUST ORIGINATING FROM CONTRACTOR OPERATIONS.

3. AIR POLLUTION CONTROL

- A. UTILIZE REASONABLY AVAILABLE METHODS AND DEVICES TO PREVENT, CONTROL, AND OTHERWISE MINIMIZE ATMOSPHERIC EMISSIONS OR DISCHARGES OF AIR CONTAMINANTS
- B. DO NOT OPERATE EQUIPMENT AND VEHICLES THAT SHOW EXCESSIVE EXHAUST GAS EMISSIONS UNTIL CORRECTIVE REPAIRS OR ADJUSTMENTS REDUCE SUCH EMISSIONS TO ACCEPTABLE LEVELS

4. NOISE CONTROL

- A. DO NOT EXCEED 80 DECIBELS (DAYTIME), AS MEASURED AT NOISE-SENSITIVE AREAS SUCH AS RESIDENCES AND SCHOOLS DURING THE HOURS OF 7:00 A.M. TO 7:00 P.M. DO NOT EXCEED NOISE LEVELS OF 65 DECIBELS (NIGHTTIME) DURING THE HOURS OF 7:00 P.M. TO 7:00 A.M.
- B. PROVIDE SPECIALTY MUFFLERS FOR CONTINUOUSLY RUNNING GENERATORS, PUMPS, AND OTHER STATIONARY EOUIPMENT TO MEET THE DECIBEL REOUIREMENTS ABOVE
- C. COMPRESSION BRAKES ARE NOT ALLOWED.
- D. PERFORM OPERATIONS PRODUCING HIGH-INTENSITY IMPACT NOISE ONLY WEEKDAYS DURING THE HOURS OF 7:00 A.M. TO 7:00 P.M.

5. WATER POLLUTION CONTROL

A. PERFORM CONSTRUCTION ACTIVITIES BY METHODS THAT WILL PREVENT ENTRANCE, OR ACCIDENTAL SPILLAGE, OF SOLID MATTER, CONTAMINANTS, DEBRIS, OR OTHER POLLUTANTS OR WASTES INTO STREAMS, FLOWING OR DRY WATERCOURSES, LAKES, WETLANDS, RESERVOIRS, OR UNDERGROUND WATER SOURCES. SUCH POLLUTANTS AND WASTES INCLUDE, BUT ARE NOT RESTRICTED TO REFUSE, GARBAGE, CEMENT, SANITARY WASTE, INDUSTRIAL WASTE, HAZARDOUS MATERIALS, RADIOACTIVE SUBSTANCES, OIL AND OTHER PETROLEUM PRODUCTS, AGGREGATE PROCESSING TAILINGS, MINERAL SALTS, AND THERMAL POLLUTION.

6. SURVEYING

- A. THE CONTRACTOR SHALL PROVIDE ALL SURVEYING TASKS NECESSARY FOR CONSTRUCTION. THIS INCLUDES, BUT IS NOT LIMITED TO: LOCATE SURVEY CONTROL AND REFERENCE POINTS, ESTABLISH HORIZONTAL AND VERTICAL CONTROL, PLACE GRADING STAKES, IDENTIFY AND STAKE THE CHANNEL CENTERLINE, IDENTIFY ALL MAJOR AND MINOR WORK COMPONENTS, AND PERIODICALLY VERIFY LOCATIONS AND ELEVATIONS OF ALL CONSTRUCTION ITEMS. AUTOCAD FILES FOR THE DESIGN ARE AVAILABLE UPON REOUEST.
- B. CONTRACTOR SHALL BE RESPONSIBLE FOR REPORTING ANY ELEVATION OR HORIZONTAL DISCREPANCIES TO THE CONTRACTING OFFICER FOR CLARIFICATION. MINOR ADJUSTMENTS TO SUIT FIELD CONDITIONS ARE ANTICIPATED, AND IT SHALL BE THE RESPONSIBILITY OF THE ENGINEER TO MAKE DECISIONS REGARDING THESE ADJUSTMENTS.
- C. ELECTRONIC VERSIONS OF THE TOPOGRAPHIC MAPPING AND DESIGN SURFACES ARE AVAILABLE IN AUTOCAD FORMAT UPON REQUEST. TOPOGRAPHIC MAPPING DO NOT INCLUDE UTILITIES AND SURFACE FEATURES, STRUCTURES, AND OTHER ITEMS MAY BE ENCOUNTERED AT THE PROJECT SITE THAT ARE NOT REFLECTED IN THE MAPPING. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CHECK EXISTING CONDITIONS PRIOR TO BIDDING OR COMMENCING WORK.
- D. CONTROL POINTS IDENTIFIED ON THE DRAWINGS SHALL BE USED FOR ALL TIES TO SPATIAL AND ELEVATION DATA LISTED IN THE DRAWINGS.
- E. ALL DIMENSIONS ON THE DRAWINGS ARE IN UNITS OF FEET AND DECIMALS, UNLESS OTHERWISE SPECIFIED.

FINAL SITE REVIEW

1. GENERAL

- A. THROUGHOUT THE PROGRESS OF THE WORK, MAINTAIN AN ACCURATE RECORD OF CHANGES IN THE CONTRACT DOCUMENTS.
- B. PRIOR TO COMMENCING DEMOBILIZATION, THE CONTRACTOR SHALL REVIEW ALL CONSTRUCTION ELEMENTS WITH THE CONTRACTING OFFICER, WHO WILL GIVE APPROVAL OR PROVIDE A WRITTEN LIST FINAL ITEMS TO BE CORRECTED.
- C. FINAL SITE REVIEW APPROVAL IS CONTINGENT ON THE SUCCESSFUL COMPLETION OF: CONSTRUCTION OF DESIGN ELEMENTS, CLEANING OF THE SITE, REMOVAL OF ALL CONSTRUCTION ACCESS ROADS, RUTS AND STAGING AREAS, RESTORATION OF AREAS DISTURBED BY CONSTRUCTION ACTIVITIES, AND OTHER TASKS AS OUTLINED IN THESE SPECIFICATIONS AND ON THE DRAWINGS.

2. RECORD DOCUMENTS

- A. CONTRACTOR'S SET: SECURE FROM THE CONTRACTING AGENCY ONE COMPLETE SET OF CONTRACT DOCUMENTS FOR USE AS THE CONTRACTOR'S SET OF RECORD DOCUMENTS. LABEL IMMEDIATELY AS "RECORD DOCUMENTS-CONTRACTOR'S SET." USE THIS SET TO RECORD ALL CHANGES IN THE WORK AS THEY OCCUR ON A DAILY BASIS
- B. MAINTAIN THE CONTRACTOR'S SET OF RECORD DOCUMENTS PROTECTED FROM DETERIORATION AND FROM LOSS AND DAMAGE UNTIL COMPLETION OF THE WORK. IN THE EVENT OF LOSS OR DAMAGE USE WHATEVER MEANS NECESSARY TO AGAIN SECURE AND RECORD THE DATA.

3. FINAL CLEANUP

- A. COMPLETE THE FOLLOWING CLEANUP TASKS BEFORE REQUESTING INSPECTION FOR COMPLETION FOR THE ENTIRE PROJECT OR A PORTION OF THE PROJECT.
 - 1. CLEAN THE PROJECT SITE AND GROUNDS IN AREAS DISTURBED BY CONSTRUCTION ACTIVITIES OF RUBBISH, WASTE MATERIALS, LITTER, AND FOREIGN SUBSTANCES. REMOVE ALL WASTE FROM THE PROPERTY, DO NOT BURN, BURY, OR OTHERWISE DISPOSE OF TRASH ON THE PROJECT SITE
 - 2. REMOVE CONSTRUCTION EQUIPMENT, TOOLS, MACHINERY, AND SURPLUS MATERIAL FROM THE SITE. WHERE EXTRA MATERIALS OF VALUE REMAIN AFTER COMPLETION, COORDINATE WITH THE CONTRACTING OFFICER ON WHERE TO LEAVE THEM ON THE PROJECT SITE.
 - 3. PREPARE ALL AREAS DISTURBED BY CONSTRUCTION ACTIVITIES THAT ARE ABOVE ORDINARY HIGH WATER FOR SEEDING SPECIFICATIONS OUTLINED IN THESE PLANS AND/OR THE SPECIFICATIONS.
 - 4. LEFTOVER WOODY MATERIAL, WOOD AND OTHER NATIVE ORGANICS MAY BE BROKEN AND BROADCAST OVER THE RESTORED AREA AS APPROVED BY THE CONTRACTING OFFICER.
 - 5. CONTRACTING OFFICER SHALL PROVIDE FINAL APPROVAL OF SITE CLEANUP PRIOR TO DEMOBILIZATION.

| DRAWINGS | rrust ETCHUM, ID DAHO |
|---------------------|--|
| 95% DESIGN DRAWINGS | WOOD RIVER LAND TRUST WARM SPRINGS CREEK, KETCHUM, ID BLAINE COUNTY, IDAHO |
| DRA FOR TRUC | <u>11/6/2024</u> ZS,MP, JY JY |
| | DRAF |

GENERAL CONSERVATION MEASURES APPLICABLE TO ALL ACTIONS

THE ACTIVITIES COVERED UNDER THESE CONSERVATION MEASURES ARE INTENDED TO PROTECT AND RESTORE FISH AND WILDLIFE HABITAT WITH LONG-TERM BENEFITS TO FISH SPECIES. THE FOLLOWING GENERAL CONSERVATION MEASURES WILL BE APPLIED TO ALL ACTIONS OF THIS PROJECT.

PROJECT DESIGN AND SITE PREPARATION.

1. STATE AND FEDERAL PERMITS

- A. ALL APPLICABLE REGULATORY PERMITS AND OFFICIAL PROJECT AUTHORIZATIONS WILL BE OBTAINED BEFORE PROJECT IMPLEMENTATION
- B. THESE PERMITS AND AUTHORIZATIONS INCLUDE, BUT ARE NOT LIMITED TO, NATIONAL ENVIRONMENTAL POLICY ACT, NATIONAL HISTORIC PRESERVATION ACT. THE APPROPRIATE STATE AGENCY REMOVAL AND FILL PERMIT, AND USACE CLEAN WATER ACT (CWA) 404 PERMITS, CWA SECTION 401 WATER QUALITY CERTIFICATIONS

2. TIMING OF IN-WATER WORK

A. APPROPRIATE STATE (IDAHO DEPARTMENT OF FISH AND GAME) GUIDELINES FOR TIMING OF IN-WATER WORK WINDOWS (IWW) WILL BE FOLLOWED. B. CHANGES TO ESTABLISHED WORK WINDOWS WILL BE APPROVED BY REGIONAL STATE BIOLOGISTS.

3. SITE LAYOUT AND FLAGGING

- A. CONSTRUCTION AREAS TO BE CLEARLY FLAGGED PRIOR TO CONSTRUCTION.
- AREAS TO BE FLAGGED WILL INCLUDE: SENSITIVE RESOURCE AREAS, SUCH AS AREAS BELOW ORDINARY HIGH WATER, SPAWNING AREAS, SPRINGS, AND WETLANDS; EQUIPMENT ENTRY AND EXIT POINTS;
- ROAD AND STREAM CROSSING ALIGNMENTS.
- STAGING, STORAGE, AND STOCKPILE AREAS; AND
- NO-SPRAY AREAS AND BUFFERS.

4. TEMPORARY ACCESS ROADS AND PATHS

- EXISTING ACCESS ROADS AND PATHS WILL BE PREFERENTIALLY USED WHENEVER REASONABLE, AND THE NUMBER AND LENGTH OF TEMPORARY ACCESS ROADS AND PATHS THROUGH RIPARIAN AREAS AND FLOODPLAINS WILL BE MINIMIZED.
- B. VEHICLE USE AND HUMAN ACTIVITIES, INCLUDING WALKING, IN AREAS OCCUPIED BY TERRESTRIAL ESA-LISTED SPECIES WILL BE MINIMIZED. C. TEMPORARY ACCESS ROADS AND PATHS WILL NOT BE BUILT ON SLOPES WHERE GRADE, SOIL, OR OTHER FEATURES SUGGEST A LIKELIHOOD OF EXCESSIVE
- EROSION OR FAILURE. IF SLOPES ARE STEEPER THAN 30%, THEN THE ROAD WILL BE DESIGNED BY A CIVIL ENGINEER WITH EXPERIENCE IN STEEP ROAD DESIGN. THE REMOVAL OF RIPARIAN VEGETATION DURING CONSTRUCTION OF TEMPORARY ACCESS ROADS WILL BE MINIMIZED. WHEN TEMPORARY VEGETATION REMOVAL
- IS REQUIRED, VEGETATION WILL BE CUT AT GROUND LEVEL (NOT GRUBBED). AT PROJECT COMPLETION, ALL TEMPORARY ACCESS ROADS AND PATHS WILL BE OBLITERATED, AND THE SOIL WILL BE STABILIZED AND REVEGETATED. ROAD AND PATH OBLITERATION REFERS TO THE MOST COMPREHENSIVE DEGREE OF DECOMMISSIONING AND INVOLVES DECOMPACTING THE SURFACE AND DITCH, PULLING THE FILL MATERIAL ONTO THE RUNNING SURFACE, AND RESHAPING TO MATCH THE ORIGINAL CONTOUR.

5. TEMPORARY STREAM CROSSINGS

- A. EXISTING STREAM CROSSINGS WILL BE PREFERENTIALLY USED WHENEVER REASONABLE, AND THE NUMBER OF TEMPORARY STREAM CROSSINGS WILL BE MINIMIZED.
- TEMPORARY BRIDGES AND CULVERTS WILL BE INSTALLED TO ALLOW FOR EQUIPMENT AND VEHICLE CROSSING OVER PERENNIAL STREAMS DURING CONSTRUCTION. TREATED WOOD SHALL NOT BE USED ON TEMPORARY BRIDGE CROSSINGS OR IN LOCATIONS IN CONTACT WITH OR DIRECTLY OVER WATER.
- C. FOR PROJECTS THAT REQUIRE EQUIPMENT AND VEHICLES TO CROSS IN THE WET: THE LOCATION AND NUMBER OF ALL WET CROSSINGS SHALL BE APPROVED BY THE BPA EC LEAD AND DOCUMENTED IN THE CONSTRUCTION PLANS;
- VEHICLES AND MACHINERY SHALL CROSS STREAMS AT RIGHT ANGLES TO THE MAIN CHANNEL WHENEVER POSSIBLE; NO STREAM CROSSINGS WILL OCCUR 300 FEET UPSTREAM OR 100 FEET DOWNSTREAM OF AN EXISTING REDD OR SPAWNING FISH; AND AFTER PROJECT COMPLETION, TEMPORARY STREAM CROSSINGS WILL BE OBLITERATED AND BANKS RESTORED.

6. STAGING, STORAGE, AND STOCKPILE AREAS

- A. STAGING AREAS (USED FOR CONSTRUCTION EQUIPMENT STORAGE, VEHICLE STORAGE, FUELING, SERVICING, AND HAZARDOUS MATERIAL STORAGE) WILL BE 150 FEET OR MORE FROM ANY NATURAL WATER BODY OR WETLAND. STAGING AREAS CLOSER THAN 150 FEET WILL BE APPROVED BY THE CONTRACTING OFFICER.
- NATURAL MATERIALS USED FOR IMPLEMENTATION OF AQUATIC RESTORATION, SUCH AS LARGE WOOD, GRAVEL, AND BOULDERS, MAY BE STAGED WITHIN 150 FEET IF CLEARLY INDICATED IN THE PLANS THAT AREA IS FOR NATURAL MATERIALS ONLY.
- C. ANY LARGE WOOD, TOPSOIL, AND NATIVE CHANNEL MATERIAL DISPLACED BY CONSTRUCTION WILL BE STOCKPILED FOR USE DURING SITE RESTORATION AT A SPECIFICALLY IDENTIFIED AND FLAGGED AREA.
- D. ANY MATERIAL NOT USED IN RESTORATION, AND NOT NATIVE TO THE FLOODPLAIN, WILL BE DISPOSED OF OUTSIDE THE 100-YEAR FLOODPLAIN.

7. EQUIPMENT

- A. MECHANIZED EQUIPMENT AND VEHICLES WILL BE SELECTED, OPERATED, AND MAINTAINED IN A MANNER THAT MINIMIZES ADVERSE EFFECTS ON THE ENVIRONMENT (E.G., MINIMALLY-SIZED, LOW PRESSURE TIRES; MINIMAL HARD-TURN PATHS FOR TRACKED VEHICLES; TEMPORARY MATS OR PLATES WITHIN WET AREAS OR ON SENSITIVE SOILS).
- EQUIPMENT WILL BE STORED, FUELED, AND MAINTAINED IN AN CLEARLY IDENTIFIED STAGING AREA THAT MEETS STAGING AREA CONSERVATION MEASURES; C. EQUIPMENT WILL BE REFUELED IN A VEHICLE STAGING AREA OR IN AN ISOLATED HARD ZONE, SUCH AS A PAVED PARKING LOT OR ADJACENT, ESTABLISHED ROAD
- (THIS MEASURE APPLIES ONLY TO GAS-POWERED EQUIPMENT WITH TANKS LARGER THAN 5 GALLONS); D. BIODEGRADABLE LUBRICANTS AND FLUIDS WILL BE USED ON EQUIPMENT OPERATING IN AND ADJACENT TO THE STREAM CHANNEL AND LIVE WATER.
- EQUIPMENT WILL BE INSPECTED DAILY FOR FLUID LEAKS BEFORE LEAVING THE VEHICLE STAGING AREA FOR OPERATION WITHIN 150 FEET OF ANY NATURAL WATER BODY OR WETLAND; AND
- F. EQUIPMENT WILL BE THOROUGHLY CLEANED BEFORE OPERATION BELOW ORDINARY HIGH WATER, AND AS OFTEN AS NECESSARY DURING OPERATION, TO REMAIN GREASE FREE.

8. EROSION CONTROL

- A. TEMPORARY EROSION CONTROL MEASURES INCLUDE:
 - 1. TEMPORARY EROSION CONTROLS WILL BE IN PLACE BEFORE ANY SIGNIFICANT ALTERATION OF THE ACTION SITE AND APPROPRIATELY INSTALLED DOWNSLOPE OF PROJECT ACTIVITY WITHIN THE RIPARIAN BUFFER AREA UNTIL SITE REHABILITATION IS COMPLETE;
 - 2. IF THERE IS A POTENTIAL FOR ERODED SEDIMENT TO ENTER THE STREAM, SEDIMENT BARRIERS WILL BE INSTALLED AND MAINTAINED FOR THE DURATION OF PROJECT IMPLEMENTATION;
 - 3. TEMPORARY EROSION CONTROL MEASURES MAY INCLUDE SEDGE MATS, FIBER WATTLES, SILT FENCES, JUTE MATTING, WOOD FIBER MULCH AND SOIL BINDER, OR GEOTEXTILES AND GEOSYNTHETIC FABRIC;
 - SOIL STABILIZATION UTILIZING WOOD FIBER MULCH AND TACKIFIER (HYDRO-APPLIED) MAY BE USED TO REDUCE EROSION OF BARE SOIL IF THE MATERIALS ARE NOXIOUS WEED FREE AND NONTOXIC TO AQUATIC AND TERRESTRIAL ANIMALS, SOIL MICROORGANISMS, AND VEGETATION, 5. SEDIMENT WILL BE REMOVED FROM EROSION CONTROLS ONCE IT HAS REACHED 1/3 OF THE EXPOSED HEIGHT OF THE CONTROL; AND 6. ONCE THE SITE IS STABILIZED AFTER CONSTRUCTION, TEMPORARY EROSION CONTROL MEASURES WILL BE REMOVED.
- EMERGENCY EROSION CONTROLS. THE FOLLOWING MATERIALS FOR EMERGENCY EROSION CONTROL WILL BE AVAILABLE AT THE WORK SITE.
- A SUPPLY OF SEDIMENT CONTROL MATERIALS; AND
- AN OIL-ABSORBING FLOATING BOOM WHENEVER SURFACE WATER IS PRESENT.

9. DUST ABATEMENT

- A. THE PROJECT SPONSOR WILL DETERMINE THE APPROPRIATE DUST CONTROL MEASURES BY CONSIDERING SOIL TYPE, EQUIPMENT USAGE, PREVAILING WIND
- DIRECTION, AND THE EFFECTS CAUSED BY OTHER EROSION AND SEDIMENT CONTROL MEASURES.
- WORK WILL BE SEQUENCED AND SCHEDULED TO REDUCE EXPOSED BARE SOIL SUBJECT TO WIND EROSION
- DUST-ABATEMENT ADDITIVES AND STABILIZATION CHEMICALS (TYPICALLY MAGNESIUM CHLORIDE, CALCIUM CHLORIDE SALTS, OR LIGNINSULFONATE) WILL NOT BE APPLIED WITHIN 25 FEET OF WATER OR A STREAM CHANNEL AND WILL BE APPLIED SO AS TO MINIMIZE THE LIKELIHOOD THAT THEY WILL ENTER STREAMS. APPLICATIONS OF LIGNINSULFONATE WILL BE LIMITED TO A MAXIMUM RATE OF 0.5 GALLONS PER SQUARE YARD OF ROAD SURFACE, ASSUMING MIXED 50:50 WITH WATER.
- APPLICATION OF DUST ABATEMENT CHEMICALS WILL BE AVOIDED DURING OR JUST BEFORE WET WEATHER, AND AT STREAM CROSSINGS OR OTHER AREAS THAT
- COULD RESULT IN UNFILTERED DELIVERY OF THE DUST ABATEMENT MATERIALS TO A WATERBODY (TYPICALLY THESE WOULD BE AREAS WITHIN 25 FEET OF A WATERBODY OR STREAM CHANNEL; DISTANCES MAY BE GREATER WHERE VEGETATION IS SPARSE OR SLOPES ARE STEEP). SPILL CONTAINMENT EQUIPMENT WILL BE AVAILABLE DURING APPLICATION OF DUST ABATEMENT CHEMICALS.
- PETROLEUM-BASED PRODUCTS WILL NOT BE USED FOR DUST ABATEMENT.

10. SPILL PREVENTION, CONTROL, AND COUNTER MEASURES.

- A. A DESCRIPTION OF HAZARDOUS MATERIALS THAT WILL BE USED, INCLUDING INVENTORY, STORAGE, AND HANDLING PROCEDURES WILL BE AVAILABLE ON-SITE.
- WRITTEN PROCEDURES FOR NOTIFYING ENVIRONMENTAL RESPONSE AGENCIES WILL BE POSTED AT THE WORK SITE.
- SPILL CONTAINMENT KITS (INCLUDING INSTRUCTIONS FOR CLEANUP AND DISPOSAL) ADEQUATE FOR THE TYPES AND QUANTITY OF HAZARDOUS MATERIALS USED AT THE SITE WILL BE AVAILABLE AT THE WORK SITE.
- WORKERS WILL BE TRAINED IN SPILL CONTAINMENT PROCEDURES AND WILL BE INFORMED OF THE LOCATION OF SPILL CONTAINMENT KITS.
- CAN BE PROPERLY TRANSPORTED TO AND DISPOSED OF AT A FACILITY THAT IS APPROVED FOR RECEIPT OF HAZARDOUS MATERIALS.
- PUMPS USED ADJACENT TO WATER SHALL USE SPILL CONTAINMENT SYSTEMS.

11. INVASIVE SPECIES CONTROL.

- A. PRIOR TO ENTERING THE SITE, ALL VEHICLES AND EQUIPMENT WILL BE POWER WASHED, ALLOWED TO FULLY DRY, AND INSPECTED TO MAKE SURE NO PLANTS, SOIL, OR OTHER ORGANIC MATERIAL ADHERES TO THE SURFACE.
- WATERCRAFT, WADERS, BOOTS, AND ANY OTHER GEAR TO BE USED IN OR NEAR WATER WILL BE INSPECTED FOR ADUATIC INVASIVE SPECIES WADING BOOTS WITH FELT SOLES ARE NOT TO BE USED DUE TO THEIR PROPENSITY FOR AIDING IN THE TRANSFER OF INVASIVE SPECIES UNLESS DECONTAMINATION PROCEDURES HAVE BEEN APPROVED BY THE EC LEAD.

WORK AREA ISOLATION AND FISH SALVAGE.

1. WORK AREA ISOLATION.

- ANY WORK AREA WITHIN THE WETTED CHANNEL WILL BE ISOLATED FROM THE ACTIVE STREAM WHENEVER FISH ARE REASONABLY CERTAIN TO BE PRESENT, OR IF THE WORK AREA IS LESS THAN 300-FEET UPSTREAM FROM KNOWN SPAWNING HABITATS.
- WORK AREA ISOLATION AND FISH SALVAGE ACTIVITIES WILL COMPLY WITH THE IN-WATER WORK WINDOW.
- DESIGN PLANS WILL INCLUDE ALL ISOLATION ELEMENTS AND AREAS (COFFER DAMS, PUMPS, DISCHARGE AREAS, FISH SCREENS, FISH RELEASE AREAS, ETC.).
- WORK AREA ISOLATION AND FISH CAPTURE ACTIVITIES WILL OCCUR DURING PERIODS OF THE COOLEST AIR AND WATER TEMPERATURES POSSIBLE, NORMALLY D EARLY IN THE MORNING VERSUS LATE IN THE DAY, AND DURING CONDITIONS APPROPRIATE TO MINIMIZE STRESS AND DEATH OF SPECIES PRESENT.

2. FISH SALVAGE.

- MONITORING AND RECORDING WILL TAKE PLACE FOR DURATION OF SALVAGE. THE SALVAGE REPORT WILL BE MAINTAINED BY THE CONTRACTING OFFICER. SALVAGE ACTIVITIES SHOULD TAKE PLACE DURING CONDITIONS TO MINIMIZE STRESS TO FISH SPECIES, TYPICALLY PERIODS OF THE COOLEST AIR AND WATER
- TEMPERATURES WHICH OCCUR IN THE MORNING VERSUS LATE IN THE DAY. C. SALVAGE OPERATIONS WILL FOLLOW THE ORDERING, METHODOLOGIES, AND CONSERVATION MEASURES SPECIFIED BELOW:
 - SLOWLY REDUCE WATER FROM THE WORK AREA TO ALLOW SOME FISH TO LEAVE VOLITIONALLY. BLOCK NETS WILL BE INSTALLED AT UPSTREAM AND DOWNSTREAM LOCATIONS AND MAINTAINED IN A SECURED POSITION TO EXCLUDE FISH FROM ENTERING THE PROJECT AREA.
 - BLOCK NETS WILL BE SECURED TO THE STREAM CHANNEL BED AND BANKS UNTIL FISH CAPTURE AND TRANSPORT ACTIVITIES ARE COMPLETE. BLOCK NETS MAY BE LEFT IN PLACE FOR THE DURATION OF THE PROJECT TO EXCLUDE FISH AS LONG AS PASSAGE REQUIREMENTS ARE MET.
 - NETS WILL BE MONITORED HOURLY DURING IN-STREAM DISTURBANCE.
 - IF BLOCK NETS REMAIN IN PLACE MORE THAN ONE DAY, THE NETS WILL BE MONITORED AT LEAST DAILY TO ENSURE THEY ARE SECURED AND FREE OF ORGANIC ACCUMULATION. IF BULL TROUT ARE PRESENT, NETS ARE TO BE CHECKED EVERY 4 HOURS FOR FISH IMPINGEMENT. CAPTURE FISH THROUGH SEINING AND RELOCATE TO STREAMS.
 - WHILE DEWATERING, ANY REMAINING FISH WILL BE COLLECTED BY HAND OR DIP NETS.
 - SEINES WITH A MESH SIZE TO ENSURE CAPTURE OF THE RESIDING ESA-LISTED FISH WILL BE USED.
 - MINNOW TRAPS WILL BE LEFT IN PLACE OVERNIGHT AND USED IN CONJUNCTION WITH SEINING
 - 10. ELECTROFISH TO CAPTURE AND RELOCATED FISH NOT CAUGHT DURING SEINING PER ELECTROFISH CONSERVATION MEASURES.
 - 11. CONTINUE TO SLOWLY DEWATER STREAM REACH.
 - 12. COLLECT ANY REMAINING FISH IN COLD-WATER BUCKETS AND RELOCATED TO THE STREAM.
 - 13. LIMIT THE TIME FISH ARE IN A TRANSPORT BUCKET. 14. MINIMIZE PREDATION BY TRANSPORTING COMPARABLE SIZES IN BUCKETS.

 - 15. BUCKET WATER TO BE CHANGED EVERY 15 MINUTES OR AERATED.
 - 16. BUCKETS WILL BE KEPT IN SHADED AREAS OR COVERED.
 - 17. DEAD FISH WILL NOT BE STORED IN TRANSPORT BUCKETS, BUT WILL BE LEFT ON THE STREAM BANK TO AVOID MORTALITY COUNTING ERRORS.

ANY WASTE LIQUIDS GENERATED AT THE STAGING AREAS WILL BE TEMPORARILY STORED UNDER AN IMPERVIOUS COVER, SUCH AS A TARPAULIN, UNTIL THEY

| Applied Science & Engineering WOOD RIVER LAND TRUST | | | | |
|---|---------------------|--|--|--|
| WARM SPRINGS PRESERVE STREAM & FLOODPLAIN ENHANCEMENT DESIGN SET | 95% DESIGN DRAWINGS | WOOD RIVER LAND TRUST WARM SPRINGS CREEK, KETCHUM, ID BLAINE COUNTY, IDAHO | | |
| DATE: DESIGNED: <u>APPROVED:</u> DRAWING N/ GI | ENERAL SERVAT | | | |

WORK AREA ISOLATION AND FISH SALVAGE (CONTINUED)

3. ELECTROFISHING.

- A. INITIAL SITE SURVEY AND INITIAL SETTINGS.
 - IDENTIFY SPAWNING ADULTS AND ACTIVE REDDS TO AVOID.
 - RECORD WATER TEMPERATURE. ELECTROFISHING WILL NOT OCCUR WHEN WATER TEMPERATURES ARE ABOVE 18 DEGREES CELSIUS.
 - IF POSSIBLE, A BLOCK NET WILL BE PLACED DOWNSTREAM AND CHECKED REGULARLY TO CAPTURE STUNNED FISH THAT DRIFT DOWNSTREAM.
 - INITIAL SETTINGS WILL BE 100 VOLTS, PULSE WIDTH OF 500 MICRO SECONDS, AND PULSE RATE OF 30 HERTZ. RECORDS FOR CONDUCTIVITY, WATER TEMPERATURE, AIR TEMPERATURE, ELECTROFISHING SETTINGS, ELECTROFISHER MODEL, ELECTROFISHER
 - CALIBRATION, FISH CONDITIONS, FISH MORTALITIES, AND TOTAL CAPTURE RATES WILL BE INCLUDED IN THE SALVAGE LOG BOOK.
- B. ELECTROFISHING TECHNIOUE.
- SAMPLING WILL BEGIN USING STRAIGHT DC. POWER WILL REMAIN ON UNTIL THE FISH IS NETTED WHEN USING STRAIGHT DC. GRADUALLY INCREASE VOLTAGE WHILE REMAINING BELOW MAXIMUM LEVELS.
- MAXIMUM VOLTAGE WILL BE 1100 VOLTS WHEN CONDUCTIVITY IS <100 MILLISECONDS, 800 VOLTS WHEN CONDUCTIVITY IS BETWEEN 100 AND 300 MILLISECONDS, AND 400 VOLTS WHEN CONDUCTIVITY IS >300 MILLISECONDS. 3. IF FISH CAPTURE IS NOT SUCCESSFUL USING STRAIGHT DC, THE ELECTROFISHER WILL BE SET TO INITIAL VOLTAGE FOR PDC. VOLTAGE, PULSE WIDTH, AND
- PULSE FREQUENCY WILL BE GRADUALLY INCREASED WITHIN MAXIMUM VALUES UNTIL CAPTURE IS SUCCESSFUL.
- MAXIMUM PULSE WIDTH IS 5 MILLISECONDS. MAXIMUM PULSE RATE IS 70 HERTZ ELECTROFISHING WILL NOT OCCUR IN ONE AREA FOR AN EXTENDED PERIOD.
- THE ANODE WILL NOT INTENTIONALLY COME INTO CONTACT WITH FISH. THE ZONE FOR POTENTIAL INJURY OF 0.5 M FROM THE ANODE WILL BE AVOIDED.
- SETTINGS WILL BE LOWERED IN SHALLOWER WATER SINCE VOLTAGE GRADIENTS LIKELY TO INCREASE.
- ELECTROFISHING WILL NOT OCCUR IN TURBID WATER WHERE VISIBILITY IS POOR (I.E. UNABLE TO SEE THE BED OF THE STREAM).
- OPERATIONS WILL IMMEDIATELY STOP IF MORTALITY OR OBVIOUS FISH INJURY IS OBSERVED. ELECTROFISHING SETTINGS WILL BE REEVALUATED.

C. SAMPLE PROCESSING.

- FISH SHOULD BE SORTED BY SIZE TO AVOID PREDATION DURING SAMPLING.
- SAMPLERS WILL REGULARLY CHECK CONDITIONS OF FISH HOLDING CONTAINERS, AIR PUMPS, WATER TRANSFERS, ETC.
- FISH WILL BE OBSERVED FOR GENERAL CONDITIONS AND INJURIES
- EACH FISH WILL BE COMPLETELY REVIVED BEFORE RELEASE. ESA-LISTED SPECIES WILL BE PRIORITIZED FOR SUCCESSFUL RELEASE.

4. DEWATERING.

- A. DEWATERING WILL OCCUR AT A RATE SLOW ENOUGH TO ALLOW SPECIES TO NATURALLY MIGRATE OUT OF THE WORK AREA.
- B. WHERE A GRAVITY FEED DIVERSION IS NOT POSSIBLE, A PUMP MAY BE USED. PUMPS WILL BE INSTALLED TO AVOID REPETIVE DEWATERING AND REWATERING. C. WHEN FISH ARE PRESENT, PUMPS WILL BE SCREENED IN ACCORDANCE WITH NMFS FISH SCREEN CRITERIA. NMFS ENGINEERING REVIEW AND APPROVAL WILL BE OBTAINED FOR PUMPS EXCEEDING 3 CUBIC FEET PER SECOND.
- D. DISSIPATION OF FLOW ENERGY AT THE BYPASS OUTFLOW WILL BE PROVIDED TO PREVENT DAMAGE TO THE STREAM CHANNEL AND RIPARIAN VEGETATION
- E. SEEPAGE WATER WILL BE PUMPED TO A TEMPORARY STORAGE AND TREATMENT SITE OF INTO UPLAND AREAS TO ALLOW WATER TO PERCOLATE THROUGH SOIL AND VEGETATION PRIOR TO REENTERING THE STREAM CHANNEL

CONSTRUCTION AND POST CONSTRUCTION CONSERVATION MEASURES.

4. FISH PASSAGE

- A. FISH PASSAGE WILL BE PROVIDED FOR ADULT AND JUVENILE FISH LIKELY TO BE PRESENT DURING CONSTRUCTION UNLESS PASSAGE DID NOT EXIST BEFORE
- CONSTRUCTION, THE STREAM IS NATURALLY IMPASSABLE, OR PASSAGE WILL NEGATIVELY IMPACT ESA-LISTED SPECIES OR THEIR HABITAT
- B. FISH PASSAGE ALTERNATIVES WILL BE APPROVED BY THE BPA EC LEAD UNDER ADVISEMENT BY THE NMFS HABITAT BIOLOGIST.

2. CONSTRUCTION AND DISCHARGE WATER.

- A. SURFACE WATER MAY BE DIVERTED TO MEET CONSTRUCTION NEEDS ONLY IF DEVELOPED SOURCES ARE UNAVAILABLE OR INADEQUATE.
- B. DIVERSIONS WILL NOT EXCEED 10% OF THE AVAILABLE FLOW.
- CONSTRUCTION DISCHARGE WATER WILL BE COLLECTED AND TREATED TO REMOVE DEBRIS, NUTRIENTS, SEDIMENT, PETROLEUM HYDROCARBONS, METALS, AND OTHER POLLUTANTS.

3. TIME AND EXTENT OF DISTURBANCE.

- A. EARTHWORK REQUIRING IN-STREAM MECHANIZED EQUIPMENT (INCLUDING DRILLING, EXCAVATION, DREDGING, FILLING, AND COMPACTING) WILL BE
- COMPLETED AS QUICKLY AS POSSIBLE.
- B. MECHANIZED EQUIPMENT WILL WORK FROM TOP OF BANK UNLESS WORK FROM ANOTHER LOCATION WILL RESULT IN LESS HABITAT DISTURBANCE (TURBIDITY, VEGETATION DISTURBANCE, ETC.)

4. CESSATION OF WORK.

- A. PROJECT OPERATIONS WILL CEASE WHEN HIGH FLOW CONDITIONS MAY RESULT IN INUNDATION OF THE PROJECT AREA (FLOOD EFFORTS TO DECREASE DAMAGES
- TO NATURAL RESOURCES PERMITTED). B. WATER QUALITY LEVELS EXCEEDED. SEE CWA SECTION 401 WATER QUALITY CERTIFICATION AND TURBIDITY MEASURES.

5. SITE RESTORATION.

- A. DISTURBED AREAS, STREAM BANKS, SOILS, AND VEGETATION WILL BE CLEANED UP AND RESTORED TO IMPROVED OR PRE-PROJECT CONDITIONS.
- B. PROJECT-RELATED WASTE WILL BE REMOVED.
- C. TEMPORARY ACCESS ROADS AND STAGING WILL BE DECOMPACTED AND RESTORED. SOILS WILL BE LOOSENED IF NEEDED FOR REVEGETATION OR WATER INFILTRATION
- D. THE PROJECT SPONSOR WILL RETAIN THE RIGHT OF REASONABLE ACCESS TO THE SITE TO MONITOR AND MAINTAIN THE SITE OVER THE LIFE OF THE PROJECT.

6. REVEGETATION.

- A. PLANTING AND SEEDING WILL OCCUR PRIOR TO OR AT THE BEGINNING OF THE FIRST GROWING SEASON AFTER CONSTRUCTION
- B. A MIX OF NATIVE SPECIES (INVASIVE SPECIES NOT ALLOWED) APPROPRIATE TO THE SITE WILL BE USED TO REESTABLISH VEGETATION, PROVIDE SHADE, AND REDUCE EROSION. REE
- C. VEGETATION SUCH AS WILLOWS, SEDGES, OR RUSH MATS WILL BE SALVAGED FROM DISTURBED OR ABANDONED AREAS TO BE REPLANTED.
- SHORT-TERM STABILIZATION MEASURE MAY INCLUDE THE USE OF NON-NATIVE STERILE SEED MIX (WHEN NATIVE NOT AVAILABLE), WEED-FREE CERTIFIED STRAW, OR OTHER SIMILAR TECHNIOUES.
- E. SURFACE FERTILIZER WILL NOT BE APPLIED WITHIN 50 FEET OF ANY STREAM, WATE BODY, OR WETLAND.
- F. FENCING WILL BE INSTALLED AS NECESSARY TO PREVENT ACCESS TO REVEGETATED SITES BY LIVESTOCK OR UNAUTHORIZED PERSONS. G. INVASIVE PLANTS WILL BE REMOVED OR CONTROLLED UNTIL NATIVE PLANT SPECIES ARE WELL ESTABLISHED (TYPICALLY THREE YEARS POST-CONSTRUCTION).

SITE ACCESS AND IMPLEMENTATION MONITORING.

- THE PROJECT SPONSOR WILL PROVIDE CONSTRUCTION MONITORING DURING IMPLEMENTATION TO ENSURE ALL CONSERVATION MEASURES ARE ADEQUATELY
- FOLLOWED, EFFECTS TO LISTED SPECIES ARE NOT GREATER THAN PREDICTED, AND INCIDENTAL TAKE LIMITATIONS ARE NOT EXCEEDED.
- B. THE PROJECT SPONSOR OR DESIGNATED REPRESENTATIVE WILL SUBMIT THE PROJECT COMPLETION FORM (PCF) WITHIN 30 DAYS OF PROJECT COMPLETION.

8. CWA SECTION 401 WATER QUALITY CERTIFICATION.

- THE PROJECT SPONSOR OR DESIGNATED REPRESENTATIVE WILL COMPLETE AND RECORD WATER QUALITY OBSERVATIONS (SEE TURBIDITY MONITORING) TO ENSURE IN-WATER WORK IS NOT DEGRADING WATER OUALITY
- DURING CONSTRUCTION, WATER QUALITY PROVISIONS PROVIDED BY THE IDAHO DEPARTMENT OF ENVIRONMENTAL QUALITY WILL BE FOLLOWED.

9. STAGED REWATERING PLAN.

- WHEN REINTRODUCING WATER TO DEWATERED AREAS AND NEWLY CONSTRUCTED CHANNELS, A STAGED REWATERING PLAN WILL BE APPLIED. B. THE FOLLOWING WILL BE APPLIED TO ALL REWATERING EFFORTS. COMPLEX REWATERING EFFORTS MAY REQUIRE ADDITIONAL NOTES OR A DEDICATED SHEET IN THE CONSTRUCTION DETAILS
 - TURBIDITY MONITORING PROTOCOL WILL BE APPLIED TO REWATERING EFFORTS.
- PRE-WASH THE AREA BEFORE REWATERING. TURBID WASH WATER WILL BE DETAINED AND PUMPED TO THE FLOODPLAIN OR SEDIMENT CAPTURE AREAS RATHER THAN DISCHARGING TO FISH-BEARING STREAMS
- INSTALL SEINE NETS AT UPSTREAM END TO PREVENT FISH FROM MOVING DOWNSTREAM UNTIL 2/3 OF TOTAL FLOW IS RESTORED TO THE CHANNEL.
- STARTING IN EARLY MORNING INTRODUCE 1/3 OF NEW CHANNEL FLOW OVER PERIOD OF 1-2 HOURS.
- INTRODUCE SECOND THIRD OF FLOW OVER NEXT 1 TO 2 HOURS AND BEGIN FISH SALVAGE OF BYPASS CHANNEL IF FISH ARE PRESENT.
- REMOVE UPSTREAM SEINE NETS ONCE 2/3 FLOW IN REWATERED CHANNEL AND DOWNSTREAM TURBIDITY IS WITHIN ACCEPTABLE RANGE (LESS THAN 40 NTU
- OR LESS THAN 10% BACKGROUND). INTRODUCE FINAL THIRD OF FLOW ONCE FISH SALVAGE EFFORTS ARE COMPLETE AND DOWNSTREAM TURBIDITY VERIFIED TO BE WITHIN ACCEPTABLE RANGE.
- INSTALL PLUG TO BLOCK FLOW INTO OLD CHANNEL OR BYPASS. REMOVE ANY REMAINING SEINE NETS.
- IN LAMPREY SYSTEMS, PERFORM LAMPREY SALVAGE AND DRY SHOCKING MAY BE NECESSARY.

10. TURBIDITY MONITORING.

- A. RECORD THE READING. LOCATION, AND TIME FOR THE BACKGROUND READING APPROXIMATELY 100 FEET UPSTREAM OF THE PROJECT AREA USING A RECENTLY CALIBRATED TURBIDIMETER OR VIA VISUAL OBSERVATION (SEE THE HIP HANDBOOK TURBIDITY MONITORING SECTION FOR A VISUAL OBSERVATION KEY).
- RECORD THE TURBIDITY READING, LOCATION, AND TIME AT THE MEASUREMENT COMPLIANCE LOCATION POINT 50 FEET DOWNSTREAM FOR STREAMS LESS THAN 30 FEET WIDE.
- 100 FEET DOWNSTREAM FOR STREAMS BETWEEN 30 AND 100 FEET WIDE.
- 200 FEET DOWNSTREAM FOR STREAMS GREATER THAN 100 FEET WIDE.
- 300 FEET FROM THE DISCHARGE POINT OR NONPOINT SOURCE FOR LOCATIONS SUBJECT TO TIDAL OR COASTAL SCOUR.
- C. TURBIDITY SHALL BE MEASURED (BACKGROUND LOCATION AND COMPLIANCE POINTS) EVERY 4 HOURS WHILE WORK IS BEING IMPLEMENTED. D. IF THERE IS A VISIBLE DIFFERENCE BETWEEN A COMPLIANCE POINT AND THE BACKGROUND, THE EXCEEDANCE WILL BE NOTED IN THE PROJECT COMPLETION
- FORM (PCF). ADJUSTMENTS OR CORRECTIVE MEASURES WILL BE TAKEN IN ORDER TO REDUCE TURBIDITY. IF EXCEEDANCES OCCUR FOR MORE THAN TWO CONSECUTIVE MONITORING INTERVALS (AFTER 8 HOURS), THE ACTIVITY WILL STOP UNTIL THE TURBIDITY LEVEL
- RETURNS TO BACKGROUND. THE BPA EC LEAD WILL BE NOTIFIED OF ALL EXCEEDANCES AND CORRECTIVE ACTIONS AT PROJECT COMPLETION. IF TURBIDITY CONTROLS (COFFER DAMS, WADDLES, FENCING, ETC.) ARE DETERMINED INEFFECTIVE, CREWS WILL BE MOBILIZED TO MODIFY AS NECESSARY.
- OCCURRENCES WILL BE DOCUMENTED IN THE PROJECT COMPLETION FORM (PCF).
- G. FINAL TURBIDITY READINGS, EXCEEDANCES, AND CONTROL FAILURES WILL BE SUBMITTED TO THE BPA EC LEAD USING THE PROJECT COMPLETION FORM (PCF).




QUANTITIES

| ITEM DESCRIPTION | QUANTITY | UNIT |
|---|----------|------|
| GENERAL | | |
| MOBILIZATION AND DEMOBILIZATION | 1 | LS |
| COFFERDAMS, PUMPING, DEWATERING, & WATER MANAGEMENT | 1 | LS |
| STORMWATER, SITE ACCESS, PREPARATION, & HOUSEKEEPING | 1 | LS |
| SURVEYING/CONSTRUCTION STAKING/MACHINE CONTROL | 1 | LS |
| SITE WORK | | |
| CHANNEL AND FLOODPLAIN EXCAVATION | 36,359 | CY |
| DEMOLITION | 1 | LS |
| CLASS 1 CONSTRUCTED RIFFLE MATERIAL | 866 | CY |
| CLASS 2 CONSTRUCTED RIFFLE MATERIAL | 323 | CY |
| CLASS 3 CONSTRUCTED RIFFLE MATERIAL | 570 | CY |
| HABITAT BOULDER | 157 | EA |
| WOOD MATERIAL ACQUISITION AND DELIVERY | 1 | LS |
| HS-1: SIX LOG STRUCTURE | 7 | EA |
| HS-3: SINGLE LOG STRUCTURE | 55 | EA |
| HS-4: WHOLE TREE STRUCTURE | 18 | EA |
| HS-5: CONSTRICTION JAM | 1 | EA |
| HS-6: SMALL APEX JAM | 1 | EA |
| HS-7: FLOODPLAIN INUNDATION STRUCTURE | 70 | LF |
| HS-8: BLEEDER JAM | 2 | EA |
| SHORT ROUGHENED EDGE TREATMENT | 550 | LF |
| WILLOW BAFFLE | 320 | LF |
| ROLLED STEEL GIRDER BRIDGE | 1 | LS |
| 2 - 36" DIA. 60-FT CORRUGATED METAL PIPE CULVERT | 1 | LS |
| BALDY CHANNEL INLET | 1 | LS |


LARGE WOOD MATERIAL QUANTITIES

| MATERIAL TYPE | SIZE (DBH) (IN) | MIN. LENGTH (FT) | ROOTWAD | MIN. ROOTWAD DIA. (FT) | BRANCHES | TOTAL (EA) |
|---------------|-----------------------|------------------------|----------|------------------------------|----------|---------------|
| TYPE 1 | 13 - 22 | 30 - 40 | YES | 4.5 | NO | 99 |
| TYPE 2 | 13 - 22 | 30 - 40 | NO | NA | NO | 95 |
| TYPE 3 | 13 - 22 | 40 - 60 | YES | 4 | YES | 20 |
| TYPE 4 | 12 - 14 | 20 - 35 | NO | NA | NO | 1 |
| TYPE 5 | 13 - 22 | 40 - 50 | YES | 4.5 | NO | 5 |
| RACKING-1 | 4 - 12 | 15 - 25 | YES | 2.5 | YES | 224 |
| RACKING-2 | 4 - 12 | 15 - 25 | OPTIONAL | NA | YES | 578 |
| SLASH-1 | 1 - 4 | 5 - 15 | NA | NA | YES | 855 |
| SLASH-2 | 1 - 4 | 5 - 15 | NA | NA | YES | 487 |
| LIVE STAKES | > 3/4 | 6 - 8 | NA | NA | NA | 1453 |


<u>NOTE</u>: ONE RACKING-1 OR RACKING-2 MEMBER PER STRUCTURE MAY BE COTTONWOOD (UP TO 144 COTTONWOOD RACKING MEMBERS).



| SAN | |
|---|--|
| <u>LEGEND</u> — – – — PROPERTY LINE | ВИМ |
| | |
| FILOODWAY FLOODPLAIN (100YR 1% ANNUAL | |
| CHANCE) EASEMENT LINE (AS NOTED) RIPARIAN SETBACK AND SCENIC | SURVEY CONTROL POINTS |
| EASEMENT 10' FISHERMAN'S & NATURE STUDY EASEMENT | NAME NORTHING ELEVATION DESCRIPTION 22 737762:930 1539351:250 5856.47 CP-Flower |
| RA — RED AVALANCHE ZONE BLUE AVALANCHE ZONE | 26 737452.677 1539125.646 5820.901 CP MAG 95 737590.333 1539002.911 5825.468 CP MAG |
| SANITARY SEWER K SANITARY SE | 97 737676.492 1538908.825 5831.349 CP SURVEY MRKR 1057 737096.029 1539446.993 5821.691 CP MAG 1027 737600 153924.202 5821.691 CP MAG |
| EXISTING TREE CONIFEROUS EXISTING TREELINE (<6" DIAMETER | 3378 737599.088 1538628.352 5832.84 BLUE REBAR |
| TREES) | 150 0 150 300 450 SCALE 1"=150' |








SANARM SARRIA Applied Science & Engineerin WOOD RIVER LAND TRUST BALD MOUNTAIN ROAD SAN - CAN WARM SPRINGS PRESERVE STREAM & FLOODPLAIN ENHANCEMENT DESIGN SET DESIGN DRAWINGS DI D TRUST , KETCHUM, , IDAHO EXISTING BRIDGE -WOOD RIVER LAND WARM SPRINGS CREEK, K BLAINE COUNTY, I EXISTING USGS GAGE DO NOT DISTURB ----95% LEGEND --- PROPERTY LINE WORKING DRAFT NOT FOR CONSTRUCTION EXISTING MEAN HIGH WATER (MHW) EXISTING CONTOUR (1-ft INTERVAL) FLOODWAY FLOODPLAIN (100YR 1% ANNUAL CHANCE) EASEMENT LINE (AS NOTED) RIPARIAN SETBACK AND SCENIC EASEMENT 10' FISHERMAN'S & NATURE STUDY EASEMENT DATE: DESIGNED: 11/6/2024 ZS,MP, JY APPROVED. RED AVALANCHE ZONE DRAWING NAME BLUE AVALANCHE ZONE EXISTING CONDITIONS SANITARY SEWER SAN EXISTING TREE DECIDUOUS _____ EXISTING TREE CONIFEROUS PLAN 2 EXISTING TREELINE (<6" DIAMETER TREES) DRAWING NO. EXISTING GRAVEL ROAD 103 C3 SHEET 9 O











SHEET 13 C

LEGEND


HABITAT STRUCTURE - 1 (HS-1) (DWG D5) HABITAT STRUCTURE - 2 (HS-2) (DWG D6) HABITAT STRUCTURE - 3 (HS-3) (DWG D7) HABITAT STRUCTURE - 4 (HS-4) (DWG D8) HABITAT STRUCTURE - 5 (HS-5) (DWG D9) HABITAT STRUCTURE - 6 (HS-6) (DWG D10) SHORT ROUGHENED EDGE (DWG D4) HABITAT STRUCTURE - 7 (HS-7) (DWG D11)


LOST HILLS


HABITAT STRUCTURE - 8 (HS-8) (DWG D12)

PROPOSED LOW FLOW INUNDATION CLASS-1 RIFFLE (DWG D2) CLASS-2 RIFFLE (DWG D2) CLASS-3 RIFFLE (DWG D2) BOULDERS (DWG D3) PROPOSED CONTOUR (1-ft INTERVAL) PROPOSED GRADING LIMIT EXISTING CONTOUR (1-ft INTERVAL) EXISTING TREE DECIDUOUS (RED INDICATES REMOVAL)

EXISTING TREE CONIFEROUS (RED INDICATES REMOVAL) EXISTING TREELINE (<6" DIAMETER RED INDICATES REMOVAL) - MHW - EXISTING MEAN HIGH WATER (MHW)










| a contraction of the second se | | Applied Si P |
|--|--|---|
| SAN | SAN VALLEY SUBDIVISION IST ADD'N, REVISEDN BLOCK 5 1 300 1 48 5 | WARM SPRINGS PRESERVE STREAM & FLOODPLAIN ENHANCEMENT DESIGN SET |
| | LEGEND HABITAT STRUCTURE - 1 (HS-1) (DWG D5) HABITAT STRUCTURE - 2 (HS-2) (DWG D6) HABITAT STRUCTURE - 3 (HS-3) (DWG D7) HABITAT STRUCTURE - 4 (HS-4) (DWG D8) HABITAT STRUCTURE - 5 (HS-5) (DWG D9) HABITAT STRUCTURE - 6 (HS-6) (DWG D10) SHORT ROUGHENED EDGE (DWG D4) HABITAT STRUCTURE - 7 (HS-7) (DWG D11) | |
| | HABITAT STRUCTURE - 8 (HS-8) (DWG D12) PROPOSED LOW FLOW INUNDATION CLASS-1 RIFFLE (DWG D2) CLASS-2 RIFFLE (DWG D2) CLASS-3 RIFFLE (DWG D2) BOULDERS (DWG D3) PROPOSED CONTOUR (1-ft INTERVAL) PROPOSED GRADING LIMIT | WORK DATE: DESIGNED APPROVED DRAWING PROPOS |
| | EXISTING CONTOUR (1-ft INTERVAL) EXISTING TREE DECIDUOUS (RED INDICATES REMOVAL) EXISTING TREE CONIFEROUS (RED INDICATES REMOVAL) EXISTING TREELINE (<6" DIAMETER RED INDICATES REMOVAL) EXISTING MEAN HIGH WATER (MHW) | DRAWING |


| Applied scie W R L T | VOO IVE AN RUS | o ngineering D R D T |
|---|-------------------------|--|
| WARM SPRINGS PRESERVE STREAM & FLOODPLAIN ENHANCEMENT DESIGN SET | 95% DESIGN DRAWINGS | WOOD RIVER LAND TRUST WARM SPRINGS CREEK, KETCHUM, ID BLAINE COUNTY, IDAHO |
| DATE: DESIGNED: APPROVED: DRAWING N/ PROPOSE | AME ED CON | 11/6/2024 ZS.MP. JY JY DITIONS |


























LEGEND

10 10.00

Vevi

A CAR

R

15/1

HABITAT STRUCTURE - 1 (HS-1) (DWG D5) HABITAT STRUCTURE - 2 (HS-2) (DWG D6) HABITAT STRUCTURE - 3 (HS-3) (DWG D7) HABITAT STRUCTURE - 4 (HS-4) (DWG D8) HABITAT STRUCTURE - 5 (HS-5) (DWG D9) HABITAT STRUCTURE - 6 (HS-6) (DWG D10) SHORT ROUGHENED EDGE (DWG D4) HABITAT STRUCTURE - 7 (HS-7) (DWG D11)

HABITAT STRUCTURE - 8 (HS-8) (DWG D12)

PROPOSED LOW FLOW INUNDATION CLASS-1 RIFFLE (DWG D2)

CLASS-2 RIFFLE (DWG D2) 757 CLASS-3 RIFFLE (DWG D2)


BOULDERS (DWG D3)

PROPOSED CONTOUR (1-ft INTERVAL)

- GL - PROPOSED GRADING LIMIT


PROPOSED COFFERDAM EXISTING CONTOUR (1-ft INTERVAL)


BALDY CHANNEL - PLAN





HORIZONTAL VERTICAL SCALE 1"=30 SCALE 1"=3





















| SLOPE | SPACING BASED ON WATTLE DIAMETER (F | | | | | |
|----------------|-------------------------------------|----|-----|-----|--|--|
| SLOPE | 6" | 9" | 12" | 20" | | |
| 1:1 | 5 | 10 | 15 | 20 | | |
| 2:1 | 10 | 20 | 30 | 40 | | |
| 3:1 | 15 | 30 | 45 | 60 | | |
| 4:1 OR FLATTER | 20 | 40 | 60 | 80 | | |

- 1. INSTALL WATTLES ON THE UPPER SLOPE IN SEEDING ZONE 5 (DISTURBED HILLSLOPES OUTSIDE OF THE
- 2. WATTLES SHALL BE INSTALLED ON CONTOUR.
- TO PREVENT RUNOFF FROM FLOWING AROUND THE
- 5. ANY DAMAGED WATTLE SHALL BE REPLACED AS DIRECTED BY THE CONTRACTING OFFICER AT THE
- STRAW WATTLE DIAMETER SHALL BE 9" UNLESS
- INSTALL STRAW WATTLES PRIOR TO PLANTING AND

| - | Applied Sci WR L T | VOO IVE AN RUS | o ngineering D R D T |
|---|---|-------------------------|--|
| | WARM SPRINGS PRESERVE STREAM & FLOODPLAIN ENHANCEMENT DESIGN SET | 95% DESIGN DRAWINGS | WOOD RIVER LAND TRUST WARM SPRINGS CREEK, KETCHUM, ID BLAINE COUNTY, IDAHO |
| | DATE: DESIGNED: APPROVED: DRAWING N | | 11/6/2024 ZS,MP, JY JY |
| | | DETAILS | OLATION |

SHEET 32 O



| WORL | KING D NOT F DNSTR | RAFT OR UCTION | 1 |
|-----------------------------|--------------------------|----------------------|----------------|
| DATE: DESIGNE APPROVE | D: | 11/6/202 ZS,MP, . | 24 1Y 1Y |
| DRAWIN | g NAME DETAI | LS | |
| CONS | STRUCTE | D RIFFLE | 2 |
| DRAWIN | ^{G NO.} D2 | 127 | Γ |

CLASS 1 RIFFLE MATERIAL NOTES:

THE LARGER COMPONENT (50% PASSING AND LARGER) OF THE CLASS 1 RIFFLE MATERIAL SHALL BE IMPORTED MATERIAL CONSISTING OF ANGULAR OR SUBANGULAR MATERIAL. THE SMALLER COMPONENT (50% PASSING AND SMALLER) CAN BE IMPORTED OR DEVELOPED ONSITE BY SCREENING AND MIXING OF NATIVE ALLUVIUM FROM PROJECT EXCAVATIONS. THE FINAL CLASS 1 RIFFLE MATERIAL SHALL BE A WELL GRADED AND UNIFORMLY MIXED SUBSTRATE BOULDERS SHALL BE INCLUDED IN CLASS-1 RIFFLE MATERIAL. CLASS 2 RIFFLE MATERIAL NOTES:

1. CLASS 2 RIFFLE MATERIAL SHALL BE IMPORTED OR DEVELOPED BY CONTRACTOR ONSITE BY SCREENING AND MIXING OF NATIVE ALLUVIUM FROM PROJECT EXCAVATIONS TO FORM A WELL GRADED AND UNIFORMLY MIXED SUBSTRATE.

CLASS 3 RIFFLE MATERIAL NOTES:

THE C.O. OR ENGINEER SHALL INSPECT SUITABILITY OF IN-SITU MATERIAL (IN EXCAVATION AREAS) AND ACCEPT OR REJECT BASED UPON THE CLASS 3 RIFFLE MATERIAL GRADATION SHOWN ON THIS DRAWING.

2. IF IN-SITU MATERIAL DOES NOT MEET THE SPECIFIED CLASS 3 RIFFLE GRADATION AT CLASS 3 RIFFLE LOCATIONS, THE CONTRACTOR SHALL OVER-EXCAVATE UNSUITABLE MATERIAL AND INSTALL A CONSTRUCTED RIFFLE PER THE DETAIL ON DRAWING D2 USING ACCEPTABLE CLASS 3 MATERIAL.

3. WHERE PLACEMENT OF CLASS 3 RIFFLE MATERIAL IS REQUIRED TO MEET FINISH GRADE (FILL AREAS), THE CONTRACTOR SHALL FOLLOW THE REQUIREMENTS OF A CONSTRUCTED RIFFLE PER DRAWING D2. THE FULL THICKNESS OF FILL MATERIAL SHALL MEET CLASS 3 RIFFLE MATERIAL SPECIFICATIONS (IF THICKER THAN 1-FT REQUIRED THICKNESS).

| CLASS 1 RIFFLE MATERIAL | | | | | |
|-------------------------|------------|--|--|--|--|
| PERCENT PASSING | SIZE CLASS | | | | |
| 100% | 32 INCHES | | | | |
| 84% | 26 INCHES | | | | |
| 50% | 16 INCHES | | | | |
| 30% | 12 INCHES | | | | |
| 16% | 8 INCH | | | | |
| 10% | <0.8 INCH | | | | |

| CLASS 2 RIFFLE MATERIAL | | | | | |
|-------------------------|-----------------|--|--|--|--|
| PERCENT PASSING | MIN. SIZE CLASS | | | | |
| 100% | 18 INCHES | | | | |
| 84% | 14 INCHES | | | | |
| 50% | 9 INCHES | | | | |
| 30% | 7 INCHES | | | | |
| 16% | 4.5 INCH | | | | |
| 10% | <0.5 INCH | | | | |

| CLASS 3 RIFFLE MATERIAL | | | | | |
|-------------------------|-----------------|--|--|--|--|
| PERCENT PASSING | MIN. SIZE CLASS | | | | |
| 100% | 8.0 INCHES | | | | |
| 84% | 6.0 INCHES | | | | |
| 50% | 4.0 INCHES | | | | |
| 30% | 3.0 INCHES | | | | |
| 16% | 2.0 INCH | | | | |
| 10% | <0.2 INCH | | | | |

RIFFLE SCHEDULE NOTES:

RIFFLE CREST IS DEFINED AS THE LONGITUDINAL (PARALLEL TO STREAM FLOW) LENGTH OF THE 0% SLOPE PORTION OF THE UPSTREAM END OF THE RIFFLE.

| | MAIN C | CHANNE | L RIFI | FLE SCI | HEDULE | |
|-------------------|-----------------|-------------------------|-----------------|------------------|--------|-------------------|
| START STA (FT) | END STA (FT) | CREST LENGTH (FT) | RIFFLE CLASS | AREA (SQ.FT.) | | BOULDER S (EA) |
| 11+01 | 12+01 | 10 | CLASS-1 | 3311 | 274 | 6 |
| 26+17 | 27+34 | 0 | CLASS-1 | 7516 | 592 | 10 |

| START STA (FT) | END STA (FT) | CREST LENGTH (FT) | RIFFLE CLASS | AREA (SQ.FT.) | RIFFLE VOLUM E (CY) | BOULDER S (EA) |
|-------------------|-----------------|-------------------------|-----------------|------------------|---------------------------|-------------------|
| 0+00 | 0+54 | 10 | CLASS-2 | 499 | 30 | 0 |
| 1+16 | 1+91 | 0 | CLASS-3 | 907 | 34 | 0 |
| 2+55 | 3+34 | 0 | CLASS-3 | 1353 | 51 | 0 |
| 3+89 | 4+41 | 0 | CLASS-3 | 889 | 33 | 0 |
| 4+90 | 5+66 | 0 | CLASS-3 | 1272 | 48 | 0 |
| 6+59 | 6+84 | 0 | CLASS-3 | 609 | 23 | 0 |
| 7+87 | 8+55 | 0 | CLASS-3 | 1080 | 41 | 0 |
| 8+86 | 9+18 | 0 | CLASS-3 | 548 | 21 | 0 |
| 9+51 | 9+69 | 0 | CLASS-3 | 323 | 12 | 0 |
| 9+94 | 10+58 | 0 | CLASS-3 | 1017 | 38 | 0 |
| 10+98 | 11+15 | 0 | CLASS-3 | 253 | 10 | 0 |
| 11+43 | 11+67 | 0 | CLASS-3 | 374 | 14 | 0 |
| 12+11 | 12+85 | 0 | CLASS-3 | 1126 | 42 | 0 |
| 13+42 | 13+91 | 0 | CLASS-3 | 797 | 30 | 0 |
| 14+29 | 14+58 | 0 | CLASS-3 | 514 | 20 | 0 |
| 14+92 | 15+34 | 0 | CLASS-3 | 701 | 26 | 0 |
| 15+80 | 16+02 | 0 | CLASS-3 | 375 | 14 | 0 |
| 16+31 | 16+74 | 0 | CLASS-3 | 745 | 28 | 0 |
| 17+09 | 17+30 | 0 | CLASS-3 | 376 | 14 | 0 |
| 17+69 | 18+77 | 10 | CLASS-2 | 3140 | 180 | 0 |
| 19+16 | 19+51 | 0 | CLASS-3 | 629 | 24 | 0 |
| 20+55 | 20+84 | 10 | CLASS-2 | 373 | 24 | 0 |
| 20+99 | 21+28 | 10 | CLASS-2 | 377 | 24 | 0 |
| 21+35 | 21+65 | 10 | CLASS-2 | 402 | 25 | 0 |
| 21+75 | 22+25 | 10 | CLASS-2 | 674 | 40 | 0 |

| W | ETLAND | CHAN | NEL R. | IFFLE S | SCHEDL | ILE |
|-------------------|-----------------|-------------------------|-----------------|------------------|---------------------------|-------------------|
| START STA (FT) | END STA (FT) | CREST LENGTH (FT) | RIFFLE CLASS | AREA (SQ.FT.) | RIFFLE VOLUM E (CY) | BOULDER S (EA) |
| 0+00 | 0+76 | 0 | CLASS-3 | 646 | 24 | 0 |
| 1+28 | 1+44 | 0 | CLASS-3 | 160 | 6 | 0 |


| | CUL | VERT R | IFFLE | SCHEL | DULE | |
|-------------------|-----------------|--------|-----------------|------------------|---------------------------|-------------------|
| START STA (FT) | END STA (FT) | | RIFFLE CLASS | AREA (SQ.FT.) | RIFFLE VOLUM E (CY) | BOULDER S (EA) |
| N/A | N/A | 0 | CLASS-3 | 472 | 17 | 0 |


BOULDERS DESCRIPTION SIZE CLASS BOULDERS 36 INCH - 48 INCH EXTRA LARGE HABITAT BOULDERS 48 INCH MIN.

- BOULDER NOTES: 1. SEE TYPICAL BOULDER PLACEMENT DETAIL, DWG. D2. BOULDERS SHALL BE IMPORTED.
- NOMINAL DIAMETER SHALL BE MEASURED AS THE INTERMEDIATE AXIS WHERE THE SMALL AND LARGE AXIS SHALL NOT BE MORE THAN 3 TIMES LESS THAN OR GREATER THAN THE NOMINAL DIAMETER. THIS PREVENTS LONG AND/OR THIN PLATE LIKE BOULDERS FROM BEING APPROVED.
- 4. BOULDERS SHALL BE ROUNDED TO SUB-ANGULAR. GRADATION NOTES:
- 1. PERCENT PASSING SIZE CLASS IS BASED ON THE NOMINAL DIAMETER OF ROCK.
- 2. NOMINAL DIAMETER SHALL BE MEASURED AS THE INTERMEDIATE AXIS WHERE THE SMALL AND LARGE AXIS SHALL NOT BE MORE THAN 3 TIMES LESS THAN OR GREATER THAN THE NOMINAL DIAMETER.
- SIZE CLASS IS UNIQUE TO THESE DRAWINGS AND IS NOT THE UNIFIED SOIL CLASSIFICATION. ACCEPTABLE RIFFLE MATERIAL MAY BE CREATED FROM
- 4. STOCKPILES OF VARIOUS SIZED SCREENED MATERIALS.











SEQUENCING NOTES:

- 1. RACKING-2 (FOOTER) SHALL BE PLACED SO ITS UPSTREAM END RESTS ON THE STREAM BED (UP TO 1 DIAMETER BURIED TO ACCOMODATE VARIED BANK HEIGHTS) ALONG THE TOE OF THE BANK. BACKFILL AND COMPACT AROUND FOOTER LOG WITH COMPACTED FILL
- RACKING-1 LOGS (WITH ROOTWADS) SHALL BE INSTALLED ON TOP OF RACKING-2 LOGS. ROOTWADS SHALL BE PLACED OVER TOP OF FOOTER LOG WITH ROOTWAD AS CLOSE TO BANK AS POSSIBLE AND AS DIRECTED BY C.O.
 PLACE SLASH BETWEEN EACH LAYER OF RACKING.
- 4. REPEAT STEPS 1 AND 2 AT THE DIRECTION OF C.O. TO BUILD TALL ROUGHENED EDGE.
- 5. PLACE GENERAL FILL OVER PLACED MATERIALS TO FINISH GRADES AND COMPACT TO 85% RELATIVE DENSITY.

| NO | TES: | |
|----|------|--|

- 1. ROUGHENED EDGE BANK TREATMENT SHALL BE CONSTRUCTED AT LOCATIONS AS SHOWN ON THE PLANS. THE EXACT LOCATION OF EACH OCCURRENCE OF BANK ROUGHNESS SHALL BE LOCATED BY THE CONTRACTOR AND APPROVED BY THE C.O. PRIOR TO CONSTRUCTING.
- 2. ALL EXPOSED ENDS OF KEY LOGS AND RACKING LOGS SHALL BE BROKEN. ALL EXPOSED CLEAN CUT ENDS OF LOGS WILL REQUIRE THE CONTRACTOR TO REPLACE WITH A BROKEN END AT NO ADDITIONAL EXPENSE.







| LOG TYPE | SIZE (DBH) | LENGTH (FT) | ROOTWAD | MIN. ROOTWAD DIA. (FT) | BRANCHES | QUANTITY |
|-------------|------------|-------------|----------|---------------------------|----------|----------|
| RACKING-1 | 4 - 12 | 15 - 25 | YES | 2.5 | YES | 3 EA |
| RACKING-2 | 4 - 12 | 15 - 25 | OPTIONAL | NA | YES | 4 EA |
| SLASH-1 | 1 - 4 | 5 - 15 | NA | NA | YES | 7 CY |
| SLASH-2 | 1 - 4 | 5 - 15 | NA | NA | YES | 7 CY |
| LIVE STAKES | > 3/4 | 6 - 8 | NA | NA | NA | 10 EA |


1. QUANTITIES SHOWN IN THE TABLES INCLUDE QUANTITIES ASSOCIATED WITH THE BRUSH BANK PORTION OF THESE TREATMENTS. 2. C.O. MAY REQUEST PLACEMENT OF ADDITIONAL MATERIAL BASED ON BANK HEIGHT AND EXPOSURE OF UNSUITABLE MATERIAL. 3. IF LIVE STAKES QUANTITY IS FOR DORMANT INSTALLATION, QUANTITY SHALL BE DOUBLED IF INSTALLED APRIL 21 TO OCTOBER 10.


(RACKING-2)

STEP 4 (ALL RACKING-2)










SHEET 36

NOTES:

- 1. INSTALL STRUCTURES AT LOCATIONS IDENTIFIED IN THE PLANS. THE EXACT LOCATION OF EACH STRUCTURE SHALL BE APPROVED BY THE CONTRACTING OFFICER PRIOR TO INSTALLATION.
- 2. IF POOL EXCAVATION IS NOT SPECIFIED IN THE GRADING PLAN, THE CONTRACTING OFFICER WILL DETERMINE IF A SCOUR POOL IS DESIRED. THE SCOUR POOL SHALL BE EXCAVATED TO A DEPTH OF 2' ADJACENT TO THE STRUCTURE AND EXTEND BEYOND ROOTWADS EXTENDING INTO CHANNEL PER THE DIRECTION OF THE CONTRACTING OFFICER.
- 3. ROUGH GRADING OF CHANNEL SHALL BE COMPLETE PRIOR TO CONSTRUCTION OF STRUCTURE INCLUDING CONSTRUCTION OF RIFFLES OR STREAMBED MATERIALS.
- RACKING, SLASH, AND LIVE STAKES SHALL BE INCORPORATED INTO THE STRUCTURE BY WEAVING THE MATERIAL IN BETWEEN PLACED LOGS, FILLING VOIDS, ETC. AT EACH STEP THROUGHOUT CONSTRUCTION AS DIRECTED BY THE CONTRACTING OFFICER. RACKING CAN BE PLACED FIRST TO LIFT THE LOG OFF CHANNEL BED AS DIRECTED BY THE CONTRACTING OFFICER. SEE STRUCTURE SEQUENCING FOR RACKING AND SLASH PLACEMENT. 4.
- LIVE STAKES SHALL BE INSTALLED PRIOR TO AND/OR DURING BACKFILLING TO ENSURE A MINIMUM OF 1-FT SUBMERGENCE IN GROUND WATER. LIVE 5. STAKES SHALL HAVE CONTINUOUS CONTACT WITH SOIL ALONG THE LENGTH OF THE STAKE LEAVING NO VOIDS.
- BACKFILL USING NATIVE EXCAVATED MATERIAL UNLESS NATIVE MATERIAL IS UNSUITABLE. UNSUITABLE IS DEFINED AS ANYTHING CLASSIFIED AS A CLAY, SILT, OR SAND. PLACE BACKFILL IN 1-FOOT MAXIMUM LIFTS. COMPACT EACH LIFT USING MECHANICAL EQUIPMENT SUCH AS AN EXCAVATOR BUCKET OR EQUIPMENT TRACKING MAKING CERTAIN TO NOT DAMAGE OR CHANGE THE ELEVATION OF THE STRUCTURE MATERIAL DURING COMPACTION.
- ALL CUT ENDS OF LOGS THAT WILL BE EXPOSED UPON COMPLETION OF STRUCTURE SHALL BE MARRED PRIOR TO INSTALLATION. THE CONTRACTOR SHALL USE AN EXCAVATOR, OR OTHER HEAVY EQUIPMENT TO TEAR APART WOOD FIBERS AT THE CUT END OF THE LOG TO CREATE THE APPEARANCE OF A LOG THAT HAS NATURALLY BROKEN APART.
- 8. LOG PLACEMENT MAY BE ADJUSTED IN THE FIELD BY THE CONTRACTING OFFICER TO PROVIDE VARIABILITY FROM STRUCTURE TO STRUCTURE.


| | HS-1: | SIX-LOG | STRUCTL | RE MATERIAL | SCHEDULE | |
|-------------|---------------|----------------|----------|---------------------------|----------|----------|
| LOG TYPE | SIZE (DBH) | LENGTH (FT) | ROOTWAD | MIN. ROOTWAD DIA. (FT) | BRANCHES | QUANTITY |
| TYPE 1 | 13 - 22 | 30 - 40 | YES | 4.5 | NO | 4 EA |
| TYPE 2 | 13 - 22 | 30 - 40 | NO | NA | NO | 2 EA |
| RACKING-1 | 4 - 12 | 15 - 25 | YES | 2.5 | YES | 6 EA |
| RACKING-2 | 4 - 12 | 15 - 25 | OPTIONAL | NA | YES | 6 EA |
| SLASH-1 | 1 - 4 | 5 - 15 | NA | NA | YES | 20 EA |
| LIVE STAKES | > 3/4 | 6 - 8 | NA | NA | NA | 15 EA |

HABITAT STRUCTURE - 1 (HS-1) SIX-LOG STRUCTURE 11



1. INSTALL STRUCTURES AT LOCATIONS IDENTIFIED IN THE PLANS. THE EXACT LOCATION OF EACH STRUCTURE SHALL BE APPROVED BY THE CONTRACTING OFFICER PRIOR TO INSTALLATION.

- IF POOL EXCAVATION IS NOT SPECIFIED IN THE GRADING PLAN, THE CONTRACTING OFFICER WILL DETERMINE IF A SCOUR POOL IS DESIRED. THE SCOUR POOL SHALL BE EXCAVATED TO A DEPTH OF 2' ADJACENT TO THE STRUCTURE AND EXTEND BEYOND ROOTWADS EXTENDING INTO CHANNEL PER THE DIRECTION OF THE CONTRACTING OFFICER.
- ROUGH GRADING OF CHANNEL SHALL BE COMPLETE PRIOR TO CONSTRUCTION OF STRUCTURE INCLUDING CONSTRUCTION OF RIFFLES OR STREAMBED 3. MATERIALS.
- RACKING, SLASH, AND LIVE STAKES SHALL BE INCORPORATED INTO THE STRUCTURE BY WEAVING THE MATERIAL IN BETWEEN PLACED LOGS, FILLING 4. VOIDS, ETC. AT EACH STEP THROUGHOUT CONSTRUCTION AS DIRECTED BY THE CONTRACTING OFFICER. RACKING CAN BE PLACED FIRST TO LIFT THE LOG OFF CHANNEL BED AS DIRECTED BY THE CONTRACTING OFFICER. SEE STRUCTURE SEQUENCING FOR RACKING AND SLASH PLACEMENT.
- LIVE STAKES SHALL BE INSTALLED PRIOR TO AND/OR DURING BACKFILLING TO ENSURE A MINIMUM OF 1-FT SUBMERGENCE IN GROUND WATER. LIVE 5. STAKES SHALL HAVE CONTINUOUS CONTACT WITH SOIL ALONG THE LENGTH OF THE STAKE LEAVING NO VOIDS.
- BACKFILL USING NATIVE EXCAVATED MATERIAL UNLESS NATIVE MATERIAL IS UNSUITABLE. UNSUITABLE IS DEFINED AS ANYTHING CLASSIFIED AS A CLAY, SILT, OR SAND. PLACE BACKFILL IN 1-FOOT MAXIMUM LIFTS. COMPACT EACH LIFT USING MECHANICAL EQUIPMENT SUCH AS AN EXCAVATOR BUCKET OR EQUIPMENT TRACKING MAKING CERTAIN TO NOT DAMAGE OR CHANGE THE ELEVATION OF THE STRUCTURE MATERIAL DURING COMPACTION.
- ALL CUT ENDS OF LOGS THAT WILL BE EXPOSED UPON COMPLETION OF STRUCTURE SHALL BE MARRED PRIOR TO INSTALLATION. THE CONTRACTOR SHALL USE AN EXCAVATOR, OR OTHER HEAVY EQUIPMENT TO TEAR APART WOOD FIBERS AT THE CUT END OF THE LOG TO CREATE THE APPEARANCE OF A LOG THAT HAS NATURALLY BROKEN APART.
- LOG PLACEMENT MAY BE ADJUSTED IN THE FIELD BY THE CONTRACTING OFFICER TO PROVIDE VARIABILITY FROM STRUCTURE TO STRUCTURE.




SHEET 37

| | HS-2: NI | NE-LOG STR | UCTURE M | ATERIAL . |
|-------------|------------|-------------|----------|------------------------------|
| LOG TYPE | SIZE (DBH) | LENGTH (FT) | ROOTWAD | MIN. ROOTWAI DIA. (FT, |
| TYPE 1 | 13 - 22 | 30 - 40 | YES | 4.5 |
| TYPE 2 | 13 - 22 | 30 - 40 | NO | NA |
| TYPE 5 | 13 - 22 | 40 - 50 | YES | 4.5 |
| RACKING-1 | 4 - 12 | 15 - 25 | YES | 2.5 |
| RACKING-2 | 4 - 12 | 15 - 25 | OPTIONAL | NA |
| SLASH-1 | 1 - 4 | 5 - 15 | NA | NA |
| LIVE STAKES | > 3/4 | 6 - 8 | NA | NA |

HABITAT STRUCTURE - 2 (HS-2) NINE-LOG STRUCTURE


12

NTS




- ROUGH GRADING OF CHANNEL SHALL BE COMPLETE PRIOR TO CONSTRUCTION OF STRUCTURE INCLUDING RIFFLE CONSTRUCTION AND PLACEMENT OF BAR MATERIAL.
 SEE STRUCTURE SCHEDULE FOR NUMBER OF STRUCTURES, LOCATIONS, LOGS, AND ASSOCIATED MATERIAL QUANTITIES.
- ALL CUT ENDS OF LOGS THAT WILL BE EXPOSED UPON COMPLETION OF STRUCTURE SHALL BE MARED PRIOR TO INSTALLATION. THE CONTRACTOR SHALL USE AN EXCAVATOR, OR OTHER HEAVY EQUIPMENT TO TEAR APART WOOD FIBERS AT THE CUT END OF THE LOG TO CREATE THE APPEARANCE OF A LOG THAT HAS NATURALLY BROKEN APART.
- FIBERS AT THE CUT END OF THE LOG TO CREATE THE APPEARANCE OF A LOG THAT HAS NATURALLY BROKEN APART.
 RACKING, SLASH, AND LIVE STAKES SHALL BE INCORPORATED INTO THE STRUCTURE WHILE PLACING LAYERS SUCH THAT IT IS WOVEN INTO STRUCTURE IN BETWEEN PLACED LOGS, FILLING VOIDS, ETC. AT EACH STEP THROUGHOUT CONSTRUCTION AS DIFFECTED BY THE CONTRACTING OFFICEP.
- CONSTRUCTION AS DIRECTED BY THE CONTRACTING OFFICER. 5. WHEN EXCAVATED INTO GROUND, BACKFILL USING NATIVE EXCAVATED MATERIAL UNLESS NATIVE MATERIAL IS UNSUITABLE FOR BACKFILL. PLACE BACKFILL IN 1-FOOT MAXIMUM LIFTS. COMPACT EACH LIFT USING MECHANICAL EQUIPMENT SUCH AS AN EXCAVATOR BUCKET OR EQUIPMENT TRACKING.
- 6. WHEN UTILIZING EXISTING VEGETATION AS PASSIVE ANCHORS THERE SHALL BE AT A MINIMUM A WILLOW CLUMP ON THE DOWNSTREAM SIDE, BUT PREFERABLY ON THE UPSTREAM SIDE AS WELL. THE CONTRACTING OFFICER SHALL AGREE TO PLACEMENT AREAS OF STRUCTURES THAT ARE NOT BURIED.
- 7. LOG PLACEMENT MAY BE ADJUSTED IN THE FIELD BY THE CONTRACTING OFFICER TO PROVIDE VARIABILITY FROM STRUCTURE TO STRUCTURE.

| ŀ | 4S-3: SI | NGLE-LC | OG STRUC | TURE MATERIA | L SCHEDULE | Ŧ |
|-------------|---------------|----------------|----------|---------------------------|------------|----------|
| LOG TYPE | SIZE (DBH) | LENGTH (FT) | ROOTWAD | MIN. ROOTWAD DIA. (FT) | BRANCHES | QUANTITY |
| TYPE 1 | 13 - 22 | 30 - 40 | YES | 4.5 | NO | 1 EA |
| RACKING-2 | 4 - 12 | 15 - 25 | OPTIONAL | NA | YES | 3 EA |
| SLASH-1 | 1 - 4 | 5 - 15 | NA | NA | YES | 3 CY |
| LIVE STAKES | > 3/4 | 6 - 8 | NA | NA | NA | 6 EA |




13) HABITAT STRUCTURE - 3 (HS-3) SINGLE-LOG STRUCTURE







| LOG TYPE | SIZE (DBH) | LENGTH (FT) | ROOTWAD | MIN. ROOTWAD DIA. (FT) | BRANCHES | QUANTITY |
|-------------|---------------|----------------|----------|---------------------------|----------|----------|
| TYPE 2 | 13 - 22 | 30 - 40 | NO | NA | NO | 1 EA |
| TYPE 3 | 13 - 22 | 40 - 60 | YES | 4 | YES | 1 EA |
| RACKING-2 | 4 - 12 | 15 - 25 | OPTIONAL | NA | YES | 2 EA |
| SLASH-1 | 1 - 4 | 5 - 15 | NA | NA | YES | 5 CY |
| LIVE STAKES | > 3/4 | 6 - 8 | NA | NA | NA | 6 EA |

HABITAT STRUCTURE - 4 (HS-4) WHOLE TREE STRUCTURE 14









| LOG TYPE | SIZE (DBH) | LENGTH (FT) | ROOTWAD | MIN. ROOTWAD DIA. (FT) |
|-------------|---------------|----------------|----------|---------------------------|
| TYPE 1 | 13 - 22 | 30 - 40 | YES | 4.5 |
| TYPE 2 | 13 - 22 | 30 - 40 | NO | NA |
| RACKING-1 | 4 - 12 | 15 - 25 | YES | 2.5 |
| RACKING-2 | 4 - 12 | 15 - 25 | OPTIONAL | NA |
| SLASH-1 | 1 - 4 | 5 - 15 | NA | NA |
| LIVE STAKES | > 3/4 | 6 - 8 | NA | NA |

- NOTES: 1. INSTALL STRUCTURES AT LOCATIONS IDENTIFIED IN THE PLANS. THE EXACT LOCATION OF EACH STRUCTURE SHALL BE LOCATED PRIOR TO INSTALLATION FOR APPROVAL BY THE CONTRACTING OFFICER.
- 2. WHERE POOL EXCAVATION IS NOT SPECIFIED IN THE GRADING PLAN, THE C.O. MAY DIRECT EXCAVATION OF A SCOUR POOL. IF A SCOUR POOL IS REQUIRED
- EXCAVATE A 2' DEEP POOL ADJACENT TO THE STRUCTURE AND EXTEND POOL OUT PAST ROOTWAD EXTENDING INTO CHANNEL. ROUGH GRADING OF CHANNEL SHALL BE COMPLETE PRIOR TO CONSTRUCTION OF STRUCTURE INCLUDING RIFFLE CONSTRUCTION AND PLACEMENT OF BAR MATERIAL.
- 3. RACKING, SLASH, AND LIVE STAKES SHALL BE INCORPORATED INTO THE STRUCTURE WHILE PLACING LAYERS SUCH THAT IT IS WOVEN INTO STRUCTURE IN BETWEEN 4.
- PLACED LOGS, FILLING VOIDS, ETC. AT EACH STEP THROUGHOUT CONSTRUCTION AS DIRECTED BY THE CONTRACTING OFFICER.
- LIVE STAKES SHALL BE INSTALLED PRIOR TO AND/OR DURING BACKFILLING TO ENSURE A MINIMUM OF 1-FT SUBMERGENCE IN GROUND WATER. LIVE STAKES SHALL HAVE CONTINUOUS CONTACT WITH SOIL ALONG THE LENGTH OF THE STAKE LEAVING NO VOIDS. BACKFILL USING NATIVE EXCAVATED MATERIAL UNLESS NATIVE MATERIAL IS UNSUITABLE. UNSUITABLE MATERIAL CLASSIFIES AS A CLAY, SILT OR SAND. PLACE 5.
- 6. BACKFILL AS THE STRUCTURE IS CONSTRUCTED IN 1-FOOT MAXIMUM LIFTS. COMPACT EACH LIFT USING MECHANICAL EQUIPMENT SUCH AS AN EXCAVATOR BUCKET OR EQUIPMENT TRACKING MAKING CERTAIN TO NOT DAMAGE OR CHANGE THE ELEVATION OF THE STRUCTURE MATERIAL DURING COMPACTION.
- 7.
- ALL EXPOSED ENDS OF LOGS SHALL BE BROKEN/MARRED AND NOT SAW CUT TO APPEAR NATURAL. LOG PLACEMENT MAY BE ADJUSTED IN THE FIELD BY THE CONTRACTING OFFICER TO PROVIDE VARIABILITY FROM STRUCTURE TO STRUCTURE. 8.








D9 SHEET 40 0


DI

WOOD RIVER LAND TRUST WARM SPRINGS CREEK, KETCHUM, BLAINE COUNTY, IDAHO




| LOG TYPE | SIZE (DBH) | LENGTH (FT) | ROOTWAD | MIN. ROOTWAD DIA. (FT) | BRANCHES | QUANTITY |
|-------------|---------------|----------------|----------|---------------------------|----------|----------|
| TYPE 1 | 13 - 22 | 30 - 40 | YES | 4.5 | NO | 2 EA |
| TYPE 2 | 13 - 22 | 30 - 40 | NO | NA | NO | 1 EA |
| TYPE 4 | 12 - 14 | 20 - 35 | NO | NA | NO | 1 EA |
| RACKING-1 | 4 - 12 | 15 - 25 | YES | 2.5 | YES | 2 EA |
| RACKING-2 | 4 - 12 | 15 - 25 | OPTIONAL | NA | YES | 8 EA |
| SLASH-1 | 1 - 4 | 5 - 15 | NA | NA | YES | 10 CY |
| LIVE STAKES | > 3/4 | 6 - 8 | NA | NA | NA | 8 EA |

- NOTES: 1. INS INSTALL STRUCTURES AT LOCATIONS IDENTIFIED IN THE PLANS. THE EXACT LOCATION OF EACH STRUCTURE SHALL BE STAKED PRIOR TO INSTALLATION FOR APPROVAL BY THE CONTRACTING OFFICER.
- ROUGH GRADING OF PILOT CHANNEL SHALL BE COMPLETE PRIOR TO INSTALLATION OF LOGS. 2
- RACKING, SLASH, AND LIVE STAKES SHALL BE INCORPORATED INTO THE STRUCTURE BY WEAVING IT IN BETWEEN PLACED LOGS, FILLING VOIDS, ETC. AT EACH STEP THROUGHOUT CONSTRUCTION AS DIRECTED BY THE CONTRACTING OFFICER. 3.
- LIVE STAKES SHALL BE INSTALLED PRIOR TO AND/OR DURING BACKFILLING TO ENSURE A MINIMUM OF 1-FT SUBMERGENCE IN GROUND 4. WATER. LIVE STAKES SHALL HAVE CONTINUOUS CONTACT WITH SOIL ALONG THE LENGTH OF THE STAKE LEAVING NO VOIDS.
- BACKFILL USING SPECIFIED WOOD STRUCTURE BACKFILL MATERIAL. NATIVE EXCAVATED MATERIAL MAY BE USED AS WOOD STRUCTURE 5. BACKFILL MATERIAL IF IT MEETS THE REQUIRED GRADATION. PLACE BACKFILL IN 1-FOOT MAXIMUM LIFTS. COMPACT EACH LIFT USING MECHANICAL EQUIPMENT SUCH AS AN EXCAVATOR BUCKET OR EQUIPMENT TRACKING MAKING CERTAIN TO NOT DAMAGE OR CHANGE THE ELEVATION OF THE STRUCTURE.
- 6.
- ALL EXPOSED ENDS OF LOGS SHALL BE BROKEN AND NOT SAW CUT TO APPEAR NATURAL. LOG PLACEMENT MAY BE ADJUSTED IN THE FIELD BY THE CONTRACTING OFFICER TO PROVIDE VARIABILITY FROM STRUCTURE TO 7. STRUCTURE.
- REPLACE ORGANIC LAYER AND/OR PREPARE SURFACE FOR SEEDING IN ACCORDANCE WITH THE PLANTING AND SEEDING PLAN AND/OR 8. SPECIFICATIONS.





STRUCTURE SEQUENCING STAGE 1 STAGE 2 STAGE 3 STAGE 4 STAGE 5





| 1 | LINEAR FOOT) | MATERIAL SC | INLUGLE |
|---|---------------------------|-------------|----------|
| | MIN. ROOTWAD DIA. (FT) | BRANCHES | QUANTITY |
| | NA | YES | 1 EA |
| | NA | YES | 1 EA |
| | NA | NA | 2 EA |






STAGE 2


| LOG TYPE | SIZE (DBH) | LENGTH (FT) | ROOTWAD | MIN. ROOTWAD DIA. (FT) | BRANCHES | QUANTITY |
|------------|------------|-------------|----------|---------------------------|----------|----------|
| TYPE 1 | 13 - 22 | 30 - 40 | YES | 4.5 | NO | 4 EA |
| TYPE 2 | 13 - 22 | 30 - 40 | NO | NA | NO | 1 EA |
| TYPE 3 | 13 - 22 | 40 - 60 | YES | 4 | YES | 1 EA |
| TYPE 5 | 13 - 22 | 40 - 50 | YES | 4.5 | NO | 1 EA |
| RACKING-1 | 4 - 12 | 15 - 25 | YES | 2.5 | YES | 2 EA |
| RACKING-2 | 4 - 12 | 15 - 25 | OPTIONAL | NA | YES | 7 EA |
| SLASH-1 | 1 - 4 | 5 - 15 | NA | NA | YES | 5 EA |
| IVE STAKES | > 3/4 | 6 - 8 | NA | NA | NA | 12 EA |


- USING MECHANICAL EQUIPMENT SUCH AS AN EXCAVATOR BUCKET OR EQUIPMENT TRACKING MAKING CERTAIN TO NOT DAMAGE OR CHANGE THE ELEVATION OF THE STRUCTURE MATERIAL DURING COMPACTION.
- WHEN UTILIZING EXISTING VEGETATION AS PASSIVE ANCHORS THERE SHALL BE AT A MINIMUM A WILLOW CLUMP ON THE 9. DOWNSTREAM SIDE, BUT PREFERABLY ON THE UPSTREAM SIDE AS WELL.
- 10. LOG PLACEMENT MAY BE ADJUSTED IN THE FIELD BY THE CONTRACTING OFFICER TO PROVIDE VARIABILITY FROM STRUCTURE TO STRUCTURE.














BANK TREATMENT - TWO LAYER FESL NOTES:

- 1. PLACE 2 LAYERS OF BIODEGRADABLE EROSION CONTROL BLANKET (ECB).
- 1.1. FINE EROSION CONTROL BLANKET SHALL BE C125BN (INSIDE LAYER)
 1.2. COARSE EROSION CONTROL BLANKET SHALL BE GEOCOIR 700 (OUTSIDE LAYER)
 2. PLACE BACKFILL MATERIAL ON TOP OF 2 LAYERS OF EROSION CONTROL BLANKET SO THAT A
- MINIMUM OF 3' IS BURIED. SOIL LIFTS SHALL NOT BE GREATER THAN 1.5' THICK. 3.
- OF THE BANK TREATMENT). FILL SHALL NOT BE PLACED DURING FIRST LIFT AT LOCATIONS WHERE BOLES OF LOGS SHALL BE 4. PLACED. FABRIC SHALL BE FOLDED UNDER THE LOG.


- PULL EXPOSED EROSION CONTROL BLANKET OVER BACKFILL MATERIAL AND PULL TIGHT. REMOVE WRINKLES/FOLDS (SEED WILL NOW BE UNDERNEATH EROSION CONTROL BLANKET). KEY IN FABRIC A MINIMUM OF 1 FT. STAKE EDGE OF ECB TO KEEP EROSION CONTROL BLANKET TIGHT. STAKE SPACING SHALL BE A MAXIMUM OF 5'. 6.
- STAKE FESL WITH 1" X 2" X 18" WOODEN STAKES; 1 ROW, PLACED 3' APART, AT FRONT EDGE OF
- FESL AND 1 ROW PLACED 3' APART, 4' BEHIND FRONT EDGE OF FESL. 8
- REPEAT STEPS 1 THROUGH 7 FOR SECOND (TOP) LIFT BACK FILL TRENCH AND COMPLETE FINISH GRADING OF THE FILL AREA. TOP OF FILL AREA SHALL
- INCLUDE A 6" TOP LAYER OF ORGANIC SOIL.



BALDY CHANNEL INLET NOTES:

- THE BALDY CHANNEL INLET SHALL BE CONSTRUCTED DURING THE FALL WHEN WILLOWS ARE DORMANT.
- BANKS SHALL BE CONSTRUCTED OF LARGE HABITAT BOULDERS
- WITH PLACEMENT TO BE APPROVED BY THE C.O. OR ENGINEER. З. WELL GRADED NATIVE ALLUVIUM SHALL BE PLACED TO FILL IN
- VOIDS IN LARGE BOULDERS AND BENEATH TWO LAYER FESL BANK TREATMENT. POTTED WILLOWS, LIVE CUTTINGS, AND SEEDED AREAS SHALL BE IRRIGATED FOR A MINIMUM OF THREE YEARS FOLLOWING
- CONSTRUCTION.

- SEED THE TOP OF THE BACKFILL MATERIAL AT THE LOCATION SHOWN IN THE DETAIL (TOP FRONT





City of Ketchum

ATTACHMENT 4:

Floodplain Development Criteria Analysis

| | | | Floor | dplain Development Permit Requirements |
|-----|--------|---------|---------------------------------|---|
| - | L. Eva | aluatio | on Standards: 17.8 | |
| Co | omplia | nt | | Standards and Staff Comments |
| Yes | No | N/ A | Guideline | City Standards and <i>Staff Comments</i> |
| | | | 17.88.050(E)1 | The proposal preserves or restores the inherent natural characteristics of the river, floodplain, and riparian zone, including riparian vegetation and wildlife habitat. Development does not alter river channel unless all stream alteration criteria for evaluation are also met. |
| | | | <i>Staff</i> <i>Comments</i> | The property has seen consistent degradation over the past 100 years, resulting in stream bank erosion, channel incision, and an ecological profile that consists of a monoculture of plant species (including invasive). The project goes well beyond preserving the inherent natural characteristics of the river by restoring the river and floodplain back to the pre-human development period of its history. The project will include excavations in and around the stream to restore the original configuration of the reach by reestablishing a functioning side channel, excavating out previous fill areas, and creating small pools for aquatic habitat and riparian function. The extensive and ecologically sensitive planting plan will further support the excavation efforts by creating a bio-diverse ecology that is more resilient long term and provides stability of the soils during flood events. These improvements rehabilitate the entire river system through the reach and re-establishes a functioning floodplain to allow for historic |
| | | | | reach and re-establishes a functioning floodplain to allow for historic flow of floodwaters through the site. Alterations to the river channel are proposed and as noted below, the project meets all stream alteration evaluation criteria. |
| | | | 17.88.050(E)2 | No temporary construction activities, encroachment or other disturbance into the 25-foot riparian zone, including encroachment of below grade structures, shall be permitted, with the exception of approved stream stabilization work and restoration work associated with a riparian zone that is degraded. |
| | | | <i>Staff Comments</i> | There will be extensive construction related activities within the stream and riparian area associated with the stream alteration work and restoration of the riparian area. As noted in condition 4, a comprehensive construction management plan will be required prior to start of construction to ensure that construction activities are well managed and do not result in any downstream impacts or impacts to adjacent properties. |
| | | | 17.88.050(E)3 | No permanent development shall occur within the 25-foot riparian zone, with the exception of approved stream stabilization work and |

| | | | Floo | dplain Development Permit Requirements |
|-----|--------|---------|---------------------------|---|
| | | | on Standards: 17.8 | |
| - | omplia | | | Standards and Staff Comments |
| Yes | No | N/ A | Guideline | City Standards and <i>Staff Comments</i> |
| | | | | restoration work associated with permit issued under this title, or exceptions as described below: a. Access to a property where no other primary access is available; b. Emergency access required by the fire department; c. A single defined pathways or staircases for the purpose of providing access to the river channel and in order to mitigate multiple undefined social paths; d. Development by the City of Ketchum. |
| | | | <i>Staff Comments</i> | There are proposed development activities within the 25-foot riparian area which include: Irrigation (well house and service lines) Defined pathways to avoid the creation of social paths |
| | | | | Existing municipal water and sewer lines proposed to remain |
| | | | | There is an existing electrical transformer and service line within the riparian area that will be relocated outside the riparian area as part of the project. |
| | | | | All development activities are permitted as they fall under subsection "d" of this criteria as development by the City of Ketchum. |
| | | | 17.88.050(E)4 | New or replacement planting and vegetation in the riparian zone shall include plantings that are low growing and have dense root systems for the purpose of stabilizing stream banks and repairing damage previously done to riparian vegetation. Examples of such plantings most commonly include: red osier dogwood, common chokecherry, serviceberry, elderberry, river birch, skunk bush sumac, Beb's willow, Drummond's willow, little wild rose, gooseberry, and honeysuckle. However, in rare instances the distance from the top- of-bank to the mean high water mark is significant and the native vegetation appropriate for the riparian zone are low growing, drought resistant grasses and shrubs. Replacement planting and vegetation shall be appropriate for the specific site conditions. Proposal does not include vegetation within the 25-foot riparian zone that is degraded, not natural, or which does not promote bank stability. |
| | | | <i>Staff Comments</i> | The existing riparian area along much of the bank is currently degraded, contains non-natural materials such as remnant concrete, and is very steep which does not promote the growth of bank stabilizing plant species. An extensive planting plan has been developed which identifies specific plant lists for each zone of restoration. Zones include Upland Meadow, Xeric (dry) floodplain, Mesic (wet) floodplain, near stream riparian, in-stream aquatic, aspen grove, and restored lawn. See sheets L2.01 and L2.02 for the detailed |

| | Floodplain Development Permit Requirements | | | | | |
|-----|--|---------|---------------------------------|--|--|--|
| | 1. Evaluation Standards: 17.88.050€ | | | | | |
| Co | Compliant | | | Standards and Staff Comments | | |
| Yes | No | N/ A | Guideline | City Standards and Staff Comments | | |
| | | | | planting mix for each zone. Specifically related to the riparian planting, Near Stream Riparian Zone is detailed with Seed Mix D and includes a wide variety of willows, cottonwoods, and grasses. Installation will include #5 containers for the trees and shrubs and a seen mix for grasses. The land scape plan notes that temporary protection from wildlife will be needed. The proposed plantings are appropriate for the specific site conditions as they have been tailored for the specific zones based on an ecological profile. Once installation is complete and plantings are | | |
| | | | | stabilized, the riparian zone will be well established and not degrade over time, ensuring long term bank stability. | | |
| | | | 17.88.050(E)5 | Landscaping and driveway plans to accommodate the function of the floodplain allow for sheet flooding. Surface drainage is controlled and shall not adversely impact adjacent properties including driveways drained away from paved roadways. Culvert(s) under driveways may be required. Landscaping berms shall be designed to not dam or otherwise obstruct floodwaters or divert same onto roads or other public pathways. | | |
| | | | <i>Staff</i> <i>Comments</i> | There is one access to the Warm Springs Preserve property and that is Lopey Lane. Lopey Lane is an existing road with a bridge that crosses Warm Springs Creek. Currently, the bridge is elevated as such that floodwaters pass under the bridge, not over. The bridge is not proposed to be altered as part of the project. The project does propose to improve the road once it crosses onto the Warm Springs Preserve property. As shown on Sheet C2.0 the road includes a set of two 36" culverts closer to the existing bridge and one additional bridge structure closer to the parking area. The existing driveway/road and proposed bridge/culverts are located outside of published FEMA 100-year floodplain extents and are designed to convey only a portion of Warm Springs Creek flood flows. Both facilities are designed to have a minimum of 1-foot of freeboard at the 100-year flow. The existing driveway/road does not become inundated at the 100- year flow under proposed conditions. Additionally, the bridge is designed to carry those flows with or without the culverts in place. The city engineer did provide some minor comments related to the finished condition of the road included crowning, amount of gravel shoulder, details of drywells, and a few others that will be addressed with issuance of the final construction plans. These items will not | | |

| | Floodplain Development Permit Requirements | | | | | |
|-------------|--|-------------|--------------------|---|--|--|
| | | | on Standards: 17.8 | | | |
| | Compliant | | | Standards and Staff Comments | | |
| Yes | No | N/ | Guideline | City Standards and <i>Staff Comments</i> | | |
| | | <u>A</u> | | impact the ability of the culverts or bridge to effectively convey flood waters. Condition of approval #2 addresses these items. There is also a pedestrian bridge to be constructed within the | | |
| | | | | southern floodplain area and that bridge is also designed to have a minimum of 1-foot of freeboard at the 100-year flow. Please see sheetL2.03 for details of the pedestrian bridge. | | |
| \boxtimes | | | 17.88.050(E)6 | Flood water carrying capacity is not diminished by the proposal. | | |
| | | | Staff Comments | Extensive 2D and 1D hydraulic modeling was conducted to evaluate the project to ensure that the flood carrying capacity is maintained post construction. Post construction, the project modeling shows a no rise in the base flood elevations in the surrounding area. This demonstrates that the project will adequately convey floods of a 100- year event as well or better than the property has historically. The proposed development also has significantly more excavation (10,064 cubic yards) than fill (2,334 cubic yards) resulting in a net cut-fill balance of 7,730 cubic yards. Based on the submittal, there is no rise of the base flood elevations when comparing the proposed condition with the effective map for the area. However, there is a small rise documented within the project site, that has no impact to off-site or downstream properties. As such, a Conditional Letter of Map Revision (CLOMR) is required to document the changed condition on the property even though there is no rise documented outside the property. Condition of approval XX addresses the requirement of a CLOMR from FEMA prior to start of construction and the subsequent Letter of Map Revision required after project | | |
| \boxtimes | | | 17.88.050(E)7 | <i>completion.</i> Impacts of the development on aquatic life, recreation, or water quality upstream, downstream or across the stream are not adverse. | | |
| | | | Staff | As mentioned above, the current condition of the property is | | |
| | | | Comments | degraded with poor aquatic and plant health. The proposed project dramatically improves the conditions for aquatic life with site specific and purposeful grading and restoration work. All proposed recreation access paths are designed to deter the creation of social trail networks to preserve the restoration work. The development proposal itself is a restoration project with no buildings or other development proposed. | | |
| | | \boxtimes | 17.88.050(E)8 | Building setback in excess of the minimum required along waterways is encouraged. An additional ten-foot building setback beyond the required 25-foot riparian zone is encouraged to provide for yards, decks and patios outside the 25-foot riparian zone. | | |

| | Floodplain Development Permit Requirements | | | | | | |
|-------------|--|-------------|---------------------|--|--|--|--|
| | 1. Evaluation Standards: 17.88.050€ | | | | | | |
| - | Compliant | | | Standards and Staff Comments | | | |
| Yes | No | N/ | Guideline | City Standards and <i>Staff Comments</i> | | | |
| | | A | <i>a</i> : <i>c</i> | | | | |
| | | | Staff | There is no construction of buildings part of this application. A | | | |
| | | | Comments | separate design review application was filed by the City for a bathroom/storage building near the parking area. That proposed | | | |
| | | | | facility is outside the floodplain and riparian areas more than 100 | | | |
| | | | | feet. | | | |
| | | \boxtimes | 17.88.050(E)9 | The top of the lowest floor of a building located in, or partially within, | | | |
| | | | | the SFHA shall be at or above the flood protection elevation (FPE). A | | | |
| | | | | building is considered to be partially within the SFHA if any portion of | | | |
| | | | | the building or appendage of the building, such as footings, attached decks, posts for upper story decks, are located within the SFHA. | | | |
| | | | | See section 17.88.060, figures 1 and 2 of this chapter to reference | | | |
| | | | | construction details. See <u>chapter 17.08</u> of this title for definition of | | | |
| | | | | "lowest floor." | | | |
| | | | | a. In the SFHA where base flood elevations (BFEs) have been | | | |
| | | | | determined, the FPE shall be 24 inches above the BFE for the subject | | | |
| | | | | property; 24 inches or two feet is the required freeboard in Ketchum | | | |
| | | | | City Limits. | | | |
| | | | | b. In the SFHA where no BFE has been established, the FPE shall be at least two feet above the highest adjacent grade. | | | |
| | | | Staff | There are no buildings proposed. | | | |
| | | | Comments | mere are no banangs proposed. | | | |
| | | \boxtimes | 17.88.050(E)1 | The backfill used around the foundation in the SFHA floodplain shall | | | |
| | | | 0 | provide a reasonable transition to existing grade but shall not be used | | | |
| | | | | to fill the parcel to any greater extent. | | | |
| | | | | a. Compensatory storage shall be required for any fill placed within | | | |
| | | | | the floodplain. | | | |
| | | | | b. A CLOMR-F shall be obtained prior to placement of any additional fill in the floodplain. | | | |
| | | | Staff | There are no buildings proposed and therefore no foundations. | | | |
| | | | Comments | , , , | | | |
| | | \boxtimes | 17.88.050(E)1 | All new buildings located partially or wholly within the SFHA shall be | | | |
| | | | 1 | constructed on foundations that are designed by a licensed | | | |
| | | | | professional engineer. | | | |
| | | | Staff | There are no buildings proposed. | | | |
| | | | Comments | | | | |
| \boxtimes | | | 17.88.050(E)1 2 | Driveways shall comply with City of Ketchum street standards; access | | | |
| | | | <u> </u> | for emergency vehicles has been adequately provided for by limiting flood depths in all roadways to one foot or less during the one | | | |
| | | | | percent annual chance event. | | | |
| | | | Staff | As noted above, the city engineer has provided some comments | | | |
| | | | Comments | related to the design of the road (which is outside the SFHA) that will | | | |
| | | | | be addressed prior to grading permit application. Condition of | | | |

| | | | Floo | dplain Development Permit Requirements | | |
|-------------|-------------------------------------|---------|---------------------------------|---|--|--|
| - | 1. Evaluation Standards: 17.88.050€ | | | | | |
| | Compliant | | Standards and Staff Comments | | | |
| Yes | No | N/ A | Guideline | City Standards and <i>Staff Comments</i> | | |
| | | | | Approval 2 addresses this item. The existing driveway/road does not become inundated at the 100-year flow with the proposed changes to the property. | | |
| \boxtimes | | | 17.88.050(E)1 3 | Landscaping or revegetation shall conceal cuts and fills required for driveways and other elements of the development. | | |
| | | | <i>Staff Comments</i> | Landscaping is proposed on all areas of the property including driveways/roads and other elements of the project. The landscaping will conceal any cuts and fills which are required. No areas will be left bare upon completion of the project. | | |
| \boxtimes | | | 17.88.050(E)1 4 | (Stream Alteration) The proposal is shown to be a permanent solution and creates a stable situation. | | |
| | | | Staff Comments | The existing condition of the property is every changing and very unstable. The city has been monitoring the stream channel for undercutting, bank erosion, and debris jams during each flooding event and frequently must approve emergency stream stabilization permits to adjacent property owners. All proposed stream alteration work is intended to create a permanent and stable solution including the addition of woody debris, in-stream riffle, and riparian plantings. Post construction, the project area will be monitored to determine efficacy of the work and whether any post construction adjustments need to be made. If any permits are required for post construction adjustments, those applications will be filed to the appropriate entities for review and approval. | | |
| | | | 17.88.050(E)1 5 | (Stream Alteration) No increase to the one percent annual chance flood elevation at any location in the community, based on hydrologic and hydraulic analysis performed in accordance with standard engineering practice and has been certified and submitted with supporting calculations and a No Rise Certificate, by a registered Idaho engineer. | | |
| | | | <i>Staff</i> <i>Comments</i> | As noted above, extensive 2D and 1D hydraulic modeling was conducted to evaluate the project to ensure that the flood carrying capacity is maintained post construction. Post construction, the project modeling shows a no rise in the base flood elevations in the surrounding area. This demonstrates that the project will adequately convey floods of a 100-year event as well or better than the property has historically. The proposed development also has significantly more excavation (10,064 cubic yards) than fill (2,334 cubic yards) resulting in a net cut-fill balance of 7,730 cubic yards. Based on the submittal, there is no rise of the base flood elevations when comparing the proposed condition with the effective map for the area. However, there is a small rise documented within the project | | |

| | | | Floo | dplain Development Permit Requirements |
|-------------|--------|---------|---------------------------------|--|
| | | | on Standards: 17.8 | |
| | omplia | | | Standards and Staff Comments |
| Yes | No | N/ A | Guideline | City Standards and <i>Staff Comments</i> |
| | | | | site, that has no impact on off-site or downstream properties. Because of this condition, a No Rise Certificate is not achievable for the project. As such, per Ketchum Municipal Code, if a no rise certificate cannot be provided, a Conditional Letter of Map Revision (CLOMR) is required to document the changed condition on the property even though there is no rise documented outside the property. Condition of approval 1 addresses the requirement of a CLOMR from FEMA prior to start of construction and the subsequent Letter of Map Revision required after project completion. |
| \boxtimes | | | 17.88.050(E)1 6 | (Stream Alteration) The project has demonstrated no adverse impact or has demonstrated all impacts will be mitigated. |
| | | | Staff Comments | As noted above, the hydraulic modeling demonstrates there are no adverse impacts from the project to any of the surrounding areas or downstream. |
| | | | 17.88.050(E)1 7 | (Stream Alteration) The recreational use of the stream including access along any and all public pedestrian/fisher's easements and the aesthetic beauty shall not be obstructed or interfered with by the proposed work. |
| | | | <i>Staff Comments</i> | One of the stated objects of the project is to "Create a Preserve that is connected and accessible to all". The project proposes a series of improvements to winter and summer recreation opportunities and increases the amount of access opportunities to the stream than exist today. The aesthetic beauty of the area will be enhanced by the proposed improvements and will ensure long term stability of the area as a result of the project. |
| \boxtimes | | | 17.88.050(E)1 8 | (Stream Alteration) Fish habitat is maintained or improved as a result of the work proposed. |
| | | | <i>Staff</i> <i>Comments</i> | Currently, the fish habitat along the northern portions of the reach are poor as a result of steep banks, limited riparian vegetation, and lack of floodplain connectivity. The proposed restoration project will reconnect the floodplain and enhance riparian and floodplain vegetation which provides more areas for aquatic life to live and creates an environment where they can thrive. Fish habitats will be improved as a result of the restoration project. |
| | | | 17.88.050(E)1 9 | (Stream Alteration) The proposed work shall not be in conflict with the local public interest, including, but not limited to, property values, fish and wildlife habitat, aquatic life, recreation and access to public lands and waters, aesthetic beauty of the stream and water quality. |
| | | | Staff Comments | The Warm Springs Preserve Master Plan was jointly created by the City of Ketchum and the community. The primary objectives of the plan are to: |

| | Floodplain Development Permit Requirements | | | | | |
|-----|--|----|---|--|--|--|
| - | 1. Evaluation Standards: 17.88.050€ | | | | | |
| | Compliant | | | Standards and Staff Comments | | |
| Yes | No | N/ | Guideline | City Standards and <i>Staff Comments</i> | | |
| | | A | | Create a Preserve that is connected and accessible to all Design for success over time Support all-season multi-functional use Demonstrate leadership through regeneration of healthy ecosystems for people, plants, and animals Restore the creek and floodplain Celebrate and educate about the past, present, and future of the preserve As these are the primary objectives of the project, and the plan has been adopted by the Ketchum City Council, the project is clearly within the public interest. As noted in the analysis above, the project results in an improvement to fish and wildlife habitat, aquatic life, recreation opportunities and river access, and aesthetic beauty. | | |
| | | | 17.88.050(E)2 0 <i>Staff</i> <i>Comments</i> | (Stream Alteration) The work proposed is for the protection of the public health, safety and/or welfare such as public schools, sewage treatment plant, water and sewer distribution lines and bridges providing particularly limited or sole access to areas of habitation. The existing condition of the property and stream create a high-risk environment during flood events, risking public safety and damage to properties. The channelization of Warm Springs Creek and adjacent development have made it difficult for water to move at reasonable velocities throughout the area. The proposed project includes re- grading to create additional side channels and removes historically places fill to recreate a functioning river and floodplain that reduces the danger to the public and property. Additionally, the project proposes to address existing exposure issues related to water/sewer mains and bridges. Finally, the study conducted by the applicant and reviewed by third party engineers seeks to ensure the long-term stability of the construction. Condition of Approval 3 requires an additional scour analysis be conducted for the materials proposed within the stream near the bridge to ensure that the materials can withstand higher flows during more significant flood events. | | |
| | | | 17.88.050(E)2 1 <i>Staff</i> <i>Comments</i> | (Wetlands) Where development is proposed that impacts any wetland the first priority shall be to move development from the wetland area. Mitigation strategies shall be proposed at time of application that replace the impacted wetland area with an equal amount and quality of new wetland area or riparian habitat improvement. Due to the size and scope of this restoration project, impact to wetlands is unavoidable as most of the identified wetlands are within the Warm Springs Creek active river channel. There are some | | |

| | Floodplain Development Permit Requirements | | | | | |
|-----|--|---|------------------------------|--|--|--|
| 1 | 1. Evaluation Standards: 17.88.050€ | | | | | |
| Co | Compliant | | Standards and Staff Comments | | | |
| Yes | Yes No N/ Guidel | | Guideline | City Standards and Staff Comments | | |
| | | Α | | | | |
| | | | | vegetative wetlands that were identified, however, the propose project largely avoids those areas. Where impacts were unavoidable, a minimum 1:1 mitigation ratio was applied. Upon completion of the project, the site will have a net gain in quality and quantity of wetland areas. | | |
| | | | | | | |