



LAWRENCEVILLE

GEORGIA

STORMWATER AUTHORITY AGENDA

Wednesday, August 19, 2026
6:00 PM

Third Floor GwMA Conference Room
70 S. Clayton St, GA 30046

Call to Order

Approval of Prior Meeting Minutes

1. May 20, 2026 – Stormwater Authority Meeting

Review of Current Projects

2. Stormwater Program Updates
3. Sandalwood Community Improvements Project Update

Review of Proposed New Projects

Comments from Utility Board Staff

Final Adjournment



LAWRENCEVILLE

GEORGIA

AGENDA REPORT

MEETING: STORMWATER AUTHORITY, AUGUST 19, 2026

AGENDA CATEGORY: REVIEW OF CURRENT PROJECTS

Item:	Stormwater Program Updates
Department:	Engineering
Date of Meeting:	Wednesday, August 19, 2026
Fiscal Impact:	\$0
Presented By:	Madison Smith, Stormwater Coordinator
Action Requested:	None

Summary: Stormwater Management Program updates to include Annual Report submission, 2NForm migration update, maintenance task assistance, stormwater utility assistance, and impaired waters plan.



LAWRENCEVILLE

GEORGIA

AGENDA REPORT

MEETING: STORMWATER AUTHORITY, AUGUST 19, 2026

AGENDA CATEGORY: REVIEW OF CURRENT PROJECTS

Item:	Sandalwood Community Improvements Project Update
Department:	Engineering
Date of Meeting:	Wednesday, August 19, 2026
Fiscal Impact:	\$0
Presented By:	Eranildo Lustosa Alves Junior, City Engineer
Action Requested:	None

Summary: The Sandalwood Community Improvement Project includes lake dredging, dam reconstruction, storm pipe replacement, water main replacement, curb and gutter reconstruction, milling and resurfacing of affected roadways, site improvements such as a turn lane, and associated site restoration.

Background:

Contractor: North Georgia Concrete, Inc.

Contract amount \$8,919,501.00 (County \$1,892,159.00 & City \$7,027,342.00)

Timeline: 450 Calendar Days

Summary Progress:

Construction began on 1/5/2026. By 8/10/2026, the contractor completed phase 1 site erosion control, water main replacement and service line connections, fire hydrant installation, lake drainage, temporary bypass pipe installation at the dam, cofferdam installation, and demolition of the existing dam. The contractor is currently dredging the lake and continuing spillway construction. Turn lane construction on New Hope Road has started, with grading and stormwater utility already finished.

Proposed Schedule (submitted as 7/1/2026):

Part 1: Site Development Plans

- New Hope Road Turn Lane: 5/29/2026 – 8/14/2026 (Under progress)
- Amenity area and dumpster enclosure: 10/1/2026 – 1/27/2027
- New mailbox/kiosk area: 10/20/2026 – 3/2/2027
- Paving: 11/16/2026 – 1/21/2027

Part 2: Lake Dredging

- Lake dredging: 5/11/2026 – 9/7/2026 (Under progress)

Part 3: Dam Rehabilitation and Pedestrian Bridge

- Lake drain & bypass pipes: 1/12/2026 – 4/1/2026 (Completed)
- Spillway construction: 4/2/2026 – 10/22/2026 (Under progress)
- Pedestrian bridge: 10/14/2026 – 10/22/2026
- Lake maintenance (refill): 10/23/2026 – 12/4/2026

Part 4: Water Main Replacement

- Install 8" water line: 1/5/2026 – 4/6/2026 (Completed)
- Service tie-ins: 4/14/2026 – 6/2/2026 (Completed)