

# PLANNING & ZONING COMMISSION

## MEETING AGENDA

NOVEMBER 13, 2023, 7:00 PM



PLANNING & ZONING COMMISSION REGULAR MEETING

HISTORIC CHURCH BUILDING - 403 N 7TH STREET, SANGER, TEXAS

### CALL THE REGULAR MEETING TO ORDER AND ESTABLISH A QUORUM

### INVOCATION AND PLEDGE

### CITIZENS COMMENTS

*This is an opportunity for citizens to address the Commission on any matter. Comments related to public hearings will be heard when the specific hearing begins. Citizens are allowed 3 minutes to speak. Each speaker must complete the Speaker's Form and include the topic(s) to be presented. Citizens who wish to address the Commission with regard to matters on the agenda will be received at the time the item is considered. The Commission is not allowed to converse, deliberate or take action on any matter presented during citizen input.*

### CONSENT AGENDA

*All items on the Consent Agenda will be acted upon by one vote without being discussed separately unless requested by a Commissioner to remove the item(s) for additional discussion. Any items removed from the Consent Agenda will be taken up for individual consideration.*

1. Consideration and possible action of the minutes from October 9, 2023, meeting.

### PUBLIC HEARING ITEMS

2. Conduct a public hearing on an amendment to Ordinance No. 04-11-22 to amend the planned development language and add 21.17 acres of land described as A0029A R BEEBE, 65B, within the City of Sanger, and generally located south of FM 455 and east of Indian Lane.

### ACTION ITEMS

3. Consideration and possible action on an amendment to Ordinance No. 04-11-22 to amend the planned development language and add 21.17 acres of land described as A0029A R BEEBE, 65B, within the City of Sanger, and generally located south of FM 455 and east of Indian Lane.

## **FUTURE AGENDA ITEMS**

*The purpose of this item is to allow the Chairman and Commissioners to bring forward items they wish to discuss at a future meeting, A Commissioner may inquire about a subject for which notice has not been given. A statement of specific factual information or the recitation of existing policy may be given. Any deliberation shall be limited to a proposal to place the subject on an agenda for a subsequent meeting. Items may be placed on a future meeting agenda with a consensus of the Commission or at the call of the Chairman.*

## **ADJOURN**

**NOTE:** The Commission reserves the right to adjourn into Executive Session as authorized by Texas Government Code, Section 551.001, et seq. (The Texas Open Meetings Act) on any item on its open meeting agenda in accordance with the Texas Open Meetings Act, including, without limitation Sections 551.071-551.087 of the Texas Open Meetings Act.

## **CERTIFICATION**

I certify that a copy of this meeting notice was posted on the bulletin board at City Hall is readily accessible to the general public at all times and posted on the City of Sanger website on November 10, 2023, at 8:00 AM.

Stefani Dodson

Stefani Dodson, Secretary

The Historical Church is wheelchair accessible. Request for additional accommodations or sign interpretation or other special assistance for disabled attendees must be requested 48 hours prior to the meeting by contacting the City Secretary's Office at 940.458.7930.



# PLANNING & ZONING COMMISSION COMMUNICATION

**DATE:** November 13, 2023  
**FROM:** Stefani Dodson, Secretary  
**AGENDA ITEM:** Consideration and possible action of the minutes from October 9, 2023, meeting.

**SUMMARY:**  
N/A

**FISCAL INFORMATION:**  
Budgeted: N/A                      Amount: N/A                      GL Account: N/A

**RECOMMENDED MOTION OR ACTION:**  
N/A

**ATTACHMENTS:**  
Minutes from October 9, 2023

# PLANNING & ZONING COMMISSION

## MEETING MINUTES

OCTOBER 09, 2023, 7:00 PM



**PLANNING & ZONING COMMISSION REGULAR MEETING**

**HISTORIC CHURCH BUILDING - 403 N 7TH STREET, SANGER, TEXAS**

### **CALL THE REGULAR MEETING TO ORDER AND ESTABLISH A QUORUM**

There being a quorum Commissioner Miller called the Planning and Zoning meeting to order at 7:00 P.M.

### **BOARD MEMBERS PRESENT**

Commissioner, Place 1	Shane Stone
Commissioner, Place 2	Sally Amendola
Commissioner, Place 3	Jackie Turner
Commissioner, Place 4	Allen McAlister
Commissioner, Place 5	Jacob Gastelum
Commissioner, Place 6	Jason Miller

### **BOARD MEMBERS ABSENT:**

Commissioner, Place 7	Lisa Freeman
-----------------------	--------------

### **STAFF MEMBERS PRESENT:**

Director of Development Services Ramie Hammonds, and Secretary Stefani Dodson

### **CITIZENS COMMENTS**

No citizens came forward.

### **CONSENT AGENDA**

1. Consideration and possible action of the minutes from August 14, 2023, meeting.
2. Consideration and possible action of the minutes from September 11, 2023, meeting.

Commissioner Miller makes a motion to approve the consent agenda  
Commissioner Gastelum seconded the motion.

Voting Yea: Commissioner Amendola, Commissioner Stone, Commissioner McAlister,  
Commissioner Turner. The motion passes unanimously.

**ACTION ITEMS**

- 3. Consideration and possible action on a Minor Plat of Lot 1, Block A, of Lotus Addition, being 0.91 acres, located in the City of Sanger, and generally located on the west side of I-35 Frontage Road approximately 190 feet south of the intersection of Bolivar Street and I-35 Frontage Road.

Director Hammonds goes over the project and explains the applicant is proposing to create 1 commercial lot. Currently, there is one main building and one accessory building located on the site. The applicant wants to use the property for a car sales lot.

Commissioner McAlister makes a motion to approve with the condition all comments are met by City Council. Commissioner Gastelum seconded the motion.

Voting Yea: Commissioner Turner, Commissioner Miller, Commissioner Amendola,  
Commissioner Stone. The motion passes unanimously.

- 4. Consideration and possible action on electing officers for the Planning and Zoning Board.

Commissioner Miller nominated Commissioner Stone for Vice Chairman.  
Commissioner Stone nominated Commissioner Miller for Chairman.  
Commissioner McAlister seconded both nominations.

Voting Yea: Commissioner Gastelum, Commissioner Turner, Commissioner Amendola.  
The motion passes unanimously.

**FUTURE AGENDA ITEMS**

No items were discussed.

**INFORMATIONAL ITEMS**

No items were discussed.

**ADJOURN**

There being no further items Commissioner Miller adjourns the meeting at 7:21 P.M.



## PLANNING & ZONING COMMISSION COMMUNICATION

**DATE:** November 13, 2023

**FROM:** Ramie Hammonds, Development Services Director

**AGENDA ITEM:** Conduct a public hearing on an amendment to Ordinance No. 04-11-22 to amend the planned development language and add 21.17 acres of land described as A0029A R BEEBE, 65B, within the City of Sanger, and generally located south of FM 455 and east of Indian Lane.

### **SUMMARY:**

- The applicant has acquired additional acreage adjacent to PD 04-11-22
- The applicant is proposing to rezone the additional acreage of approximately 21.17 acres from Agricultural (A) to Planned Development (PD).
- The applicant has amended some of the language and requirements in PD 04-11-22. Below are the changes the applicant is proposing:
  - Increased acreage by 21.17 acres
  - Added language to Community Features to allow metal or wood as materials for entry monuments, screening walls, and community signage. Originally was only brick or stone.
  - Decreased the Garden lot depth from 120 square feet to 110 square feet and the overall size of the lot from 4800 square feet to 4400 square feet.
  - Decreased the depth of the cul-de-sac lots from the original 120 square feet to 95 square feet. The minimum lot square footage still applies.
  - Added language to the single-family rear setback for **all front entry lots** to be 20 feet. No setback was referenced for anything other than the front entry lots. Originally was a standard 20 feet for rear setback.
  - In single-family attached added section for **Driveway/Garage location stating all residential dwellings shall be either front entry from a public street or rear entry from an alleyway.**
  - Added language to single-family attached front yard setback **for all lots facing a street shall be 20 feet, all others are 10 feet.** Originally all front yard building setbacks were 20 feet.
  - In single-family attached reduced side yard setback from 7.5 feet to 5 feet on each side of the attached dwelling and reduced the side yard setback adjacent a street or corner lot from 20 feet to 10 feet.
  - Added language in single-family attached **for end dwelling units that abut a common area lot rather than an alley or street right-of-way, the minimum side yard setback adjacent the common area lot shall be 5 feet.** Was originally 7.5 feet.
  - In single-family attached added language **all front entry lots shall be 10 feet from the rear façade of the residence (excluding porches and projecting architectural features) to the rear lot line. All rear entry lots shall have a 20-foot setback from the garage to the alley right-of-way. Porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the rear yard a maximum of five feet.**

- Amended language to single-family attached parking, two off-street parking will be provided per unit **within the required garage. Guest parking will be provided within the site at a ratio of 1 space per 4 units.** Originally was two off-street parking spaces shall be provided per unit and shall not be within the required front yard.
- Parkland was reduced from 59.7 acres to 38.50 acres and open space increased from 83.783 acres to 86.69 acres.
- Reduced multi-family from 18.5 acres to 12 acres.
- The added acreage will increase Garden lots (40' x 110') from 158 to 299, Manor Lots (50' x 120') from 541 to 603, and Estate Lots (60' x 120') from 46 to 54. This increases the total lot count from 875 to 1086. Townhome remained the same at 130 lots.
- Multi-family is not called out as a separate district on the concept plan and is included in the Business District. Originally was called out as a separate district with location indicated on concept plan.
- The trail system increased from 2.56 miles to 3.02 miles.
- Roadway reconfiguration on concept plan.
- Staff mailed out 65 public hearing notices to owners of properties within 200 feet of the subject property and received no response at the time of this report.

**FISCAL INFORMATION:**

Budgeted: N/A

Amount: N/A

GL Account: N/A

**RECOMMENDED MOTION OR ACTION:**


N/A

**ATTACHMENTS:**



Location Map


# Denton CAD Web Map

Item 2.



10/26/2023, 2:38:11 PM

-  Parcels
-  Roads







## PLANNING & ZONING COMMISSION COMMUNICATION

**DATE:** November 13, 2023

**FROM:** Ramie Hammonds, Development Services Director

**AGENDA ITEM:** Consideration and possible action on an amendment to Ordinance No. 04-11-22 to amend the planned development language and add 21.17 acres of land described as A0029A R BEEBE, 65B, within the City of Sanger, and generally located south of FM 455 and east of Indian Lane.

### **SUMMARY:**

- The applicant has acquired additional acreage adjacent to PD 04-11-22
- The applicant is proposing to rezone the additional acreage of approximately 21.17 acres from Agricultural (A) to Planned Development (PD).
- The applicant has amended some of the language and requirements in PD 04-11-22. Below are the changes the applicant is proposing:
  - Increased acreage by 21.17 acres
  - Added language to Community Features to allow metal or wood as materials for entry monuments, screening walls, and community signage. Originally was only brick or stone.
  - Decreased the Garden lot depth from 120 square feet to 110 square feet and the overall size of the lot from 4800 square feet to 4400 square feet.
  - Decreased the depth of the cul-de-sac lots from the original 120 square feet to 95 square feet. The minimum lot square footage still applies.
  - Added language to the single-family rear setback for **"all front entry lots"** to be 20 feet. No setback was referenced for anything other than the front entry lots. Originally was a standard 20 feet for rear setback.
  - In single-family attached added section for **"Driveway/Garage location stating all residential dwellings shall be either front entry from a public street or rear entry from an alleyway"**.
  - Added language to single-family attached front yard setback **"for all lots facing a street shall be 20 feet, all others are 10 feet"**. Originally all front yard building setbacks were 20 feet.
  - In single-family attached reduced side yard setback from 7.5 feet to 5 feet on each side of the attached dwelling and reduced the side yard setback adjacent a street or corner lot from 20 feet to 10 feet.
  - Added language in single-family attached **"for end dwelling units that abut a common area lot rather than an alley or street right-of-way, the minimum side yard setback adjacent the common area lot shall be 5 feet"**. Was originally 7.5 feet.
  - In single-family attached added language **"all front entry lots shall be 10 feet from the rear façade of the residence (excluding porches and projecting architectural features) to the rear lot line. All rear entry lots shall have a 20-foot setback from the garage to the alley right-of-way. Porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the rear yard a maximum of five feet"**.

- Amended language to single-family attached parking, two off-street parking will be provided per unit **“within the required garage. Guest parking will be provided within the site at a ratio of 1 space per 4 units”**. Originally was “two off-street parking spaces shall be provided per unit and shall not be within the required front yard”.
  - Parkland was reduced from 59.7 acres to 38.50 acres and open space increased from 83.783 acres to 86.69 acres.
  - Reduced multi-family from 18.5 acres to 12 acres.
- The added acreage will increase Garden lots (40’ x110’) from 158 to 299, Manor Lots (50’ x 120’) from 541 to 603, and Estate Lots (60’ x 120’) from 46 to 54. This increases the total lot count from 875 to 1086. Townhome remained the same at 130 lots.
  - Multi-family is not called out as a separate district on the concept plan and is included in the Business District. Originally was called out as a separate district with location indicated on concept plan.
  - The trail system increased from 2.56 miles to 3.02 miles.
  - Roadway reconfiguration on concept plan.
  - Staff mailed out 65 public hearing notices to owners of properties within 200 feet of the subject property and received no response at the time of this report.

**FISCAL INFORMATION:**

Budgeted: N/A                      Amount: N/A                      GL Account: N/A

**RECOMMENDED MOTION OR ACTION:**


Staff recommends DENIAL.

**ATTACHMENTS:**

- Location Map
- Revised PD
- Legal Description
- Lane Ranch Concept Map
- Lane Ranch Park Plan
- Application
- Letter of Intent
- PD Markup
- Original Approved PD
- Review Comments


# Denton CAD Web Map

Item 3.



10/26/2023, 2:38:11 PM

-  Parcels
-  Roads



Denton County Appraisal District, Harris Govern -- [www.harrisgovern.com](http://www.harrisgovern.com)  
This product is for informational purposes only and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries.

## **347.329 ACRE LANE RANCH PD SUMMARY**

Purpose Statement - To amend PD 04-11-22 and establish a quality master planned multi-phase and multiple product residential and commercial community for the property described by metes and bounds on Exhibit "A" (the "Property") of this PD Ordinance. Development and use of the Property shall comply with the Sanger Zoning Ordinance as it existed on the date of its adoption on August 3, 1987 and subsequent amended (the "The Zoning Ordinance") and this PD ordinance. In the event of a conflict between the Zoning Ordinance and this PD Ordinance, this PD ordinance shall control.

### **PROPOSED USES**

#### Single Family (210.499 Acres)

Approximately 190.299 acres are proposed as single-family detached uses and 20.20 acres as single family attached (townhome).

#### Business District (50.14 Acres)

Approximately 50.14 acres are proposed as local business and retail. Within this area we also anticipate approximately 8 acres of assisted living along with 12 acres of multi-family.

### **COMMUNITY FEATURES**

The hardscape within the community shall include entry monuments, screening walls and community signage constructed of brick, stone, metal or wood. Signs shall not be within the sight visibility triangles.

A mandatory homeowners association shall be established to own and maintain the private open spaces, common areas and greenbelts; all private landscape improvements; dog parks and dog waste stations, perimeter masonry and tubular steel fencing; entry monuments and signage. The homeowner's association shall maintain on street parking spaces within a street right-of-way and any parking spaces located within a common area lot. Private trails and sidewalks shall be constructed within a pedestrian access easement and owned and maintained by the HOA.

The 100-year floodplain shall be designated as a public drainage easement within the Public Parkland dedication. Maintenance responsibility shall be identified on the plat using the City of Sanger Standard drainage easement inscription.

**RESIDENTIAL LAND USES**

**I. Lot Sizes, Setbacks, etc. for Single Family Detached.** Except as otherwise provided below, detached single family residences shall comply with Section 53, “R-1” RESIDENTIAL DISTRICT -1 of the Zoning Ordinance, subject to the following changes:

A. Minimum Lot Width, Depth, and Size.

The Estate Lots:

The minimum lot width shall be 60 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 7,200 square feet.

The Manor Lots:

The minimum lot width shall be 50 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 6,000 square feet.

The Garden Lots:

The minimum lot width shall be 40 feet. The minimum lot depth shall be 110 feet. The minimum lot size shall be 4,400 square feet.

B. Lot Depths for Cul-de-Sac and Eyebrow Lots.

The minimum lot depth for all lots within any proposed residential use along a cul-de-sac or eyebrow may have a reduced lot depth of 95 feet. The lot minimum square footage still applies.

C. Minimum House Size.

The Estate Lots:

The minimum air-conditioned area within each residence shall be 2,250 square feet.

The Manor Lots:

The minimum air-conditioned area within each residence shall be 1,800 square feet. Over the entire development, the Manor Lots shall average over 2,000 square feet in house size. The Manor Lots shall place a limit of 15% of the total lot count to be below 2,000 square feet.

The Garden Lots:

The minimum air-conditioned area within each residence shall be 1,500 square feet. Over the entire development, the Garden Lots shall average over 1,650 square feet in house size. The Garden Lots shall place a limit of 15% of the total lot count to be below 1,650 square feet.

D. Maximum Height.

The maximum building height shall be 2 stories or 35 feet.

E. Front Yard Setback.

The minimum front yard building setback for all lots facing a street shall be 25 feet. Front porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the front yard a maximum of five feet.

F. Side Yard Setback.

The minimum side yard building setback shall be five feet (5') on each side. A side yard adjacent to a street on a corner lot shall always have a minimum ten-foot (10') side yard building setback.

G. Rear Yard Setback.

The minimum rear yard building setback for all front entry lots shall be 20 feet from the rear facade of the residence (excluding porches and projecting architectural features) to the rear lot line. Porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the rear yard a maximum of five feet (5').

H. Maximum Lot Coverage.

The maximum lot coverage will be 65% for any residential lot.

I. Garages.

An enclosed parking area of at least four hundred square feet shall be provided for a garage (this does not count towards the minimum house size). The face of a garage door must be located at least 20 feet from the street right-of-way line that the garage door faces. The garage door does not have to be behind the street facing façade of the house. Split garage doors with a separate door for each vehicle bay are not required.

J. Design Elements

All residential dwellings will meet the City of Sanger Exterior Façade Design Criteria Manual as adopted on October 7, 2019.

**II. Lot Sizes, Setbacks, etc. for Single Family Attached.** Except as otherwise provided below, attached single family residences shall comply with Section 57, "TH" TOWNHOME RESIDENTIAL DISTRICT of the Zoning Ordinance, subject to the following changes:

A. Minimum Lot Width, Depth, and Size.

The minimum lot width shall be 22 feet. The minimum lot depth shall be 90 feet. The minimum lot size shall be 1,980 square feet.

B. Minimum House Size.

The minimum air-conditioned area within each residence shall be 1,300 square feet.

C. Maximum Height.

The maximum building height shall be 2 stories or 40 feet.

D. Driveway/Garage Locations.

All residential dwellings shall be either front entry from a public street, or rear entry from an alleyway.

E. Front Yard Setback.

The minimum front yard building setback for all lots facing a street shall be 20 feet, all others are 10 feet. Front porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the front yard a maximum of five feet.

F. Side Yard Setback.

The minimum side yard building setback shall be five feet (5') on each side. A side yard adjacent to a street on a corner lot shall always have a minimum ten-foot (10') side yard building setback. For end dwelling units that abut a common area lot rather than an alley or street right of way, the minimum side yard setback adjacent to the common area lot shall be 5 feet.

G. Rear Yard Setback.

The minimum rear yard building setback for all front entry lots shall be 10 feet from the rear facade of the residence (excluding porches and projecting architectural features) to the rear lot line. All rear entry lots shall have a 20-foot setback from the garage to the alley right-of-way. Porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the rear yard a maximum of five feet (5').

H. Maximum Lot Coverage.

The maximum lot coverage shall not apply to any townhomes.

I. Parking.

Two off-street parking spaces shall be provided per unit within the required garage. Guest parking will be provided within the site at a ratio of 1 space per 4 units.

J. Design Elements

All residential dwellings will meet the City of Sanger Exterior Façade Design Criteria Manual as adopted on October 7, 2019.

**III. Lot Sizes, Setbacks, etc. for Multi-Family.** Multi-Family residences shall comply with Section 19, “MF-2” MULTI-FAMILY RESIDENTIAL DISTRICT – 2 of the Zoning Ordinance.

**IV. General Conditions.**

- A. For the purposes of determining compliance with the lot width requirements, lot widths shall be measured at the rear of the required front yard setback as shown on the Final Plats.
- B. Sidewalks may be located outside of the public right-of-way if located within an adjacent open space lot with a pedestrian access easement to provide for meandering sidewalks and trails that may be located within adjacent common area lots or to preserve existing trees along perimeter roads.

**V. Residential Single Family Detached Landscape Requirements.** Except as otherwise provided below, landscape requirements shall comply with Section 48, Landscape Regulations of the Zoning Ordinance, subject to the following changes:

The following requirements apply to single family residential development:

- A. Each single-family residence shall have an irrigation system in the front yard and street corner side yard with a freeze sensor regulator shut off.
- B. Each Home lot shall have a minimum of two shade trees that are at least three inches in caliper planted. The trees shall be planted in the front and rear yard. If the lot fronts or sides onto a common area lot, the front yard requirement may be satisfied with the trees located in the adjacent greenspace. No other front yard or side yard tree planting requirement shall apply.
- C. All required trees shall be selected from a tree list approved during the Home Permitting stage.
- D. Each Home lot shall have a minimum of twelve (12) shrubs placed in the front yard. Individual shrubs shall be a minimum of three (3) gallons in size when planted.

**VI. Multifamily, Townhome and Non-residential Uses Landscape Requirements.**



All landscape requirements shall comply with Sections 48.4 and 48.5, Landscape Regulations of the Zoning Ordinance.

## **VII. Parkland/Open Space (86.69 Acres)**

- A. The developer, and its assigns, agree to dedicate approximately 38.50 acres of the total 86.69 acres of open space/floodplain as Public Park property (the “Parkland”) to the City of Sanger. Common areas shall include floodplain, ponds, detention areas, and small open spaces as shown on the Preliminary Park Concept Plan. Small Open Spaces shall be connected with sidewalks to be a comprehensive pedestrian system. Common areas will abut a public street right-of-way in at least one location with a sidewalk connection. The Parkland shall be credited toward the Park Land Dedication requirement.
- B. A pedestrian circulation system shall be provided that affords connectivity to the entire community and the perimeter of the Property. The pedestrian circulation system shall include concrete trails that are a minimum of six feet in width. Trails in greenbelts will be constructed of concrete and shall connect with the project sidewalks. The pedestrian circulation system may be located on private property with a pedestrian access easement or within the right-of-way. The pedestrian circulation system shall include such items as benches, landscaping, signage, lighting, bike racks, water fountains, trash cans, and doggie waste stations. These items are represented on the Preliminary Park Concept Plan.
- C. All interior residential street rights-of-way shall be improved with sidewalks that are a minimum of four feet in width and (1) constructed by the homebuilders at the time of adjacent house construction; or (2) constructed by the developer for all non-buildable lots. All sidewalks along Collector and Arterial Road frontages are to be five feet in width. The pedestrian circulation system will replace the required public sidewalk along Lane Ranch Drive as shown on the Preliminary Park Concept Plan.
- D. The developer, and its assigns, agree to also install additional amenities such as an off-street parking lot, dog park, covered picnic area, playground equipment and fishing docks as shown on the Preliminary Park Concept Plan. The exact number and location of these amenities may change during the final design process. They are generally represented on the Preliminary Park Concept Plan.
- E. The phasing of the park improvements will coincide with the residential phasing plan and is noted on the overall Preliminary Park Concept Plan.

## **VIII. Fencing Requirements**

- A. The developer shall install a perimeter brick or stone screening wall along Major Collector Streets as shown on the Concept Plan. Floodplain, parks, open spaces, right-of- way shall be

exempt from the screening requirements in this Section; however, tubular steel fencing may be installed in these areas at the developer's option.

- B. Homebuilder side yard and back yard fencing on residential lots shall be a maximum of six feet in height and shall be setback a minimum of five feet from the front building line shown on the Detail Plan.
- C. Fencing on all residential lots abutting an open space lot or greenbelt shall be restricted to tubular steel painted black. No solid fencing other than a brick and/or stone masonry courtyard wall under 42 inches shall be permitted abutting an open space lot or greenbelt; however, landscape borders, including trimmed hedges, are permitted.

#### **IX. Street Typology**

- A. Standard curbs will be required adjacent to streets abutting all residential lot types unless otherwise approved by the City's engineering department.
- B. Streets fronting open space lots must have standard curbs adjacent to the common area lot. Streets adjacent to common area lots may provide for on-street parking. In addition, the street faces adjacent to open spaces near the flood plain will have a maintenance access location.
- C. Developer shall work with City to determine the location and number of stop signs within the subdivision and speed limits to facilitate traffic calming and maximum the benefit from the pedestrian system.

#### **X. Utilities and Equipment**

- A. Electrical and gas utility meters and AC condensers should be unobtrusively located beyond the front or side street facade zone and screened from view from adjacent streets or common open spaces with landscaping or appropriate fencing.
- B. Transformers on individual lots should be screened to minimize visual impact.
- C. Satellite dishes and solar panels should be located in less conspicuous locations and out of view from adjacent streets or common open spaces when possible.
- D. Antennas should be located inside the building when possible.
- E. Solar panels, when visible from the front, should be flush with the roof.

#### **XI. Refuse Locations**

- A. Refuse containers should be stored within an enclosed storage area, fenced, or walled to be screened from view from adjacent streets or common open spaces with landscaping can be added.

**XII. Home Variety**

- A. Detached home designs with the same or similar facade, materials, or colors should be separated by a minimum of three lots on the same side of the street and should not be located directly across or diagonally across the street from each other.
  
- B. If a detached home plan is repeated on an adjacent lot, it should be elevated with a different architectural style or two of the following three elevation changes - brick color, roof color, or flipped plan.

**BUSINESS DISTRICT USES**

Except as otherwise provided below, commercial uses shall comply with Section 23, “B-2” Business District - 2 of the Zoning Ordinance, subject to the following changes:

1. A 12-acre multi-family site will be allowed. The base zoning for this tract will be “MF-2” Multi-Family Residential District - 2 at 20 units per gross acre.
2. Self-Storage facilities may be allowed by SUP approval.
3. Boat storage facilities may be allowed by SUP approval.
4. The building height for a pitched roof building shall be a maximum of 45 feet.
5. The front, rear, and side building setbacks adjacent to any internal street shall be a minimum of 15 feet.
6. Any mechanical equipment including roof top equipment shall be screened from residential districts either by fencing, landscaping, or rooftop screening as applicable.

## LEGAL DESCRIPTION

All that certain lot, tract, or parcel of land, being part of the Rueben Bebee Survey, Abstract No. 29, Denton County, Texas, and being all of that tract of land described in a deed to Hien & Duyet Nguyen recorded in Document No. 2016-27020 Real Property Records of Denton, County, Texas (RPRDCT) and all of that tract of land described in a deed to Dualbond Holdings, LLC recorded in Document No. 2016-27021 (RPRDCT) and all of that tract of land described in a deed to Sanger Town Center LLC recorded in Document No. 2017-48301 (RPRDCT) and a part of that tract of land described in a deed to Marion Hills Apartments, LLC recorded in Document No. 2017-48293 (RPRDCT), being more completely described as follows, to-wit:

BEGINNING at 1/2" iron rod set for the southeast corner of the Hien & Duyet Nguyen tract and the north right-of-way line of McReynolds Road;

THENCE with the north right-of-way line of McReynolds Road North 87°54'58" West a distance of 1,789.63 feet to a 1/2" iron rod set for the southwest corner of the Hien & Duyet Nguyen tract and the southeast corner of a tract of land described in a deed to Winston Grove Apartments, LLC recorded in Document No. 2018-13037 (RPRDCT);

THENCE North 2°23'22" East a distance of 2,526.23 feet to 1/2" iron rod set for the northeast corner of a tract of land described in a deed to Marion Hills Apartments, LLC recorded in Document No. 2017-92008 (RPRDCT);

THENCE North 88°13'32" West a distance of 1,325.35 feet to a 2" iron rod found for the northwest corner of the Marion Hills Apartments, LLC;

THENCE South 2°25'03" West a distance of 2,504.45 feet to a 1/2" iron rod set for the southwest corner of Lake Ridge Estates, Phase 1 an addition to the City of Sanger recorded in Cabinet V, Page 752 of the Plat Records of Denton County, Texas (PRDCT) and the north right-of-way line of McReynolds Road;

THENCE with the north right-of-way line of McReynolds Road North 87°25'44" West a distance of 612.45 feet to a 1/2" iron rod set for the southwest corner of the Sanger Town Center LLC tract and the east right-of-way line of Indian Lane right-of-way recorded in Document No. 2004-145888 (RPRDCT);

THENCE with the east right-of-way line of Indian Lane as follows:

North 2°15'10" East a distance of 1,935.36 feet to a 1/2" iron rod set for corner;

North 5°39'58" East a distance of 200.32 feet to a 1/2" iron rod set for corner;

North 2°02'56" East a distance of 24.96 feet to the beginning of a curve to the left, having a radius of 550.39 feet, a chord of North 16° 40' 37" West – 354.48 feet, a distance of 360.91 feet to a 1/2" iron rod set for corner in the east line of a tract of land described in a deed to Sanger ISD (herein called Tract 1) recorded in Volume 1841, Page 662 (RPRDCT);

THENCE South 88°03'30" East a distance of 21.92 feet to a 1/2" iron rod set for the southwest corner of a tract of land described in a deed to Sanger ISD recorded in Document No. 2022-160016 (RPRDCT);

THENCE with the south and east line of the Sanger ISD tract

North 56°02'48" East a distance of 62.25 feet to a 1/2" iron rod set for corner;

North 02°36'29" East a distance of 643.72 feet to a 1/2" iron rod set for corner;

North 45°05'54" East a distance of 148.05 feet to a 1/2" iron rod set for corner;

North 02°36'29" East a distance of 1013.28 feet to a 1/2" iron rod set for the northeast corner of a tract of land described in a deed to Sanger ISD recorded in Document No. 2022-160017 (RPRDCT);

THENCE with the north line of the Sanger ISD tract North  $87^{\circ}23'31''$  West a distance of 150.00 feet to a 1/2" iron rod set for corner in the east line of a tract of land described in a deed to Sanger ISD Tract 1;

THENCE with the east line of the Sanger ISD Tract 1 North  $2^{\circ}36'29''$  East a distance of 616.01 feet to a 1/2" iron rod set for the northeast corner of the Sanger ISD Tract 1 and the northwest corner of the Sanger Town Center LLC and the south right-of-way line of West Chapman Road;

THENCE with the south right-of-way line of West Chapman Road and the north line of the Sanger Town Center LLC as follows:

South  $87^{\circ}53'26''$  East a distance of 1,269.90 feet to a 1/2" iron rod set for corner;

South  $88^{\circ}02'57''$  East a distance of 500.69 feet to a 1/2" iron rod set for corner;

South  $87^{\circ}47'23''$  East a distance of 2,068.95 feet to a 1/2" iron rod set for the northeast corner of the Dualbond Holdings, LLC Tract and the northwest corner of a tract of land described in a deed to Miller Family Trust recorded in Document No. 94-0089391 (RPRDCT);

THENCE with the west line of the Miller Family Trust tract South  $2^{\circ}58'32''$  West a distance of 1,272.08 feet to a 1/2" iron rod set for corner;

THENCE South  $2^{\circ}42'07''$  West a distance of 3,659.25 feet to the place of beginning, containing 347.329 acres, or 15,129,632 square feet of land.



**LEGEND**

[Red]	GENERAL BUSINESS AREAS
[Pink]	60' ESTATE LOTS
[Yellow]	50' MANOR LOTS
[Light Blue]	40' GARDEN LOTS
[Blue]	TOWN HOME LOTS
[Green]	GRASS / OPEN SPACE
[Dark Green]	LAKES
[Light Green]	LAKERIDGE PD

APPROX. RESIDENTIAL LOT COUNT BY TYPE

54 LOTS (ESTATE LOTS)
603 LOTS (MANOR LOTS)
299 LOTS (GARDEN LOTS)
130 LOTS (TOWN HOMES)
TOTAL 1086 LOTS

RESIDENTIAL AREA 210,499 AC.

- SINGLE FAMILY 190,299 AC.
- TOWN HOMES 20.20 AC.

GENERAL BUSINESS AREA 50.14 AC.

OPEN SPACE / FLOODPLAIN 86.69 AC.

PRELIMINARY - FOR REVIEW ONLY  
 These documents are for design review or permit purposes only and are not to be construed as a contract or binding agreement. F. E. MIDDLETON, JR., P.E. 67449


No.	DATE	REVISION	APPROX.
1	9-18-23		9-18-23

**Middleton PROJECT ENGINEER & Associates, LLC.**  
 CONSULTING CIVIL ENGINEERS & LAND PLANNERS  
 TYPE # - 10900  
 2785 ROCKBROOK DRIVE, SUITE 105  
 LEWISVILLE, TEXAS 75067 (972) 393-9800

**CONCEPT PLAN**

**LANE RANCH**  
**347.329 ACRES - CITY OF SANGER**  
**DENTON COUNTY TEXAS**

Drawing File: 0001032CONCEPT.DWG DATE: 9-18-23 SCALE: 1"=250' SHEET NO: 1  
 Project No. 0001032



WILLER FAMILY TRUST  
 DOC. NO. 94-0089291

50750' ENSERCH MEASURING STATION ESMT.  
 DOC. #94-R0019695

PROG. SCREENING WALL  
 OPEN SPACE  
 APPARENT 28" GAS ESMT. NO RECORDING INFO

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL

SCREENING WALL



**LEGEND**

- PARK BENCH/DOG WASTE STATION/TRASH CANS
- 6' HIKE & BIKE TRAIL
- PARK AREA/OPEN SPACE
- LAKES
- ☐ COVERED PICNIC AREA
- ⊙ PLAYGROUND
- ⊥ FISHING PIER
- ① PARK PHASE NUMBER
- PARK PHASE LINE
- ▭ PARKING AREA FOR PARKS

TOTAL OPEN SPACE - 86.69 AC.


PARKLAND DEDICATION REQUIREMENT

- SINGLE FAMILY (1 AC./50 D.U.) 21.70 AC.
- MULTI-FAMILY (1 AC./21 BEDROOMS) 16.80 AC.
- TOTAL 38.50 AC.

PARKLAND DEDICATION WILL BE ACCOMPLISHED BY DEDICATING OPEN SPACE AND USABLE FLOODPLAIN WITHIN THE 90.69 ACRES.

TOTAL LENGTH OF TRAIL SYSTEM=15,976 L.F. (3.02 MILES)

PRELIMINARY - FOR REVIEW ONLY  
 These documents are for design review and not intended for construction or permit purposes. The approval of F. E. MIDDLETON, JR. P.E. 67449




No.	DATE	REVISION	APPROV.
			9-18-23

**Middleton PROJECT ENGINEER:  
& Associates, LLC.**

CONSULTING CIVIL ENGINEERS & LAND PLANNERS  
 TBPE #10900 © Copyright 2023  
 2785 ROCKBROOK DRIVE, SUITE 105  
 LEWISVILLE, TEXAS 75067 (972) 393-9800

**PRELIMINARY PARK CONCEPT PLAN**

**LANE RANCH**  
 347.329 ACRES - CITY OF SANGER  
 DENTON COUNTY TEXAS



Drawing File: 0001032CONCEPT6-PARK	DATE: 9-18-23	SCALE: 1"=250'	SHEET NO: 1
Project No. 0001032			1



201 Bolivar Street/PO Box 1729 \* Sanger, TX 76266  
940-458-2059(office) www.sangertexas.org

### ZONING CHANGE/SUP APPLICATION

Zoning Change

Specific Use Permit

Applicant	Owner (if different from applicant)
Name: <b>Mr. Casey McGinnis</b>	Name: <b>See attached sheet</b>
Company: <b>JTWSCM Development LLC</b>	Company:
Address: <b>4029 Veneto Drive</b>	Address:
City, State, Zip: <b>Frisco, Texas 75033</b>	City, State, Zip
Phone: <b>214-232-6180</b>	Phone:
Fax: <b>N/A</b>	Fax:
Email: <b>mcginnisdevelopment@gmail.com</b>	Email:

#### Submittal Checklist

<input checked="" type="checkbox"/>	Site Plan (for Specific Use Permits Only)
<input checked="" type="checkbox"/>	Letter of Intent
<input checked="" type="checkbox"/>	Application Fee (Check Payable to City of Sanger)

I certify that I am the legal owner of the above referenced property and that to the best of my knowledge this is a true description of the property upon which I have requested the above checked action. I designate the applicant listed as my representative.

Describe the subject property (address, location, size, etc.):

347.329 acres located at the northeast corner of Indian Land and McReynolds Road (known as Lane Ranch)

Describe the proposed zoning change or Specific Use Permit (SUP):

Amending the original PD zoning Ordinance No. 4-11-22 to add the Marion Property Holding tract (21.17 acres)

See attached sheet for owner signatures

Owner Signature

Applicant Signature

Date

May 31, 2023  
Date

Office Use

Fee	
Date	

City of Sanger  
201 Bolivar / P.O. Box 1729  
Sanger, TX 76266  
940-458-2059 (office) www.sangertexas.org




LANE RANCH PD OWNERSHIPS (THIS INFORMATION WAS TAKEN FROM THE DENTON COUNTY APPRASIAL WEB SITE)

1)

NGUYEN, HIEN T & DUJET 151.67 ACRES  
3608 WAYNOKA DR,  
CARROLLTON, TX, 75007-2792  
PHONE: 469-900-7113  
EMAIL: [nguyenhelen15@gmail.com](mailto:nguyenhelen15@gmail.com)

A0029A R. BEEBE, TR 56B, 149.658 ACRES, OLD DCAD SHT 2, TR 3


A0029A R. BEEBE, TR 56A, 2.012 ACRES

SIGNATURE: 

2)

DUALBOND HOLDINGS LLC 51.17 ACRES  
MR. JONATHAN WANG  
101 FOREST BEND DR,  
COPPELL, TX, 75019-2040  
PHONE: 214-316-2256  
EMAIL: [wangjtc@verizon.net](mailto:wangjtc@verizon.net)

A0029A R. BEEBE, TR 56, 51.17 ACRES, OLD DCAD SHT 2, TR 3

SIGNATURE: 


3)

SANGER TOWN CENTER LLC 122.52 ACRES  
MR. JONATHAN WANG  
101 FOREST BEND DR,  
COPPELL, TX, 75019-2040  
PHONE: 214-316-2256  
EMAIL: [wangjtc@verizon.net](mailto:wangjtc@verizon.net)

A0029A R. BEEBE, TR 65(PT), 84.5014 ACRES, OLD DCAD SHT 2, TR 4

A0029A R. BEEBE, TR 60, 25.22 ACRES, OLD DCAD SHT 2, TR 7

A0029A R. BEEBE, TR 61, 12.8 ACRES, OLD DCAD SHT 2, TR 8

SIGNATURE: 

4)

MARION PROPERTY HOLDING LLC    21.1720 ACRES  
MR. JONATHAN WANG  
101 FOREST BEND DR,  
COPPELL, TX, 75019-2040  
PHONE: 214-316-2256  
EMAIL: [wangjtc@verizon.net](mailto:wangjtc@verizon.net)

A0029A R. BEEBE, TR 65B

SIGNATURE:  \_\_\_\_\_

## 347.329 ACRE LANE RANCH PD SUMMARY

Purpose Statement - To amend PD 04-11-22 and establish a quality master planned multi-phase and multiple product residential and commercial community for the property described by metes and bounds on Exhibit "A" (the "Property") of this PD Ordinance. Development and use of the Property shall comply with the Sanger Zoning Ordinance as it existed on the date of its adoption on August 3, 1987 and subsequent amended (the "The Zoning Ordinance") and this PD ordinance. In the event of a conflict between the Zoning Ordinance and this PD Ordinance, this PD ordinance shall control.

### PROPOSED USES

#### Single Family (268.101 Acres)

Approximately 180.98 acres are proposed as single family detached uses, 16.2 acres as single family attached (townhome) and 70.92 acres of open space. The net density is 3.79 units/acre.

#### Business District (83.935 Acres)

Approximately 42.93 acres are proposed as local business and retail, 5.0 acres of assisted living along with 19.15 acres of multi-family and 12.13 acres of open space.

### COMMUNITY FEATURES

The hardscape within the community shall include entry monuments, screening walls and community signage constructed of brick or stone. Signs shall not be within the sight visibility triangles.

A mandatory homeowners association shall be established to own and maintain the private open spaces, common areas and greenbelts; all private landscape improvements; dog parks and dog waste stations, perimeter masonry and tubular steel fencing; entry monuments and signage. The homeowner's association shall maintain on street parking spaces within a street right-of-way and any parking spaces located within a common area lot. Private trails and sidewalks shall be constructed within a pedestrian access easement and owned and maintained by the HOA.

The 100-year floodplain shall be designated as a public drainage easement within the Public Parkland dedication. Maintenance responsibility shall be identified on the plat using the City of Sanger Standard drainage easement inscription.

**RESIDENTIAL LAND USES**

**I. Lot Sizes, Setbacks, etc. for Single Family Detached.** Except as otherwise provided below, detached single family residences shall comply with Section 53, "R-1" RESIDENTIAL DISTRICT -1 of the Zoning Ordinance, subject to the following changes:

**A. Minimum Lot Width, Depth, and Size.**

The Estate Lots (60' X 120'):

The minimum lot width shall be 60 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 7,200 square feet.

The Manor Lots (50' X 120'):

The minimum lot width shall be 50 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 6,000 square feet.

The Garden Lots (40' X 120'):

The minimum lot width shall be 40 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 4,800 square feet.

**B. Minimum House Size.**

The Estate Lots:

The minimum air-conditioned area within each residence shall be 2,250 square feet.

The Manor Lots:

The minimum air-conditioned area within each residence shall be 1,800 square feet. Over the entire development, the Manor Lots shall average over 2,000 square feet in house size. The Manor Lots shall place a limit of 15% of the total lot count to be below 2,000 square feet.

The Garden Lots:

The minimum air-conditioned area within each residence shall be 1,500 square feet. Over the entire development, the Garden Lots shall average over 1,650 square feet in house size. The Garden Lots shall place a limit of 15% of the total lot count to be below 1,650 square feet.

**C. Maximum Height.**

The maximum building height shall be 2 stories or 35 feet.

D. Front Yard Setback.

The minimum front yard building setback shall be twenty-five feet (25'). Front porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the front yard a maximum of five feet (5').

E. Side Yard Setback.

The minimum side yard building setback shall be five feet (5') on each side. A side yard adjacent to a street on a corner lot shall always have a minimum ten-foot (10') side yard building setback.

F. Rear Yard Setback.

The minimum rear yard building setback shall be twenty feet (20') from the rear facade of the residence (excluding porches and projecting architectural features) to the rear lot line. Porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the rear yard a maximum of five feet (5').

G. Maximum Lot Coverage.

The maximum lot coverage will be 65% for any residential lot.

H. Garages.

An enclosed parking area of at least four hundred square feet shall be provided for a garage (this does not count towards the minimum house size). The face of a garage door must be located at least 20 feet from the street right-of-way line that the garage door faces. The garage door does not have to be behind the street facing façade of the house. Split garage doors with a separate door for each vehicle bay are not required.

I. Design Elements

All residential dwellings will meet the City of Sanger Exterior Façade Design Criteria Manual as adopted on October 7, 2019.

**II. Lot Sizes, Setbacks, etc. for Single Family Attached.** Except as otherwise provided below, attached single family residences shall comply with Section 57, "TH" TOWNHOME RESIDENTIAL DISTRICT of the Zoning Ordinance, subject to the following changes:

A. Minimum Lot Width, Depth, and Size.

The minimum lot width shall be 22 feet. The minimum lot depth shall be 90 feet. The minimum lot size shall be 1,980 square feet.

B. Minimum House Size.

The minimum air-conditioned area within each residence shall be 1,300 square feet.

C. Maximum Height.

The maximum building height shall be 2 stories or 35 feet.

D. Front Yard Setback.

The minimum front yard building setback shall be twenty-five feet (20'). Front porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the front yard a maximum of five feet (5').

E. Side Yard Setback.

The minimum side yard building setback at the end of each building shall be seven- and one-half feet (7.5') on each side creating a 15-foot separation between buildings. A side yard adjacent to a street on a corner lot shall always have a minimum twenty-foot (20') side yard building setback.

F. Rear Yard Setback.

The minimum rear yard setback shall be five feet from the rear facade of the residence to the alley right-of-way.

G. Maximum Lot Coverage.

The maximum lot coverage shall not apply to any townhomes.

H. Parking

Two off-street parking spaces shall be provided per unit and shall not be within the required front yard.

I. Design Elements

All residential dwellings will meet the City of Sanger Exterior Façade Design Criteria Manual as adopted on October 7, 2019.

**III. Lot Sizes, Setbacks, etc. for Multi-Family.** Multi-Family residences shall comply with Section 19, "MF-2" MULTI-FAMILY RESIDENTIAL DISTRICT – 2 of the Zoning Ordinance.

**IV. General Conditions.**

- A. For the purposes of determining compliance with the lot width requirements, lot widths shall be measured at the rear of the required front yard setback as shown on the Final Plats.
- B. Sidewalks may be located outside of the public right-of-way if located within an adjacent open space lot with a pedestrian access easement to provide for meandering sidewalks and trails that may be located within adjacent common area lots or to preserve existing trees along perimeter roads.

**V. Residential Single Family Detached Landscape Requirements.** Except as otherwise provided below, landscape requirements shall comply with Section 48, Landscape Regulations of the Zoning Ordinance, subject to the following changes:

The following requirements apply to single family residential development:

- A. Each single-family residence shall have an irrigation system in the front yard and street corner side yard with a freeze sensor regulator shut off.
- B. Each Home lot shall have a minimum of two shade trees that are at least three inches in caliper planted. The trees shall be planted in the front and rear yard. If the lot fronts or sides onto a common area lot, the front yard requirement may be satisfied with the trees located in the adjacent greenspace. No other front yard or side yard tree planting requirement shall apply.
- C. All required trees shall be selected from a tree list approved during the Detail Plan stage.
- D. Each Home lot shall have a minimum of twelve (12) shrubs placed in the front yard. Individual shrubs shall be a minimum of three (3) gallons in size when planted.

**VI. Multifamily, Townhome and Non-residential Uses Landscape Requirements.**

All landscape requirements shall comply with Sections 48.4 and 48.5, Landscape Regulations of the Zoning Ordinance.

**VII. Parkland/Open Space (83.054 Acres)**

- A. Developer, and its assigns, agree to dedicate approximately 59.7 acres of the total 83.054 acres of floodplain/open space as Public Park property (the "Parkland") to the City of Sanger. Common areas shall include floodplain, ponds, detention areas, and small open spaces as shown on the Preliminary Park Concept Plan. Small Open Spaces shall be connected with sidewalks to be a comprehensive pedestrian system. Common areas will abut a public street right-of-way in at least one location with a sidewalk connection. The Parkland shall be credited toward the Park Land Dedication requirement.
- B. A pedestrian circulation system shall be provided that affords connectivity to the entire community and the perimeter of the Property. The pedestrian circulation system shall include concrete trails that are a minimum of six feet in width. Trails in greenbelts will be constructed of concrete and shall connect with the project sidewalks. The pedestrian circulation system may be located on private property with a pedestrian access easement or within the right-of-way. The pedestrian circulation system shall include such items as benches, landscaping, signage, lighting, bike racks, water fountains, trash cans, and doggie waste stations. These items are represented on the Park Plan.

- C. All interior residential street rights-of-way shall be improved with sidewalks that are a minimum of four feet in width and (1) constructed by the homebuilders at the time of adjacent house construction; or (2) constructed by the developer for all non-buildable lots. All sidewalks along Collector and Arterial Road frontages are to be five feet in width. The pedestrian circulation system will replace the required public sidewalk along Lane Ranch Drive as shown on the Preliminary Park Concept Plan.
- D. Developer, and its assigns, agree to also install additional amenities such as an off-street parking lot, dog park, covered picnic area, playground equipment and fishing docks as shown on the Preliminary Park Concept Plan. The exact number and location of these amenities may change during the final design process. They are generally represented on the Park Plan.
- E. The phasing of the park improvements will coincide with the residential phasing plan and is noted on the overall Preliminary Park Concept Plan.

### **VIII. Fencing Requirements**

- A. The developer shall install a perimeter brick or stone screening wall along Major Collector Streets as shown on the Detail Plan. Floodplain, parks, open spaces, right-of-way shall be exempt from the screening requirements in this Section; however, tubular steel fencing may be installed in these areas at the developer's option.
- B. Homebuilder side yard and back yard fencing on residential lots shall be a maximum of six feet in height and shall be setback a minimum of five feet from the front building line shown on the Detail Plan.
- C. Fencing on all residential lots abutting an open space lot or greenbelt shall be restricted to tubular steel painted black. No solid fencing other than a brick and/or stone masonry courtyard wall under 42 inches shall be permitted abutting an open space lot or greenbelt; however, landscape borders, included trimmed hedges, are permitted.

### **IX. Street Typology**

- A. Standard curbs will be required adjacent to streets abutting all residential lot types unless otherwise approved by the City's engineering department.
- B. Streets fronting open space lots must have standard curbs adjacent to the common area lot. Streets adjacent to common area lots may provide for on-street parking. In addition, the street faces adjacent to open spaces near the flood plain will have a maintenance access location.
- C. Developer shall work with City to determine the location and number of stop signs within the subdivision and speed limits to facilitate traffic calming and maximum the benefit from the pedestrian system.

### **X. Utilities and Equipment**



- A. Electrical and gas utility meters and AC condensers should be unobtrusively located beyond the front or side street facade zone and screened from view from adjacent streets or common open spaces with landscaping or appropriate fencing.
- B. Transformers on individual lots should be screened to minimize visual impact.
- C. Satellite dishes, and solar panels should be located in less conspicuous locations and out of view from adjacent streets or common open spaces when possible.
- D. Antennas should be located inside the building when possible.
- E. Solar panels when visible from the front should be flush with the roof.

#### **XI. Refuse Locations**

- A. Refuse containers should be stored within an enclosed storage area, fenced, or walled to be screened from view from adjacent streets or common open spaces with landscaping can be added.

#### **XII. Home Variety**


- A. Detached home designs with the same or similar facade, materials, or colors should be separated by a minimum of three lots on the same side of the street and should not be located directly across or diagonally across the street from each other.
- B. If a detached home plan is repeated on an adjacent lot, it should be elevated with a different architectural style or two of the following three elevation changes - brick color, roof color, or flipped plan.

#### **BUSINESS DISTRICT USES**

Except as otherwise provided below, commercial uses shall comply with Section 23, "B-2" Business District - 2 of the Zoning Ordinance, subject to the following changes:

1. An 19.15-acre multi-family site will be allowed. The base zoning for this tract will be "MF-2" Multi-Family Residential District - 2 at 20 units per gross acre.
2. Self-Storage facilities may be allowed by SUP approval.
3. Boat storage facilities may be allowed by SUP approval.

4. The building height for a pitched roof building shall be a maximum of 45 feet.
5. The front, rear and side building setbacks adjacent to any internal street shall be a minimum of 15 feet.
6. Any mechanical equipment including roof top equipment shall be screened from residential districts either by fencing, landscaping or rooftop screening as applicable.



**MIDDLETON & ASSOCIATES, LLC**

**CONSULTING CIVIL ENGINEERS AND LAND PLANNERS**

November 6, 2023

Ms. Ramie Hammonds  
Director of Development Services  
City of Sanger  
201 Bolivar Street  
Sanger, Texas 76266

RE: Letter of Intent  
Rezoning for Lane Ranch  
Sanger, Texas

Dear Ramie:

Please accept this Letter of Intent for the rezoning of the Lane Ranch property located at the northeastern intersection of McReynolds Road and Indian Lane in Sanger. This zoning application is to amend the current zoning Ordinance 04-11-22 for Lane Ranch. The property is approximately 347 acres consisting of seven (7) different properties owned by Hien T. & Duyet Nguyen, Dualbond Holdings, LLC, Sanger Town Center, LLC and Marion Property Holding, LLC. This tract is currently open pastureland with no tree cover.

The purpose of this request is to amend the current PD zoning to now include an additional 21 acres known as the Marion Hills Property and to update the Concept Plan based on our flood study. The 21-acre tract was acquired by the owners of Lane Ranch, and they are requesting it be part of the overall Lane Ranch PD. The amended PD would add an additional 211 single family residential lots to the current PD. This PD amendment would also revise the roadway configuration for Lane Ranch Drive as it intersects FM 455. Unfortunately, the negotiations with the Sanger ISD did not allow for the anticipated continuation of the roadway across school property.

The applicant for this submittal is Mr. Casey McGinnis with JTWSCM Development. If you have any other questions or would like additional information regarding our submittal, please contact me at 972-393-9800 or Mr. McGinnis at 214-232-6180.

Sincerely,  
**MIDDLETON & ASSOCIATES, LLC.**

Eugene Middleton, P.E.  
President

## **347.329 ACRE LANE RANCH PD SUMMARY**

Purpose Statement - To amend PD 04-11-22 and establish a quality master planned multi-phase and multiple product residential and commercial community for the property described by metes and bounds on Exhibit "A" (the "Property") of this PD Ordinance. Development and use of the Property shall comply with the Sanger Zoning Ordinance as it existed on the date of its adoption on August 3, 1987 and subsequent amended (the "The Zoning Ordinance") and this PD ordinance. In the event of a conflict between the Zoning Ordinance and this PD Ordinance, this PD ordinance shall control.

### **PROPOSED USES**

#### **Single Family (210.499 Acres)**

Approximately 190.299 acres are proposed as single-family detached uses and 20.20 acres as single family attached (townhome).

#### **Business District (50.14 Acres)**

Approximately 50.14 acres are proposed as local business and retail. Within this area we also anticipate approximately 8 acres of assisted living along with 12 acres of multi-family.

### **COMMUNITY FEATURES**

The hardscape within the community shall include entry monuments, screening walls and community signage constructed of brick, stone, **metal or wood**. Signs shall not be within the sight visibility triangles.

A mandatory homeowners association shall be established to own and maintain the private open spaces, common areas and greenbelts; all private landscape improvements; dog parks and dog waste stations, perimeter masonry and tubular steel fencing; entry monuments and signage. The homeowner's association shall maintain on street parking spaces within a street right-of-way and any parking spaces located within a common area lot. Private trails and sidewalks shall be constructed within a pedestrian access easement and owned and maintained by the HOA.

The 100-year floodplain shall be designated as a public drainage easement within the Public Parkland dedication. Maintenance responsibility shall be identified on the plat using the City of Sanger Standard drainage easement inscription.

**RESIDENTIAL LAND USES**

**I. Lot Sizes, Setbacks, etc. for Single Family Detached.** Except as otherwise provided below, detached single family residences shall comply with Section 53, “R-1” RESIDENTIAL DISTRICT -1 of the Zoning Ordinance, subject to the following changes:

**A. Minimum Lot Width, Depth, and Size.**

The Estate Lots:

The minimum lot width shall be 60 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 7,200 square feet.

The Manor Lots:

The minimum lot width shall be 50 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 6,000 square feet.

The Garden Lots:

The minimum lot width shall be 40 feet. The minimum lot depth shall be 110 feet. The minimum lot size shall be 4,400 square feet.

**B. Lot Depths for Cul-de-Sac and Eyebrow Lots.**

The minimum lot depth for all lots within any proposed residential use along a cul-de-sac or eyebrow may have a reduced lot depth of 95 feet. The lot minimum square footage still applies.

**C. Minimum House Size.**

The Estate Lots:

The minimum air-conditioned area within each residence shall be 2,250 square feet.

The Manor Lots:

The minimum air-conditioned area within each residence shall be 1,800 square feet. Over the entire development, the Manor Lots shall average over 2,000 square feet in house size. The Manor Lots shall place a limit of 15% of the total lot count to be below 2,000 square feet.

The Garden Lots:

The minimum air-conditioned area within each residence shall be 1,500 square feet. Over the entire development, the Garden Lots shall average over 1,650 square feet in house size. The Garden Lots shall place a limit of 15% of the total lot count to be below 1,650 square feet.

D. Maximum Height.

The maximum building height shall be 2 stories or 35 feet.

E. Front Yard Setback.

The minimum front yard building setback for all lots facing a street shall be 25 feet. Front porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the front yard a maximum of five feet.

F. Side Yard Setback.

The minimum side yard building setback shall be five feet (5') on each side. A side yard adjacent to a street on a corner lot shall always have a minimum ten-foot (10') side yard building setback.

G. Rear Yard Setback.

The minimum rear yard building setback for **all front entry lots** shall be 20 feet from the rear facade of the residence (excluding porches and projecting architectural features) to the rear lot line. Porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the rear yard a maximum of five feet (5').

H. Maximum Lot Coverage.

The maximum lot coverage will be 65% for any residential lot.

I. Garages.

An enclosed parking area of at least four hundred square feet shall be provided for a garage (this does not count towards the minimum house size). The face of a garage door must be located at least 20 feet from the street right-of-way line that the garage door faces. The garage door does not have to be behind the street facing façade of the house. Split garage doors with a separate door for each vehicle bay are not required.

J. Design Elements

All residential dwellings will meet the City of Sanger Exterior Façade Design Criteria Manual as adopted on October 7, 2019.

**II. Lot Sizes, Setbacks, etc. for Single Family Attached.** Except as otherwise provided below, attached single family residences shall comply with Section 57, "TH" TOWNHOME RESIDENTIAL DISTRICT of the Zoning Ordinance, subject to the following changes:

A. Minimum Lot Width, Depth, and Size.

The minimum lot width shall be 22 feet. The minimum lot depth shall be 90 feet. The minimum lot size shall be 1,980 square feet.

B. Minimum House Size.

The minimum air-conditioned area within each residence shall be 1,300 square feet.

C. Maximum Height.

The maximum building height shall be 2 stories or 40 feet.

D. Driveway/Garage Locations.

All residential dwellings shall be either front entry from a public street, or rear entry from an alleyway.

E. Front Yard Setback.

The minimum front yard building setback for all lots facing a street shall be 20 feet, all others are 10 feet. Front porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the front yard a maximum of five feet.

F. Side Yard Setback.

The minimum side yard building setback shall be five feet (5') on each side. A side yard adjacent to a street on a corner lot shall always have a minimum ten-foot (10') side yard building setback. For end dwelling units that abut a common area lot rather than an alley or street right of way, the minimum side yard setback adjacent to the common area lot shall be 5 feet.

G. Rear Yard Setback.

The minimum rear yard building setback for all front entry lots shall be 10 feet from the rear facade of the residence (excluding porches and projecting architectural features) to the rear lot line. All rear entry lots shall have a 20-foot setback from the garage to the alley right-of-way. Porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the rear yard a maximum of five feet (5').

H. Maximum Lot Coverage.

The maximum lot coverage shall not apply to any townhomes.

I. Parking.

Two off-street parking spaces shall be provided per unit within the required garage. Guest parking will be provided within the site at a ratio of 1 space per 4 units.

J. Design Elements

All residential dwellings will meet the City of Sanger Exterior Façade Design Criteria Manual as adopted on October 7, 2019.

**III. Lot Sizes, Setbacks, etc. for Multi-Family.** Multi-Family residences shall comply with Section 19, “MF-2” MULTI-FAMILY RESIDENTIAL DISTRICT – 2 of the Zoning Ordinance.

**IV. General Conditions.**

- A. For the purposes of determining compliance with the lot width requirements, lot widths shall be measured at the rear of the required front yard setback as shown on the Final Plats.
- B. Sidewalks may be located outside of the public right-of-way if located within an adjacent open space lot with a pedestrian access easement to provide for meandering sidewalks and trails that may be located within adjacent common area lots or to preserve existing trees along perimeter roads.

**V. Residential Single Family Detached Landscape Requirements.** Except as otherwise provided below, landscape requirements shall comply with Section 48, Landscape Regulations of the Zoning Ordinance, subject to the following changes:

The following requirements apply to single family residential development:

- A. Each single-family residence shall have an irrigation system in the front yard and street corner side yard with a freeze sensor regulator shut off.
- B. Each Home lot shall have a minimum of two shade trees that are at least three inches in caliper planted. The trees shall be planted in the front and rear yard. If the lot fronts or sides onto a common area lot, the front yard requirement may be satisfied with the trees located in the adjacent greenspace. No other front yard or side yard tree planting requirement shall apply.
- C. All required trees shall be selected from a tree list approved during the Home Permitting stage.
- D. Each Home lot shall have a minimum of twelve (12) shrubs placed in the front yard. Individual shrubs shall be a minimum of three (3) gallons in size when planted.

**VI. Multifamily, Townhome and Non-residential Uses Landscape Requirements.**



All landscape requirements shall comply with Sections 48.4 and 48.5, Landscape Regulations of the Zoning Ordinance.

## **VII. Parkland/Open Space (86.69 Acres)**

- A. The developer, and its assigns, agree to dedicate approximately 38.50 acres of the total 86.69 acres of open space/floodplain as Public Park property (the “Parkland”) to the City of Sanger. Common areas shall include floodplain, ponds, detention areas, and small open spaces as shown on the Preliminary Park Concept Plan. Small Open Spaces shall be connected with sidewalks to be a comprehensive pedestrian system. Common areas will abut a public street right-of-way in at least one location with a sidewalk connection. The Parkland shall be credited toward the Park Land Dedication requirement.
- B. A pedestrian circulation system shall be provided that affords connectivity to the entire community and the perimeter of the Property. The pedestrian circulation system shall include concrete trails that are a minimum of six feet in width. Trails in greenbelts will be constructed of concrete and shall connect with the project sidewalks. The pedestrian circulation system may be located on private property with a pedestrian access easement or within the right-of-way. The pedestrian circulation system shall include such items as benches, landscaping, signage, lighting, bike racks, water fountains, trash cans, and doggie waste stations. These items are represented on the Preliminary Park Concept Plan.
- C. All interior residential street rights-of-way shall be improved with sidewalks that are a minimum of four feet in width and (1) constructed by the homebuilders at the time of adjacent house construction; or (2) constructed by the developer for all non-buildable lots. All sidewalks along Collector and Arterial Road frontages are to be five feet in width. The pedestrian circulation system will replace the required public sidewalk along Lane Ranch Drive as shown on the Preliminary Park Concept Plan.
- D. The developer, and its assigns, agree to also install additional amenities such as an off-street parking lot, dog park, covered picnic area, playground equipment and fishing docks as shown on the Preliminary Park Concept Plan. The exact number and location of these amenities may change during the final design process. They are generally represented on the Preliminary Park Concept Plan.
- E. The phasing of the park improvements will coincide with the residential phasing plan and is noted on the overall Preliminary Park Concept Plan.

## **VIII. Fencing Requirements**

- A. The developer shall install a perimeter brick or stone screening wall along Major Collector Streets as shown on the Concept Plan. Floodplain, parks, open spaces, right-of- way shall be

exempt from the screening requirements in this Section; however, tubular steel fencing may be installed in these areas at the developer's option.

- B. Homebuilder side yard and back yard fencing on residential lots shall be a maximum of six feet in height and shall be setback a minimum of five feet from the front building line shown on the Detail Plan.
- C. Fencing on all residential lots abutting an open space lot or greenbelt shall be restricted to tubular steel painted black. No solid fencing other than a brick and/or stone masonry courtyard wall under 42 inches shall be permitted abutting an open space lot or greenbelt; however, landscape borders, including trimmed hedges, are permitted.

#### **IX. Street Typology**

- A. Standard curbs will be required adjacent to streets abutting all residential lot types unless otherwise approved by the City's engineering department.
- B. Streets fronting open space lots must have standard curbs adjacent to the common area lot. Streets adjacent to common area lots may provide for on-street parking. In addition, the street faces adjacent to open spaces near the flood plain will have a maintenance access location.
- C. Developer shall work with City to determine the location and number of stop signs within the subdivision and speed limits to facilitate traffic calming and maximum the benefit from the pedestrian system.

#### **X. Utilities and Equipment**

- A. Electrical and gas utility meters and AC condensers should be unobtrusively located beyond the front or side street facade zone and screened from view from adjacent streets or common open spaces with landscaping or appropriate fencing.
- B. Transformers on individual lots should be screened to minimize visual impact.
- C. Satellite dishes and solar panels should be located in less conspicuous locations and out of view from adjacent streets or common open spaces when possible.
- D. Antennas should be located inside the building when possible.
- E. Solar panels, when visible from the front, should be flush with the roof.

#### **XI. Refuse Locations**

- A. Refuse containers should be stored within an enclosed storage area, fenced, or walled to be screened from view from adjacent streets or common open spaces with landscaping can be added.

**XII. Home Variety**

- A. Detached home designs with the same or similar facade, materials, or colors should be separated by a minimum of three lots on the same side of the street and should not be located directly across or diagonally across the street from each other.
- B. If a detached home plan is repeated on an adjacent lot, it should be elevated with a different architectural style or two of the following three elevation changes - brick color, roof color, or flipped plan.

**BUSINESS DISTRICT USES**

Except as otherwise provided below, commercial uses shall comply with Section 23, “B-2” Business District - 2 of the Zoning Ordinance, subject to the following changes:

1. A 12-acre multi-family site will be allowed. The base zoning for this tract will be “MF-2” Multi-Family Residential District - 2 at 20 units per gross acre.
2. Self-Storage facilities may be allowed by SUP approval.
3. Boat storage facilities may be allowed by SUP approval.
4. The building height for a pitched roof building shall be a maximum of 45 feet.
5. The front, rear, and side building setbacks adjacent to any internal street shall be a minimum of 15 feet.
6. Any mechanical equipment including roof top equipment shall be screened from residential districts either by fencing, landscaping, or rooftop screening as applicable.

**CITY OF SANGER, TEXAS**

**ORDINANCE No. 04-11-22**

**AN ORDINANCE OF THE CITY OF SANGER, DENTON COUNTY, TEXAS, REZONING APPROXIMATELY 326 ACRES OF TRACTS DESCRIBED AS A0029A R. BEEBE, TR 56, 56A, 56B, 60, 61 and 65, FROM “A” AGRICULTURAL TO “PD” PLANNED DEVELOPMENT; PROVIDING FOR THE REPEAL OF ALL ORDINANCES IN CONFLICT; PROVIDING FOR A SEVERABILITY CLAUSE; PROVIDING FOR A PENALTY OF FINE IN ACCORDANCE WITH SECTION 1.109 OF THE CODE OF ORDINANCE FOR VIOLATIONS; AND PROVIDING FOR AN EFFECTIVE DATE.**

**WHEREAS**, the City of Sanger (the “City”) is a home rule municipality regulated by state law and Charter; and

**WHEREAS**, the City Council finds it necessary for the public health, safety, and welfare that development occur in a controlled and orderly manner; and

**WHEREAS**, the Planning and Zoning Commission on May 9, 2022, duly covered and conducted public hearing for the purpose of assessing a request for amendment to the Zoning Map, recommending approval for the hereinafter described property; and

**WHEREAS**, On May 9, 2022 the City Council approved the amendment to the Zoning Map from Agricultural (A) to Planned Development (PD); and

**WHEREAS**, all request for amendment to the Zoning Map were duly filed with the City of Sanger, Texas, concerning the hereinafter described property; and

**WHEREAS**, the following provision of proper legal notice requirements, including written notice to owners within 200 feet of the subject property, were made in the time and manner prescribed by law; and

**WHEREAS**, the City Council finds that the passage of this Ordinance is in the best interest of the citizens of Sanger.

**NOW, THEREFORE, BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF SANGER, TEXAS:**

**SECTION 1.** That the legal description of the tracts zoned herein is generally described as **A0029A R. BEEBE, TR 56, 56A, 56B, 60, 61 and 65 326 ACRES.**

**SECTION 2.** That the subject property described in Section 1 and further described through metes and bounds in Exhibit A, and generally located on the south side of FM 455 and approximately 330 feet east of the intersection of Marion Road and FM 455 and continuing south

to McReynolds Rd, is rezoned from A (Agricultural) to PD (Planned Development), as illustrated in Exhibit B and the conceptual plan as illustrated in Exhibit C.

**SECTION 3.** That all matters stated in the preamble are found to be true and correct and are incorporated herein as if copied in their entirety.

**SECTION 4.** All ordinances or parts of ordinances in conflict herewith are, to the extent of such conflict, hereby repealed.

**SECTION 5.** It is hereby declared to be the intention of the City Council that the sections, paragraphs, sentences, clauses, phrases and words of this Ordinance are severable and, if any word, phrase, clause, sentence, paragraph, or section of this Ordinance shall be declared unconstitutional by the valid judgment or decree of any court of competent jurisdiction, such unconstitutionality shall not affect any of the remaining portions of this Ordinance, since the same would have been enacted by the City Council without the incorporation in this Ordinance of any such unconstitutional word, phrase, clause, sentence, paragraph, or section.


**SECTION 6.** Any person, firm or corporation who shall violate any of the provisions of this article shall be guilty of a misdemeanor and upon conviction shall be fined in accordance with the general penalty provision found in The Code of Ordinances, Section 1.109 General Penalty for Violations of Code.

**SECTION 7.** This ordinance will take effect immediately from and after its passage and the publication of the caption, as the law and Charter in such cases provide.

**DULY PASSED, APPROVED AND ADOPTED** by the City Council of the City of Sanger, Texas, on this 9th day of May, 2022.

**ATTEST:**

Kelly Edwards  
Kelly Edwards, City Secretary



**APPROVED:**

Thomas E. Muir  
Thomas E. Muir, Mayor

**APPROVED TO FORM:**

Hugh Coleman  
Hugh Coleman, City Attorney

## EXHIBIT A

## LEGAL DESCRIPTION

All that certain lot, tract, or parcel of land, being part of the Rueben Bebee Survey, Abstract No. 29, Denton County, Texas, and being all of that tract of land described in a deed to Hien & Duyet Nguyen recorded in Document No. 2016-27020 Real Property Records of Denton, County, Texas (RPRDCT) and all of that tract of land described in a deed to Dualbond Holdings, LLC recorded in Document No. 2016-27021 (RPRDCT) and all of that tract of land described in a deed to Sanger Town Center LLC recorded in Document No. 2017-48301 (RPRDCT), being more completely described as follows, to-wit:

BEGINNING at 1/2" iron rod set for the southeast corner of the Hien & Duyet Nguyen tract and the north right-of-way line of McReynolds Road;

THENCE with the north right-of-way line of McReynolds Road North 87°54'58" West a distance of 1,789.63 feet to a 1/2" iron rod set for the southwest corner of the Hien & Duyet Nguyen tract and the southeast corner of a tract of land described in a deed to Winston Grove Apartments, LLC recorded in Document No. 2018-13037 (RPRDCT);

THENCE North 2°23'22" East a distance of 2,526.23 feet to 1/2" iron rod set for the northeast corner of a tract of land described in a deed to Marion Hills Apartments, LLC recorded in Document No. 2017-92008 (RPRDCT);

THENCE North 88°13'32" West a distance of 1,325.35 feet to a 2" iron rod found for the northwest corner of the Marion Hills Apartments, LLC;

THENCE South 2°25'03" West a distance of 2,504.45 feet to a 1/2" iron rod set for the southwest corner of Lake Ridge Estates, Phase 1 an addition to the City of Sanger recorded in Cabinet V, Page 752 of the Plat Records of Denton County, Texas (PRDCT) and the north right-of-way line of McReynolds Road;

THENCE with the north right-of-way line of McReynolds Road North 87°25'44" West a distance of 612.45 feet to a 1/2" iron rod set for the southwest corner of the Sanger Town Center LLC tract and the east right-of-way line of Indian Lane right-of-way recorded in Document No. 2004-145888 (RPRDCT);

THENCE with the east right-of-way line of Indian Lane as follows:

North 2°15'10" East a distance of 1,935.36 feet to a 1/2" iron rod set for corner;

North 5°39'58" East a distance of 200.32 feet to a 1/2" iron rod set for corner;

North 2°02'56" East a distance of 24.96 feet to the beginning of a curve to the left, having a radius of 550.39 feet, a chord of North 14° 26' 46" West – 313.65 feet, a distance of 318.05 feet to a 1/2" iron rod set for the southwest corner of land described in a deed to Marion Hills Apartments, LLC recorded in Document No. 2017-48293 (RPRDCT);

THENCE with the east line of the Marion Hills Apartments, LLC as follows:

North 56°02'48" East a distance of 658.23 feet to a 1/2" iron rod set for the beginning of a curve to the left, having a radius of 800.00 feet, a chord of North 29° 03' 15" East – 726.20 feet, a distance of 753.77 feet to a 1/2" iron rod set corner;

North 2°03'42" East a distance of 408.45 feet to the beginning of a curve to the left, having a radius of 800.00 feet, a chord of North 05° 18' 19" West – 205.15 feet, a distance of 205.72 feet to a 1/2" iron rod set for the northeast corner of the Marion Hills Apartments, LLC tract;

THENCE with the north line of the Marion Hills Apartments, LLC as follows:

South 78°30'05" West a distance of 64.61 feet to a curve to the right, having a radius of 800.00 feet, a chord of South 85° 33' 17" West – 196.47 feet, a distance of 196.97 feet to a 1/2" iron rod set corner;

Ordinance – #04-11-22

North 87°23'31" West a distance of 565.51 feet to a 1/2" iron rod set for the northwest corner of the Marion Hills Apartments, LLC and the east line of a tract of land described in a deed to Sanger ISD recorded in Volume 1841, Page 662 (RPRDCT);

THENCE with the east line of the Sanger ISD tract North 2°36'29" East a distance of 840.18 feet to a 1/2" iron rod set for the northeast corner of the Sanger ISD tract and the northwest corner of the Sanger Town Center LLC and the south right-of-way line of West Chapman Road;

THENCE with the south right-of-way line of West Chapman Road and the north line of the Sanger Town Center LLC as follows:

South 87°53'26" East a distance of 1,269.90 feet to a 1/2" iron rod set for corner;

South 88°02'57" East a distance of 500.69 feet to a 1/2" iron rod set for corner;

South 87°47'23" East a distance of 2,068.95 feet to a 1/2" iron rod set for the northeast corner of the Dualbond Holdings, LLC Tract and the northwest corner of a tract of land described in a deed to Miller Family Trust recorded in Document No. 94-0089391 (RPRDCT);

THENCE with the west line of the Miller Family Trust tract South 2°58'32" West a distance of 1,272.08 feet to a 1/2" iron rod set for corner;

THENCE South 2°42'07" West a distance of 3,659.25 feet to the place of beginning, containing 326.825 acres, or 14,236,483 square feet of land.

## EXHIBIT B

### 326.825 ACRE LANE RANCH PD SUMMARY

Purpose Statement - To establish a quality master planned multi-phase and multiple product residential and commercial community for the property described by metes and bounds on Exhibit "A" (the "Property") of this PD Ordinance. Development and use of the Property shall

comply with the Sanger Zoning Ordinance as it existed on the date of its adoption on August 3, 1987 and subsequent amended (the "The Zoning Ordinance") and this PD ordinance. In the event of a conflict between the Zoning Ordinance and this PD Ordinance, this PD ordinance shall control.

#### PROPOSED USES

##### Single Family (242.890 Acres)

Approximately 152.38 acres are proposed as single family detached uses, 16.35 acres as single family attached (townhome) and 74.16 acres of open space. The net density is 3.76 units/acre.

##### Business District (83.935 Acres)

Approximately 43.079 acres are proposed as local business and retail, 8.762 acres of assisted living along with 18.469 acres of multi-family and 13.625 acres of open space.

#### COMMUNITY FEATURES

The hardscape within the community shall include entry monuments, screening walls and community signage constructed of brick or stone. Signs shall not be within the sight visibility triangles.

A mandatory homeowners association shall be established to own and maintain the private open spaces, common areas and greenbelts; all private landscape improvements; dog parks and dog waste stations, perimeter masonry and tubular steel fencing; entry monuments and signage. The homeowner's association shall maintain on street parking spaces within a street right-of-way and any parking spaces located within a common area lot. Private trails and sidewalks shall be constructed within a pedestrian access easement and owned and maintained by the HOA.



The 100-year floodplain shall be designated as a public drainage easement within the Public Parkland dedication. Maintenance responsibility shall be identified on the plat using the City of Sanger Standard drainage easement inscription.

**RESIDENTIAL LAND USES**

**I. Lot Sizes, Setbacks, etc. for Single Family Detached.** Except as otherwise provided below, detached single family residences shall comply with Section 53, “R-1” RESIDENTIAL DISTRICT -1 of the Zoning Ordinance, subject to the following changes:

**A. Minimum Lot Width, Depth, and Size.**

The Estate Lots (60’ X 120’):

The minimum lot width shall be 60 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 7,200 square feet.

The Manor Lots (50’ X 120’):

The minimum lot width shall be 50 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 6,000 square feet.

The Garden Lots (40’ X 120’):

The minimum lot width shall be 40 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 4,800 square feet.

**B. Minimum House Size.**

The Estate Lots:

The minimum air-conditioned area within each residence shall be 2,250 square feet.

The Manor Lots:

The minimum air-conditioned area within each residence shall be 1,800 square feet. Over the entire development, the Manor Lots shall average over 2,000 square feet in house size. The Manor Lots shall place a limit of 15% of the total lot count to be below 2,000 square feet.

The Garden Lots:

The minimum air-conditioned area within each residence shall be 1,500 square feet. Over the entire development, the Garden Lots shall average over 1,650 square feet in house size. The Garden Lots shall place a limit of 15% of the total lot count to be below 1,650 square feet.

**C. Maximum Height.**

The maximum building height shall be 2 stories or 35 feet.

D. Front Yard Setback.

The minimum front yard building setback shall be twenty-five feet (25'). Front porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the front yard a maximum of five feet (5').

E. Side Yard Setback.

The minimum side yard building setback shall be five feet (5') on each side. A side yard adjacent to a street on a corner lot shall always have a minimum ten-foot (10') side yard building setback.

F. Rear Yard Setback.

The minimum rear yard building setback shall be twenty feet (20') from the rear facade of the residence (excluding porches and projecting architectural features) to the rear lot line. Porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the rear yard a maximum of five feet (5').

G. Maximum Lot Coverage.

The maximum lot coverage will be 65% for any residential lot.

H. Garages.

An enclosed parking area of at least four hundred square feet shall be provided for a garage (this does not count towards the minimum house size). The face of a garage door must be located at least 20 feet from the street right-of-way line that the garage door faces. The garage door does not have to be behind the street facing façade of the house. Split garage doors with a separate door for each vehicle bay are not required.

I. Design Elements

All residential dwellings will meet the City of Sanger Exterior Façade Design Criteria Manual as adopted on October 7, 2019.

**II. Lot Sizes, Setbacks, etc. for Single Family Attached.** Except as otherwise provided below, attached single family residences shall comply with Section 57, "TH" TOWNHOME RESIDENTIAL DISTRICT of the Zoning Ordinance, subject to the following changes:

A. Minimum Lot Width, Depth, and Size.

The minimum lot width shall be 22 feet. The minimum lot depth shall be 90 feet. The minimum lot size shall be 1,980 square feet.

B. Minimum House Size.

The minimum air-conditioned area within each residence shall be 1,300 square feet.

C. Maximum Height.

The maximum building height shall be 2 stories or 35 feet.

D. Front Yard Setback.

The minimum front yard building setback shall be twenty-five feet (20'). Front porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the front yard a maximum of five feet (5').

E. Side Yard Setback.

The minimum side yard building setback at the end of each building shall be seven- and one-half feet (7.5') on each side creating a 15-foot separation between buildings. A side yard adjacent to a street on a corner lot shall always have a minimum twenty-feet (20') side yard building setback.

F. Rear Yard Setback.

The minimum rear yard setback shall be five feet from the rear facade of the residence to the alley right-of-way.

G. Maximum Lot Coverage.

The maximum lot coverage shall not apply to any townhomes.

H. Parking

Two off-street parking spaces shall be provided per unit and shall not be within the required front yard.

I. Design Elements

All residential dwellings will meet the City of Sanger Exterior Façade Design Criteria Manual as adopted on October 7, 2019.

**III. Lot Sizes, Setbacks, etc. for Multi-Family.** Multi-Family residences shall comply with Section 19, "MF-2" MULTI-FAMILY RESIDENTIAL DISTRICT – 2 of the Zoning Ordinance.

**IV. General Conditions.**

- A. For the purposes of determining compliance with the lot width requirements, lot widths shall be measured at the rear of the required front yard setback as shown on the Final Plats.
- B. Sidewalks may be located outside of the public right-of-way if located within an adjacent open space lot with a pedestrian access easement to provide for meandering sidewalks and trails that may be located within adjacent common area lots or to preserve existing trees along perimeter roads.

**V. Residential Single Family Detached Landscape Requirements.** Except as otherwise provided below, landscape requirements shall comply with Section 48, Landscape Regulations of the Zoning Ordinance, subject to the following changes:

The following requirements apply to single family residential development:

- A. Each single-family residence shall have an irrigation system in the front yard and street corner side yard with a freeze sensor regulator shut off.
- B. Each Home lot shall have a minimum of two shade trees that are at least three inches in caliper planted. The trees shall be planted in the front and rear yard. If the lot fronts or sides onto a common area lot, the front yard requirement may be satisfied with the trees located in the adjacent greenspace. No other front yard or side yard tree planting requirement shall apply.
- C. All required trees shall be selected from a tree list approved during the Detail Plan stage.
- D. Each Home lot shall have a minimum of twelve (12) shrubs placed in the front yard. Individual shrubs shall be a minimum of three (3) gallons in size when planted.

**VI. Multifamily, Townhome and Non-residential Uses Landscape Requirements.**

All landscape requirements shall comply with Sections 48.4 and 48.5, Landscape Regulations of the Zoning Ordinance.

**VII. Parkland/Open Space (83.783 Acres)**

- A. Developer, and its assigns, agree to dedicate approximately 59.7 acres of the total 83.783 acres of floodplain/open space as Public Park property (the "Parkland") to the City of Sanger. Common areas shall include floodplain, ponds, detention areas, and small open spaces as shown on the Preliminary Park Concept Plan. Small Open Spaces shall be connected with sidewalks to be a comprehensive pedestrian system. Common areas will abut a public street right-of-way in at least one location with a sidewalk connection. The Parkland shall be credited toward the Park Land Dedication requirement.
- B. A pedestrian circulation system shall be provided that affords connectivity to the entire community and the perimeter of the Property. The pedestrian circulation system shall include concrete trails that are a minimum of six feet in width. Trails in greenbelts will be constructed of concrete and shall connect with the project sidewalks. The pedestrian circulation system may be located on private property with a pedestrian access easement or within the right-of-way. The pedestrian circulation system shall include such items as benches, landscaping, signage, lighting, bike racks, water fountains, trash cans, and doggie waste stations. These items are represented on the Park Plan.

- C. All interior residential street rights-of-way shall be improved with sidewalks that are a minimum of four feet in width and (1) constructed by the homebuilders at the time of adjacent house construction; or (2) constructed by the developer for all non-buildable lots. All sidewalks along Collector and Arterial Road frontages are to be five feet in width. The pedestrian circulation system will replace the required public sidewalk along Lane Ranch Drive as shown on the Preliminary Park Concept Plan.
- D. Developer, and its assigns, agree to also install additional amenities such as an off-street parking lot, dog park, covered picnic area, playground equipment and fishing docks as shown on the Preliminary Park Concept Plan. The exact number and location of these amenities may change during the final design process. They are generally represented on the Park Plan.
- E. The phasing of the park improvements will coincide with the residential phasing plan and is noted on the overall Preliminary Park Concept Plan.

### **VIII. Fencing Requirements**

- A. The developer shall install a perimeter brick or stone screening wall along Major Collector Streets as shown on the Detail Plan. Floodplain, parks, open spaces, right-of-way shall be exempt from the screening requirements in this Section; however, tubular steel fencing may be installed in these areas at the developer's option.
- B. Homebuilder side yard and back yard fencing on residential lots shall be a maximum of six feet in height and shall be setback a minimum of five feet from the front building line shown on the Detail Plan.
- C. Fencing on all residential lots abutting an open space lot or greenbelt shall be restricted to tubular steel painted black. No solid fencing other than a brick and/or stone masonry courtyard wall under 42 inches shall be permitted abutting an open space lot or greenbelt; however, landscape borders, included trimmed hedges, are permitted.

### **IX. Street Typology**

- A. Standard curbs will be required adjacent to streets abutting all residential lot types unless otherwise approved by the City's engineering department.
- B. Streets fronting open space lots must have standard curbs adjacent to the common area lot. Streets adjacent to common area lots may provide for on-street parking. In addition, the street faces adjacent to open spaces near the flood plain will have a maintenance access location.
- C. Developer shall work with City to determine the location and number of stop signs within the subdivision and speed limits to facilitate traffic calming and maximum the benefit from the pedestrian system.

### **X. Utilities and Equipment**

- A. Electrical and gas utility meters and AC condensers should be unobtrusively located beyond the front or side street facade zone and screened from view from adjacent streets or common open spaces with landscaping or appropriate fencing.
- B. Transformers on individual lots should be screened to minimize visual impact.
- C. Satellite dishes, and solar panels should be located in less conspicuous locations and out of view from adjacent streets or common open spaces when possible.
- D. Antennas should be located inside the building when possible.
- E. Solar panels when visible from the front should be flush with the roof.

#### **XI. Refuse Locations**

- A. Refuse containers should be stored within an enclosed storage area, fenced, or walled to be screened from view from adjacent streets or common open spaces with landscaping can be added.

#### **XII. Home Variety**


- A. Detached home designs with the same or similar facade, materials, or colors should be separated by a minimum of three lots on the same side of the street and should not be located directly across or diagonally across the street from each other.
- B. If a detached home plan is repeated on an adjacent lot, it should be elevated with a different architectural style or two of the following three elevation changes - brick color, roof color, or flipped plan.

### **BUSINESS DISTRICT USES**

Except as otherwise provided below, commercial uses shall comply with Section 23, "B-2" Business District - 2 of the Zoning Ordinance, subject to the following changes:

1. An 18.5-acre multi-family site will be allowed. The base zoning for this tract will be "MF-2" Multi-Family Residential District - 2 at 20 units per gross acre.
2. Self-Storage facilities may be allowed by SUP approval.
3. Boat storage facilities may be allowed by SUP approval.

4. The building height for a pitched roof building shall be a maximum of 45 feet.
5. The front, rear and side building setbacks adjacent to any internal street shall be a minimum of 15 feet.
6. Any mechanical equipment including roof top equipment shall be screened from residential districts either by fencing, landscaping or rooftop screening as applicable.


















# EXHIBIT C



# DRC MEDIA COMPANY

## NEWS & ADVERTISING SOLUTIONS

One company delivers it all.


3555 Duchess Drive  
P.O. Box 369  
Denton, TX 76202  
940-387-3811

Publication(s): Denton Record-Chronicle


### PROOF OF PUBLICATION

Being duly sworn (s)he is the Publisher/authorized designee of Denton Record-Chronicle, in City of Denton/surrounding areas in Denton County; Newspaper of general circulation which has been continuously and regularly published for a period of not less than one year preceding the date of the attached notice, and that the said notice was published in said newspaper Denton Record-Chronicle on the following dates below:


06/10/2022 06/12/2022 06/14/2022

  
\_\_\_\_\_  
(signature of Authorized Designee)


Subscribed and sworn to before me  
this 14th day of June, 2022 by

  
\_\_\_\_\_  
(printed name of Designee)

Witness my hand and official seal:

  
\_\_\_\_\_  
(signature name of Designee)

Notary Public, Denton County, Texas



**CITY OF SANGER, TEXAS**  
**ORDINANCE No. 04-11-22**

AN ORDINANCE OF THE CITY OF SANGER, DENTON COUNTY, TEXAS, REZONING APPROXIMATELY 326 ACRES OF TRACTS DESCRIBED AS A0029A R. BEEBE, TR 56, 56A, 56B, 60, 61 and 65, FROM "A" AGRICULTURAL TO "PD" PLANNED DEVELOPMENT; PROVIDING FOR THE REPEAL OF ALL ORDINANCES IN CONFLICT; PROVIDING FOR A SEVERABILITY CLAUSE; PROVIDING FOR A PENALTY OF FINE IN ACCORDANCE WITH SECTION 1.109 OF THE CODE OF ORDINANCE FOR VIOLATIONS; AND PROVIDING FOR AN EFFECTIVE DATE.

SECTION 6. Any person, firm or corporation who shall violate any of the provisions of this article shall be guilty of a misdemeanor and upon conviction shall be fined in accordance with the general penalty provision found in The Code of Ordinances, Section 1.109 General Penalty for Violations of Code. DULY PASSED, APPROVED AND ADOPTED by the City Council of the City of Sanger, Texas, on this 9th day of May, 2022.

drc 06/10/2022 & 06/14/2022

SANGER CITY OF  
P O BOX 1729  
SANGER TX 76266

Ad Number: 45702

Price: \$56.70



Ad Copy:  
CITY OF SANGER, TEXAS  
ORDINANCE No. 04-11-22

AN ORDINANCE OF THE CITY OF SANGER, DENTON COUNTY, TEXAS, REZONING APPROXIMATELY 326 ACRES OF TRACTS DESCRIBED AS A0029A R. BEEBE, TR 56, 56A, 56B, 60, 61 and 65, FROM "A" AGRICULTURAL TO "PD" PLANNED DEVELOPMENT; PROVIDING FOR THE REPEAL OF ALL ORDINANCES IN CONFLICT; PROVIDING FOR A SEVERABILITY CLAUSE; PROVIDING FOR A PENALTY OF FINE IN ACCORDANCE WITH SECTION 1.109 OF THE CODE OF ORDINANCE FOR VIOLATIONS; AND PROVIDING FOR AN EFFECTIVE DATE. SECTION 6. Any person, firm or corporation who shall violate any of the provisions of this article shall be guilty of a misdemeanor and upon conviction shall be fined in accordance with the general penalty provision found in The Code of Ordinances, Section 1.109 General Penalty for Violations of Code. DULY PASSED, APPROVED AND ADOPTED by the City Council of the City of Sanger, Texas, on this 9th day of May, 2022.

drc 06/10/2022 & 06/14/2022



**DATE: 10/26/2023**

**1<sup>st</sup> REVIEW COMMENTS “AMENDED 11-2-23” – Lane Ranch - Zoning**

The request is for an amendment to PD 4-11-22 by amending PD language and adding 21.17 acres. Below are the comments that should be addressed before City Council approval. Resubmit the Amending PD.

**Planning**

Provide the following

1. The acreage under Proposed Uses doesn't match the acreage in the title. Break down the acreage under Proposed Uses the same way it was broken down in the original PD and make sure the acreages there match the acreages in the title.
2. Staff recommends the higher standard of brick and stone for entry, monument, screening walls, and community signage. Wood and metal could be used to add interest.
3. Single Family - rear setback, why is there a difference between front entry setback and rear entry setback? What would the rear entry setback be? There wasn't one listed.
4. Single Family Attached - Staff recommends the side yard setback to remain 7.5 feet on each side to allow access for emergency personnel.
5. Single Family Attached – Townhomes are individually owned, so staff recommends all front yard setbacks remain at 20 feet.
6. Single Family Attached Parking – off-street parking needs to be provided in addition to garage space.
7. Parkland/Open Space – Explain the reduced acreage of the public park. It appears there is a 20 acre reduction.
8. Multi-Family needs to be called out and not generalized under the Business District and also needs to be shown on the concept plan.

**Added Comments**

1. Staff recommends adding a covered picnic area and possibly playground in the open space between the business uses and extending the trail into that area.

**Informational Comments**

1. The property is within the City of Sanger.
2. The PD Amendment will be scheduled for the Planning and Zoning (P&Z) Commission meeting on Monday, November 13, 2023, and the City Council meeting on Monday, December 4, 2023.