

DEVELOPMENT REVIEW COMMITTEE

Tuesday, August 24, 2021, at 3:00 PM Court Room/Council Chambers (2nd Floor) and Online

MEETINGS HELD IN PERSON & ONLINE

The public is invited to participate as outlined below:

- In Person Meetings are held on the 2nd floor in the Court Room/Council Chambers at City Hall
- YouTube Live Public meetings will be shown live on the Santaquin City YouTube Channel, which can be found at https://bit.ly/2P7ICfQ or by searching for Santaquin City Channel on YouTube.

ADA NOTICE

If you are planning to attend this Public Meeting and due to a disability need assistance in understanding or participating in the meeting, please notify the City Office ten or more hours in advance and we will, within reason, provide what assistance may be required.

AGENDA

MEETING AMENDED FOR 3:00 PM ON TUESDAY AUGUST 24, 2021.

NEW BUSINESS

1. DeGraffenried Single Lot Split Concept Review

A concept review of a single lot split located at 245 E. 100 N.

2. Ridley's Pad Site A (Fiiz Drinks) Site Plan Review

A site plan review of a commercial building located at approximately 30 N. 400 E.

3. Traffic Control Device Request- 4 Way Stop Sign

The DRC will review a request for a 4 way stop at 400 S. and 100 W.

4. Traffic Control Device Request- Cross Walk and School Signs

The DRC will review a request for a cross walk and school signs along 200 E.

MEETING MINUTES APPROVAL

5. August 10, 2021

AJOURNMENT

CERTIFICATE OF MAILING/POSTING

The undersigned duly appointed City Recorder for the municipality of Santaquin City hereby certifies that a copy of the foregoing Notice and Agenda was e-mailed to the Payson Chronicle, Payson, UT, 84651, posted on www.santaquin.org, as well as posted on the State of Utah's Public Notice Website.

BY: K. Vara Shirley


K. Aaron Shirley, City Recorder


DEGRAFFENRIED

A RESIDENTIAL SUBDIVISION SANTAQUIN, UTAH COUNTY, UTAH PRELIMINARY PLAN SET **APRIL 2021**

-SHEET INDEX-

SHEET	SHEET NAME			
1	COVER			
2	EXISTING TOPOGRAPHY			
3	UTILITY PLAN			
4	PRELIMINARY PLAT			
5	FINAL PLAT			
6	ROS			











PHONE: 801-655-0566 FAX: 801-655-0109 946 E. 800 N. SUITE A SPANISH FORK, UT 84660


OWNER/DEVELOPER JIMMY DeGRAFFENRIED WOODLAND HILLS, UTAH 801-830-5490












Designed by: SY

21-003 CV

30 North 400 East Street Santaquin City, Utah





Civil Sheet Index

CO.O Cover Sheet	CO.0
CO.1 Demolition Plan	CO.1
C1.1 Site Plan	C1.1
C2.1 Grading Plan	C2.1
C3.1 Utility Plan	C3.1
C4.1 Details	C4.1
C4.2 Details	C4.2
C4.3 Details	C4.3
C5.1 Erosion Control Plan	<i>C5.1</i> · · ·
L1.1 Landscape Plan	L1.1
L2.1 Irrigation Plan	L2.1
L3.1 Landscape & Irrigation Details	<i>L3.1</i> ····

Owner / Developer

Owned and developed by CJM Limited Liability Limited Partnership.

Registered Address at 621 Washington Street South, Twin Falls, Idaho 83301.

Santaquin City Notes

The developer and the general contractor understand that it is his/her responsibility to ensure that all improvements installed within this development are constructed in full compliance with all state and Santaquin City codes, ordinances and standards. These plans are not all inclusive of all minimum codes, ordinances and standards. This fact does not relieve the developer or general contractor from the full compliance with all minimum state and Santaquin City codes, ordinances and standards.

Santaquin City Note to Developers & General Contractors

All recommendations made in the provided geotechnical report/study shall be followed explicitly during construction of building and site improvements.

Legal Description
Lot 4, Ridley's Subdivision

SHAUN A YOU SHAUN


10 Aug, 2021

CO.0

BCR Begin Curb Return PT Point of Tangency
BOL Bollard PVC Polyvinyl Chloride
BRW Finish Grade — Bottom of Retaining Wall PVI Point of Vertical Intersection
CATV Cable Television Box RCP Reinforced Concrete Pipe
CB Catch Basin RD Roof Drain
CMP Corrugated Metal Pipe SB Signal Box
COB Cleanout Box SD Storm Drain
COTG Cleanout to Grade SDMH Storm Drain Manhole
EA Edge of Asphalt SMH Sewer Manhole
EB Electrical Box SP Signal Pole
ECC End of Curve SS Sanitary Sewer
ECR End Curb Return SVZ Sight Visibility Zone
GB Grade Break SW Secondary Water
GM Gas Meter TA Top of Asphalt
HB Hose Bib TB Telephone Box
HP High Point TBC Top Back of Curb
I Irrigation Line TG Top of Grate
ICB Irrigation Control Box TMH Telephone Manhole
Lip Lip of Gutter TP Top of Concrete
LP Light Pole TRW Finish Grade — Top of Retaining Wall
MH Manhole TW Top of Walk
Mon Monument VC Vertical Curve
PCC Point of Curvature VPC Vertical Point of Curve
PCC Point of Curvature VPC Vertical Point of Tangency
PI Point of Intersection WL Watering Point
PP Power Pole WW Water Valve

Abbreviations

W:\21-003 Fiiz Drinks Santaquin\dwgs\21-0




Drafted by: KF Client Name:

Ridley's 21-003 DM

10 Aug, 2021

CO.1





Scale: 1" = 10'

Site Construction Notes

- 1 Const. 24" Curb & Gutter
- 4 Const. Thickened Edge Sidewalk
- Const. Accessible Striping per MUTCD & ICC/ANSI
 A117.1 (Latest Edition)
 (See Accessible Details and Notes)
- 6 Const. Accessible Ramp per ICC/ANSI A117.1 (Latest Edition) (See Accessible Details and Notes)
- (7) Const. Boulder Retaining Wall (2' Max Height) 8 Const. Accessible VAN Sign per MUTCD & ICC/ANSI (2)
 A117.1 (Latest Edition)
 (See Accessible Details and Notes)
- 9 Const. 4" White Paint Stripe (Typ.) Contractor shall provide 15 mils min. thickness
- $\langle 10 \rangle$ Const. Concete Paving $\left(\frac{6}{C4.1} \right)$
- (11) Sawcut; Provide Smooth Clean Edge
- (12) Dumpster Enclosure (See Arch. Plans)
- (13) Const. Directional Arrows per MUTCD
- Connect to Existing Improvements and Match Grade Elevation
- $\langle 15 \rangle$ Const. Painted Crosswalk
- $\langle 16 \rangle$ Const. Handrails (See Architectural Details)

- 1. All dimensions are to back of curb unless otherwise
- Fire lane markings and signs to be installed as directed by the Fire Marshal.
- Aisle markings, directional arrows and stop bars will be painted at each driveway as shown on the plans.
- 4. Const. curb transition at all points where curb abuts sidewalk, see detail.
- Contractor shall place asphalt paving in the direction of vehicle travel where possible.
- 6. Limits of demolition/disturbed areas shown on the plans may not be an exact depiction. It is the contractor's responsibility to determine the means and methods of how the work will be completed. The contractor shall determine the area of construction impact. The contractor is responsible to restore all

Construction Survey Note:


The Construction Survey Layout for this project will be provided by Anderson Wahlen & Associates. The Layout Proposal and Professional Services Agreement will be provided to the General Contractor(s) for inclusion in base bids. The Survey Layout proposal has been broken out into Building Costs and Site Costs for use in the Site Work Bid Form.

Survey Control Note:

The contractor or surveyor shall be responsible for following the National Society of Professional Surveyors (NSPS) model standards for any surveying or construction layout to be completed and Analysis and Associated ALTA Surveys or Anderson Wahlen and Associates construction improvement plans. Prior to proceeding with construction staking, the surveyor shall be responsible for verifying horizontal control from the survey monuments and for verifying any additional control points shown on an ALTA survey, improvement plan, or on electronic data provided by Anderson Wahlen and Associates. The surveyor shall them to be a second to the second than the same than the shown on the plan, and verify them against no less than three existing hard improvement elevations included on these plans or on electronic data provided by Anderson Wahlen and Associates. If any discrepancies are encountered, the surveyor shall immediately notify the engineer and resolve the discrepancies before proceeding with any construction staking.

PRIVATE ENGINEER'S NOTICE TO CONTRACTORS


The Contractor agrees that he shall assume sole and complete responsibility for job site conditions during the course of construction of this project, including safety of all persons and property: that this requirement shall apply continuously and not be limited to normal working hours; and that the contractor shall defend, indemnify, and hold the owner and the engineer harmless from any and all liability, real or alleged, in connection with the performance of work on this project, excepting for liability arising from the sole negligence of the owner or the engineer.



Drafted by: KF Client Name:


21-003 SP

rinks



10 Aug, 2021

C1.1



General Grading Notes:

- 1. All grading shall be in accordance with the project geotechnical study.
- 2. Cut slopes shall be no steeper than 3 horizontal to 1 vertical.
- 3. Fill slopes shall be no steeper than 3 horizontal to 1 vertical.
- Fills shall be compacted per the recommendations of the geotechnical report prepared for the project and shall be certified by a Geotechnical Engineer.
- Areas to receive fill shall be properly prepared and approved by a Geotechnical Engineer prior to placing fill.
- 6. Fills shall be benched into competent material as per specifications and geotechnical report.
- All trench backfill shall be tested and certified by a Geotechnical Engineer.
- 8. A geotechnical engineer shall perform periodic inspections and submit a complete report and map upon completion of the rough grading.
- 9. The final compaction report and certification from a Geotechnical Engineer shall contain the type of field testing performed. Each test shall be identified with the method of obtaining the in-place density, whether sand cone or drive ring and shall be so noted for each test. Sufficient maximum density determinations shall be performed to verify the accuracy of the maximum density curves used by the field technician.
- 10. Dust shall be controlled by watering.
- The location and protection of all utilities is the responsibility of the permitee.
- Approved protective measures and temporary drainage provisions must be used to protect adjoining properties during the grading process.
- 13. All public roadways must be cleared daily of all dirt, mud and debris deposited on them as a result of the grading operation. Cleaning is to be done to the satisfaction of the City Engineer.
- 14. The site shall be cleared and grubbed of all vegetation and deleterious matter prior to grading.
- 15. The contractor shall provide shoring in accordance with OSHA requirements for trench walls.
- Aggregate base shall be compacted per the geotechnical report prepared for the project.
- 17. The recommendations in the following Geotechnical Engineering Report by GSH are included in the requirements of grading and site Preparation. The Report is titled "Proposed Ridley's Market Development (NEC) of Main Street and 400 South"
- Project No.: 2588-001-18
 Dated: April 26, 2018


 As part of the construction documents,
- 18. As part of the construction documents, owner has provided contractor with a topographic survey performed by manual or aerial means. Such survey was prepared for project design purposes and is provided to the contractor as a courtesy. It is expressly understood that such survey may not accurately reflect existing topographic conditions.
- 19. If Contractor observes evidence of hazardous materials or contaminated soils he shall immediately contact the project engineer to provide notification and obtain direction before proceeding with disturbance of said materials or contaminated soil.

Curb and Gutter Construction Notes:

- 1. Open face gutter shall be constructed where drainage is directed away from curb.
- 2. Open face gutter locations are indicated by shading and notes on the grading plan.
 - It is the responsibility of the surveyor to adjust top of asphalt grades to top of curb grades at the time of construction staking.
 - 4. Refer to the typical details for standard and open face curb and gutter dimensions.
- Transitions from open face to standard curb and gutter are to be smooth. Hand form these areas if necessary.
 - Spot elevations are shown on this plan with text masking. Coordinate and verify site information with project drawings.

Sidewalk Construction Notes:

- Concrete sidewalk shall be constructed with a cross slope of 1.5% (2.08% Maximum) unless shown otherwise on plan.
- Running slope of sidewalks shall be built per grades shown on the plan.
 where grades are not provided, sidewalks shall be constructed with a
 maximum running slope of 4.5%
- 3. Refer to the Site Plan for sidewalk dimensions.



Drafted by: KF
Client Name:
Ridley's

21-003 GR


SON WAHLEN & ASSOCIATE

Drinks
400 East Street

No. 7879289 SHAUN A TOUNG FRANCE OF UTAL OF UT

10 Aug, 2021

C2.1



General Utility Notes:

- All sewer and water facilities shall be constructed per local jurisdiction standards and specifications. Contractor is responsible to obtain standards and specifications.
- 2. Coordinate all utility connections to building with plumbing plans and
- Verify depth and location of all existing utilities prior to constructing any new utility lines. Notify Civil Engineer of any discrepancies or conflicts prior to any connections being made.
- 4. All catch basin and inlet box grates are to be bicycle proof.
- 5. Refer to the site electrical plan for details and locations of electrical lines, transformers and light poles.
- 6. Gas lines, telephone lines, and cable TV lines are not a part of these
- 7. Water meters are to be installed per city standards and specifications. It will be the contractor's responsibility to install all items required.
- 8. Water lines, valves, fire hydrants, fittings etc. are to be constructed as shown. Contractor is responsible, at no cost to the owner, to construct any vertical adjustments necessary to clear sewer, storm drain, or other transportations are designed. hydrant spools to proper grade.
- 9. Contractor shall install a 12" concrete collar around all manholes, valves, catch basins, cleanouts & any other structures located within the asphalt.

Utility Piping Materials:

All piping materials shall be per local agency standards or the specifications below at a minimum. All utility piping shall be installed per manufacturers recommendations. Refer to project specifications for more detailed information regarding materials, installation, etc.

- 1. Polyethylene (PE) Water Pipe (Up to 3 inches diameter), AWWA C901, PE 3408, SDR 9 (200 psi)
- 2. Copper Pipe (Up to 3 inches diameter): Type "K."

Water Main Lines and Fire Lines

Polyvinyl Chloride (PVC) (4 inches to 12 inches diameter): AWWA C900, Class 200

All sewer piping to be Polyvinyl Chloride (PVC) sewer pipe, ASTM D3034, Type PSM, SDR 35

- 12" pipes or smaller Polyvinyl Chloride (PVC) sewer pipe, ASTM D3034, Type PSM, SDR 35
- 2. 15" pipes or larger Reinforced Concrete Pipe, ASTM C76, Class III

The locations and/or elevations of existing utilities as shown on these plans are based on records of the various utility companies and, where possible, measurements taken in the field. The information is not to be relied on as being exact or complete.

Storm Drain & Sanitary Sewer Note:

All Storm Drainage & Sanitary Sewer Pipe Lengths and Slopes are from Center of Structure to Center of Structure

Onsite Utility Connection Notes:

- Contractor shall field verify all utility connection elevations prior to any utility construction has begun.
- 2. Contractor shall construct utility lines into site prior to any onsite utility construction. Gravity lines are to be constructed starting at the lowest point and be installed prior to any waterline installation


Know what's **below.**

Call 811 before you dig.

BLUE STAKES OF UTAH UTILITY NOTIFICATION CENTER, INC.

www.bluestakes.org 1-800-662-4111

Construction of any onsite utilities prior to the offsite connection will be done at the contractors risk.



rinks

Utility

Designed by: SY Drafted by: KF


Ridley's


21-003 UT

Client Name:

10 Aug, 2021


C3.1






Fire Hydrant & Water Valve

Not to Scale









Santaquin City Std. Dwg. UT3
Typical Trench Section

Not to Scale





1. Grey iron casting: ASTM A48 Class 35

2. Coat all metal parts with asphaltum paint.

Provide double inlet & frame where

Inlet Grate Frame

B

Plan View

1 1/8" Typ. → 15 1/2" 1 1/8" Typ.

Section D-D

Curb Box adjustable

Plan View

12 Equal Spaces @ 2 13/16" V A A A A A A A A A A A

—— 5/8" Typ. /-55° Typ.

Section C-C

Section A-A

−35 1/2"−−−

Santaquin City Std. Dwg. SD1
Curb Inlet Box Assembly

Not to Scale

STATE OF UNANDARD

rinks

10 Aug, 2021

C4.2

W:\21-003 Fiiz Drinks Santaquin\dwgs\21-003 DT.c

...


Item 2.


Designed by: SY


Drafted by: KF
Client Name:

Ridley's

21-003 DT








Legend

Place Inlet Protection at all Inlet Locations to prevent boxes from silting. **—**X— Limit of Disturbance Construction Entrance / Truck Wash (50'x24' Min.) CW Concrete Washout Area Gravel Sock Existing Contour Existing Spot o(78.00TA) ---78---

Limits of Disturbance = 17,688 s.f. or 0.406 acres


Erosion Control Notes

- 1. Storm water will be discharged into an existing drainage system. Existing Lines shall be inspected prior to Certificate of Occupancy and cleaned if necessary.
- 2. The Storm Water Prevention Plan shall conform to all State Division of Environmental Protection Regulations.
- 3. All Construction equipment will enter thru Designated Construction
- 4. Coordinate Entrance locations with the local jurisdiction.
- Inlet Protection Devices and Barriers shall be Repaired or Replaced if they Show Signs of Undermining or Deterioration.
- Silt Fences shall be Repaired to their Original Conditions if Damaged, Sediment shall be Removed from Silt Fences when it Reaches one—half the Height of the Silt Fence.
- 7. The Construction Entrances shall be Maintained in a Condition which will Prevent Tracking or Flow of Mud onto Public Right—of—Way. This may
 Require Periodic Top Dressing of the Construction Entrances as Conditions Demand.
- All Materials Spilled, Dropped, Washed or Tracked from Vehicles onto Roadways or into Storm Drains must be Removed Immediately.
- 9. Due to the Grade Changes During the Development of the Project, the Contractor shall be Responsible for Adjusting the Erosion Control Measures (Silt Fences, Inlet Protection, Etc...) to Prevent Erosion.
- 10. Contractor shall use Vehicle Tracking Control at all Locations where Vehicles will Enter or Exit the Site. Control Facilities will be Maintained while Construction is in Progress, Moved when Necessary and Removed when the Site is Paved.
- Inlet Protection Devices shall be Installed Immediately upon Individual Inlets becoming Functional.
- 12. This Document is Fluid Allowing for Changes, Modifications, Updates and Alternatives. It is the Responsibility of the Contractor to Keep Record of all Alterations made to the Erosion Control Measures Implemented for the Project on this Plan and in the Storm Water Pollution Prevention Plan.
- 13. Cover Exposed stockpiles of soils, construction and landscaping materials with heavy plastic sheeting.
- 14. Re-vegetate areas where landscaping has died or not taken hold.
- 15. Divert storm water runoff around disturbed soils with berms or dirt
- 16. Contractor to provide permanent stabilization to any areas disturbed by construction by hydroseeding native vegetation (if not otherwise
- 17. Contractor is responsible for obtaining a fugitive dust control permit through the Division of Air Quality. All responsibilities relating to the production of the dust control plan shall be the responsibility of the



Ridley's

21-003 EC



10 Aug, 2021

C5.1

Designed by: SY
Drafted by: KF

Ridley's

21-003 LS

Client Name:

PLANT SCHEDULE

DECIDUOUS TREES	<u>QTY</u>	BOTANICAL / COMMON NAME	<u>SIZE</u>
$\overline{(\cdot)}$	3	Koelreuteria paniculata / Golden Rain Tree	2" Caliper
$\left(\begin{array}{c} \cdot \end{array}\right)$	2	Quercus robur 'Skyrocket' / Skyrocket English Oak	2" Caliper
$\langle \cdot \rangle$	4	Syringa reticulata 'Ivory Silk' / Ivory Silk Japanese Tree Lilac	2" Caliper
EVERGREEN TREES	<u>QTY</u>	BOTANICAL / COMMON NAME	<u>SIZE</u>
200 C	5	Picea pungens glauca / Columnar Spruce	6-8' Ht.
<u>EVERGREEN SHRUBS</u>	<u>QTY</u>	BOTANICAL / COMMON NAME	<u>SIZE</u>
\odot	24	Buxus x 'Green Mound' / Green Mound Boxwood	5 gal
	16	Juniperus horizontalis 'Bar Harbor' / Bar Harbor Creeping Juniper	5 gal
ORNAMENTAL GRASSES	<u>QTY</u>	BOTANICAL / COMMON NAME	<u>SIZE</u>
**	15	Calamagrostis x a. 'Karl Foerster' / Feather Grass	1 gal
\oplus	26	Helictotrichon sempervirens 'Sapphire' / Blue Oat Grass	1 gal
<u>PERENNIALS</u>	QTY	BOTANICAL / COMMON NAME	<u>SIZE</u>
	13	Hemerocallis x 'Red Hot Returns' / Red Hot Returns Daylily	1 gal
£	13	Nepeta x faassenii 'Dropmore' / Catmint	1 gal
DECIDUOUS SHRUB	QTY	BOTANICAL / COMMON NAME	<u>SIZE</u>
\ + \	8	Berberis thunbergii 'Orange Rocket' / Orange Rocket Barberry	5 gal
	5	Euonymus alatus 'Compactus' / Compact Burning Bush	5 gal
•	6	Prunus x cistena / Purple Leaf Sand Cherry	5 gal
	9	Ribes alpinum 'Green Mound' / Green Mound Alpine Currant	5 gal
	12	Spiraea x bumalda 'Goldflame' / Goldflame Spirea	5 gal
<u>LAWN</u>	QTY	BOTANICAL / COMMON NAME	<u>IYPE</u>
,	2,797 sf	Poa pratensis / Kentucky Bluegrass Blend	sod

Landscape Data

Site Area = 22,907 s.f. (0.526 ac.)

Landscape Area Required = 2,291 s.f. (10%)

Landscape Area Provided = 6,082 s.f. (27%)

Parking Area = 4,838 s.f.

Landscape Parking Required = 484 s.f. (10%)

Landscape Parking Provided = 538 s.f. (11.1%)

400 East Street Frontage = 126 l.f.

400 East Street Trees Req. = 3 Trees (3 Provided)

Landscape Notes:

- 1. All Landscape Material Shall be Fully Irrigated by an Automatic Irrigation System. Drip for Shrub Areas and Spray for Lawn Areas. See Irrigation Sheets L2.1 for Layout and Sheet L3.1 for Details.
- Adjust Landscape Material as Needed to Allow Access to all New and Existing Utilities. Irrigation Components Shall be Spaced Between Plant Material to Allow Easy Access for Maintenance.
- 3. All Areas Disturbed by Construction Shall be Landscaped and Not Left Undone. Blend New Landscape into Existing Corner Landscape.

Landscape Keynotes

1 Install New Lawn

2 Install Landscape Concrete Curbing

3 Existing Landscape Concrete Curbing
Install Shrub Planter with Decorative Stone
Weed Barrier

Irrigation Water Meter and Connection

— See Irrigation Plan for More Detail

New Fire Hydrant; Verify that There is

3' Clearance Around Hydrant

7 Planting Screen for Dumpster

8 3' High Evergreen Planting Screen for Parking Lot

9 Rock Retaining Wall; Clean Dirt Out
Between Rocks and Install Decorative
Stone; Wash Dirt off of Rocks; See
Material Schedule for More Detail

10 Irrigation Secondary Meter – See
Utility and Irrigation Plan for More

UT — Existing/New Utility Box or Manhole

MATERIAL SCHEDULE

Avoid Existing and New Utilities.

Decorative Stone #1 - Install a (3) Three Inch Depth over Dewitt Pro5 Weed Barrier;

Stone Shall be Used in Shall Planters Where Shown on Plant Stone Shall be Washed

Stone Shall be Used in Shrub Planters Where Shown on Plan; Stone Shall be Washed Prior to Installation; Stone Shall be 1" Diameter Crushed, Fractured Talon's Cove (Gray Color) Stone from Utah Landscape Rock (435–250–3851)

Decorative Stone #2 — Install a (4) Four Inch Depth over Dewitt Pro5 Weed Barrier;
Stone Shall be Used in Shrub Planters Where Shown on Plan; Stone Shall be Washed
Prior to Installation; Stone Shall be 2" Dia. Crushed, Fractured Stone from Staker
Parson Copper Canyon Pit (385–239–0804); Boulders for Wall Shall Match This
Decorative Stone Color (Tan and Angular): Install Stone Between Boulders in Retaining
Wall

4" x 6" Landscape Concrete Curbing — Install Flush to all Concrete Edges between

Lawn and Planting Areas; Curbing Shall be Continuous; Adjust Curbing as Needed to Detail: 4/L3.1

1 11

General Landscape Notes:

[3]

0

1. Plant material quantities are provided for bidding purposes only. It is the contractors responsibility to verify all quantities listed on the plans and the availability of all plant materials and their specified sizes prior to submitting a bid. The contractor must notify the Landscape Architect prior to submitting a bid if the contractor determines a quantity deficiency or availability problem with specified material. The contractor shall provide sufficient quantities of plants equal to the symbol count or to fill the area shown on the plan using the specified spacing. Plans take precedence over plant schedule quantities.

Fiiz Drinks

1,480 Sq. Ft.

FF=4943.50

- 2. Contractor shall call Blue Stake before excavation for plant material.
- 3. Prior to construction, the contractor shall be responsible for locating all underground utilities and shall avoid damage to all utilities during the course of the work. It shall be the responsibility of the contractor to protect all utility lines during the construction period, and repair any and all damage to utilities, structures, site appurtenances, etc. which occurs as a result of the landscape construction.
- 4. The landscape contractor shall examine the site conditions under which the work is to be performed and notify the general contractor in writing of unsatisfactory conditions. Do not proceed until conditions have been corrected.
- 5. The contractor shall provide all materials, labor and equipment required for the proper completion of all landscape work as specified and shown on the drawings.
- 6. See civil and architectural drawings for all structures, hardscape, grading, and drainage information.

3.4°

3.0°

- 7. Contractor safety and cleanup must meet OSHA standards at all times. All contractors must have adequate liability, personnel injury and property damage insurance. Clean—up must be performed daily, and all hardscape areas must be washed free of dirt and mud on final cleanup. Construction must occur in a timely manner.
- 8. All new plant material shall conform to the minimum guidelines established by the American Standard for Nursery Stock Published by the American Association of Nurseryman, Inc. In addition, all new plant material shall be of specimen quality.
- 9. The Owner/Landscape Architect has the right to reject any and all plant material not conforming to the plans and specifications.

10. Any proposed substitutions of plant species shall be made with plants of equivalent overall form, height, branching habit, flower, leaf, color, fruit and culture only as approved by the Landscape Architect.

2

 (\blacktriangle)

4

- 11. It is the contractors responsibility to furnish all plant materials free of pests or plant diseases. It is the contractor's obligation to maintain and warranty all plant materials.
- 12. The contractor shall take all necessary scheduling and other precautions to avoid winter, climatic, wildlife, or other damage to plants. The contractor shall install the appropriate plants at the appropriate time to guarantee life of plants
- 13. The contractor shall install all landscape material per plan, notes and details.

- 14. All existing and relocated trees shall be properly protected. Trees damaged during construction shall be replaced at no cost to the owner.
- 15. Plant names are abbreviated on the drawings, see plant Ischedule for symbols, abbreviations, botanical, common names, sizes, estimated quantities and remarks.
- 16. No grading or soil placement shall be undertaken when soils are wet or frozen.
- 17. Imported topsoil shall be used for landscape areas. The landscape contractor shall perform a soil test on imported topsoil and amend per soil test recommendations. Soil test to be done by a certified soil testing agency. Provide new imported topsoil as needed from a local source. Imported topsoil must be a premium quality dark sandy loam, free of rocks, clods, roots, and plant matter. Topsoil to be installed in all landscaping areas.
- 18. Prior to placement of topsoil in all landscaping areas, all subgrade areas shall be loosened by scarifying the soil to a depth of 6 inches in order to create a transition layer between existing and new soils.
- 19. Provide a 12" depth of imported topsoil in parking islands and an 8 inch depth in all other shrub areas.

- 20. All plant material holes shall be dug twice the diameter of the rootball and 6 inches deeper. Excavated material shall be removed from the site and replaced with plant backfill mixture. The top of the root balls, shall be planted flush with the finish grade.
- 21. Plant backfill mix shall be composed of 3 parts topsoil to 1 part soil pep, and shall be mixed at the planting hole. Deep water all plant material immediately after planting. Add backfill mixture to depressions as needed.
- 22. All new plants to be balled and burlapped or container grown, unless otherwise noted on plant schedule. <u>Container grown trees</u> shall have the strings, burlap or plastic cut and pulled away from the trunk exposing 1/3 of the root ball. For trees in wire baskets, cut and remove the wire basket.
- 23. Upon completion of planting operations, all landscape areas with trees, shrubs, and perennials, shall receive specified stone over Dewitt Pro5 Weed Barrier (Black Woven Fabric). Stone shall be evenly spread on a carefully prepared grade free of weeds. The top of stone should be slightly below finish grade and concrete areas.
- 24. All deciduous trees shall be double staked per tree staking detail. It is the contractors responsibility to remove tree staking in a timely manner once staked trees have taken root. Deciduous tree ties to be V.I.T. Cinche Ties #CT32.
- 25. Install landscape concrete curbing between lawn and shrub areas. Curbing shall be installed level and uniform and shall match top finish grades of concrete walks and curbs. See landscape concrete curbing detail.
- 26. Provide a 4 inch depth of imported topsoil in all lawn areas.
- 27. Sod must be premium quality, evenly cut, established, healthy, weed and disease free, and from an approved source.
- 28. All lawn areas to have uniform grades by float raking. Prior to laying sod, apply a starter fertilizer at a rate recommended by the manufacturer. Sod must be laid with no gaps between pieces on a carefully prepared topsoil layer. Sod to be slightly below finish grade and concrete walks and curbing. The laid sod must be immediately watered after installation. Any burned areas will require replacement. Adjust sprinkler system to assure healthy green survival of the sod without water waste.
- 29. The contractor shall comply with all warranties and guarantees set forth by the Owner, and in no case shall that period be less than one year following the date of completion and final acceptance.






(1)

N

10 Aug, 2021

L1.1



IRRIGATION SCHEDULE

Main Service Line & Other Irrigation Components Are Shown In Paved Or Hardscape Surfaced For Clarity Purposes

ONLY! Install All Irrigation Components

within Landscaped Areas.

Symbol	Manufacturer/Model #	<u>Description</u>	<u>Notes</u>	<u>Detail</u>
Sprayheads				
LCS RCS SST	Rain Bird 1804	4" Pop-Up Sprayhead with 15' Strip Nozzle	Adjust Radius Reduction Screws as Needed to Achieve Appropriate Radii Coverages	13/L3.1
4 6 8 10 4 6 8 10 12 15 18 12 15 18	Rain Bird 1804	4" Pop-Up Sprayhead with 15' Strip Nozzle	Adjust Radius Reduction Screws as Needed to Achieve Appropriate Radii Coverages	13/L3.1
Valves				
	Rain Bird 150—PESB	Lawn Remote Control Valve with Scrubber Technology	1 Inch Size; Install in Standard Valve Box with 3" Depth of Gravel over Weed Barrier; Install with Water Proof Wire Connectors	14/L3.1
	Rain Bird XCZ-100-PRB-COM	Drip Remote Control Valve Kit	1 Inch Size; Install in Standard Valve Box with 3" Depth of Gravel over Weed Barrier; Install with Water Proof Wire Connectors	6/L3.1
	Rain Bird 44-NP	Quick Coupler with Non-Potable Cover and Swing Joint	1 Inch Size; Install in 10" Round Valve Box with 3" Depth of Gravel over Weed Barrier	7/L3.1
$\langle \overline{D} \rangle$	Matco-Norca 759	Manual Drain Ball Valve	1/2 Inch Size; Install at End of the Mainline in a 10" Round Valve Box with Weed Barrier and a Gravel Sump	10/L3.1
Drip				
	PVC Pipe To Drip Tubing	Provide Connection Fittings	Install 1" Feeder Line To All Drip Areas	11/L3.1
	Rain Bird XBS-700 Rain Bird XQ-100 Rain Bird XB-20PC Rain Bird TS025 Rain Bird DBC-025 Rain Bird MDCFCAP	1/2" Distribution Tubing — Pipe shown on Plan is Sci 1/4" Distribution Tubing — Install one per Emitter Xeri—Bug Emitter (2 Gal/Hr.) — 1 per Perennial/Orna Tie Down Stake — Tubing to be Staked every 3' Diffuser Bug Cap — Install one per Emitter Removable Flush Cap — Install at the End of Each L	amental Grass, 2 per Shrub, & 4 per Tree	5&9/L3.1
P.O.C. Com	ponents			
	Mueller Oriseal Mark II	Stop and Waste Valve	1 1/2 Inch Size; Install in 10" Round Valve Box with Weed Barrier and Gravel Sump	16/L3.1
F	Amiad Tagline Canister Filter	Secondary Water Filter	1 1/2 Inch Size; Filter with 155 Mesh; Install in Regular Size Box with Weed Barrier and 3" Depth of Clean Gravel; Filter Shall be Installed Underground	15/L3.1
Pipes				
	Schedule 40 PVC	Mainline Pipe	1 1/2 Inch Size; See Plan for Locations; Schedule 80 Fittings Shall be Used for Mainline Components	8/L3.1
	Schedule 40 PVC	Lateral Line Pipe	See Plan for Pipe Sizes; Pipes Unmarked Shall be 1 Inch; Minimum Pipe Size Shall be 1 Inch for PVC Pipe	8/L3.1
Controller &	& Accessories			
С	Rain Bird ESP4MEI Rain Bird ESPSM3	4 Base Station Indoor Controller 3 Station Expansion Module	See Plan for Location of Controller; Coordinate Power Supply With Building Electrical Contractor	12/L3.1
Sleeving				
===	Schedule 40 PVC	Provide for Irr. Mainlines, Laterals, and Controller Wire Located Under Concrete and Asphalt Paving at Specified Depths	Contractor Shall Coordinate the Installation of Sleeving with the Installation of Concrete Flatwork and Asphalt Paving; All Sleeving Shall be by the Landscape Contractor Unless Otherwise Noted	17/L3.1
		Valve Number Valve Flow		

General Irrigation Notes:

must occur in a timely manner.

0

- Prior to construction, the contractor shall be responsible for locating all underground utilities and shall avoid damage to all utilities during the course of the work. It shall be the responsibility of the contractor to protect all utility lines during the construction period, and repair any and all damage to utilities, structures, site appurtenances, etc. which occurs as a result of the landscape construction.
- 2. The irrigation contractor shall examine the site conditions under which the work is to be performed and notify the general contractor in writing of unsatisfactory conditions. Do not proceed until conditions have been corrected.
- 3. The contractor shall provide all materials, labor and equipment required for the proper completion of all irrigation work as specified and shown on the drawings.
- 4. See civil and architectural drawings for all structures, hardscape, grading, and drainage information.
 5. Contractor safety and cleanup must meet OSHA standards at all times. All contractors must have adequate liability, personnel injury and property damage insurance. Clean—up must be performed daily, and all hardscape areas must be washed free of dirt and mud on final cleanup. Construction
- 6. The Owner/Landscape Architect has the right to reject any and all irrigation material not conforming to the plans and specifications.
- 7. The contractor shall install all irrigation material per plan, notes and details.
- 8. Irrigation system components must be premium quality only and installed to manufactures requirements and specifications. The contractor is responsible for checking state and local laws for all specified materials and workmanship. Substitutions must be approved by landscape architect. Provide owner and maintenance personnel with instruction manual and all products data to operate, check, winterize, repair, and adjust system.
- Irrigation system guarantee for all materials and workmanship shall be one year from the time of final project acceptance. Guarantee will include, but is not limited to winterizing, spring activation, repair, trench setting, backfilling depressions, and repairing freeze damage.
- 10. Irrigation system check must be done before the system is backfilled. Irrigation mainline and each control valve section must be flushed and pressure checked. Assure the complete system has no documented problems and full head to head coverage with adequate pressure for system operation. Adjust system to avoid spray on building, hardscape, and adjacent property. Any problems or plan discrepancies must be reported to the landscape architect.

11. Irrigation laterals must be schedule 40 P.V.C. with schedule 40 fittings. one (1) inch minimum size. Solvent weld all joints as per manufactures specifications for measured static p.s.i. Teflon tape all threaded fittings. The minimum depth of lateral lines shall be twelve (12) inches. Adapt system to manual compression air blowout.

2" Sleeve

2" Sleeve

- 12. Irrigation mainline that are 2" and smaller mainlines shall be schedule 40 PVC pipe with schedule 80 fittings. Solvent weld all joints as per manufactures specifications for measured static pressure. Use teflon tape on all threaded joints. Line depth must be twenty-four (24) inches minimum.
- 13. Install dielectric fittings whenever dissimilar metals are joined.
- 14. Design locations are approximate. Make minor adjustments necessary to avoid plantings and obstructions such as signs and light standards. Maintain 100(%) percent irrigation coverage of areas indicated.
- 15. Controller valves to be grouped together wherever possible. Install valve boxes with long side perpendicular to walk, curb, lawn, building or landscape features. Valve boxes to conform with finish grades.
- 16. Control valve wire shall be #14 single conductor: white for common wire, red for hot wire and blue for the spare wire. Provide (2) two spare wire that runs the length of the mainline and to the controller. All wiring shall be UF-UL rated. All connections shall be made with water tight connectors (DBR/Y or equivalent) and contained in control valve boxes. Provide 36" extra wire length at each remote control valve in valve box. Install control wiring with main service line where possible. Provide slack in control wires at all changes in direction.
- 17. Control valve size, type, quantity, and location to be approved by landscape architect. install in heavy duty plastic vandal proof box. Size boxes according to valve type and size for ease of maintenance and repair. Install one (1) cubic feet of pea gravel for sump in base of boxes. Boxes to be Carson Brooks or equal.
- 18. Quick couplers shall be a Rain Bird 44-NP (Non-Potable Cover) with a 1 inch Lasco swing joint assembly. Support with rebar in each retainer lug. Install where shown on the plans.
- 19. Irrigation system backfill must occur only after system check is completed as specified. Use only rock free clean fill around pipes, valves, drains, or any irrigation system components. Water settle all trenches and excavations.
- 20. All irrigation pipe running through walls, under sidewalk, asphalt, or other hard surface shall be sleeved prior to paving. It is the irrigation contractors responsibility to coordinate sleeving with concrete and pavement contractors. Sleeves will be schedule 40 P.V.C. The depth for mainline sleeves shall be twenty—eight (28) inches minimum. Depth for lateral sleeves shall be sixteen (16) inches

- minimum. Sleeves shall be a minimum of two sizes larger than the pipe to be sleeved. All valve wiring shall be contained in separate sleeving.
- 21. Plans are diagrammatic and approximate due to scale. where possible, all piping is to be installed within the planting areas. No tees, ells, or changes in direction shall occur under hardscape.

1" Secondary Service Line and Meter; See Utility Plan for Exact

- 22. It is the contractors responsibility to verify all quantities based upon the plan prior to completion of a construction cost estimate.
- 23. The irrigation contractor shall flush and adjust all sprinkler heads for optimum performance and to prevent possible overspray onto walks, roadways, and/or buildings as much as possible. This shall include selecting the best degree of arc to fit the site and to throttle the flow control of each valve to obtain the optimum operating pressure for each system. All mainlines shall be flushed prior to the installation of irrigation heads.
- 24. All sprinkler heads shall be set perpendicular to finish grade of the areas to be irrigated and shall be installed 6-8" from buildings walls, or within 4" of pavement, curbs, or header edges.
- 25. Drip system piping shall consist of a rigid schedule 40 PVC pipe distribution system connecting drip irrigated planter areas. Poly tubing or drip line shall be run off the rigid PVC in each planting area or island with a PVC to poly tubing adapter. No poly tubing shall run under pavement.
- 26. Electrical power source at the controller location shall be provided by electrical contractor.


 Contractor shall verify location of controller prior to installation with owner.
- 27. Provide and install all manufacturer's recommended surge and lighting protection equipment on all controllers.
- 28. All lines shall slope to manual drains (see details). If field conditions necessitate additional drains, these drains shall be installed for complete drainage of the entire system. Provide a gravel sump under each drain. All drains shall be a minimum of 6" below grade.
- under each drain. All drains shall be a minimum of 6" below grade.

 29. Upon completion and approval of irrigation system, irrigation contractor to provide the owner with two sets of drawings indicating actual location of piping, valves, sprinkler heads, wiring, and zones.
- 30. An irrigation zone map shall be provided in a protective jacket and be kept with the main irrigation controller. The map shall show all approved irrigation and include all zone valve locations.
- 31. It shall be the responsibility of the sprinkler contractor to demonstrate to the Owner the proper winterization and start—up procedures for the entire system prior to final payment.

VALVE SCHEDULE

VALVE	STATION	VALVE SIZE	IRRIGATION TYPE	FLOW (GPM)	PSI	PSI @ POC	PRECIP. RATE
	1	1-1/2"	Turf Spray	18.62	<i>34.5</i>	<i>38.24</i>	1.83 in/h
	2	1-1/2"	Turf Spray	19.25	34.52	36.39	3.45 in/h
	3	1-1/2"	Turf Spray	16.97	<i>34.55</i>	36.01	3.45 in/h
	4	1-1/2"	Turf Spray	13.98	<i>34.22</i>	<i>35.21</i>	3.4 in/h
	5	1"	Area for Drip Emitters	4.63	34.0	34.08	1.04 in/h
	6	1"	Area for Drip Emitters	<i>3.16</i>	32.22	32.23	0.63 in/h
	7	1-1/2"	Turf Spray	15.24	<i>34.3</i>	<i>34.88</i>	1.51 in/h






Designed by: SY
Drafted by: KF
Client Name:

21-003 IR

10 Aug, 2021

L2.1



To whom it may concern:

Subject: Install 4-way stop at 400 south and 100 west

There are three homes at this intersection with children playing in the area. Also, during the school year, there are three school buses that stop near the intersection. People coming to and from Morley Meadows subdivision and the cul-de-sac at the top of the street drive at speeds much faster that the posted 25 mph . When the speed cart was set up on 100 west, I saw speeds well in excess of 35 mph consistently.

With more people walking around the block on the road side, the traffic doesn't even slow down or move over when passing these people. Sometimes the drivers will honk at the people walking with kids on weekends and also work days.

With school starting soon, children will be walking and riding bikes to the grade school, especially with the price of gas right now. As there are no sidewalks in the area, it makes it even more dangerous.

Center street, one block east, is a main road. Also 200 West, one block west, is a main road going out to the red barn and the south exit to the freeway. 100 west is not a main traffic road but a residentail street.

For these reasons, I am asking for a four-way stop to be placed at the intersection of 400 south and 100 west for the safety of our children and the people who live on this street.

Thank you for your consideration.

Terry Rasmussen 350 South 100 West Santaquin, Utah 84655 801-369-0502 or 801-369-0575 Santaquin City Corporation

Request for Traffic Control Device

Community Development Department 275 West Main Street, Santaquin, Utah (801) 754-1011 www.santaquin.org



<u>Note:</u> This application, in addition to all required information and exhibits, must be turned into the Community Development Department 14 days prior to a regularly scheduled Development Review Committee meeting for it to be on an agenda. All submitted proposals will be reviewed in accordance with Santaquin City Code 6.20.

<u>Meetings:</u> Development Review Committee meetings are held the 2nd and 4th Tuesdays of each month. The meeting is held in the City Offices, located at 275 West Main. Depending on the date of application, the Community Development Department will inform you of the day and time in which your request will be considered by the Development Review Committee.

Applicant Information	
Applicant Name:	
Shanna Stilson Telephone: Alternate Telephone:	Email:
801.885.0584	Shannastilson@gmail.com
Requested Traffic Control Device Information	
Address of Proposed Traffic Control Device:	
Address of Proposed Traffic Control Device: MO N. 200 E (6 r 770 N or 730 N.) Type of Traffic Control Device Requested:	
Crosswalk, School Zones Signs,	
Description and Justification for the Request	
There is a steady stream of C	ars before and
Mere 15 h standy streether 1	1 1 0100 (2001
after school on 200 E. Kids that	need to Choss 2006
have no safe way of doing so.	I have watched
multiple times when kids have	to jot across inbetween
the stream of cars, nearly of	Hing hit It is
irresponsible of our city, school d	istrict (all in charge) to
not have a crosswalk or any 5	ignage PLEASE
do something.	
Applicable Exhibits ()	
Please attach any drawing, map, or other information that can illustrate your requ	uest.

Santaquin

DRC Meeting Minutes

Tuesday, August 10, 2021

DRC Members in Attendance: Building Official Randy Spadafora, Police Chief Rod Hurst, Public Works Director Jason Callaway, Fire Chief Ryan Lind, Community Development Director Jason Bond, Assistant City Manager Norm Beagley and Engineer Jon Lundell.

Others in Attendance: Officer Russ Woodland, City Manager Ben Reeves, Operations Manager Dennis Marker, Staff Planner Ryan Harris.

Pete Evans representing Flagship Homes.

Steve Larsen attending via zoom, Ken Berg and Scott Larsen representing the Grey Cliffs Subdivision.

Brad Gilson (Attending Via Zoom) representing the Summit Ridge Commercial Subdivision.

John Caldwell with Revere Homes and Kyle Spencer with Northern Engineering Representing the Orchards F-6 Subdivision.

Mr. Lundell called the meeting to order at 10:00 a.m.

Santaquin Estates Subdivision Concept Review

A concept review of a proposed 86-lot subdivision located at approximately Main Street and 900 E. A zone change will be discussed during this review.

Mr. Lundell explained that this subdivision proposal includes commercial lots as well as residential lots. R-10 sized lots as well as PUD sized lots associated with this plan.

Building Official: Mr. Spadafora asked if there are existing contours to know how steep the roads will be. Mr. Lundell stated that they have potential contours, but they have not provided final grading.

Police: Chief Hurst asked why the extension of 900 East is designed as a curve and not a T? Mr. Lundell explained that exit 240 is tight with the current traffic flow. UDOT is looking at proposing some solutions to solve that. One issue UDOT has identified is how close the intersection of SR 198 and Highland Drive is. This proposal is one solution that has been discussed with UDOT; to shift the existing roads and help move traffic away from the freeway entrance. Chief Hurst pointed out that there would be limited street parking for any of the units because of the curve.

Public Works: Mr. Callaway stated that he likes the way this proposal improves the connectivity on the bench. He thinks this would help alleviate traffic concerns on 900 E.

Planning and Zoning: Mr. Bond expressed concern with the lots fronting Main Street. He indicated that staff has talked to the developer about providing a better lot configuration on the southeast corner of Main Street. He noted that there is a need for a storm drain retention within the development and that corner maybe a good location for it. Mr. Bond pointed out that there is currently no guest parking

DRC Meeting Minutes
August 10, 2021
Page 2 of 7

shown for the townhome units. The garages can be counted as two stalls if they are 24 feet by 24 feet in dimension.

Mr. Bond noted that the current phasing plan splits up the development into phase 1 which includes R-10 standard sized lots and phase 2 would require a rezone to a PUD. He explained that a PUD doesn't come in to affect until a development agreement is approved by the city council. Mr. Bond suggested that the proposed phases be done as two separate projects rather than two phases. He also asked the developer to mitigate some of the impacts that this development would create by making a truck route to avoid heavy equipment moving through the adjacent neighborhoods. Mr. Pete Evans answered that they typically come up with an internal phasing plan to separate construction traffic from existing homes. He expressed concern with proposing this development as two different projects due to the perception of density. He recognized the value of realigning the Frontage Road for the city. He stated that having two projects, one that matches the zoning and the other which doesn't, could cause the perception that the density looks higher as a separate project.

Administration: Mr. Beagley noted that there is a misconception by the public that only a sliver of land is needed for a planned debris basin in the area. The planned debris basin may utilize the area proposed to be dedicated to the city as part of a potential PUD. He clarified that it is unknown how much of this piece is needed for the debris basin. He stated that whatever amount is needed it will likely render the rest of the one and half acres of that property undevelopable for homes. The city could potentially acquire roughly 4.7 acres from the developer between the need for property for the debris basin, the Frontage Road Realignment, and 900 East (being a wider width than a normally required local road). This could either be acquired through a purchase by the city or through a PUD designation/negotiation.

Engineering: Mr. Lundell stated that some of the proposed lots that abut the standard R-10 zoning are not shown as the appropriate sizes. The homes that have dual frontage on 900 East may not have a driveway access onto 900 East. He communicated that written approval will be required for the power line easements from Rocky Mountain Power. Mr. Lundell indicated that the trail layout would need to be shown as plans move forward. He expressed concern regarding lot 18 not having enough buildable space due to the power line easement and lack of frontage on the secondary side of the lot. He also noted there is a waterline pressure break between pressure zones in the area and stated that PRV's would be required. Mr. Beagley brought up the potential for waterline looping from 900 E. to Main Street.

Mr. Bond thanked Flagship Homes for taking a step back and considering the Frontage Road Re-Alignment as this information was recently received from UDOT.

No comments from Fire.

No action taken as this is just a concept review to provide comments/feedback to the developer.

Grey Cliffs Subdivision Concept Review

DRC Meeting Minutes
August 10, 2021
Page 3 of 7

A concept review of a proposed 217-lot residential subdivision with approximately 25.99 acres of commercial space; located east of State Road 198 and approximately 600 N. A zone change will be discussed during this review.

Police: Chief Hurst asked if these streets will be collector streets? Mr. Lundell answered that it's proposed that Grey Cliff's Drive (the main road through the development) will be a collector sized road, the others will be standard local road widths. Mr. Berg added that High Bluff Street to Grey Cliffs Drive, and Abundance Ave will also collector street sized. He noted that there will be a wide pedestrian path along Grey Cliffs Drive as well. Mr. Lundell explained that the road widths will be provided with the preliminary plan.

Public Works: Mr. Callaway noted the different pressure zones, and the need for boosters and potential lift stations. He stated that he is excited to see how they address these issues.

Fire: Chief Lind explained that the some of the lots will be in a Wild Land Urban Interface (WLUI), He expects it to include any lots east of High Bluff Street. These lots would have to meet certain fire-resistant construction standards and or have fire sprinklers. He indicated that they would work with the developer regarding these requirements.

Planning and Zoning: Mr. Bond suggested that there be collector roads connecting to Grey Cliffs Drive on either side. He noted that some of the lots have double frontage and asked that the access of those lots be provided on the minor street. He asked that this information be added onto a plat note as well. Mr. Bond explained that it is anticipated that an amendment will be made to the development agreement. It is also expected that the developer will dedicate part of the mountain area to the City for natural open space as well as improving some mountain biking trails. Mr. Bond added that the zoning would need to be worked out as part of the development agreement.

Administration: Mr. Beagley explained that written approval will be required from UDOT prior to the City granting final approval. Specifically, for the turn lanes, into the subdivision. Mr. Berg answered that they still need to finalize the details with the traffic study, but they have been working with UDOT. Chief Hurst noted that his main concern is the entrance to the north of the subdivision because of the hill.

Engineering: Mr. Lundell reiterated that the developer needs to ensure that the double frontage lots have appropriate noting on the plats and clear labeling. He explained that city code requires perimeter fencing for developments that abut agricultural uses. He added that the items identified in the geologic hazard investigation must be addressed. Mr. Lundell indicated that a debris basin may be needed to protect the homes. He noted that a fault line runs through the development, because of this a proposal will be needed regarding how the waterlines will be built to better withstand an earthquake. He noted that there is water dedication requirement required for all subdivisions. Mr. Lundell clarified that this subdivision is within a hillside overlay zone and that city code will need to be followed regarding this.

Mr. Bond asked that the developer provide more information regarding what would be allowed within the conservation easement. Mr. Lundell pointed out that it is the City's understanding that a large portion of the northwest area of the development will need a sewer lift station that would serve that

DRC Meeting Minutes
August 10, 2021
Page 4 of 7

portion of the development. He added that there are a few roads which exceed the maximum road length for a dead-end road. He clarified that dead end roads can be a maximum of 500 feet, with maximum of 750-foot that would require approval from the City Council. Mr. Lundell indicated that an easement would need to be worked out with the property owner to the east of the development. He added that the widths of the lots need to have the appropriate frontages for the zone.

No comments from Building Official.

No action taken as this is just a concept review to provide comments/feedback to the developer.

Cedar Point Plat F at Summit Ridge Concept Review

A concept review of a proposed 2-lot Subdivision located at 1371 West Cedar Pass Drive.

Mr. Bond explained that lot number one has an existing home on it. A boundary line agreement will be needed on the south property line to give the applicant the frontage needed for their proposed two lots.

Building Official: Mr. Spadafora asked if the lots meet the required frontage? Mr. Lundell confirmed that they are meeting the 80-foot requirement for the City's R-10 land use regulations.

Public Works: Mr. Callaway asked if since the utilities are stubbed for only one lot, additional utility services would need to be provided for the new lot. Mr. Beagley explained that since this is concept it is unknown at this point how many road cuts would be needed, but that each lot would need to have their own separate utility connections.

Planning and Zoning: Mr. Bond stated that the Summit Ridge Development agreement expired last year so this proposal is subject to the R-10 regulations. He asked that the applicant coordinate with the HOA.

Engineering: Mr. Lundell explained that a note needs to be added onto the plat, stating that this is an agricultural community. He added that full separate utility laterals will be required for each lot in the appropriate location.

No comments from Police, Fire and Administration.

No action taken as this is just a concept review to provide comments/feedback to the developer.

Summit Ridge Commercial Subdivision Preliminary Review

A preliminary review of a proposed 8-lot commercial subdivision located South of the intersection of Summit Ridge Parkway and South Ridge Farms Road.

Building Official: Mr. Spadafora indicated that he will provide the addressing for this development.

DRC Meeting Minutes
August 10, 2021
Page 5 of 7

Police: Chief Hurst asked if there will be traffic control signs? Mr. Lundell answered that they have not shown locations yet. Mr. Gilson indicated that they should be shown on subsequent sheets.

Fire: Chief Lind explained that since this is a commercial subdivision the hydrants need to be spaced every 300 feet (rather than 500 feet). He noted that currently hydrants sit on the south side of Summit Ridge Parkway or the east side of the Mona Road. He suggested that the developer move every other hydrant on the opposite side of the road. So, all the hydrants aren't located off major roads which would be closed in the event of a fire. Chief Lind added that the hydrants need to be looped so there are no dead-end hydrants. Mr. Gilson stated that the hydrant spacing on the plans is now 300-foot.

Administration: Mr. Beagley asked that the additional hydrants they are adding to meet the 300-foot requirement be shown on the west side of Highway 191 and the south side of Summit Ridge Parkway. Mr. Gilson stated that that can be done.

Engineering: Mr. Lundell pointed out that there is an existing storm water retention basin on lot H. He explained that the storm drain volume that is already existing needs to be taken into consideration and preserved. Mr. Beagley explained that there has been some discussion with the developer regarding underground retention in which the city could possibly participate, through impact fees. He asked that this is noted on the plans.

Mr. Lundell indicated that the proposed phasing is unclear, he asked that clarification be provided on how the subdivision, particularly the roadway improvements will be phased. Mr. Gilson asked what improvements would be required for lot A? Mr. Beagley stated that it is anticipated that everything adjacent of lot A be improved as well as any accesses to the lot. Mr. Bond suggested that the more infrastructure that can be put in at once the better to avoid a piece meal road.

Mr. Lundell indicated that the storm drain report is needed to verify that the existing retention is adequate for the extension of highway 191, etc. He informed the developer that the minimum pipe size for a P.I. line is 6 inches. He explained that the waterline that extends along lot D exceeds the 500-foot maximum allowed in code. He added that if the developer would like to have it extend to the 750-foot maximum it would need approved by the City Council. Mr. Gilson asked if the waterline could be stubbed down the frontage of lot D? Mr. Beagley noted that the waterline could extend to the southern border of lot D, it doesn't have to go down the road. Mr. Lundell noted that all the utilities need to be stubbed to all lots. He explained that the valve cluster for P.I. needs to extend to the property lines, per Santaquin City Standards. Mr. Lundell added that a written legal description will be required for the waterline easements.

Mr. Callaway asked if high mountain runoff water comes through near the Ahlin pond, if it would extend to the lots east of Mona Road. Mr. Beagley explained that there is a culvert in that area and water was seen there in 2019 entering approximately onto lot A. He added that the property owner is aware of this situation, and plan provisions are being made accordingly. Mr. Beagley explained that NRCS is looking at the reconstructing the debris basin at the mouth of Santaquin Canyon that would alleviate this issue, but timing for such is a long way out.

DRC Meeting Minutes
August 10, 2021
Page 6 of 7

No comments from Planning and Zoning and Public Works.

Motion: Mr. Beagley motioned to recommend Preliminary approval of the Santaquin Commercial Subdivision with the condition that the redlines be addressed prior to moving forward to Planning Commission. Mr. Spadafora seconded. The motion passed unanimously in the affirmative.

Orchards F-6 Final Plat Review

A final review of a proposed 7-lot subdivision located at approximately Ginger Gold Road and 260 W.

John Caldwell with Revere Homes, Kyle Spencer with Northern Engineering Representing Orchards F-6.

Mr. Lundell outlined that this is within the Orchards Development on the North end of town.

Building Official: Mr. Spadafora indicated that he has assigned addressing to match the grid which will be included on redlines.

Police: Chief Hurst asked for confirmation that these are public roads. Mr. Lundell confirmed that both Ginger Gold Road and 260 West are public roads.

Public Works: Mr. Callaway asked if Ginger Gold Road will tie into the existing portion of the road? Mr. Lundell answered that there will be a gap, until the subdivision to the east is Constructed. Mr. Bond noted that the developer is currently working on that development area also.

Engineering: Mr. Lundell explained that Orchards F-5 has been approved and is under construction. He added that there is a modification between the lot boundary of Orchards F-5 and F-6 which needs to be updated on both plats prior to recordation. He noted that an additional plat note will be required stating that Santaquin is an agricultural community that supports agriculture. Mr. Lundell explained that the culinary water line and P.I. are shown reversed from City Standards and needs to be updated. He noted that city records show different locations of the existing culinary and P.I. water lines from what is shown. He offered to provide GIS data if needed, upon request.

Mr. Beagley explained that the trail needs to tie in closer to the railroad tracks and meet the existing asphalt trail and still show pedestrian access to the south. Mr. Lundell explained that a P.I. drain will be needed at the dead end of Ginger Gold Road since it won't be continued until later. He asked that the streetlights and signage be shown on the plans. Mr. Callaway pointed out that the sewer Force Main is in this area as well. Mr. Lundell indicated that staff will provide the developer with GIS data so existing utilities can be shown on the plans. He explained that the developer will need to provide a method to control the storm drainage at the dead-end road to keep the curb from washing out. He clarified that RCP pipe is not required by City code. Mr. Lundell explained that a storm drain report is required, showing that the additional storm water generated by this subdivision can be handled by the existing facilities to the east. He added that all curb inlets need a 3-foot sump.

No comments from Fire, Planning and Zoning and Administration.

DRC Meeting Minutes
August 10, 2021
Page 7 of 7

Motion: Mr. Bond motioned to approve the final plat for Orchards F-6 with the condition that all engineering redlines be addressed. And that the developer work with staff regarding the trail alignment from the corner of the intersection to the southwest of the development. Mr. Callaway seconded. The motion passed unanimously in the affirmative.

MEETING MINUTES APPROVAL

July 27, 2021

Motion: Mr. Beagley motioned to approve the DRC meeting minutes from July 27, 2021. Chief Lind seconded. The motion passed unanimously in the affirmative.

ADJOURNMENT

Mr. Bond motioned to adjourn at 11:32 a.m.

on Lundell, City Engineer	Kira Petersen, Deputy Recorder	