



# CITY OF SWEET HOME CITY COUNCIL AGENDA

August 25, 2020, 5:30 PM  
Sweet Home City Hall, 3225 Main Street  
Sweet Home, OR 97386

WIFI Passcode: guestwifi

PLEASE silence all cell phones – Anyone who wishes to speak, please sign in.

## Mission Statement

The City of Sweet Home will work to build an economically strong community with an efficient and effective local government that will provide infrastructure and essential services to the citizens we serve. As efficient stewards of the valuable assets available, we will be responsive to the community while planning and preparing for the future.

---

## Meeting Information

The City Council will hold a City Council Work Session at 5:30 p.m. in the City Council Chambers at City Hall, 3225 Main Street. In order to protect residents, staff, and elected officials due to the novel COVID-19 virus, the frequency and length of public meetings, including the City Council, boards and commissions, will be minimized. Non-urgent and non-essential City business with expected public feedback will be postponed whenever possible. Individuals attending public meetings in person will be limited to the first six people, required to maintain appropriate social distancing, (6-ft.) and be free of symptoms related to COVID-19. The City of Sweet Home City Council is streaming the meeting via the Microsoft Teams platform and asks the public to consider this option. There will be opportunity for public input via the live stream. To view the City Council meeting live, online visit [live.sweethomeor.gov](https://live.sweethomeor.gov). If you don't have access to the internet you can call in to 541-367-5128 and you'll be asked to choose option #1 to be logged in to the call.

This video stream and call in options are allowed under Council Rules, meet the requirements for Oregon public meeting law, and has been approved by the Mayor as Chairperson of the meeting. All votes will be conducted by Roll Call Vote.

## Call to Order

## Roll Call

## Old Business:

- a) [Information Only - Wastewater Treatment Plant Improvements 60% Design](#)

## Adjournment

# Sweet Home WWTP Improvements Project 60% Update



*murraysmith*




August 2020

# Project Foundation

**“...make decisions that do the most good, for the most people, for the longest period of time”**

*Source: 2017-18 City Council Goals*

# Agenda



# Introductions

The background features a dark blue upper section. Below it, there are abstract shapes: a light blue wavy band and a large green area that rises from the bottom left towards the right, resembling a hill or a landscape feature.

# Team Introductions



Greg Springman  
Public Works Director



Steven Haney  
Utility Manager



Tom Perry, PE  
Principal-in-Charge



Austin Rambin, PE  
Project Manager



Miaomiao Zhang, PE  
Design Manager



Trish Rice  
Engineering Technician

CITY



Patrick Davis, EIT  
Staff Engineer



Jessica Cawley, PE  
Staff Engineer



Justin Moman, PE  
Staff Engineer

MURRAYSMITH

# Project History



# Original Facilities Plan Review


City of Sweet Home  
**Wastewater Facilities Plan**

December 2016


**Original Recommended Plan:**

- \$42 Million over 30 years
- Separate Peak Flow Process
- Limited Rehabilitation

**Brown and Caldwell**  
100% Environmental | Employee Owned | Offices Nationwide | BrownandCaldwell.com





# Continued Collection System Focus



**Peak hour flows do not account for future population growth or expansion of the City's service area**

# Continued Collection System Focus

- Allow for future growth
- Address aging collection system
- Maintain WWTP Flow < 12 MGD




**\$3 - 6M of targeted collection system rehabilitation:**

- Remove ~2 MGD of RDII over next 20 years
- To be completed in-house by City staff
- City working on manhole sealing now

# Existing WWTP Review


Upper Plant –  
Expansion Area



Lower Plant –  
Existing Facility Area

# Existing WWTP Challenges

- Secondary only, complete mix process
- No Headworks (rags everywhere)
- Early 1990's upgrade added tertiary sand filters
- Undersized CCB
- Inadequate Aerated Sludge Storage Basin
- Dewatering Facility with significant code violations
- Limited SCADA/automation




**Multiple DEQ fines  
for permit violations  
in past few years**

# “3R” Asset Management Approach


- **Rehabilitate existing structures**
- **Reuse existing assets**
- **Re-purpose existing processes/areas**



# Rehabilitation @ Half the Cost of New Construction – if done timely!



# Targeted Avg. Monthly Wastewater Rate





# 60% Design Update

Sweet Home WWTP

# Project Status Update

- Key Milestones
  - 60% Review Period – now
  - 90% Design Development – this fall
  - 100% Design Development and Regulatory Review – early 2021
  - Bidding – Summer 2021
  - Construction – Summer 2021 to Fall 2023
- Funding
  - Required VE Study – RFP soon
  - USDA & DEQ – application process now
  - USDA PER/ER review to follow complete application submission
- Permitting
  - Anti-degradation Evaluation for Mass Load Increase
  - Working to get NPDES Permit Renewal expedited with DEQ

# WWTP 60% Site Plan



# 60% Design – “3R” Elements

## “3R” Elements:

- Influent Pump Station
- Aeration Basin Expansion
- Secondary Clarifiers
- Chlorine Contact Chamber
- Aerobic Digester
- South Electrical Room



# Site Flyover

Forthcoming

# Administration Building



# Administration Building



**Partial Front Elevation**  
1/4" = 1'-0"

# Maintenance Building



- Service bay for vehicle storage and maintenance
- Shop for in-house equipment maintenance
- Storage space for spare parts and records


# Headworks, Dewatering & Cake Storage



- Three processes combined
- Protects downstream mechanical equipment
- Reduces volume of biosolids
- Storage for biosolids prior to disposal




# Process Building




- Primary Sludge Pump Station, Blower Room, & North Electrical Room
- Removes solids from liquid stream
- Houses equipment critical for biological treatment process
- Stores electrical equipment at ideal environmental conditions

# Digester Complex



- Solids stream treatment
- Primary & Secondary Digesters
- Building in center for equipment



# Cost Update

	20% Schematic Design <sup>(1)</sup>	60% Design Development <sup>(2)</sup>
Influent Pump Station	\$2,100,000	\$1,600,000
Headworks Screening and Grit Removal	\$2,900,000	\$3,200,000
Primary Clarifier	\$1,700,000	\$2,100,000
Aeration Basin Modifications	\$3,500,000	\$4,900,000
Secondary Clarifiers	\$2,400,000	\$2,200,000
Tertiary Filter	\$1,850,000	\$1,400,000
UV Disinfection	\$1,300,000	\$1,500,000
Solids Thickening	\$900,000	\$700,000
Solids Digestion	\$3,100,000	\$3,400,000
Dewatering and Biosolids Storage	\$1,300,000	Included in Headworks
Civil Site Improvements	\$1,500,000	\$2,200,000
New Administration/Lab Building	\$1,250,000	\$1,800,000
New Maintenance Building	-	\$1,000,000
Offsite Class A Biosolids Composting Facility	\$1,600,000	\$1,600,000
Electrical and Instrumentation	\$2,800,000	\$2,500,000
<b>Total OPPC</b>	<b>\$28.2 M</b>	<b>\$30.1 M</b>

(1) Costs include markups for General Conditions (8%), Mobilization (8%), Contractor O&P (12%), Contingency (30%), and Engineering, Legal, and Contract Administration (25%)

(2) Costs include markups for General Conditions (8%), Mobilization (8%), Contractor O&P (12%), Contingency (20%), and negotiated Engineering, Legal, and Contract Administration fees

# From Schematic Design to Now

- Primary Clarifier Cover – Keeping Odors at Bay = Good Neighbor
- Advanced Process Control Valves – More Efficient, Better Treatment
- Thickening Building – Changing Materials and a Focused Approach
- Drying Beds – Operator Flexibility and Breathing Room
- Administration Building – Futureproofing Through Expanded Scope
- Maintenance Building – Value Added with Improved Functionality
- Subsurface Conditions – A Clearer Picture Beneath Our Feet

# Providing for future WWTP expansion beyond 20 year planning horizon

- Additional channel for additional influent screen in Headworks
- Provide piping for future Primary Clarifier if needed
- Providing for future Aeration Basin Capacity expansion
- Provide for future filter capacity expansion
- Provide additional office space in Admin Building



# Long Term O&M Considerations

**“...make decisions that do the most good, for the most people, for the longest period of time”** *(2017-18 City Council Goals)*

- “3R” Approach brings aging facility back to life for 40-50 years
- Full plant automation reduces staffing requirements and cost
- Upgrades provide for cost-effective expansion in future to address unforeseen challenges (e.g. NPDES Permit, Industrial Growth, etc.)
- High quality compost eliminates \$130k/year in landfill costs and provides a valuable end product for use by the City and residents

# Project Funding Update

- **City Funds.** With WW rate increase, the City is building considerable reserves to support the project.
  - Currently projecting ~\$7M in local funds contribution
- **Earmark Funding.** City is currently utilizing a \$2M earmark from the Oregon State Legislature. Another \$7M earmark was approved with Senate Bill 5723 a few weeks ago.
- **USDA Grant Discussions.** Discussions with USDA indicate a grant of up to 25% of the unfunded balance may be available.
- **ETO Incentives.** Currently working with the Energy Trust of Oregon to identify energy efficiency incentives for the project. \$330k incentives for Primary Treatment and Aeration Basin blowers in final stages of approval.
- **Loans.** Discussing interim loan funding using DEQ's State Revolving Fund.


The background features a dark blue base with a diagonal line rising from the bottom left. Above this line, there are three overlapping shapes: a large green trapezoid on the left, a teal trapezoid on the right, and a blue trapezoid in the center that overlaps both the green and teal shapes.

# Schedule and Next Steps

Sweet Home WWTP

# Overall Project Schedule

## Sweet Home WWTP Overall Project Schedule



# Next Steps

- VE Study
- Proceed with 90% Design Development
- Continue coordination with Oregon DEQ on NPDES Permit
  - Anti-degradation Evaluation for Mass Load Increase
  - NPDES Permit Renewal
- Continue work on project funding (USDA, DEQ, Business Oregon)



Questions?

