



BOARD OF COMMISSIONERS REGULAR MEETING

Tuesday, October 06, 2026 at 6:00 PM

Historic Walton County Courthouse, 111 South Broad Street, Monroe Georgia

Phone: 770-267-1301 | Fax: 770-267-1400

AGENDA

1. PRESENTATIONS

- 1.1. Proclamation - Retired Educators Day, November 1, 2026
- 1.2. Retirement Recognition - Michael Stamey and Charlie Dalton, Walton Co. Sheriff's Office
- 1.3. Recognition - Walton Co. EMS

2. MEETING OPENING

- 2.1. Pledge of Allegiance & Invocation
- 2.2. Call to Order
- 2.3. Roll Call

3. ADOPTION OF AGENDA

- 3.1. Additions/Deletions

4. DISCUSSION

- 4.1. County Managers Report/Update

5. PLANNING & DEVELOPMENT

- 5.1. LU26-0188 & Z26-0187 - Land Use Change from Rural Residential and Agriculture to Suburban and Rezone 5.99 acres from A1 to R1 to create a 5-lot residential subdivision - Applicant/Owner: Mark Sanchez - property located on Locklin Road - Map/Parcel C1780012Z00 - District 4 (Tabled 9/1/26)

Planning Commission recommended denial.

- 5.2. Z26-0222 - Rezone 6.15 acres from A1 to A to grow and sell fruits and vegetables - Applicant: Ravishankar Doejode/Owners: Ravishankar, Rahul and Shreyas Doejode and Sunitha Rao - property located at 440 Mt Vernon Road - Map/Parcel C1790096 - District 4

Planning Commission recommended approval as submitted.

6. ADMINISTRATIVE CONSENT AGENDA | *All items listed below are voted on by the board in one motion unless otherwise specified by the Board*

- [6.1.](#) Approval of September 1, 2026 Meeting Minutes
- [6.2.](#) Contracts & Budgeted Purchases of \$25,000 or Greater
- [6.3.](#) Declaration of Surplus
- [6.4.](#) Acceptance of Grant - Juvenile Court - Criminal Justice Coordinating Council for Children in Need of Services - Truancy Intervention Program and Consulting Contract with Break the Cycle Consulting
- [6.5.](#) 2027 Holiday Schedule
- [6.6.](#) Hazard Mitigation Plan Update
- [6.7.](#) Appointment - 2026 Legislative Leadership Conference Voting Delegate - Lee Bradford (for the record)
- [6.8.](#) Acceptance of Donated Equipment from Takeda for Fire Rescue
- [6.9.](#) Acceptance of Donated Equipment from Deputies Beyond the Badge - 2027 Ford Expedition to Walton Co. Fire Rescue
- [6.10.](#) Contribution Agreement - Amendment #1 - Georgia Association of Conservation Districts (for the record)

7. FINANCE

- [7.1.](#) Resolution - Amendment to Walton County Fiscal Policy
- [7.2.](#) Resolution - FY27 Budget Amendment and Summary
- [7.3.](#) FY27 Capital Funding Request - Vehicles/Equipment/Site Improvements

8. SHERIFF

- [8.1.](#) LeadsOnline, LLC - Total Track Investigation System

9. BIDS/PROPOSALS

- [9.1.](#) Precision Planning, Inc. - Alternate Solution for Space Needs

10. PUBLIC COMMENT | *3 Minute Limit Per Speaker. To speak at the meeting please follow the instructions outlined at the end of this Agenda.*

11. ANNOUNCEMENTS

12. EXECUTIVE SESSION**13. ADJOURNMENT**

If you are an individual with a disability and require special assistance at this meeting, please contact our office at 770-267-1301 at least 48 hours prior to the meeting and arrangements will be made.

People wanting to make a Public Comment before the Board of Commissioners must complete a Public Comment Form and return it to the County Clerk no later than 4:00 PM the day prior to the meeting. You may email, fax, mail or deliver the form. The form may be found on our website at **www.waltoncountyga.gov**.

For more information, please contact Rhonda Hawk.



Planning and Development Department Case Information

Case Number: LU26-0188 & Z26-0187

Meeting Dates: Planning Commission 08-06-2026

Board of Commissioners 9-01-2026 – TABLED TO 10-06-2026

Applicant/Owner:

Mark Sanchez
313 Milledge Avenue
Monroe, Georgia 30655

Current Zoning: The current zoning is A1.

Request: Land Use Change from Rural Residential and Agriculture to Suburban and Rezone 5.99 acres from A1 to R1 for a 5-lot residential subdivision.


Address: 0 Locklin Road, Monroe, Georgia 30655

Map Number/Site Area: C1780012Z00 – 5.99 acres


Character Area: Rural Residential and Agriculture

District 4 Commissioner- Lee Bradford Planning Commission – Michelle Trammel

Existing Site Conditions: The property is vacant.




The surrounding properties are zoned R1OSC and A1.



The property is not in a Watershed Protection Area.

The Future Land Use Map for this property is Rural Residential and Agriculture.



History: No History

Staff Comments/Concerns:

Public Works: Public Works recommends installing a deceleration lane and verifying sight distance with the entrance location.

Sheriff's Department: The addition of new homes will increase public safety calls for service and ultimately drive the need for additional public safety staffing.

Water Authority: This area is not currently served, but an existing 8" diameter water main is located to the east along Locklin Road (static pressure: 130 psi, Estimated fire flow: 1,450 gpm @ 20 psi). **A NEW WATER MAIN WILL BE REQUIRED TO EXTEND AND DISTRIBUTE WATER WITHIN THE DEVELOPMENT. PLEASE COORDINATE WITH WCWD.**

Fire Marshall Review: Project shall comply with all codes set forth by the Office of Commissioner of Insurance State Fire Marshal Rules and Regulations, Walton County Ordinances, Life Safety Code and International Fire Code.

Fire Department Review: Increased Fire and EMS demand.

Board of Education: This will have no affect on the school system.

(There will be more students for the schools and buses and may need to hire more teachers.)

GDOT: Will not affect GDOT.

City of Monroe: No comment received.

City of Social Circle: No comment received.

City of Loganville: No comment received.

PC ACTION 8/6/2026:

LU26-0188 & Z26-0187 – Land Use Change from Rural Residential and Agriculture to Suburban and Rezone 5.99 acres from A1 to R1 to create a 5-lot residential subdivision – Applicant/Owner: Mark Sanchez – property located on Locklin Road – Map/Parcel C1780012Z00 - District 4

Presentation: Mark Sanchez, who lives at 313 Milledge, represented the case. He is asking for 5.99 acres on Locklin Road to be rezoned from A1 to R1 for a 5-lot subdivision with 1-acre sites. The property is raw land. The lots will have a residential character. He stated that 500 feet from this property, water has been installed to a 24-lot subdivision and he would like to bring water to be installed in this subdivision and he will have a proposed road with a cul-de-sac. The subdivision's name will be Locklinburg. The types of homes will match the surrounding areas.

Mark Banks asked if the property was to the west of the new subdivision and were the lots 1 acre and he stated that they were.

Michelle Trammel asked about larger tracts, and he stated that the homes would be 3,200 to 3,800 sq. ft.

Josh Ferguson asked if there was a pond on the property and Mr. Sanchez stated there it wasn't.

Tim Hinton asked if he was going to do a detention pond and he was advised that a detention pond would need to be done and that would be on the civil drawings.

Tim Hinton advised Mr. Sanchez that he had a ton of frontage, and he could build houses off the property instead of 5 lots and a street. If he does a subdivision there would be some of the property donated to the county that the county has to maintain. The detention pond will probably take one of the lots and that will be the burden of the homeowners.

Michelle Trammel stated that on the paperwork it shows that public works stated that he may need a decel lane.

He was advised that the subdivision will be curb and gutter and he will be able to put whatever lots due to the density of the land.

Mr. Sanchez stated that he did not know he needed a decel lane.

Michelle Trammel asked about septic on the lots because the paperwork says that it is needed.

Speaking: Doug Fisher spoke and stated that he wanted to know the sizes of the homes and prices of the homes.

Rebuttal: Mark Sanchez came back for rebuttal. Mark Banks asked at 1141 Locklin Road how much square footage is in the homes and Mr. Sanchez stated that the size of the homes would be 3,200 to 3,800 sq. ft. and the prices would be compatible with the nearby homes.

Recommendation: Michelle Trammel made a motion to recommend denial with a second by Josh Ferguson. Michelle Trammel, Josh Ferguson and Tim Hinton voted to deny. Robert Post and Mark Banks voted to approve. The motion passed 3 to 2 to deny the rezone.

BOC 9/1/2026 – TABLED CASE UNTIL 10/6/2026

Character Area Map Amendment

Application # LU26-0188

Planning Comm. Meeting Date 8/6/26 at 6:00PM held at **WC Board of Comm. Meeting Room**

Board of Comm. Meeting Date 9/1/26 at 6:00PM held at **WC Historical Court House**

You or your agent must be present at both meetings

Please Type or Print Legibly

Map/Parcel C1780012700

Applicant Name/Address/Phone #

Property Owner Name/Address/Phone

MARK SANCHEZ

MARK SANCHEZ

313 Milledge Ave Monroe 30655

313 Milledge Ave Monroe 30655

678-570-8255

678-570-8255

(If more than one owner, attach Exhibit "A")

Phone # _____

Phone # _____

E-mail Address: _____

Location: Locklin Rd Acreage 5.99

Existing Character Area: Rural Residential and Agriculture

Proposed Character Area: Suburban

Is this a Major or Minor amendment to the plan? Minor amendment
Note: Major amendments to the plan DO NOT become effective until approved by RDC and DCA

Is the property located within a watershed protection overlay district? no

Proposed Development: ☒ Single-family _____ Multi-family _____ Commercial _____ Industrial _____

Proposed Zoning: R1 Number of Lots: 5 Minimum Lot Size: 1 acre

Public Sewer: _____ Provider: _____ Septic Tank: ☒

The above statements and accompanying materials are complete and accurate. Applicant hereby grants permission for planning and zoning personnel to enter upon and inspect the property for all purposes allowed and required by the Comprehensive Land Development Ordinance.

Signature [Signature]

Date 7-2-26

\$ _____ Fee Paid

Rezone Application # 226-0187
Application to Amend the Official Zoning Map of Walton County, Georgia

Planning Comm. Meeting Date 8/6/26 at 6:00PM held at **WC Historical Court House, 111 S. Broad St, Monroe, Ga (2nd Floor)**

Board of Comm Meeting Date 9/1/26 at 6:00PM held at **WC Historical Court House**

You or your agent must be present at both meetings

Map/Parcel C1780012200

Applicant Name/Address/Phone #

Property Owner Name/Address/Phone

Mark Sanchez

Mark Sanchez

313 Milledge Ave Monroe 30655

313 Milledge Ave Monroe 30655

678-570-8255

678-570-8255

(If more than one owner, attach Exhibit "A")

Location: Locklin Rd Requested Zoning R1 Acreage 5.99

Existing Use of Property: A1 - Raw land

Existing Structures: None

The purpose of this rezone is to develop a 5 lot subdivision.

Plan includes running county water to tract. No wells or septic exists.

Property is serviced by the following:

Public Water: _____ Provider: _____ Well: n/a

Public Sewer: _____ Provider: _____ Septic Tank: n/a

The above statements and accompanying materials are complete and accurate. Applicant hereby grants permission for planning and zoning personnel to enter upon and inspect the property for all purposes allowed and required by the Comprehensive Land Development Ordinance.

Signature [Signature] Date 7-1-26 Fee Paid \$ 600.00

Public Notice sign will be placed and removed by P&D Office

Signs will not be removed until after Board of Commissioners meeting

Office Use Only:

Existing Zoning A1 Surrounding Zoning: North R10SC A1 South R10SC A1
 East A1 West R10SC
Rural Residential

Comprehensive Land Use: and Agriculture **DRI Required?** Y _____ N ✓

Commission District: 4-Lee Bradford Watershed: ✓ TMP ✓

I hereby withdraw the above application _____ Date _____

Disclosure of Campaign Contributions

In accordance with the Conflict of Interest in Zoning Act, O.C.G.A., Chapter 36-67A, the following questions must be answered:

Have you the applicant made \$250 or more in campaign contributions to a local government official within two years immediately preceding the filing of this application?

_____ yes X no

If the answer is yes, you must file a disclosure report with the governing authority of Walton County showing:

1. The name and official position of the local governing authority in Walton County to whom the campaign contribution was made.
2. The dollar amount and description of each campaign contribution made during the two years immediately preceding the filing of this application and the date of each such contribution was made.

This disclosure must be filed when the application is submitted.

 7-1-26
Signature of Applicant/Date

Check one: Owner X Agent _____

Article 4, Part 4, Section 160 Standard Review Questions.

Walton County Rezoning Application

Map/Parcel: C1780012Z00

Applicant / Owner: Mark Sanchez

Address: 313 Milledge Ave., Monroe, GA 30655

Existing Zoning: A1

Requested Zoning: R1

Acreage: 5.99

Existing Use: Raw undeveloped land

Existing Structures: None

Purpose of Rezone: To rezone the property from A1 to R1 to permit development of a five-lot single-family residential subdivision consisting of approximately one-acre homesites. The proposed development is designed to be compatible with the surrounding residential character while utilizing planned public water service and individual septic systems.

Public Water: Yes (proposed)

Public Sewer: No

Septic: Yes

1. Existing uses and zoning of nearby property

The surrounding area consists primarily of agricultural and low-density residential uses, including newer custom homes on large lots. Residential development has continued along the Locklin Road corridor, making the proposed R1 zoning compatible with the existing and developing character of the area.

2. Property values

The existing A1 zoning limits the reasonable residential development potential of the property. Rezoning to R1 will allow orderly residential development that is consistent with surrounding land uses while enhancing the property's economic utility.

3. Health, safety and welfare

The proposed development promotes the public welfare by providing quality single-family housing while utilizing county water and approved individual septic systems. The development will comply with all Walton County development standards and will not adversely affect the surrounding area.

4. Public gain versus hardship

Approval of the rezoning will provide additional high-quality residential housing opportunities that are consistent with the Comprehensive Plan while allowing efficient use of planned public infrastructure. Denial of the request would unnecessarily restrict reasonable residential use of property that is suitable for such development.

5. Suitability

The subject property is well suited for low-density residential development. It has adequate road frontage, favorable topography, sufficient acreage for five one-acre homesites, and access to planned public water service. The proposed development is compatible with surrounding residential growth along the Locklin Road corridor.

6. Length of vacancy

The property has remained vacant and undeveloped while surrounding residential development has continued. The requested rezoning will allow the property to be developed in a manner that is consistent with existing development trends and the character of the surrounding area.

Mark Sanchez
 313 Milledge Avenue
 Monroe, GA 30655

July 1, 2026

Walton County Planning & Development
 126 Court Street
 Monroe, GA 30655

RE: Character Area Map Amendment and Rezoning Request

Parcel: C1780012Z00

Current Zoning: A1 (Agricultural)

Requested Zoning: R1 (Single-Family Residential)

Existing Character Area: Rural Residential and Agriculture

Proposed Character Area: Suburban

Proposed Subdivision: Locklinver

Dear Members of the Walton County Planning Commission and Board of Commissioners,

I respectfully submit this application requesting approval of a **Character Area Map Amendment** and the rezoning of Parcel C1780012Z00 from **A1 (Agricultural)** to **R1 (Single-Family Residential)**.

The purpose of this request is to develop a small, thoughtfully designed residential subdivision to be known as **Locklinver**. The proposed development consists of five approximately one-acre estate homesites served by a single internal public road terminating in a cul-de-sac. The subdivision is intended to provide high-quality single-family residences that are compatible with the existing and emerging residential character of the Locklin Road corridor.

The subject property is well suited for low-density residential development due to its size, topography, existing road frontage, and surrounding land uses. The proposed subdivision has been designed to preserve the rural character of the area while providing attractive estate-sized homesites for custom residential construction.

Character Area Map Amendment

Concurrent with this rezoning request, the Applicant requests approval of a **Character Area Map Amendment** from **Rural Residential and Agriculture** to **Suburban**.

The proposed amendment is appropriate because the property is transitioning from agricultural use to a low-density residential neighborhood that is consistent with the

existing pattern of development occurring along the Locklin Road corridor. The surrounding area includes established rural residences together with newer custom homes, reflecting an orderly transition toward quality residential development. The proposed five-lot subdivision will maintain generously sized one-acre homesites while preserving the area's rural character and supporting Walton County's long-term planning objectives.

Neighborhood Compatibility

The Locklin Road corridor has experienced substantial investment in high-quality residential development. Nearby homes have recently sold or are currently listed in the approximate range of **\$850,000 to over \$1,100,000**, demonstrating strong demand for custom homes in this area.

Locklinver is intended to complement this existing pattern of development by creating generously sized homesites suitable for custom-built residences that are consistent with the architectural quality and residential character already established within the surrounding community.

Public Water and Utilities

The proposed subdivision is intended to be served by Walton County public water.

If the requested rezoning is approved and the property is developed, **the developer of the subdivision shall design, permit, construct, and dedicate all public water infrastructure necessary to serve the proposed lots in accordance with Walton County Water Department standards and requirements. Public water will be extended to the property and throughout the subdivision prior to final plat approval.**

This commitment is also reflected on the submitted concept plan through a general utility note regarding the extension of public water infrastructure.

Each proposed lot will be served by an individual septic system approved by Walton County Environmental Health.

Proposed Development

The proposed subdivision will:

- Create five approximately one-acre residential homesites.
- Extend Walton County public water infrastructure to serve all proposed lots.
- Utilize individual septic systems approved by Walton County Environmental Health.

- Construct a single internal public road terminating in a cul-de-sac designed in accordance with Walton County standards.
- Be developed in compliance with Walton County zoning regulations, subdivision regulations, engineering requirements, and all applicable development standards.
- Provide a well-planned residential community that is compatible with surrounding development while enhancing the long-term character and value of the Locklin Road corridor.

This request represents an orderly transition from agricultural land to low-density residential development that is consistent with the existing development pattern in the area. The proposed subdivision will make productive use of the property while maintaining compatibility with surrounding residences and contributing positively to Walton County's continued growth.

Thank you for your consideration of this application. **I respectfully request approval of both the Character Area Map Amendment from Rural Residential and Agriculture to Suburban and the rezoning of Parcel C1780012Z00 from A1 (Agricultural) to R1 (Single-Family Residential) to allow the development of Locklinver.**

Respectfully submitted,

Mark Sanchez

Property Owner / Applicant



[illegible]

NOTES:
1) NO PORTION OF THE SUBJECT PROPERTY LIES WITHIN A DESIGNATED
FLOOD HAZARD AREA PER WALTON COUNTY F.I.R.M. PANEL 13297C0155E,
DATED 12/15/22.

3) THE SUBJECT PROPERTY IS CURRENTLY ZONED A1, PROPOSED ZONING R1.

4) THE MINIMUM SETBACKS FOR R1 ARE FRONT-40' (50' ALONG LOCKLIN RD),
SIDE-15', REAR-40'.

5) THE MINIMUM LOTS SIZE IS 1.000 ACRES.

6) THE SUBJECT PROPERTY WILL BE SERVED BY COUNTY WATER AND INDIVIDUAL SEPTIC SYSTEMS.

7) THE SUBJECT PROPERTY IS NOT LOCATED IN A WATERSHED AREA.

8) THE PURPOSE OF THIS PLAN IS TO PRESENT PROPOSED LOTS FOR A REZONE OF THE SUBJECT PROPERTY FROM A1 TO R1.

N/F
BRIGHT VIEW HOMES, LLC
D.E. 5589 PG. 587
P.B. 121 PG. 165
TAX PARCEL: C1780012Y00
ZONED: R1 OSC

N/F
WILLIAM OBRIEN
D.B. 5089 PG. 333
P.B. 121 PG. 165
TAX PARCEL: C1780012AAC
ZONED: A1

VICINITY MAP N.T.S.

CONCEPT PLAN FOR:

LOCKLINVER

MARK SANCHEZ
313 MILLEDGE AVE
MONROE, GA 30655



**NORTHEAST LAND
SURVEYING, LLC**

A Georgia Land Surveying Firm:LSF: #1240

P.O. Box 384

Braselton, Georgia 30517

Phone: (678) 776-7494

Phone: (616) 776-7434

**NORTHEAST
LAND SURVEYING**

Project Name: LOCKLIN RD

Project Name: LOCKLIN RD

Project Address:

Land Use No. (s)	343	primary	age
------------------	-----	---------	-----

Case No. (s)	242	District	JAD
--------------	-----	----------	-----

City: _____
County: State: _____ MAIL ROOM 000001

DRAWN	SCALE
-------	-------

KLC	
-----	--

CHECKED
GDN

CDN
DATE OF

FIELD WORK
06/08/26 SHEET

DATE	PROJECT
------	---------

1"=50'

1 OF

101

CT No. 336

260

18

0' 50' 100' 150'

SCALE 1"=50'



Planning and Development Department Case Information

Case Number: Z26-0222

Meeting Dates: Planning Commission 09-03-2026

Board of Commissioners 10-06-2026

Applicant:

Ravishankar Doejode
490 Gene Bell Road
Monroe, Georgia 30655

Owners:

Ravishankar Doejode,
Sunitha Rao, and
Rahul Ravishankar Doejode
490 Gene Bell Road
Monroe, Georgia 30655

Shreyas Ravishankar Doejode
638 Caryle Trail Lane
Loganville, Georgia 30052

Current Zoning: The current zoning is A1.

Request: Rezone 6.15 acres from A1 to A to grow and sell fruits and vegetables to take to the market.

Address: 440 Mt Vernon Road, Monroe, Georgia 30655

Map Number/Site Area: C1790096– 6.15 acres

Character Area: Rural Residential/Agriculture


District 4 Commissioner- Lee Bradford

Planning Commission–Michelle Trammel

Existing Site Conditions: Property is vacant land.




The surrounding properties are zoned A1 and R1OSC.



The property is not in a Watershed Protection Area.

The Future Land Use Map for this property is Rural Residential/Agriculture.



History: No History

Staff Comments/Concerns:

Public Works: Public Works would recommend a commercial driveway to be installed for a business.

Sheriff's Department: No comment received.

Water Authority: No system impacts anticipated.

Fire Marshall Review: No Comments

Fire Department Review: No impacts foreseen

Board of Education: Will have no affect on the Walton County School System.

GDOT: Will not require GDOT coordination.

City of Loganville: No comment received.

City of Social Circle: No comment received.

City of Monroe: No comment received.

PC ACTION 9/3/2026:

Z26-0222 – Rezone 6.15 acres from A1 to A to grow and sell fruits and vegetables – Applicant: Ravishankar Doejode/Owners: Ravishankar, Rahul and Shreyas Doejode and Sunitha Rao - property located at 440 Mt Vernon Road – Map/Parcel C1790096 – District 4

Presentation: Ravishankar Doejode, who lives at 490 Gene Bell Rd., Monroe, Georgia represented the case. He is asking for a rezone from A1 to A to grow fruits and vegetables and sell them at farmer markets. He stated that there will not be tractors on the property, the working of the farm will be done by hand, and they will not be using any pesticides. They will be using handheld tools to work on the farm and there will be no noise on the farm. They will be using compost and maybe some organic items, but they will not have any harmful effects on humans or animals. Mr. Doejode stated that he and his wife are not troublemakers and want to be very good neighbors who do not want any problems.

Josh Ferguson asked where they planned to sell the fruits and vegetables and Mr. Doejode stated that they would sell mostly at farmers' markets. Josh Ferguson asked if they would be having a farm stand on the property and Mr. Doejode stated that they would not.

Timothy Kemp asked if there are no tractors then how they plan to grow fruits and vegetables and Mr. Doejode stated that they would use handheld tools.

Chris Alexander asked if there was going to be any livestock on the property and Mr. Doejode stated no.

Robert Post asked if they had any plans to build a barn or shed on the property and Mr. Doejode stated that they may build a shed on the property to store the tools in.

Timothy Kemp asked if they would be delivering the produce to the market on the day that they are picked and Mr. Doejode stated that they live close and that is the plan and Mr. Kemp wanted to know what kind of vegetables and Mr. Doejode stated things like tomatoes, okra, bell peppers, or whatever the customers want.

Speaking: No one

Recommendation: Josh Ferguson made a motion to recommend approval as submitted with a second by Timothy Kemp. The Motion carried unanimously.

Rezone Application # Z26-0222

Application to Amend the Official Zoning Map of Walton County, Georgia

Planning Comm. Meeting Date 9-3-2026 at 6:00PM held at **WC Historical Court House, 111 S. Broad St, Monroe, Ga (2nd Floor)**

Board of Comm Meeting Date 10-6-2026 at 6:00PM held at **WC Historical Court House**

You or your agent must be present at both meetings

Map/Parcel C1790096

Applicant Name/Address/Phone #

RAVISHANKAR DOBBODE
490 GENE BELL RD
MONROE GA 30655

Property Owner Name/Address/Phone

RAVISHANKAR DOBBODE
490 GENE BELL RD
MONROE GA 30655

(If more than one owner, attach Exhibit "A")
(See attached - More owners)

440 MT. VERNON RD
MONROE GA 30655

Location: _____ Requested Zoning _____ Acreage 6.05 Acre

Existing Use of Property: NOT USED

Existing Structures: NONE

The purpose of this rezone is USE THE PROPERTY FOR
FARMING/AGRICULTURE.

Property is serviced by the following:

Public Water: X Provider: WALTON COUNTY WATER DEPT Well: _____

Public Sewer: _____ Provider: _____ Septic Tank: _____

The above statements and accompanying materials are complete and accurate. Applicant hereby grants permission for planning and zoning personnel to enter upon and inspect the property for all purposes allowed and required by the Comprehensive Land Development Ordinance.

Signature [Signature] Date 8/1/2026 Fee Paid \$ 600.00

Public Notice sign will be placed and removed by P&D Office

Signs will not be removed until after Board of Commissioners meeting

Office Use Only:

Existing Zoning A1 Surrounding Zoning: North A1 South A1
East A1 West R10SC

Comprehensive Land Use: Rural Residential/Agriculture **DRI Required?** Y _____ N ✓

Commission District: 4-Lee Bradford Watershed: ✓ TMP ✓

I hereby withdraw the above application _____ Date _____

Additional owners – My wife and two sons are co-owners

Sunitha Rao

490 Gene Bell Rd

Monroe, GA 30655

678-982-9259

Shreyas Ravishankar Doejode

638 Caryle Trail Ln

Loganville, GA 30052

678-982-2501

Rahul Ravishankar Doejode

490 Gene Bell Rd

Monroe, GA 30655

678-982-0480

Disclosure of Campaign Contributions

In accordance with the Conflict of Interest in Zoning Act, O.C.G.A., Chapter 36-67A, the following questions must be answered:

Have you the applicant made \$250 or more in campaign contributions to a local government official within two years immediately preceding the filing of this application?

_____ yes X _____ no

If the answer is yes, you must file a disclosure report with the governing authority of Walton County showing:

1. The name and official position of the local governing authority in Walton County to whom the campaign contribution was made.
2. The dollar amount and description of each campaign contribution made during the two years immediately preceding the filing of this application and the date of each such contribution was made.

This disclosure must be filed when the application is submitted.



Signature of Applicant/Date

Check one: Owner X Agent _____

Article 4, Part 4, Section 160 Standard Review Questions:

Provide written documentation addressing each of the standards listed below:

1. Existing uses and zoning of nearby property;

RESIDENTIAL 401

2. The extent to which property values are diminished by the particular zoning restrictions;

NO IDEA

3. The extent to which the destruction of property values of the plaintiffs promotes the health, safety, morals or general welfare of the public;

NO NEGATIVE IMPACT

4. The relative gain to the public, as compared to the hardship imposed upon the individual property owner;

WE ARE LOOKING TO GROW FRUITS & VEGETABLES FOR THE COMMUNITY. HAVING A LOCAL SOURCE OF PRODUCE IS A GOOD THING FOR THE COMMUNITY. EVERYTHING WILL BE GROWN ORGANICALLY AND SOLD AT AN AFFORDABLE PRICE.

5. The suitability of the subject property for the zoned purposes; and

LAND HAS BEEN CLEARED BY THE PREVIOUS
OWNERS. LAND IS FLAT AND CONDUCTIVE
FOR FARMING,

6. The length of time the property has been vacant as zoned, considered in the context of land development in the area in the vicinity of the property

NO IDEA

Letter of Intent - Our Little Family Farm, LLC.

To whom it may concern


My name is Ravishankar Doejode and I recently moved with my wife and son to Monroe. We currently live at 490 Gene Bell Rd, Monroe, GA 30655. My son goes to school at Virginia Tech, where he is pursuing his undergraduate degree in Biomedical Engineering. I have an older son and daughter-in-law that live in Loganville. I have been working for AT&T for the last 27 years and my wife Sunitha Rao works for a Pediatric Clinic in Loganville.

We moved to Monroe with an intent to start farming. We recently bought farming land at 440 Mt. Vernon Rd, Monroe, GA, to start a farm. This property is currently zoned A1, and we would like to get it changed to A, which allows us to grow and sell fruits and vegetables. I will be farming part time for the next 3 years and do it on a full-time basis after.

Farming will be my second career. I have dreamt of farming for a very long time. We moved from India about 28 years ago and have been citizens of this great country for many years. My long-term employment at AT&T has given us the resources for us to embark on this dream of mine. My two sons and wife are fully behind this endeavor of ours and they will be helping me with farming. This country has provided so much to me and my family. We strongly believe in being decent citizens and contribute to the society. Farming is our way to give back to the community. We will be growing fruits and vegetables strictly following organic practices. With increased news of health issues from consumption of food grown in other countries and distant places, it is imperative that we have more sources of locally grown produce for the community. Our effort at farming is to play a small role in addressing the need for locally and organically grown produce. We will use a good portion of the profits to support philanthropic efforts in the community.

Farming provides me and my family a greater sense of purpose. We are eager to get started with this dream project of ours. We have registered our farming business – **Our Little Family Farm, LLC**, with the Georgia Secretary of State and received the Employment Identification Number (EIN) from IRS. We have provided copies of these two documents herewith.

We hereby request you to allow and support the rezoning of our farming land to A, and grant us the license to run a farming business in Monroe, GA.



A.C.E.
ALCOBY CONSULTING ENGINEERING
AND ASSOCIATES, L.L.C.
P.O. BOX 181704, PE
485 Edwards Rd.
Columbus, Georgia

This drawing and any permitted reproductions, in whole or part, are the sole property of Alcooby Consulting Engineering and Associates, L.L.C. and shall not be reproduced or transmitted in any way without the written permission of Alcooby Consulting Engineering and Associates, L.L.C.

GEORGIA
811
MISSISSIPPI
ALABAMA
LOUISIANA
FLORIDA
MISSISSIPPI
ALABAMA
LOUISIANA
FLORIDA

SITE PLAN

PROPOSED FRUIT AND VEGETABLE FARM

PARCEL: C1790096
LAND LOT: 190
DISTRICT: 3RD
440 MT VERNON RD
WALTON COUNTY, GA

DATE: 8/03/2026
SCALE: 1"=50'

OWNER / DEVELOPER / PRIMARY PERMITTEE
RAVISHANKAR J. DOEJODE
480 GENE BELL RD
MORGEE, GA 30655

24 HOUR - EMERGENCY CONTACT
RAVISHANKAR J. DOEJODE

REVISIONS

NO.	DATE	DESCRIPTION

JOB No. # 26-050
RZ-1


Control Number : 26071796

STATE OF GEORGIA**Secretary of State****Corporations Division****313 West Tower****2 Martin Luther King, Jr. Dr.****Atlanta, Georgia 30334-1530****CERTIFICATE OF ORGANIZATION**


I, **Brad Raffensperger**, the Secretary of State and the Corporation Commissioner of the State of Georgia, hereby certify under the seal of my office that

Our Little Family Farm LLC
a Domestic Limited Liability Company

has been duly organized under the laws of the State of Georgia on **03/24/2026** by the filing of articles of organization in the Office of the Secretary of State and by the paying of fees as provided by Title 14 of the Official Code of Georgia Annotated.



WITNESS my hand and official seal in the City of Atlanta
and the State of Georgia on **03/31/2026**.



Brad Raffensperger

Brad Raffensperger
Secretary of State

ARTICLES OF ORGANIZATION

Electronically Filed

Secretary of State

Filing Date: 3/24/2026 9:29:12 PM

BUSINESS INFORMATION

CONTROL NUMBER 26071796
BUSINESS NAME Our Little Family Farm LLC
BUSINESS TYPE Domestic Limited Liability Company
EFFECTIVE DATE 03/24/2026

PRINCIPAL OFFICE ADDRESS

ADDRESS 490 Gene Bell Rd, Monroe, GA, 30655, USA

REGISTERED AGENT

NAME Ravishankar Janardhan Rao Doejode
ADDRESS 490 Gene Bell Rd, Monroe, GA, 30655, USA
COUNTY Walton

ORGANIZER(S)

NAME Ravishankar Janardhan Rao Doejode
TITLE ORGANIZER
ADDRESS 490 Gene Bell Rd, Monroe, GA, 30655, USA

OPTIONAL PROVISIONS

N/A

AUTHORIZER INFORMATION

AUTHORIZER SIGNATURE Ravishankar Doejode
AUTHORIZER TITLE Organizer

September 1, 2026

The Walton County Board of Commissioners held its regular monthly meeting on Tuesday, September 1, 2026 at 6:00 p.m. at the Historic Walton County Courthouse. Those participating in the meeting included Vice Chairman Timmy Shelnutt, Commissioners Amarie Warren, Pete Myers, Lee Bradford, Jeremy Adams and Kirklyn Dixon, County Clerk Rhonda Hawk, County Manager John Ward, Planning Director Kristi Parr, Sheriff Keith Brooks and staff Scott Whisnant and Kim McCord, Public Works Director John Allman and County Attorney Chip Ferguson. A list of employees and citizens in attendance at the meeting is on file in the auxiliary file under this meeting date. Chairman Thompson did not attend.

MEETING OPENING

Vice Chairman Shelnutt called the meeting to order at 6:00 p.m. and led the Pledge of Allegiance and gave the invocation.

ADOPTION OF AGENDA

Motion: *Commissioner Bradford made a motion, seconded by Commissioner Adams, to adopt the agenda. The motion passed 6-0 with all voting in favor.*

OLD BUSINESS

Repurposing Administrative Portion of Old Jail for Department Expansions (Previously tabled on 6/2 & 7/7 and 8/4)

County Manager John Ward reviewed cost comparisons for phasing the expansion and updated the Board on the latest fund balance information.

Motion: *Commissioner Warren made a motion to table the matter until the November meeting. Commissioner Adams seconded the motion. The motion passed unanimously.*

RESOLUTIONS

Resolution - Approving the Execution and Delivery of an Intergovernmental Contract with the Walton County Water and Sewerage Authority

Andrew Tritt and Jim Woodward with Stifel Public Finance presented the Resolution and Intergovernmental Contract with the Walton County Water and Sewerage Authority for the issuance of Series 2026 Revenue Bonds in the amount of \$44,221,000.00. Walton County has achieved a AAA Bond Rating from Moody's. The purpose of the bonding is to provide funds to acquire, construct and install a water plant expansion, transmission lines and other additions to the County's water system.

Motion: *Commissioner Adams made a motion to adopt the resolution. Commissioner Dixon*

seconded the motion; voted and carried unanimously.

DISCUSSION

County Manager's Report/Update

County Manager John Ward gave an update and report on county matters to the Board.

Request by Department of Driver Services to Transfer Property for Motorcycle Repair Shop

Bob Griffin, Deputy Commissioner of the Department of Driver Services, presented a request to transfer the property currently leased to the DDS for the purpose of constructing a motorcycle repair shop. In the event that the property was no longer needed, it would revert back to the County.

Motion: *Commissioner Adams made a motion, seconded by Commissioner Warren to approve the transfer subject to review by the County Attorney. All voted in favor.*

PLANNING & DEVELOPMENT

Planning & Development Director Kristi Parr presented the Planning Commission recommendations.

Z26-0159 - Rezone a portion of Parcel C0590057 (4.00) acres from R1 to A1 to have personal outside animals - Applicant/Owner: Fig Leaf Risk Advisors, LLC - property located at 3084 Brooks Trail - District 1

Planning Commission recommended approval with the following condition: 1) No more than four sheep, four goats and twelve chickens ever.

Planning & Development Director Kristi Parr advised the Board that she had received a request from the applicant to withdraw the rezone application.

Motion: *Commissioner Warren made a motion to accept a withdrawal of the proposed rezone application. Commissioner Bradford seconded the motion; all voted in favor.*

LU26-0188 & Z26-0187 - Land Use Change from Rural Residential and Agriculture to Suburban and Rezone 5.99 acres from A1 to R1 to create a 5-lot residential subdivision - Applicant/Owner: Mark Sanchez - property located on Locklin Road - Map/Parcel C1780012Z00 - District 4

Planning Commission recommended denial.

Planning & Development Director Kristi Parr advised the Board that the applicant was unable to attend and had revised the site plan. The applicant was requesting that the matter be tabled until October.

Attorney Chip Ferguson opened the public hearing on the matter. There was no one present to

Speak in favor due to the absence of the applicant. Lora Morris spoke in opposition. Attorney Ferguson closed the public hearing on the matter.

Motion: Commissioner Bradford made a motion to accept the Planning Commission recommendation to deny. Commissioner Adams seconded the motion. Commissioner Bradford, Adams and Warren voted in favor of the denial. Vice Chairman Shelnett, Commissioners Myers and Dixon voted in opposition. The motion failed 3-3.

Motion: Commissioner Warren made a motion to table the matter until the October meeting and to hold another public hearing at that time. Commissioner Myers seconded the motion. Vice Chairman Shelnett, Commissioners Warren, Myers and Dixon voted in favor. Commissioners Bradford and Adams opposed the motion. The motion carried 4-2.

Z26-0189 - Rezone 5.70 acres from A1/B3/M1/M2 to M2 & B3 for Motor Vehicle Sales, Auto Repair & Maintenance, Salvage Yard, Warehouse and Outdoor Storage and Variances on setbacks, buffers and eliminate the 10 ft. landscape strip along Highway 11 - Applicant/Owner: Reyes Autos & Trucks, LLC - property located at 2412 Highway 11 - Map/Parcels C0850109, C0850109B00 & C0850111 - District 5

Planning Commission recommended approval with the following conditions: 1) South side of the property: along the south side, from the point where the retention pond no longer intersects the adjoining property and continuing past the warehouses to the area already identified as screened salvage storage, the entire boundary must be screened in the same manner as the rear salvage storage. This screening must include a minimum 6-foot opaque fence along the entire south boundary; 2) North side of the property: in the area identified as tire repair, a 6-foot opaque fence must be installed from the section identified as salvage storage screening to the adjoining property line at Highway 11. The fence must also extend behind the tire repair building; 3) Front of the property - car dealership: for the portion of the property identified as a car dealership, including the area where the parking spaces are shown near the street, the landscape strip requirement may be removed. This exception applies only to the area identified as the car dealership; 4) Other areas facing Highway 11: any other portion of the property fronting Highway 11, including the areas identified for auto repair and tire repair, must maintain the required landscape strip as established by the applicable code.

County Attorney Chip Ferguson opened the public hearing on the matter. Easa Khan spoke in favor on behalf of the applicant. He stated that they would abide by the recommendations of the Planning Commission and would like to request that they be able to operate seven days per week. There was no opposition present. Attorney Ferguson closed the public hearing on the matter.

Motion: Commissioner Adams made a motion to approve per the Planning Commission recommendations, plus hours to be 7 days per week, 24 hours a day for wrecker service and Monday - Saturday, 7 a.m. to 7 p.m. for used vehicle sales and other proposed uses. Commissioner Dixon seconded the motion; all voted in favor.

Z26-0192 - Rezone 103.56 acres from A2 to R1OSC to create a 57-lot residential subdivision - Applicant: Baldpates General Contracting, LLC/Owner: Grady Thompson Enterprises, LLLP -

property located on Nicholasville Road - Map/Parcel C0850158 - District 5

Planning Commission recommended approval with the following conditions: 1) For the disturbed entry between single family homes and the commercial properties on the corner, this would need to have fencing, shrubs, and trees as well as the buffer between Nicholasville Road to this development.

County Attorney Chip Ferguson opened the public hearing on the matter. Attorney Andrea Gray spoke in favor on behalf of the applicant. There was no opposition present. Attorney Ferguson closed the public hearing on the matter.

Motion: *Commissioner Adams made a motion to approve per the Planning Commission recommendations and maintaining the 1.49 acre density. Commissioner Warren seconded the motion. Commissioners Warren, Myers, Adams and Dixon voted in favor. Vice Chairman Shelnett and Commissioner Bradford abstained. The motion carried 4-2.*

Z26-0195 - Rezone 14.97 acres from A1 to A2 to create two 1.50-acre buildable lots for his children - Applicant/Owner: Sunil G. Rampersad - property located at 2940 Fannie Thompson Road - Map/Parcel C0850028B00 - District 5

Planning Commission recommended approval as submitted.

County Attorney Chip Ferguson opened the public hearing on the matter. Sunil Rampersad spoke in favor. There was no one present to speak in opposition. Attorney Ferguson closed the public hearing.

Motion: *Commissioner Adams made a motion, seconded by Commissioner Dixon to approve the rezone as submitted. All voted in favor.*

LU26-0179 and Z26-0177 - Land Use Change from Employment Center to Neighborhood Residential and Rezone 32.479 acres from A1 to R1OSC to create a 20-lot residential subdivision - Applicant: Reliant Homes GA, LLC/Owner: 81 Investment Company, LLC - property located on Cedar Ridge Road - Map/Parcel C0910004 - District 5

Planning Commission recommended approval with the following conditions: 1) For the disturbed area for the entry that anything that has or is currently tree-lined along the right of way will be left except for what needs to be disturbed for the entry; 2) That disturbed entry will be fenced have shrubs and trees planted and trees for future screening of that neighborhood from the public right of way.

County Attorney Chip Ferguson opened the public hearing on the matter. Ned Butler of Reliant Homes spoke in favor. There was no one present to speak in opposition. Attorney Ferguson closed the public hearing on the matter.

Motion: *Commissioner Adams made a motion to approve per the Planning Commission recommendations. Commissioner Dixon seconded the motion; voted and carried unanimously.*

FINANCE

Resolution - Project Length Budget for Resurfacing Project and FY27 Budget Amendment

Public Works Director John Allman presented a Resolution for the SPLOST 5 Resurfacing Project Length Budget and FY27 Budget Amendment for resurfacing.

Motion: *Commissioner Bradford made a motion to adopt the Resolution for the SPLOST 5 Resurfacing and FY27 Budget Amendment. Commissioner Adams seconded the motion. All voted in favor.*

SHERIFF'S OFFICE

Sheriff Keith Brooks, Scott Whisnant and Kim McCord presented requests from the Sheriff's Office.

Agreement with Fulton County Sheriff's Office for Temporary Housing of Inmates

Motion: *Commissioner Adams made a motion, seconded by Commissioner Dixon to approve the agreement. Vice Chairman Shelnett, Commissioners Warren, Myers, Adams and Dixon voted in favor with Commissioner Bradford opposing the motion. The motion carried 5-1.*

Request - Reallocate CID Temp Position, Reclassification/Position Changes and Budget Amendment

Motion: *Commissioner Dixon made a motion, seconded by Commissioner Adams to approve the request. All voted in favor.*

HUMAN RESOURCES

Transfer Request - Solid Waste Employee to Roadways and Walkways

Motion: *Commissioner Bradford made a motion, seconded by Commissioner Adams to approve the transfer request; voted and carried unanimously.*

ADMINISTRATIVE CONSENT AGENDA

1. Approval of August 4, 2026 Meeting Minutes
2. Contracts & Budgeted Purchases of \$25,000 or Greater
3. Declaration of Surplus
4. Ratification of Actions taken by WCWSA on September 1, 2026
5. Acceptance of Right of Way - Carruth Farms (60')
6. Contract Renewals for Debris Removal and Monitoring - Southern Disaster Recovery, LLC and Thompson Consulting - EMA
7. Change Proposal #43 - Reeves + Young - The Grove Park - (\$24,750.57)
8. Quitclaim Deeds - ROW @ Lake Shore Estates
9. Agreement Renewal - Walton Co. School District - School Resource Officers

Motion: Commissioner Adams made a motion, seconded by Commissioner Dixon, to approve the Administrative Consent Agenda. All voted in favor.

CONTRACTS

Intergovernmental Contract - City of Monroe - Development Services/Annexation - Dycom Industries, Inc.

Motion: Commissioner Bradford made a motion to approve the Intergovernmental Contract with the City of Monroe due to the annexation. Commissioner Warren seconded the motion; voted and carried unanimously.

Georgia Power Easements - 550 Fairplay Drive, Parcel SC160007 and Fairplay Drive, Parcel SC130041, 573 Fairplay Drive, Parcel SC130040

Motion: Commissioner Bradford made a motion, seconded by Commissioner Adams to approve the easements for Georgia. Power. All voted in favor.

EXECUTIVE SESSION

Motion: At 7:12 p.m., Commissioner Adams made a motion to enter into Executive Session to discuss real estate. Commissioner Bradford seconded the motion and all voted in favor.

Motion: At 7:31 p.m., Commissioner Adams made a motion, seconded by Commissioner Bradford to return to regular session. All voted in favor.

Motion: Commissioner Dixon made a motion to transfer property located at 111 E. Spring Street and 203 Milledge Avenue to the Walton Co. Development Authority for marketing purposes. Commissioner Adams seconded the motion; voted and carried unanimously.

ANNOUNCEMENTS

Motion: Commissioner Warren made a motion to have an informal discussion with Planning & Development with no more than three commissioners over certain ordinances and to bring back before the Board in November. Commissioner Adams seconded the motion. All voted in favor.

ADJOURNMENT

Motion: Commissioner Adams made a motion, seconded by Commissioner Bradford, to adjourn the meeting. The motion carried and the meeting was adjourned at 7:34 p.m.

All documents of record for this meeting are on file in either the addendum book or auxiliary file under this meeting date.

TIMMY SHELNUTT, VICE CHAIRMAN

RHONDA HAWK, COUNTY CLERK

Walton County Board of Commissioners
Purchases \$25,000.00
Meeting

October 6, 2026

Department	Fund	Description	Payee	Amount
Budget Year FY27				
	100	Premium for October 2026-For the Record	One America	\$ 47,944.91
	Various	Replenish Funds In Workers Comp-For the Record	Walton Co BOC Workers Comp Trust Fund	\$ 139,780.00
	Various	Replenish Funds in Health Benefits Trust-For the Record	Walton Co Health Benefits Trust	\$ 200,000.00
Law				
	1530 100	General Legal Fees-August 26-For the Record	Atkinson/Ferguson	\$ 26,303.25
Public Facilities				
	1565 100	2027 Ford E-350	Loganville Ford	\$ 62,463.56
Jail				
	3325 100	Inmate Meals Weeks Ending: 8/7/26, 8/14/26, 8/21/26, 8/28/26 and 9/4/26	Summit Food Service, LLC	\$ 118,778.23
	3325 100	Inmate Medical-August 2026	MedTrust, LLC	\$ 537,183.39
Fire				
	3520.270 270	Parts & Labor to repair Engine #9	Peach State Truck Centers, LLC	\$ 35,570.70
Public Works				
	4251 100	Stormdrain Restoration: 5408 Forest Falls Drive, 2055 Wood Valley Drive and 4000, 2053, 2053CD, 2040 Wood Valley Drive	Utility Asset Management, Inc	\$ 72,090.00
Splost 2019				
	6220.19 323	Construction Phase July-September 2026-For the Record	Ascension Program Management, LLC	\$ 8,400.00

Department	Fund	Description	Payee	Amount
Splost 2024				
	4220.24	324	Pannell Road Resurfacing Project-City Limits to Old Monroe Madison Hwy	E.R. Snell Contractor, Inc. \$ 194,238.50
	4220.24	324	Asphalt Deep Patching-Various County Roads	MHB Paving, Inc \$ 380,952.00
Solid Waste Disposal				
	4530	540	Tipping Fees-August 26	City of Monroe Public Works \$ 25,773.29
Debt Services				
	8000	400	Least Payment #1- For the Record	Ford Motor Credit Company \$ 82,557.87
Water Operations Distribution				
	4446	507	Water Testing-For the Record	Cornish Creek Water Fund \$ 247,681.00
	4446	507	Water Use from Ozora Rd-For the Record	Gwinnett Co Dept of Water Resources \$ 28,794.80
HLC Water Treatment Facility				
	504		Professional Engineer August 26	Archer Western Construction \$ 4,094,555.73
	504		Water Transmission Facility Aug 2026/Mains Aug 2026-For the Record	Atkinson Ferguson LLC \$ 1,277.50
	504		Professional Engineer August 2026- For the Record	Engineering Strategies Inc \$ 2,656.00
	504		Professional Engineer August 26- For the Record	Jacobs Engineering \$ 140,734.56
	504		Water Transmission Mail Phase 2-August 2026 - For the Record	Legacy Water Group, LLC \$ 2,124,299.88
	504		Phase 3 appraisal & acquisition-Transmission Main-For the Record	LJA Engineering INC \$ 1,450.00
	504		HLC Management- Water Treatment- For the Record	Precision Planning INC \$ 73,233.97
	4430	504	Fiscal Agent Fees-Water Treatment-For the Record	Regions Bank \$ 2,600.00
Hard Labor Creek				
	4405	508	Daily Monitoring of Traps & Removal of Animals August 2026-For the Record	Alan D Barton \$ 2,475.00
	4405	508	Turf Fertiliazion and Weed Control-For the Record	GroundsMen LLC \$ 1,750.00
	508		Professional Engineer July 1, 2026 to August 28, 2026, Apalachee Intake- For the Record	Jacobs Engineering \$ 2,927.97

Department	Fund	Description	Payee	Amount
	508	Aug 10- Aug 31 Apalachee River Intake Professional Services-For the Record	Reeves Young, LLC	\$ 255,645.00
	508	Apalachee River Intake-For the Record	Precision Planning, Inc	\$ 5,638.64
				\$8,917,755.75

Walton County Department Agenda Request

Department Name: **Facilities/Risk Mgmt.**

Department Head/Representative: **Hank Shirley**

Meeting Date Request: **October 6, 2026**

Has this topic been discussed at past meetings? **No**

If so, When?

TOPIC: **Surplus**

Wording For Agenda: **Declaration of Surplus property**

This Request: Informational Purposes Only

Needs Action by Commissioners* **Yes**

*What action are you seeking from the Commissioners? **Declare items surplus and give permission to sell on Gov Deals and/or to metal company whichever is of greater value or if there is no value permission to discard of unusable/unsaleable items.**

Department Comments/Recommendation:

Additional Documentation Attached? **Yes**

Is review of this request or accompanying documentation by the County Attorney required? **No**

If so, has a copy of the documentation been forwarded to County Attorney? **N/A**

Date forwarded to County Attorney: **N/A**

Has the County Attorney review been completed? **N/A**

If this request involves the expenditure of county funds, please answer the following:

Approved in current budget?

Budget information attached?

Comments:

Purchasing Department Comments:

County Attorney Comments:

Chairman's Comments:

Walton County Miscellaneous Surplus

Items released as County Surplus Property on the 6th day of October, 2026

[illegible]

Walton County Department Agenda Request

Department Name: Juvenile Court

Department Head/Representative: Michele Nash, Representative

Meeting Date Request: October 7, 2026

Has this topic been discussed at past meetings? Yes

If so, When? 2025 October Meeting

TOPIC: Contract for Break the Cycle Counseling and Consulting, LLC

Wording For Agenda: Consultant Contract for the Truancy Intervention Program Grant (CHINS). Second year award

This Request: Informational Purposes Only Needs Action by Commissioners* Yes

*What action are you seeking from the Commissioners? Approval of the Contract

Department Comments/Recommendation: This will be our second year being awarded the grant.

Additional Documentation Attached? Contract

Is review of this request or accompanying documentation by the County Attorney required? Yes

If so, has a copy of the documentation been forwarded to County Attorney? Yes

Date forwarded to County Attorney: September 24, 2026

Has the County Attorney review been completed? Not at the time of this request

If this request involves the expenditure of county funds, please answer the following:

Approved in current budget? N/A

Budget information attached? N/A

Comments:

Purchasing Department Comments:

County Attorney Comments:

Chairman's Comments:



PROFESSIONAL SERVICES AGREEMENT

THIS AGREEMENT is made and entered as of the 1st day of October 2026, by and between **WALTON COUNTY, GEORGIA**, a political subdivision of the State of Georgia, acting by and through its governing authority, the County Board of Commissioners (hereinafter referred to as the "County"), and **BREAK THE CYCLE COUNSELING & CONSULTING, LLC.**, a Georgia for-profit limited liability company, (hereinafter referred to as the "Contractor"), collectively referred to herein as the "Parties."

WITNESSETH:

WHEREAS, County desires to retain Contractor to provide certain services in the completion of a Project (defined below); and

WHEREAS, County finds that specialized knowledge, skills, and training are necessary to perform the Work (defined below) contemplated under this Agreement; and

WHEREAS, Contractor has represented that it is qualified by training and experience to perform the Work; and

WHEREAS, Contractor desires to perform the Work as set forth in this Agreement under the terms and conditions provided in this Agreement; and

WHEREAS, the public interest will be served by this Agreement; and

WHEREAS, Contractor has familiarized itself with the nature and extent of the Agreement, the Project, and the Work, and with all local conditions and federal, state and local laws, ordinances, rules and regulations that may in any manner affect cost, progress or performance of Work.

NOW, THEREFORE, for and in consideration of the mutual promises, the public purposes, and the acknowledgements and agreements contained herein, and other good and adequate consideration, the sufficiency of which is hereby acknowledged, the Parties do mutually agree as follows:

I. SCOPE OF SERVICES AND TERMINATION DATE

A. Agreement. The Agreement shall consist of this Professional Services Agreement and each of the Exhibits hereto, which are incorporated herein by reference, including:

Exhibit “A” – Scope of Services

Exhibit “B” – Contractor Affidavit

Exhibit “C” – Subcontractor Affidavit

Exhibit “D” – Key Personnel

B. Project Description. The contractor will provide evidence-based programming; to include the following: Active Parenting, Teens in Action, in-home parenting, behavioral aide services, family assessments, and individual and family counseling. The contractor will assist with data collection in reference to grant management as needed.

C. The Work. The Work to be completed under this Agreement (the “Work”) includes, but shall not be limited to, the work described in the Scope of Work provided in **Exhibit “A”**, attached hereto and incorporated herein by reference. Unless otherwise stated in **Exhibit “A”**, the Work includes all material, labor, insurance, tools, equipment, machinery, water, heat, utilities, transportation, facilities, services and any other miscellaneous items and work necessary to complete the Work. Some details necessary for proper execution and completion of the Work may not be specifically described in the Scope of Work, but they are a requirement of the Work if they are a usual and customary component of the contemplated services or are otherwise necessary for proper completion of the Work.

D. Schedule, Completion Date, and Term of Agreement. Contractor understands that time is of the essence of this Agreement and warrants and represents that it will perform the Work in a prompt and timely manner, which shall not impose delays on the progress of the Work. The term of this Agreement (“Term”) shall commence as of **October 1, 2026** (the “Effective Date”), and the Work shall be completed, and the Agreement shall terminate, on **September 30, 2027** (provided that certain obligations will survive termination/expiration of this Agreement). The Term of this Agreement is for one year (FY2027). Title to any supplies, materials, equipment, or other personal property shall remain in Contractor until fully paid for by County._

II. WORK CHANGES

A. Change Order Defined. A “Change Order” means a written modification of the Agreement, signed by representatives of County and Contractor with appropriate authorization.

B. Right to Order Changes. County reserves the right to order changes in the Work to be performed under this Agreement by altering, adding to, or deducting from the Work. All such changes shall be incorporated in written Change Orders and executed by Contractor and County. Such Change Orders shall specify the changes ordered and any necessary adjustment of compensation and completion time. If the Parties cannot reach an agreement on the terms for performing the changed work within a reasonable time to avoid delay or other unfavorable impacts as determined by County in its sole discretion, County shall have the right to determine reasonable terms, and Contractor shall proceed with the changed work.

C. Change Order Requirement. Any work added to the scope of this Agreement

by a Change Order shall be executed under all the applicable conditions of this Agreement. No claim for additional compensation or extension of time shall be recognized, unless contained in a written Change Order duly executed on behalf of County and Contractor.

D. Authority to Approve Change Order. Any Change Order affecting the price where the Maximum Contract Price (as amended) is equal to or less than \$5,000 must be approved by the Head of the Department supervising the performance of this Agreement. Any Change Order affecting the price where the Maximum Contract Price (as amended) is between \$5,000.01 and \$24,999.99 must be approved by the Chair of the County Board of Commissioners (for public works projects) or by the County Manager (for all other projects). Any Change Order affecting the price where the Maximum Contract Price (as amended) is equal to or greater than \$25,000 must be approved by resolution of the County Board of Commissioners.

III. COMPENSATION AND METHOD OF PAYMENT

A. Payment Terms. County agrees to pay Contractor for the Work to be performed by Contractor in accordance with the Agreement. Compensation for Work performed shall be paid to Contractor upon receipt of an invoice of services performed from Contractor. Invoices shall be submitted on a monthly basis, and such invoices shall reflect the services provided.

B. Maximum Contract Price. The total amount paid under this Agreement as compensation for Work performed shall not, in any case, exceed one hundred thousand dollars (\$100,000.00) (the "Maximum Contract Price"), except as outlined in Section II(C) above, and Contractor represents that this amount is sufficient to perform all of the Work set forth in and contemplated by this Agreement.

C. Reimbursement for Costs. The Maximum Contract Price set forth in Section III(B) above includes all costs, direct and indirect, needed to perform the Work and complete the Project, including Director directives, work schedules, uncompensated overtime, and additional position responsibilities, and there shall be no additional reimbursement for costs.

IV. COVENANTS OF CONTRACTOR

A. Expertise of Contractor; Licenses, Certification and Permits. Contractor accepts the relationship of trust and confidence established between it and County, recognizing that County's intention and purpose in entering into this Agreement is to engage an entity with the requisite capacity, experience, and professional skill and judgment to provide the Work in pursuit of the timely and competent completion of the Work undertaken by Contractor under this Agreement. Contractor shall employ only persons duly qualified in the appropriate area of expertise to perform the Work described in this Agreement. In particular, Contractor shall ensure that any individuals performing Work under this Agreement have undergone a criminal history investigation (including a fingerprint record check) to confirm fitness to supervise and provide treatment to minors, and such individuals shall also be instructed in the requirements set forth in O.C.G.A. § 19-7-5 relating to the reporting of child abuse.

Contractor covenants and declares that it has obtained all diplomas, certificates, licenses,

permits or the like required of Contractor by any and all national, state, regional, county, or local boards, agencies, commissions, committees or other regulatory bodies in order to perform the Work contracted for under this Agreement. Further, Contractor agrees that it will perform all Work in accordance with the standard of care and quality ordinarily expected of competent professionals and in compliance with all federal, state, and local laws, regulations, codes, ordinances, or orders applicable to the Project, including, but not limited to, any applicable records retention requirements and Georgia's Open Records Act (O.C.G.A. § 50-18-71, *et seq.*). Any additional work or costs incurred as a result of error and/or omission by Contractor as a result of not meeting the applicable standard of care or quality will be provided by Contractor at no additional cost to County. This provision shall survive termination of this Agreement.

B. Budgetary Limitations. Contractor agrees and acknowledges that budgetary limitations are not a justification for breach of sound principals of Contractor's profession and industry. Contractor shall take no calculated risk in the performance of the Work. Specifically, Contractor agrees that, in the event it cannot perform the Work within the budgetary limitations established without disregarding sound principles of Contractor's profession and industry, Contractor will give written notice immediately to County.

C. County's Reliance on the Work. Contractor acknowledges and agrees that County does not undertake to approve or pass upon matters of expertise of Contractor and that, therefore, County bears no responsibility for Contractor's Work performed under this Agreement. Contractor acknowledges and agrees that the acceptance of Work by County is limited to the function of determining whether there has been compliance with what is required to be produced under this Agreement. County will not, and need not, inquire into adequacy, fitness, suitability or correctness of Contractor's performance. Contractor further agrees that no approval of designs, plans, specifications or other work product by any person, body or agency shall relieve Contractor of the responsibility for adequacy, fitness, suitability, and correctness of Contractor's Work under professional and industry standards, or for performing services under this Agreement in accordance with sound and accepted professional and industry principles.

D. Contractor's Reliance on Submissions by County. Contractor must have timely information and input from County in order to perform the Work required under this Agreement. Contractor is entitled to rely upon information provided by County, but Contractor shall provide immediate written notice to County if Contractor knows or reasonably should know that any information provided by County is erroneous, inconsistent, or otherwise problematic.

E. Contractor's Representative. Carrie Tinsley shall be authorized to act on Contractor's behalf with respect to the Work as Contractor's designated representative, provided that this designation shall not relieve either Party of any written notice requirements set forth elsewhere in this Agreement.

F. Assignment of Agreement. Contractor covenants and agrees not to assign or transfer any interest in, or delegate any duties of this Agreement, without the prior express written consent of County. As to any approved subcontractors, Contractor shall be solely responsible for reimbursing them, and County shall have no obligation to them.

G. Responsibility of Contractor and Indemnification of County. Contractor covenants and agrees to take and assume all responsibility for the Work rendered in connection with this Agreement. Contractor shall bear all losses and damages directly or indirectly resulting to it and/or County on account of the performance or character of the Work rendered pursuant to this Agreement. Contractor shall defend, indemnify and hold harmless County and County's elected and appointed officials, officers, boards, commissions, employees, representatives, Contractors, servants, agents, attorneys and volunteers, including without limitation judges and staff of the County Juvenile Court (individually an "Indemnified Party" and collectively "Indemnified Parties") from and against any and all claims, suits, actions, judgments, injuries, damages, losses, costs, expenses and liability of any kind whatsoever, including but not limited to attorney's fees and costs of defense ("Liabilities"), which may arise from or be the result of an alleged willful, negligent or tortious act or omission arising out of the Work, performance of contracted services, or operations by Contractor, any subcontractor, anyone directly or indirectly employed by Contractor or subcontractor or anyone for whose acts or omissions Contractor or subcontractor may be liable, regardless of whether or not the act or omission is caused in part by a party indemnified hereunder; provided that this indemnity obligation does not include Liabilities caused by or resulting from the sole negligence of an Indemnified Party. This indemnity obligation shall not be construed to negate, abridge, or otherwise reduce any other right or obligation of indemnity which would otherwise exist as to any party or person described in this provision.

In any and all claims against an Indemnified Party, by any employee of Contractor, its subcontractor, anyone directly or indirectly employed by Contractor or subcontractor or anyone for whose acts Contractor or subcontractor may be liable, the indemnification obligation set forth in this provision shall not be limited in any way by any limitation on the amount or type of damages, compensation or benefits payable by or for Contractor or any subcontractor under workers' or workmen's compensation acts, disability benefit acts or other employee benefit acts. This obligation to indemnify, defend, and hold harmless the Indemnified Party(ies) shall survive expiration or termination of this Agreement, provided that the claims are based upon or arise out of actions or omissions that occurred during the performance of this Agreement.

H. Independent Contractor. Contractor hereby covenants and declares that it is engaged in an independent business and agrees to perform the Work as an independent contractor and not as the agent or employee of County or the County's Juvenile Court. Nothing in this Agreement shall be construed to make Contractor or any of its employees, servants, or subcontractors, an employee, servant or agent of County for any purpose. Contractor agrees to be solely responsible for its own matters relating to the time and place the Work is performed and the method used to perform such Work; the instrumentalities, tools, supplies and/or materials necessary to complete the Work; hiring of Contractors, agents or employees to complete the Work; and the payment of employees, including benefits and compliance with Social Security, withholding and all other regulations governing such matters. Contractor agrees to be solely responsible for its own acts and those of its subordinates, employees, and subcontractors during the life of this Agreement. There shall be no contractual relationship between any subcontractor or supplier and County by virtue of this Agreement with Contractor. Any provisions of this Agreement that may appear to give County the right to direct Contractor as to the details of the

services to be performed by Contractor or to exercise a measure of control over such services will be deemed to mean that Contractor shall follow the directions of County with regard to the results of such services only. It is further understood that this Agreement is not exclusive, and County may hire additional entities to perform the Work related to this Agreement.

Inasmuch as County and Contractor are independent of each other, neither has the authority to bind the other to any third person or otherwise to act in any way as the representative of the other, unless otherwise expressly agreed to in writing signed by both Parties hereto. Contractor agrees not to represent itself as County's agent for any purpose to any party or to allow any employee of Contractor to do so, unless specifically authorized, in advance and in writing, to do so, and then only for the limited purpose stated in such authorization. Contractor shall assume full liability for any contracts or agreements Contractor enters into on behalf of County without the express knowledge and prior written consent of County.

I. Insurance.

- (1) Requirements: Contractor shall have and maintain in full force and effect for the duration of this Agreement, insurance insuring against claims for injuries to persons or damages to property which may arise from or in connection with the performance of the Work by Contractor, its agents, representatives, employees or subcontractors. All policies shall be subject to approval by County as to form and content. These requirements are subject to amendment or waiver if so approved in writing by the County Manager.
- (2) Minimum Limits of Insurance: Contractor shall maintain the following insurance policies with coverage and limits no less than:
 - (a) Commercial General Liability coverage of at least \$1,000,000 (one million dollars) combined single limit per occurrence and \$2,000,000 (two million dollars) aggregate for comprehensive coverage including for bodily and personal injury, sickness, disease or death, injury to or destruction of property, including loss of use resulting therefrom.
 - (b) Commercial Automobile Liability (owned, non-owned, hired) coverage of at least \$1,000,000 (one million dollars) combined single limit per occurrence for comprehensive coverage including bodily and personal injury, sickness, disease or death, injury to or destruction of property, including loss of use resulting therefrom.
 - (c) Professional Liability of at least \$1,000,000 (one million dollars) limit for claims arising out of professional services and caused by Contractor's errors, omissions, or negligent acts.
 - (d) Workers' Compensation limits as required by the State of Georgia

and Employers' Liability limits of \$1,000,000 (one million dollars) per occurrence or disease. (If Contractor is a sole proprietor, who is otherwise not entitled to coverage under Georgia's Workers' Compensation Act, Contractor must secure Workers' Compensation coverage approved by both the State Board of Workers' Compensation and the Commissioner of Insurance. The amount of such coverage shall be the same as what is otherwise required of employers entitled to coverage under the Georgia Workers' Compensation Act. Further, Contractor shall provide a certificate of insurance indicating that such coverage has been secured and that no individual has been excluded from coverage.)

- (3) Deductibles and Self-Insured Retentions: Any deductibles or self-insured retentions must be declared to and approved by County in writing so that County may ensure the financial solvency of Contractor; self-insured retentions should be included on the certificate of insurance.
- (4) Other Insurance Provisions: Each policy shall contain, or be endorsed to contain, the following provisions respectively:
 - (a) General Liability, Automobile Liability and (if applicable) Umbrella Liability Coverage.
 - (i) *Additional Insured Requirement.* County and County's elected and appointed officials, officers, boards, commissioners, employees, representatives, Contractors, servants, agents and volunteers (individually "Insured Party" and collectively "Insured Parties") shall be named as additional insureds as respects: liability arising out of activities performed by or on behalf of Contractor; products and completed operations of Contractor; premises owned, leased, or used by Contractor; automobiles owned, leased, hired, or borrowed by Contractor. The coverage shall contain no special limitations on the scope of protection afforded to the Insured Parties. Nothing contained in this section shall be construed to require the Contractor to provide liability insurance coverage to any Insured Party for claims asserted against such Insured Party for its sole negligence.
 - (ii) *Primary Insurance Requirement.* Contractor's insurance coverage shall be primary noncontributing insurance as respects to any other insurance or self-insurance available to the Insured Parties. Any insurance or self-insurance maintained by the Insured Parties shall be in excess of Contractor's insurance and shall not contribute with it.

- (iii) *Reporting Requirement.* Any failure to comply with reporting provisions of the policies shall not affect coverage provided to the Insured Parties.
 - (iv) *Separate Coverage.* Coverage shall state that Contractor's insurance shall apply separately to each insured against whom claim is made or suit is brought, except with respect to limits of insurance provided.
 - (v) *Defense Costs/Cross Liability.* Coverage shall be provided on a "pay on behalf" basis, with defense costs payable in addition to policy limits. There shall be no cross liability exclusion.
 - (vi) *Subrogation.* The insurer shall agree to waive all rights of subrogation against the Insured Parties for losses arising from Work performed by Contractor for County.
- (b) Workers' Compensation Coverage. The insurer providing Workers' Compensation Coverage will agree to waive all rights of subrogation against the Insured Parties for losses arising from Work performed by Contractor for County.
- (c) All Coverages.
- (i) *Notice Requirement.* Each insurance policy required by this Agreement shall be endorsed to state that coverage shall not be suspended, voided, or canceled except after thirty (30) calendar days prior written notice (or 10 calendar days if due to non-payment) has been given to County. County reserves the right to accept alternate notice terms and provisions, provided they meet the minimum requirements under Georgia law.
 - (ii) *Starting and Ending Dates.* Policies shall have concurrent starting and ending dates.
 - (iii) *Incorporation of Indemnification Obligations.* Policies shall include an endorsement incorporating the indemnification obligations assumed by Contractor under the terms of this Agreement, including but not limited to Section IV(G) of this Agreement.
- (5) Acceptability of Insurers: The insurance to be maintained by Contractor must be issued by a company licensed or approved by the Insurance

Commissioner to transact business in the State of Georgia. Such insurance policies shall be placed with insurer(s) with an A.M. Best Policyholder's rate of no less than "A-" and with a financial rating of Class VII or greater. The Contractor shall be responsible for any delay resulting from the failure of its insurer to provide proof of coverage in the proscribed form.

- (6) Verification of Coverage: Contractor shall furnish to County for County approval certificates of insurance and endorsements to the policies evidencing all coverage required by this Agreement prior to the start of work. Without limiting the general scope of this requirement, Contractor is specifically required to provide an endorsement naming County as an additional insured when required. The certificates of insurance and endorsements for each insurance policy are to be on a form utilized by Contractor's insurer in its normal course of business and are to be signed by a person authorized by that insurer to bind coverage on its behalf, unless alternate sufficient evidence of their validity and incorporation into the policy is provided. County reserves the right to require complete, certified copies of all required insurance policies at any time. Contractor shall provide proof that any expiring coverage has been renewed or replaced prior to the expiration of the coverage.
- (7) Subcontractors: Contractor shall either (1) ensure that its insurance policies (as described herein) cover all subcontractors and the Work performed by such subcontractors or (2) ensure that any subcontractor secures separate policies covering that subcontractor and its Work. All coverage for subcontractors shall be subject to all of the requirements stated in this Agreement, including, but not limited to, naming the Insured Parties as additional insureds.
- (8) Claims-Made Policies: Contractor shall extend any claims-made insurance policy for at least six (6) years after termination or final payment under the Agreement, whichever is later, and have an effective date which is on or prior to the Effective Date.
- (9) County as Additional Insured and Loss Payee: County shall be named as an additional insured and loss payee on all policies required by this Agreement, except County need not be named as an additional insured and loss payee on any Professional Liability policy or Workers' Compensation policy.
- (10) Progress Payments: The making of progress payments to Contractor shall not be construed as relieving Contractor or its subcontractors or insurance carriers from providing the coverage required in this Agreement.

J. Employment of Unauthorized Aliens Prohibited – E-Verify Affidavit.
Pursuant to O.C.G.A. § 13-10-91, County shall not enter into a contract for the physical performance of services unless:

- (1) Contractor shall provide evidence on County-provided forms, attached hereto as **Exhibits “B” and “C”** (affidavits regarding compliance with the E-Verify program to be sworn under oath under criminal penalty of false swearing pursuant to O.C.G.A. § 16-10-71), that it and Contractor’s subcontractors have registered with, are authorized to use and use the federal work authorization program commonly known as E-Verify, or any subsequent replacement program, in accordance with the applicable provisions and deadlines established in O.C.G.A. § 13-10-91, and that they will continue to use the federal work authorization program throughout the contract period, **or**
- (2) Contractor provides evidence that it is not required to provide an affidavit because it is an *individual* (not a company) licensed pursuant to Title 26 or Title 43 or by the State Bar of Georgia and is in good standing.

Contractor hereby verifies that it has, prior to executing this Agreement, executed a notarized affidavit, the form of which is provided in **Exhibit “B”**, and submitted such affidavit to County or provided County with evidence that it is an individual not required to provide such an affidavit because it is licensed and in good standing as noted in sub-subsection (2) above. Further, Contractor hereby agrees to comply with the requirements of the federal Immigration Reform and Control Act of 1986 (IRCA), P.L. 99-603, O.C.G.A. § 13-10-91 and Georgia Department of Labor Rule 300-10-1-.02.

In the event Contractor employs or contracts with any subcontractor(s) in connection with the covered contract, Contractor agrees to secure from such subcontractor(s) attestation of the subcontractor’s compliance with O.C.G.A. § 13-10-91 and Rule 300-10-1-.02 by the subcontractor’s execution of the subcontractor affidavit, the form of which is attached hereto as **Exhibit “C”**, which subcontractor affidavit shall become part of the Contractor/subcontractor agreement, or evidence that the subcontractor is not required to provide such an affidavit because it is an *individual* licensed and in good standing as noted in sub-subsection (2) above. If a subcontractor affidavit is obtained, Contractor agrees to provide a completed copy to County within five (5) business days of receipt from any subcontractor.

Where Contractor is required to provide an affidavit pursuant to O.C.G.A. § 13-10-91, the County Manager or his/her designee shall be authorized to conduct an inspection of Contractor’s and Contractor’s subcontractors’ verification process at any time to determine that the verification was correct and complete. Contractor and Contractor’s subcontractors shall retain all documents and records of their respective verification process for a period of five (5) years following completion of the contract. Further, where Contractor is required to provide an affidavit pursuant to O.C.G.A. § 13-10-91, the County Manager or his/her designee shall further be authorized to conduct periodic inspections to ensure that no County Contractor or Contractor’s subcontractors employ unauthorized aliens on County contracts. By entering into a

contract with County, Contractor and Contractor's subcontractors agree to cooperate with any such investigation by making their records and personnel available upon reasonable notice for inspection and questioning. Where Contractor or Contractor's subcontractors are found to have employed an unauthorized alien, the County Manager or his/her designee may report same to the Department of Homeland Security. Contractor's failure to cooperate with the investigation may be sanctioned by termination of the Agreement, and Contractor shall be liable for all damages and delays occasioned by County thereby.

Contractor agrees that the employee-number category designated below is applicable to Contractor.

- ☐ 500 or more employees.
- ☐ 100 or more employees.
- ☒ Fewer than 100 employees.

Contractor hereby agrees that, in the event Contractor employs or contracts with any subcontractor(s) in connection with this Agreement and where the subcontractor is required to provide an affidavit pursuant to O.C.G.A. § 13-10-91, Contractor will secure from the subcontractor(s) such subcontractor(s') indication of the above employee-number category that is applicable to the subcontractor.

The above requirements shall be in addition to the requirements of state and federal law, and shall be construed to be in conformity with those laws.

K. Records, Reports and Audits.

(1) Records:

- (a) Books, records, documents, account ledgers, data bases, and similar materials relating to the Work performed for County under this Agreement ("Records") shall be established and maintained by Contractor in accordance with applicable law and requirements prescribed by County with respect to all matters covered by this Agreement. Except as otherwise authorized or required, such Records shall be maintained for at least three (3) years from the date that final payment is made to Contractor by County under this Agreement. Furthermore, Records that are the subject of audit findings shall be retained for three (3) years or until such audit findings have been resolved, whichever is later.
- (b) All costs claimed or anticipated to be incurred in the performance of this Agreement shall be supported by properly executed payrolls, time records, invoices, contracts, or vouchers, or other official documentation evidencing in proper detail the nature and

propriety of the charges. All checks, payrolls, invoices, contracts, vouchers, orders or other accounting documents pertaining in whole or in part to this Agreement shall be clearly identified and readily accessible.

- (2) **Reports and Information:** Upon request, Contractor shall furnish to County any and all Records in the form requested by County. All Records provided electronically must be in a format compatible with County's computer systems and software.
- (3) **Audits and Inspections:** At any time during normal business hours and as often as County may deem necessary, Contractor shall make available to County or County's representative(s) for examination all Records. Contractor will permit County or County's representative(s) to audit, examine, and make excerpts or transcripts from such Records. Contractor shall provide proper facilities for County or County's representative(s) to access and inspect the Records, or, at the request of County, shall make the Records available for inspection at County's office. Further, Contractor shall permit County or County's representative(s) to observe and inspect any or all of Contractor's facilities and activities during normal hours of business for the purpose of evaluating Contractor's compliance with the terms of this Agreement. In such instances, County or County's representative(s) shall not interfere with or disrupt such activities.

L. Ethics Code; Conflict of Interest. Contractor agrees that it shall not engage in any activity or conduct that would result in a violation of the Walton County Code of Ethics or any other similar law or regulation. Contractor certifies that to the best of its knowledge no circumstances exist which will cause a conflict of interest in performing the Work. Should Contractor become aware of any circumstances that may cause a conflict of interest during the Term of this Agreement, Contractor shall immediately notify County. If County determines that a conflict of interest exists, County may require that Contractor take action to remedy the conflict of interest or terminate the Agreement without liability. County shall have the right to recover any fees paid for services rendered by Contractor when such services were performed while a conflict of interest existed if Contractor had knowledge of the conflict of interest and did not notify County within five (5) business days of becoming aware of the existence of the conflict of interest.

M. Confidentiality. Contractor acknowledges that it may receive confidential information of County and that it will protect the confidentiality of any such confidential information and will require any of its subcontractors, Contractors, and/or staff to likewise protect such confidential information. Contractor agrees that confidential information it learns or receives or such reports, information, opinions or conclusions that Contractor creates under this Agreement shall not be made available to, or discussed with, any individual or organization, including the news media, without prior written approval of County. Contractor shall exercise reasonable precautions to prevent the unauthorized disclosure and use of County information whether specifically deemed confidential or not.

In performing the Work, Contractor may receive County records that contain personal identifying information, including addresses, social security numbers, phone numbers, birth dates, and medical information. Contractor may use such personal information only for purposes of performing the Work and shall not share this information with any third party except as necessary to perform the Work, and then only if the third party agrees to the use restrictions found in this paragraph.

Contractor acknowledges that County's disclosure of documentation is governed by Georgia's Open Records Act, and Contractor further acknowledges that if Contractor submits records containing trade secret information, and if Contractor wishes to keep such records confidential, Contractor must submit and attach to such records an affidavit affirmatively declaring that specific information in the records constitutes trade secrets pursuant to Article 27 of Chapter 1 of Title 10, and the Parties shall follow the requirements of O.C.G.A. § 50-18-72(a)(34) related thereto.

N. Key Personnel. All of the individuals identified in **Exhibit "D"**, attached hereto, are necessary for the successful completion of the Work due to their unique expertise and depth and breadth of experience. There shall be no change in Contractor's Project Manager or members of the Project team, as listed in **Exhibit "D"**, without written approval of County. Contractor recognizes that the composition of this team was instrumental in County's decision to award the Work to Contractor and that compelling reasons for substituting these individuals must be demonstrated for County's consent to be granted. Any substitutes shall be persons of comparable or superior expertise and experience. Failure to comply with the provisions of this paragraph shall constitute a material breach of Contractor's obligations under this Agreement and shall be grounds for termination.

O. Meetings. Contractor is required to meet with County's personnel, or designated representatives, to resolve technical or contractual problems that may occur during the Term of this Agreement at no additional cost to County. Meetings will occur as problems arise and will be coordinated by County. County shall inform Contractor's Representative of the need for a meeting and of the date, time and location of the meeting at least three (3) full business days prior to the date of the meeting. Face-to-face meetings are desired. However, at Contractor's option and expense, a conference call meeting may be substituted. Consistent failure to participate in problem resolution meetings, two consecutive missed or rescheduled meetings, or failure to make a good faith effort to resolve problems, may result in termination of this Agreement for cause.

P. Authority to Contract. The individual executing this Agreement on behalf of Contractor covenants and declares that it has obtained all necessary approvals of Contractor's board of directors, stockholders, general partners, limited partners or similar authorities to simultaneously execute and bind Contractor to the terms of this Agreement, if applicable.

Q. Ownership of Work. All reports, designs, drawings, plans, specifications, schedules, work product and other materials, including, but not limited to, those in electronic form, prepared or in the process of being prepared for the Work to be performed by Contractor

("Materials") shall be the property of County, and County shall be entitled to full access and copies of all Materials in the form prescribed by County. Any Materials remaining in the hands of Contractor or subcontractor upon completion or termination of the Work shall be delivered immediately to County whether or not the Project or Work is commenced or completed; provided, however, that Contractor may retain a copy of any deliverables for its records. Contractor assumes all risk of loss, damage or destruction of or to Materials. If any Materials are lost, damaged or destroyed before final delivery to County, Contractor shall replace them at its own expense. Any and all copyrightable subject matter in all Materials is hereby assigned to County, and Contractor agrees to execute any additional documents that may be necessary to evidence such assignment.

R. Nondiscrimination. In accordance with Title VI of the Civil Rights Act of 1964, as amended, 42 U.S.C. § 2000d, section 303 of the Age Discrimination Act of 1975, as amended, 42 U.S.C. § 6102, section 202 of the Americans with Disabilities Act of 1990, 42 U.S.C. § 12132, and all other provisions of Federal law, Contractor agrees that, during performance of this Agreement, Contractor, for itself, its assignees and successors in interest, will not discriminate against any employee or applicant for employment, any subcontractor, or any supplier because of race, color, creed, national origin, gender, age or disability. In addition, Contractor agrees to comply with all applicable implementing regulations and shall include the provisions of this paragraph in every subcontract for services contemplated under this Agreement.

V. COVENANTS OF COUNTY

A. Right of Entry. County shall provide for right of entry for Contractor and all necessary equipment as required for Contractor to complete the Work; provided that Contractor shall not unreasonably encumber the Project site(s) with materials or equipment.

B. County's Representative. Chief Judge Anne LaMalva shall be authorized to act on County's behalf with respect to the Work as County's designated representative on this Project; provided that any changes to the Work or the terms of this Agreement must be approved as provided in Section II above.

VI. TERMINATION

A. For Convenience. County may terminate this Agreement for convenience at any time upon providing written notice thereof at least fifteen (15) calendar days in advance of the termination date.

B. For Cause. Contractor shall have no right to terminate this Agreement prior to completion of the Work, except in the event of County's failure to pay Contractor within thirty (30) calendar days of Contractor providing County with notice of a delinquent payment and an opportunity to cure. In the event of Contractor's breach or default under this Agreement, County may terminate this Agreement for cause. County shall give Contractor at least seven (7) calendar days' written notice of its intent to terminate the Agreement for cause and the reasons therefor. If Contractor fails to cure the breach or default within that seven (7) day period, or otherwise

remedy the breach or default to the reasonable satisfaction of County, then County may, at its election: (a) in writing terminate the Agreement in whole or in part; (b) cure such default itself and charge Contractor for the costs of curing the default against any sums due or which become due to Contractor under this Agreement; and/or (c) pursue any other remedy then available, at law or in equity, to County for such default.

Notwithstanding the above, this Agreement may be terminated by the County immediately and without prior notice for any of the following:

- (1) Contractor's failure to perform its duties in a competent manner, as determined by the Juvenile Court Judge, in his or her sole discretion;
- (2) Contractor's failure to perform the duties assigned, as determined by the Juvenile Court Judge, in his or her sole discretion;
- (3) Contractor is charged with a felony, crime of moral turpitude, act of fraud or other crime involving dishonesty, or any crime against children;
- (4) Contractor violates any applicable duties of confidentiality;
- (5) Contractor uses any illegal drug; or
- (6) Contractor commits any act or acts that could reflect discredit on or bring disrepute to the County.

For purposes of this Section, "Contractor" includes any employee or agent of Contractor providing services to the County Juvenile Court.

C. Statutory Termination. In compliance with O.C.G.A. § 36-60-13, this Agreement shall be deemed terminated as provided in I(D) of this Agreement. Further, this Agreement shall terminate immediately and absolutely at such time as appropriated or otherwise unobligated funds are no longer available to satisfy the obligation of County.

D. Payment Upon Termination. Upon termination, County shall provide for payment to Contractor for services rendered and, where authorized, expenses incurred prior to the termination date; provided that, where this Agreement is terminated for cause, County may deduct from such payment any portion of the cost for County to complete (or hire someone to complete) the Work, as determined at the time of termination, not otherwise covered by the remaining unpaid Maximum Contract Price.

E. Conversion to Termination for Convenience. If County terminates this Agreement for cause and it is later determined that County did not have grounds to do so, the termination will be converted to and treated as a termination for convenience under the terms of Section VI(A) above.

F. Requirements Upon Termination. Upon termination, Contractor shall: (1)

promptly discontinue all services, cancel as many outstanding obligations as possible, and not incur any new obligations, unless the County directs otherwise; and (2) promptly deliver to County all data, drawings, reports, summaries, and such other information and materials as may have been generated or used by Contractor in performing this Agreement, whether completed or in process, in the form specified by County.

G. Reservation of Rights and Remedies. The rights and remedies of County and Contractor provided in this Article are in addition to any other rights and remedies provided under this Agreement or at law or in equity.

VII. MISCELLANEOUS

A. Entire Agreement. This Agreement, including any exhibits hereto, constitutes the complete agreement between the Parties and supersedes any and all other agreements, either oral or in writing, between the Parties with respect to the subject matter of this Agreement. No other agreement, statement or promise relating to the subject matter of this Agreement not contained in this Agreement shall be valid or binding. This Agreement may be modified or amended only by a written Change Order (as provided in Section II above) or other document signed by representatives of both Parties with appropriate authorization.

B. Successors and Assigns. Subject to the provision of this Agreement regarding assignment, this Agreement shall be binding on the heirs, executors, administrators, successors and assigns of the respective Parties.

C. Governing Law. This Agreement shall be governed by and construed in accordance with the laws of the State of Georgia without regard to choice of law principles. If any action at law or in equity is brought to enforce or interpret the provisions of this Agreement, the rules, regulations, statutes and laws of the State of Georgia will control. Any action or suit related to this Agreement shall be brought in the Superior Court of Walton County, Georgia, or the U.S. District Court for the Northern District of Georgia – Atlanta Division, and Contractor submits to the jurisdiction and venue of such court.

D. Captions and Severability. All headings herein are intended for convenience and ease of reference purposes only and in no way define, limit or describe the scope or intent thereof, or of this Agreement, or in any way affect this Agreement. Should any article(s) or section(s) of this Agreement, or any part thereof, later be deemed illegal, invalid or unenforceable by a court of competent jurisdiction, the offending portion of the Agreement should be severed, and the remainder of this Agreement shall remain in full force and effect to the extent possible as if this Agreement had been executed with the invalid portion hereof eliminated, it being the intention of the Parties that they would have executed the remaining portion of this Agreement without including any such part, parts, or portions that may for any reason be hereafter declared invalid.

E. Business License. Prior to commencement of the Work to be provided hereunder, Contractor shall apply to County for a business license, pay the applicable business license fee, and maintain said business license during the Term of this Agreement, unless

Contractor provides evidence that no such license is required.

F. Notices.

- (1) **Communications Relating to Day-to-Day Activities.** All communications relating to the day-to-day activities of the Work shall be exchanged between County's Representative (named above) for County and Contractor's Representative (named above) for Contractor.
- (2) **Official Notices.** All other notices, requests, demands, writings, or correspondence, as required by this Agreement, shall be in writing and shall be deemed received, and shall be effective, when: (1) personally delivered, or (2) on the third day after the postmark date when mailed by certified mail, postage prepaid, return receipt requested, or (3) upon actual delivery when sent via national overnight commercial carrier to the Party at the address given below, or at a substitute address previously furnished to the other Party by written notice in accordance herewith.

NOTICE TO COUNTY shall be sent to:

Walton County
Attn: County Manager (John A. Ward)
111 S. Broad Street
Monroe, Georgia 30655

With a copy to:

Walton County Juvenile Court
Attn: Judge Anne LaMalva
Walton County Government Building
303 South Hammond Drive; Suite 223
Monroe, Georgia 30655

NOTICE TO CONTRACTOR shall be sent to:

Break the Cycle Counseling & Consulting, LLC
Attn: Carrie Tinsley
115 Alcovy Forest Drive
Covington, GA 30014

G. Waiver of Agreement. No failure by County to enforce any right or power granted under this Agreement, or to insist upon strict compliance by Contractor with this Agreement, and no custom or practice of County at variance with the terms and conditions of this Agreement shall constitute a general waiver of any future breach or default or affect County's right to demand exact and strict compliance by Contractor with the terms and conditions of this Agreement. Further, no express waiver shall affect any term or condition other

than the one specified in such waiver, and that one only for the time and manner specifically stated.

H. Survival. All sections of this Agreement which by their nature should survive termination will survive termination, including, without limitation, confidentiality obligations and insurance maintenance requirements.

I. No Third Party Rights. This Agreement shall be exclusively for the benefit of the Parties and shall not provide any third parties with any remedy, claim, liability, reimbursement, cause of action or other right.

J. Sovereign Immunity; Ratification. Nothing contained in this Agreement shall be construed to be a waiver of County's sovereign immunity or any individual's qualified, good faith or official immunities. Ratification of this Agreement by a majority of the County Board of Commissioners shall authorize the Chair to execute this Agreement on behalf of County.

K. No Personal Liability. Nothing herein shall be construed as creating any individual or personal liability on the part of any of County's elected or appointed officials, officers, boards, commissions, employees, representatives, Contractors, servants, agents, attorneys or volunteers. No such individual shall be personally liable to Contractor or any successor in interest in the event of any default or breach by County or for any amount which may become due to Contractor or successor or on any obligation under the terms of this Agreement. Likewise, Contractor's performance of services under this Agreement shall not subject Contractor's individual employees, officers, or directors to any personal contractual liability, except where Contractor is a sole proprietor. The Parties agree that, except where Contractor is a sole proprietor, their sole and exclusive remedy, claim, demand or suit for contractual liability shall be directed and/or asserted only against Contractor or County, respectively, and not against any elected or appointed official, officers, boards, commissions, employees, representatives, Contractors, servants, agents, attorneys and volunteers.

L. Counterparts; Agreement Construction and Interpretation. This Agreement may be executed in any number of counterparts, each of which shall be deemed an original, but all of which taken together shall constitute one and the same instrument. Contractor represents that it has reviewed and become familiar with this Agreement and has notified County of any discrepancies, conflicts or errors herein. In the event of a conflict in the terms of this Agreement and/or the exhibits attached hereto, the terms most beneficial to County shall govern. The Parties hereto agree that, if an ambiguity or question of intent or interpretation arises, this Agreement is to be construed as if the Parties had drafted it jointly, as opposed to being construed against a Party because it was responsible for drafting one or more provisions of the Agreement. In the interest of brevity, the Agreement may omit modifying words such as "all" and "any" and articles such as "the" and "an," but the fact that a modifier or an article is absent from one statement and appears in another is not intended to affect the interpretation of either statement. Words or terms used as nouns in the Agreement shall be inclusive of their singular and plural forms, unless the context of their usage clearly requires contrary meaning.

M. Force Majeure. Neither County nor Contractor shall be liable for its respective non-negligent or non-willful failure to perform or shall be deemed in default with respect to the failure to perform (or cure a failure to perform) any of its respective duties or obligations under this Agreement or for any delay in such performance due to: (i) any cause beyond its respective reasonable control; (ii) any act of God; (iii) any change in applicable governmental rules or regulations rendering the performance of any portion of this Agreement legally impossible; (iv) earthquake, fire, explosion or flood; (v) strike or labor dispute, excluding strikes or labor disputes by employees and/or agents of Contractor; (vi) delay or failure to act by any governmental or military authority; or (vii) any war, hostility, embargo, sabotage, civil disturbance, riot, insurrection or invasion. In such event, the time for performance shall be extended by an amount of time equal to the period of delay caused by such acts, and all other obligations shall remain intact.

N. Material Condition. Each term of this Agreement is material, and Contractor's breach of any term of this Agreement shall be considered a material breach of the entire Agreement and shall be grounds for termination or exercise of any other remedies available to County at law or in equity.

IN WITNESS WHEREOF County and Contractor have executed this Agreement.

[SIGNATURES ON FOLLOWING PAGE]

CONTRACTOR:

**BREAK THE CYCLE COUNSELING & CONSULTING,
LLC**

By: _____

[SEAL]

Attest/Witness:

Signature: _____

WALTON COUNTY, GEORGIA

By: _____
David Thompson, Chairman of the Board of Commissioners

[COUNTY SEAL]

Attest:

Signature: _____
Print Name: _____
Title: County Clerk

Approved as to form:

County Attorney

Date

EXHIBIT "A"**SCOPE OF SERVICES**

The Contractor shall provide the following services to or on behalf of the County:

Treatment Services:

4 cycles of Active Parenting (8 groups per cycle at the rate of \$350.00/group) (32 total groups)

4 cycles of Teen in Action (8 groups per cycle at the rate of \$350.00/group) (32 groups total)

2 cycles of Active Parenting-mini sessions (4 groups per cycle at the rate of \$350.00/group) (8 total groups)

2 cycles of Teen in Action-mini sessions (4 groups per cycle at the rate of \$350.00/group) (8 groups total)

In-home parenting (80 hours at the rate of \$50.00 per hour)

Behavioral aide services (426 hours at the rate of \$50.00 per hour)

Individual and Family counseling (70 hours at the rate of \$65.00 per hour)

Family Assessments (40 assessments at the rate of \$300.00 per assessment)

Grant Management (299 hours at the rate of \$50.00 per hour)

Treatment Staffings:

Staffings w/ Court Staff (\$50.00 per hour for 8 hours-\$200.00)

EXHIBIT "B"

STATE OF Georgia
 COUNTY OF Walton

CONTRACTOR AFFIDAVIT AND AGREEMENT

By executing this affidavit, the undersigned contractor verifies its compliance with O.C.G.A. § 13-10-91, stating affirmatively that the individual, firm, or corporation which is engaged in the physical performance of services on behalf of Walton County, Georgia has registered with, is authorized to use and uses the federal work authorization program commonly known as E-Verify, or any subsequent replacement program, in accordance with the applicable provisions and deadlines established in O.C.G.A. § 13-10-91. Furthermore, the undersigned contractor will continue to use the federal work authorization program throughout the contract period and the undersigned contractor will contract for the physical performance of services in satisfaction of such contract only with subcontractors who present an affidavit to the contractor with the information required by O.C.G.A. § 13-10-91(b).

Contractor hereby attests that its federal work authorization user identification number and date of authorization are as follows:

 Federal Work Authorization User Identification
 Number

 Signature of Authorized Officer or Agent

 Date of Authorization

 Printed Name and Title of Authorized Officer or
 Agent

Break the Cycle Counseling & Consulting, LLC
 Name of Contractor

SUBSCRIBED AND SWORN BEFORE ME
 ON THIS THE _____ DAY OF
 _____, 20____.

Juvenile Court CHINS Grant
 Name of Project

Walton County, Georgia
 Name of Public Employer

 NOTARY PUBLIC

[NOTARY SEAL]

My Commission Expires:

I hereby declare under penalty of perjury that the foregoing is true and correct.

Executed on _____, 20____ in
 _____ (city), _____ (state).

EXHIBIT "C"

STATE OF Georgia
COUNTY OF Walton

SUBCONTRACTOR AFFIDAVIT

NOT APPLICABLE – No Subcontractors will be used.

EXHIBIT "D"

The following individuals are designated as Key Personnel under this Agreement and, as such, are necessary for the successful prosecution of the Work:

<u>Individual</u>	<u>Position</u>
Carrie Tinsley	CEO of Break the Cycle Counseling and Consulting, LLC
Kim Gable	CEO of Break the Cycle Counseling and Consulting, LLC

Walton County Department Agenda Request

Department Name: **Human Resources**

Department Head/Representative: **Hannah Correll**

Meeting Date Request: **10/6/2026**

Has this topic been discussed at past meetings? **Yes**

If so, When? **annually**

TOPIC: **Holiday Schedule 2027**

Wording For Agenda: **Human Resources presents the 2027 Walton County Holiday Schedule**

This Request: Informational Purposes Only Needs Action by Commissioners* **Yes**

*What action are you seeking from the Commissioners? **Review and Approval**

Department Comments/Recommendation: **Approval of the same scheduled holidays (count) in the previous calendar year.**

Additional Documentation Attached? **Yes**

Is review of this request or accompanying documentation by the County Attorney required? **No**

If so, has a copy of the documentation been forwarded to County Attorney?

Date forwarded to County Attorney:

Has the County Attorney review been completed?

If this request involves the expenditure of county funds, please answer the following:

Approved in current budget? **Yes**

Budget information attached? **Included in calculations for regular full time employee fringes.**

Comments:

Purchasing Department Comments:

County Attorney Comments:

Chairman's Comments:



Walton County Board of Commissioners Human Resources

2027 Holiday Schedule

January 1, 2027 (Friday)	New Year's Day
January 18, 2027 (Monday)	Martin Luther King, Jr. Day
March 26, 2027 (Friday)	Good Friday
May 31, 2027 (Monday)	Memorial Day
June 18, 2027 (Friday)	In observance of Juneteenth
July 5, 2027 (Monday)	In observance of Independence Day
September 6, 2027 (Monday)	Labor Day
November 11, 2027 (Thursday)	Veterans Day
November 24, 2027 (Wednesday)	½ day before Thanksgiving
November 25, 2027 (Thursday)	Thanksgiving
November 26, 2027 (Friday)	Day after Thanksgiving
December 23, 2027 (Thursday)	½ day before Christmas Eve
December 24, 2027 (Friday)	Christmas Eve
December 27, 2027 (Monday)	In observance of Christmas Day

BOC Awaiting Approval 9.21.2026

WALTON COUNTY HAZARD MITIGATION PLAN 2025 - 2030

Walton County Emergency Management Agency

Director Carl Morrow

1764 Highway 81


Loganville, Georgia 30052

carl.morrow@co.walton.ga.us

770.267.1336

Walton County, Georgia

Hazard Mitigation Plan Update 2025 – 2030



Prepared for the Walton County Board of Commissioners
303 South Hammond Drive
Monroe, Georgia 30655
770.267.1400
www.waltoncountyga.gov

This document was funded in part by the Federal Emergency Management Agency's (FEMA) Hazard Mitigation Planning Grant awarded to Walton County, Georgia, through the Georgia Emergency Management Agency (GEMA) to fulfill the requirements of the Federal Disaster Mitigation Act of 2000 (DMA 2000). Walton County's 2021 Hazard Mitigation Plan was updated by the Walton County Hazard Mitigation Plan Update Committee and was prepared by Lux Mitigation and Planning Corp. For additional information, please contact Walton County Emergency Management Agency.

Preface

Mitigation Vision for the Future

Emergency Managers succeed or fail based on how well they follow the following fundamental principles of emergency management, mitigation, preparedness, response, and recovery. Purposefully, our emergency management forefathers put the word mitigation first as a “means” to prevent or minimize the effects of disasters.

Mitigation is commonly defined as sustained actions taken to reduce or eliminate long-term risk to people and property from hazards and their effects. Hazard mitigation focuses attention and resources on community policies and actions that will produce successive benefits over time. A mitigation plan states the aspirations and specific courses of action that a community intends to follow to reduce vulnerability and exposure to future hazard events. These plans are formulated through a systematic process centered on the participation of citizens, businesses, public officials, and other community stakeholders.

Mitigation forms, or should form, the very foundation of every emergency management agency. To reduce, minimize, or eliminate hazards in their communities, emergency management agencies adopt and implement mitigation practices. The Federal DMA 2000 sets the benchmark and outlines the criteria for communities with the vision to implement hazard mitigation practices in their communities.

Walton County and its municipalities realize the benefits achieved by the development and implementation of mitigation plans and strategies in their community. Walton County’s elected officials, public safety organizations, planners, and many others have proven that by working together towards the development and implementation of this plan, they can reduce the loss of life and property in their communities.

The jurisdictions covered by this plan include the following:

- Walton County
- City of Loganville
- City of Monroe
- City of Social Circle
- City of Walnut Grove
- Town of Between
- Town of Good Hope
- Town of Jersey

Adoption Resolution – Walton County

Requirement §201.6(c)(5)

RESOLUTION – WALTON COUNTY, GEORGIA

WALTON COUNTY HAZARD MITIGATION PLAN 2025 - 2030

WHEREAS, Walton County and its municipalities recognize that it is threatened by several different types of natural and man-made hazards that can result in loss of life, property loss, economic hardship and threats to public health and safety; and

WHEREAS, the Federal Emergency Management Agency (FEMA) requires that every county and municipality have a pre-disaster mitigation plan in place, and requires the adoption of such plans in order to receive specific disaster assistance and mitigation grant opportunities; and

WHEREAS, a Hazard Mitigation Plan is a community's plan for evaluating hazards, identifying resources and capabilities, selecting appropriate actions, and developing and implementing the preferred mitigation actions to eliminate or reduce future damage in order to protect the health, safety and welfare of the residents in the community; and

WHEREAS, Walton County's 2025 Hazard Mitigation Plan has been prepared in accordance with FEMA requirements at 44 CFR 201.6; and

WHEREAS, the Plan will be updated every five years;

NOW, THEREFORE, BE IT RESOLVED, by the Board of Commissioners of Walton County, Georgia, that:

- 1) Walton County, Georgia, has adopted Walton County's 2025 Hazard Mitigation Plan; and
- 2) It is intended that the Plan be a working document and is the first of many steps toward improving rational, long-range mitigation planning and budgeting for Walton County and its municipalities.

PASSED, APPROVED AND ADOPTED by the Board of Commissioners of Walton

County, Georgia, in regular session this _____ day of _____, 20____.

Chairperson

County Clerk

Adoption Resolution – City of Loganville

RESOLUTION – CITY OF LOGANVILLE, GEORGIA

WALTON COUNTY HAZARD MITIGATION PLAN 2025 - 2030

WHEREAS, Walton County and its municipalities recognize that it is threatened by several different types of natural and man-made hazards that can result in loss of life, property loss, economic hardship and threats to public health and safety; and

WHEREAS, the Federal Emergency Management Agency (FEMA) requires that every county and municipality have a pre-disaster mitigation plan in place, and requires the adoption of such plans in order to receive specific disaster assistance and mitigation grant opportunities; and

WHEREAS, a Hazard Mitigation Plan is a community's plan for evaluating hazards, identifying resources and capabilities, selecting appropriate actions, and developing and implementing the preferred mitigation actions to eliminate or reduce future damage in order to protect the health, safety and welfare of the residents in the community; and

WHEREAS, Walton County's 2025 Hazard Mitigation Plan has been prepared in accordance with FEMA requirements at 44 CFR 201.6; and

WHEREAS, the Plan will be updated every five years;

NOW, THEREFORE, BE IT RESOLVED, by the Mayor and City Council of Loganville, Georgia, that:

- 1) The City of Loganville, Georgia, has adopted Walton County's 2025 Hazard Mitigation Plan;
- 2) It is intended that the Plan be a working document and is the first of many steps toward improving rational, long-range mitigation planning and budgeting for Walton County and its municipalities.

PASSED, APPROVED AND ADOPTED by the Mayor and Council of the City of

Loganville, Georgia, in regular session this ____ day of _____, 20____.

Mayor

City Clerk

Adoption Resolution – City of Monroe

RESOLUTION – CITY OF MONROE, GEORGIA

WALTON COUNTY HAZARD MITIGATION PLAN 2025 - 2030

WHEREAS, Walton County and its municipalities recognize that it is threatened by several different types of natural and man-made hazards that can result in loss of life, property loss, economic hardship and threats to public health and safety; and

WHEREAS, the Federal Emergency Management Agency (FEMA) requires that every county and municipality have a pre-disaster mitigation plan in place, and requires the adoption of such plans in order to receive specific disaster assistance and mitigation grant opportunities; and

WHEREAS, a Hazard Mitigation Plan is a community's plan for evaluating hazards, identifying resources and capabilities, selecting appropriate actions, and developing and implementing the preferred mitigation actions to eliminate or reduce future damage in order to protect the health, safety and welfare of the residents in the community; and

WHEREAS, Walton County's 2025 Hazard Mitigation Plan has been prepared in accordance with FEMA requirements at 44 CFR 201.6; and

WHEREAS, the Plan will be updated every five years;

NOW, THEREFORE, BE IT RESOLVED, by the Mayor and City Council of Monroe, Georgia, that:

- 1) The City of Monroe, Georgia, has adopted Walton County's 2025 Hazard Mitigation Plan;
- 2) It is intended that the Plan be a working document and is the first of many steps toward improving rational, long-range mitigation planning and budgeting for Walton County and its municipalities.

PASSED, APPROVED AND ADOPTED by the Mayor and Council of the City of Monroe, Georgia, in regular session this ____ day of _____, 20____.

Mayor

City Clerk

Adoption Resolution – City of Social Circle

RESOLUTION – CITY OF SOCIAL CIRCLE, GEORGIA WALTON COUNTY HAZARD MITIGATION PLAN 2025 - 2030

WHEREAS, Walton County and its municipalities recognize that it is threatened by several different types of natural and man-made hazards that can result in loss of life, property loss, economic hardship and threats to public health and safety; and

WHEREAS, the Federal Emergency Management Agency (FEMA) requires that every county and municipality have a pre-disaster mitigation plan in place, and requires the adoption of such plans in order to receive specific disaster assistance and mitigation grant opportunities; and

WHEREAS, a Hazard Mitigation Plan is a community's plan for evaluating hazards, identifying resources and capabilities, selecting appropriate actions, and developing and implementing the preferred mitigation actions to eliminate or reduce future damage in order to protect the health, safety and welfare of the residents in the community; and

WHEREAS, Walton County's 2025 Hazard Mitigation Plan has been prepared in accordance with FEMA requirements at 44 CFR 201.6; and

WHEREAS, the Plan will be updated every five years;

NOW, THEREFORE, BE IT RESOLVED, by the Mayor and City Council of Social Circle, Georgia, that:

- 1) The City of Social Circle, Georgia, has adopted Walton County's 2025 Hazard Mitigation Plan;
- 2) It is intended that the Plan be a working document and is the first of many steps toward improving rational, long-range mitigation planning and budgeting for Walton County and its municipalities.

PASSED, APPROVED AND ADOPTED by the Mayor and Council of the City of Social Circle, Georgia, in regular session this ____ day of _____, 20 ____.

Mayor

City Clerk

Adoption Resolution – City of Walnut Grove

RESOLUTION – CITY OF WALNUT GROVE, GEORGIA

WALTON COUNTY HAZARD MITIGATION PLAN 2025 - 2030

WHEREAS, Walton County and its municipalities recognize that it is threatened by several different types of natural and man-made hazards that can result in loss of life, property loss, economic hardship and threats to public health and safety; and

WHEREAS, the Federal Emergency Management Agency (FEMA) requires that every county and municipality have a pre-disaster mitigation plan in place, and requires the adoption of such plans in order to receive specific disaster assistance and mitigation grant opportunities; and

WHEREAS, a Hazard Mitigation Plan is a community's plan for evaluating hazards, identifying resources and capabilities, selecting appropriate actions, and developing and implementing the preferred mitigation actions to eliminate or reduce future damage in order to protect the health, safety and welfare of the residents in the community; and

WHEREAS, Walton County's 2025 Hazard Mitigation Plan has been prepared in accordance with FEMA requirements at 44 CFR 201.6; and

WHEREAS, the Plan will be updated every five years;

NOW, THEREFORE, BE IT RESOLVED, by the Mayor and City Council of Walnut Grove, Georgia, that:

- 1) The City of Walnut Grove, Georgia, has adopted Walton County's 2025 Hazard Mitigation Plan;
- 2) It is intended that the Plan be a working document and is the first of many steps toward improving rational, long-range mitigation planning and budgeting for Walton County and its municipalities.

PASSED, APPROVED AND ADOPTED by the Mayor and Council of the City of Walnut Grove, Georgia, in regular session this ____ day of _____, 20 ____.

Mayor

City Clerk

Adoption Resolution – Town of Between

RESOLUTION – TOWN OF BETWEEN, GEORGIA

WALTON COUNTY HAZARD MITIGATION PLAN 2025 - 2030

WHEREAS, Walton County and its municipalities recognize that it is threatened by several different types of natural and man-made hazards that can result in loss of life, property loss, economic hardship and threats to public health and safety; and

WHEREAS, the Federal Emergency Management Agency (FEMA) requires that every county and municipality have a pre-disaster mitigation plan in place, and requires the adoption of such plans in order to receive specific disaster assistance and mitigation grant opportunities; and

WHEREAS, a Hazard Mitigation Plan is a community's plan for evaluating hazards, identifying resources and capabilities, selecting appropriate actions, and developing and implementing the preferred mitigation actions to eliminate or reduce future damage in order to protect the health, safety and welfare of the residents in the community; and

WHEREAS, Walton County's 2025 Hazard Mitigation Plan has been prepared in accordance with FEMA requirements at 44 CFR 201.6; and

WHEREAS, the Plan will be updated every five years;

NOW, THEREFORE, BE IT RESOLVED, by the Mayor and Town Council of Between, Georgia, that:

- 1) The Town of Between, Georgia, has adopted Walton County's 2025 Hazard Mitigation Plan;
- 2) It is intended that the Plan be a working document and is the first of many steps toward improving rational, long-range mitigation planning and budgeting for Walton County and its municipalities.

PASSED, APPROVED AND ADOPTED by the Mayor and Council of the Town of

Between, Georgia, in regular session this ____ day of _____, 20__.

Mayor

Town Clerk

Adoption Resolution – Town of Good Hope

RESOLUTION – TOWN OF GOOD HOPE, GEORGIA

WALTON COUNTY HAZARD MITIGATION PLAN 2025 - 2030

WHEREAS, Walton County and its municipalities recognize that it is threatened by several different types of natural and man-made hazards that can result in loss of life, property loss, economic hardship and threats to public health and safety; and

WHEREAS, the Federal Emergency Management Agency (FEMA) requires that every county and municipality have a pre-disaster mitigation plan in place, and requires the adoption of such plans in order to receive specific disaster assistance and mitigation grant opportunities; and

WHEREAS, a Hazard Mitigation Plan is a community's plan for evaluating hazards, identifying resources and capabilities, selecting appropriate actions, and developing and implementing the preferred mitigation actions to eliminate or reduce future damage in order to protect the health, safety and welfare of the residents in the community; and

WHEREAS, Walton County's 2025 Hazard Mitigation Plan has been prepared in accordance with FEMA requirements at 44 CFR 201.6; and

WHEREAS, the Plan will be updated every five years;

NOW, THEREFORE, BE IT RESOLVED, by the Mayor and Town Council of Good Hope, Georgia, that:

- 1) The Town of Good Hope, Georgia, has adopted Walton County's 2025 Hazard Mitigation Plan;
- 2) It is intended that the Plan be a working document and is the first of many steps toward improving rational, long-range mitigation planning and budgeting for Walton County and its municipalities.

PASSED, APPROVED AND ADOPTED by the Mayor and Council of the Town of Good

Hope, Georgia, in regular session this ____ day of _____, 20____.

Mayor

Town Clerk

Adoption Resolution – Town of Jersey

RESOLUTION – TOWN OF JERSEY, GEORGIA

WALTON COUNTY HAZARD MITIGATION PLAN 2025 - 2030

WHEREAS, Walton County and its municipalities recognize that it is threatened by several different types of natural and man-made hazards that can result in loss of life, property loss, economic hardship and threats to public health and safety; and

WHEREAS, the Federal Emergency Management Agency (FEMA) requires that every county and municipality have a pre-disaster mitigation plan in place, and requires the adoption of such plans in order to receive specific disaster assistance and mitigation grant opportunities; and

WHEREAS, a Hazard Mitigation Plan is a community's plan for evaluating hazards, identifying resources and capabilities, selecting appropriate actions, and developing and implementing the preferred mitigation actions to eliminate or reduce future damage in order to protect the health, safety and welfare of the residents in the community; and

WHEREAS, Walton County's 2025 Hazard Mitigation Plan has been prepared in accordance with FEMA requirements at 44 CFR 201.6; and

WHEREAS, the Plan will be updated every five years;

NOW, THEREFORE, BE IT RESOLVED, by the Mayor and Town Council of Jersey, Georgia, that:

- 1) The Town of Jersey, Georgia, has adopted Walton County's 2025 Hazard Mitigation Plan;
- 2) It is intended that the Plan be a working document and is the first of many steps toward improving rational, long-range mitigation planning and budgeting for Walton County and its municipalities.

PASSED, APPROVED AND ADOPTED by the Mayor and Council of the Town of Jersey,

Georgia, in regular session this ____ day of _____, 20__.

Mayor

Town Clerk

Table of Contents

Preface	2
Resolution – Walton County	3
Resolution – City of Loganville	4
Resolution – City of Monroe	5
Resolution – City of Social Circle	6
Resolution – City of Walnut Grove	7
Resolution – Town of Between	8
Resolution – Town of Good Hope	9
Resolution – Town of Jersey	10

CHAPTER ONE – INTRODUCTION **14**

Summary Of Updates for Chapter One	14
Purpose	15
Goals	15
Scope	16
Funding	16
Consistency with Federal and State Mitigation Policies	17
Authority	18
Plan Review	19
Significant Changes to the 2019 Plan	20
Hazard Mitigation Plan Update Committee	21
Public Participation	28
Multi-jurisdictional Considerations	29
Incorporation of Existing Plans, Studies, and Resources	30

CHAPTER TWO – WALTON COUNTY PROFILE **32**

Summary of Updates for Chapter Two	32
History	33
Past Hazards	34
Past Events	35
Demographics	36
Social Vulnerability Information	37
Economy	39
Utilities	39
Transportation	39
Government	40
Climate	41
NFIP Compliance	42
Municipal Information	43

CHAPTER THREE – HAZARD PROFILES **50**

Summary of Updates for Chapter Three	50
Risk Assessment	52
Natural Hazards	56
<i>Thunderstorm</i>	56
<i>Winter Storm</i>	72
<i>Flooding</i>	78
<i>Tornado</i>	93
<i>Drought</i>	98
<i>Wildfire</i>	102
<i>Geologic</i>	129
<i>Tropical Cyclone</i>	134
Technological Hazards	141
<i>Hazardous Materials Incident</i>	141
<i>Dam Failure</i>	144
<i>Transportation Incident</i>	146
<i>Terrorism</i>	148
<i>Critical Infrastructure Failure</i>	150
<i>Civil Unrest</i>	152
<i>Emerging Infectious Disease</i>	153

CHAPTER FOUR – HAZARD MITIGATION STRATEGIES **157**

Summary of Updates to Chapter Four	157
Goals and Objectives	158
Identification and Analysis of Mitigation Techniques	159
Mitigation Strategies	162
<i>Natural Hazards</i>	162
<i>Technological Hazards</i>	176
<i>Completed Mitigation Strategies</i>	178
<i>Deleted Mitigation Strategies</i>	178

CHAPTER FIVE – PLAN IMPLEMENTATION AND MAINTENANCE **179**

Summary of Updates to Chapter Five	179
Maintenance	180
Plan Distribution	182
Implementation	183
Evaluation	185
Peer Review	186
Plan Update	187
Conclusion	187

APPENDICIES

Appendix A – Hazard Mitigation Plan Update Committee Sign-In Sheets	188
Appendix B – Natural Hazard Data Tables	201
Appendix C – Walton County Worksheet 3As	227
Appendix D – Documentation of Peer Review	251
Appendix E – Walton County HAZUS Report	257

CHAPTER ONE – INTRODUCTION

Summary of Updates for Chapter One

The following table provides a description of each section of this chapter and a summary of the changes that have been made to the Walton County Hazard Mitigation Plan 2021.

<u>Chapter 1 Section</u>	<u>Updates</u>
Introduction	• Identification of Mitigation Goals
Authority	• Verbiage updated
Funding	• New Section – Not in 2021 Plan
Scope	• Verbiage updated
Purpose	• Verbiage updated
Consistency with Federal Guidelines	• New Section – Not in 2021 Plan
Plan Review	• Verbiage updated • Updated mitigation meeting dates for 2025 planning process
Hazard Mitigation Plan Update Committee	• Updated committee list with the 2025 planning participants • Updated to meet Federal guidelines
Public Participation	• Updated to match the 2025 planning process
Multi-Jurisdictional Considerations	• Updated with requirement descriptions
Incorporation of Existing Plans, Studies, and Resources	• New Section – Not in 2021 Plan

Purpose

The purpose of the Walton County Hazard Mitigation Plan Update is to:

- Protect life, promote safety, and preserve property by reducing the potential for future damages and economic losses that result from natural and technological hazards;
- Make communities in Walton County safer places to live, work, and play;
- Qualify for grant funding in both the pre-disaster and post-disaster environments;
- Speed the recovery and redevelopment process following future disaster events;
- Demonstrate a firm local commitment to hazard mitigation principles; and,
- Comply with state and federal legislative requirements for local multi-jurisdictional hazard mitigation plans.

Goals

The Walton County Hazard Mitigation Plan Update is the first phase of a multi-hazard mitigation strategy for the entire community. This Plan encourages cooperation among various organizations and crosses political sub-divisions. As written, this Plan fulfills the requirements of the Federal DMA 2000. DMA 2000 provides federal assistance to state and local emergency management agencies and other disaster response organizations to reduce damage from disasters. The Act is administered by GEMA and FEMA.

It is important that state and local government, public-private partnerships, and community citizens can see the results of these mitigation efforts; therefore, the goals and strategies need to be achievable. Walton County's Hazard Mitigation Plan Update Committee adopted the following goals during plan development:

GOAL 1

Maximize the use of all resources by promoting intergovernmental coordination and partnerships in the public and private sectors

GOAL 2

Harden communities against the impacts of disasters through the development of new mitigation strategies and strict enforcement of current regulations that have proven effective

GOAL 3

Reduce and, where possible, eliminate repetitive damage, loss of life and property from disasters

GOAL 4

Bring greater awareness throughout the community about potential hazards and the need for community preparedness

This plan complies with all requirements and scope of work as described in Walton County's Hazard Mitigation Grant application.

Scope

The scope of the Walton County Hazard Mitigation Plan Update encompasses all areas of Walton County, including municipalities. The Plan identifies all natural and technological hazards that could threaten life and property in Walton County. The scope of this Plan includes both short and long-term mitigation strategies with implementation and possible sources of project funding.

The Hazard Mitigation Plan Update is organized to incorporate the requirements of Interim Final Rule 44 CFR 201.4.

Chapter One includes an overview of the Hazard Mitigation Plan Update, the overall goals of the plan, and details of the planning process as required by Interim Final Rule 44 CFR 201.4(c)(1).

Chapter Two of the Plan details the Walton County profile, including the demographics, municipalities, and history of the county.

Chapter Three identifies the risk assessment process, past natural hazard events with associated losses, and current natural hazard risks. Potential losses are also analyzed as required by Interim Final Rule 44 CFR 201.4(c)(2). Additionally, Chapter Three identifies and analyzes potential technological hazards faced by Walton County.

Chapter Four identifies Walton County's hazard mitigation goals and objectives, mitigation strategies and actions, and sources of potential funding for mitigation projects as required by Interim Final Rule 44 CFR 201.4(c)(3).

Chapter Five identifies the maintenance and implementation strategies for the Plan. The process for evaluation of the Hazard Mitigation Plan implementation progress is also detailed as required by Interim Final Rule 44 CFR 201.4(c)(4) and (5).

Funding

Walton County was awarded a Hazard Mitigation Planning Grant by FEMA through GEMA for the update of Walton County's 2021 Hazard Mitigation Plan. FEMA contributed 90% toward the total cost of the Plan Update. The Hazard Mitigation Planning Grant required a 10% match by Walton County. This match was fulfilled entirely (100%) by In-Kind contributions; time spent by county and municipal employees, local stakeholders, representatives from organizations, and citizen volunteers updating the Plan was provided instead of cash from the County's budget.

Consistency with Federal and State Mitigation Policies

The Plan is intended to enhance and complement state and federal recommendations for the mitigation of natural and technological hazards in the following ways:

- Substantially reduce the risk of life, injuries, and hardship from the destruction of natural and technological disasters on an ongoing basis;
- Create greater public awareness about the need for individual preparedness and about the need to safer, more disaster resistant communities;
- Develop strategies for long-term community sustainability during disasters; and,
- Develop governmental and business continuity plans that will continue essential private sector and governmental activities during disasters.

FEMA publishes several guidance documents for local governments on mitigating natural disasters. The updated Walton County Hazard Mitigation Plan recognizes, adopts, incorporates, and endorses the following principles:

- Develop a strategic mitigation plan for Walton County;
- Enforce current building codes;
- Develop incentives to promote mitigation;
- Incorporate mitigation of natural hazards into land use plans;
- Promote awareness of mitigation opportunities and programs throughout our community on a continual basis; and,
- Identify potential funding sources for mitigation projects.

It is vital that the private sector is included in mitigation efforts that are consistent with state and federal recommendations, such as the following:

- Develop mitigation incentives with insurance agencies and lending institutions;
- Encourage the creation of a business continuity plan for the continuance of commerce during and following a disaster; and,
- Partner with local businesses to educate customers about potential hazards in the community and possible mitigation ideas.

Individual citizens must be made aware of the hazards they may encounter. Additionally, they must be educated on how to protect themselves from the hazards they face. They must be shown that mitigation is an important part of reducing loss of life and property in their community. Their support is critical to the success of any mitigation effort. The updated Walton County Hazard Mitigation Plan supports the following FEMA recommendations regarding individual citizens:

- Become educated on the hazards that may impact your community;
- Become part of the process by supporting and encouraging mitigation programs that reduce vulnerability to disasters; and,
- An individual's responsibility is to safeguard his/her family, as well as themselves, prior to a disaster event.

Authority

In the past, federal legislation has provided funding for disaster relief, recovery, and some hazard mitigation planning. The DMA 2000 is the latest legislation to improve the planning aspect of that process; it reinforces the importance of mitigation planning and emphasizes planning for disasters before they occur. The DMA 2000 establishes a pre-disaster hazard mitigation program and designates new requirements for the national post-disaster Hazard Mitigation Grant Program (HMGP). Section 322 identifies the new requirements for planning activities and increases the amount of HMGP funds available to states that have developed a comprehensive mitigation plan prior to the disaster.

State and local communities must have an approved mitigation plan in place prior to receiving post-disaster HMGP funds. Local mitigation plans must demonstrate that their proposed mitigation measures are based on a sound planning process that accounts for the risk to and the capabilities of the individual communities. To implement the new DMA 2000 requirements, FEMA prepared an Interim Final Rule, published in the Federal Register on February 26, 2002, at 44 CFR Parts 201 and 206, which establishes planning and funding criteria for states and local communities.

Developed in accordance with current state and federal rules and regulations governing local hazard mitigation plans, Walton County's Updated Hazard Mitigation Plan will be brought forth to each participating jurisdiction in Walton County to be formally adopted. The Plan shall be routinely monitored and revised to maintain compliance with the following provisions, rules, and legislation:

Section 322, Mitigation Planning, of the Robert T. Stafford Disaster Relief and Emergency Assistance Act, as enacted by Section 104 of the Disaster Mitigation Act of 2000 (P.L. 106-390); and FEMA's Interim Final Rule published in the Federal Register on February 26, 2002, at 44 CFR Part 201.

Plan Review

Requirement §201.6(c)(1)

The contractor, Lux Mitigation and Planning, had the primary responsibility for collecting updated information and presenting pertinent data to the Plan Update Committee. An online, Dropbox folder was created for Walton County's Plan Update. The approved 2021 Hazard Mitigation Plan was uploaded to the Dropbox folder, and the link to the folder was emailed to all members of the Hazard Mitigation Plan Update Committee. Each chapter of the 2021 Plan was reviewed. Hazard vulnerability and risk assessment data was updated, as was critical infrastructure information.

Special attention and consideration were given to the review and edit of mitigation strategies listed in the 2021 Plan. The Plan Update Committee examined each strategy and determined whether the strategy had been completed, needed to be modified, was in progress, or no longer applied. The Committee was highly encouraged to create new mitigation strategies to meet the current needs of the county and municipalities. Mitigation strategies from other Georgia counties were reviewed to help with the creation of new strategies. When the Committee agreed a new mitigation action would be beneficial, it was tailored to Walton County's needs and was included in the 2025 Plan. The contractor sent the Committee, including sporadically attending participants, regular emails which contained a Dropbox link to the most updated version of the Plan and encouraged the Committee to thoroughly critique each version.

Hazard Mitigation Plan Update Committee Meeting Dates

Tuesday, February 18, 2025

Morning Session
(10:00am – 11:30am)

Kick-Off Meeting; Introduction to Hazard Mitigation

Afternoon Session
(12:00pm – 1:30pm)

Hazard Identification and Prioritization;
Community Risk Assessment Tabletop Exercise

Tuesday, March 18, 2025

Morning Session
(10:00am – 11:30am)

Community Risk Assessment Analysis;
Review and Edit Mitigation Strategies from 2020 Plan

Afternoon Session
(12:00pm – 1:30pm)

Review and Edit Mitigation Strategies from 2020 Plan

Tuesday, April 22, 2025

Morning Session
(10:00am – 11:30am)

Review and Edit Mitigation Strategies from 2020 Plan;
Create New Mitigation Strategies for 2025 Plan

Afternoon Session
(12:00pm – 1:30pm)

Create New Mitigation Strategies for 2025 Plan;
Discuss Available Hazard Mitigation Grants;
Discuss Draft of 2025 Plan

*The public was welcome and encouraged to attend all Hazard Mitigation Plan Update meetings.

Significant Changes to the 2019 Plan

Each section of Walton County's 2021 Hazard Mitigation Plan has been revised in some manner. Therefore, a summary of those changes will be listed in the first section of each chapter. Significant additions/modifications to this Plan include the following:

- Addition of Geologic Hazards to Natural Hazards (Incorporated Earthquake from previous plan)
- Addition of Infrastructure Failure to Technological Hazards

Hazard Mitigation Plan Update Participants

Requirement §201.6(b)(2)

The following 73 participants contributed to the update of Walton County’s 2021 Hazard Mitigation Plan: *(in alphabetical order)*

Janil Adair

Secretary (Volunteer)
East Georgia LEPC

Jeff Adair

Volunteer
Walton County Citizen’s Corps

Brad Adcock

Loss Control Director
Walton Electric Membership Cooperative

John Allman

Director
Walton County Public Works

Talmadge Armistead

Superintendent
City of Monroe Water Department

Jack Armstrong

HSE Specialist II
Hitachi Astemo

William Ayers

Mass Care Lead – Georgia Region
American Red Cross

Carla Batchelor

Medical Reserve Corp Coordinator; CERT Member (Volunteer)
Walter County Emergency Management Agency

Rhonda Bell

Environmental Compliance
City of Social Circle

Josh Bowman

Emergency Preparedness Director
Georgia Department of Public Health – Northeast Health District

Lee Broach

Sign and Marketing Tech
City of Monroe

Doug Brown
Training Chief
Walton County Fire Rescue

Greg Boyd
Water Systems Coordinator
Walton County Water Department

Jody Carter
HSE Specialist II
Hitachi Astemo

Ashley Cason
Director
Walton County Traffic Operations

Lee Cochran
Global Security Area Manager
Meta

Brian Collins
Assistant Director
Walton County Facilities & Risk Management

Charlie Dalton
Captain – Uniform Patrol Division
Walton County Sheriff's Office

Jessica de Benedicts
Wastewater Treatment Plan Manager
City of Monroe

Julie DeVries
Chairman of the Board
Walton County Citizen's Corp Council

Andrew Dykes
Chief
City of Monroe Fire Department

W. Stanley Edwards, PhD
Consultant
ARES

Steven Ervin
Assistant Manager
City of Monroe Water Treatment Plant

Ronnie Fulcher
Sewer Superintendent
City of Monroe

Randy Garrett
Mayor
Town of Good Hope

Josh Gearirn
Captain – Court Services
Walton County Sheriff's Office

Mathew George
Pump Station Mech
City of Monroe

Robbie Groves
Director
City of Social Circle Public Works

Jason Guest
Chief
City of Social Circle Police Department

Ben Hammond
Public Information Officer
Walton County Board of Commissioners

Kevin Haney
Chief
Walton County Fire Rescue

Wayne Harper
Volunteer
Walton County LEPC

Jim Holbrooks
Superintendent
City of Monroe Electric Department

William B. Jennings
EMS Supervisor
Walton County Emergency Medical Services

Jody Johnson
Director
Walton County Parks & Recreation Department

Ray Johnson*Assistant Director*

Walton County Public Works

Timothy Johnson*Chief*

City of Loganville Fire Department

Jonathan Jones*Field Coordinator – Area 1*

Georgia Emergency Management and Homeland Security Agency

Kevin Jones*Deputy Site Head*

Hitachi Astemo

Morris Jordan*Director*

Walton County Water Department

Andy Latimer*Facility Director*

Piedmont Walton Hospital

Craig League*Deputy Chief*

Walton County Fire Rescue

Patrick McCullough*Battalion Chief*

Walton County Fire Rescue

Joshua Mobley*EMS Supervisor*

Walton County Emergency Medical Services

Michael Moon*Battalion Chief*

City of Loganville Fire Department

Carl Morrow*Director*

Walton County Emergency Management Agency

Keith Murrell*Street Supervisor*

City of Social Circle

Charna Parker*Director*

Walton County Planning & Development

Kristi Q. Parr*Assistant Director*

Walton County Planning & Development

Wendy Patterson*Director*

Newton County Emergency Management Agency

James H. Peters, Jr.*Street, Transportation, & Stormwater Supervisor*

City of Monroe

J. Garrett Polston*Trauma Program Manager*

Piedmont Walton Hospital

Robert Post*Mayor*

Town of Between

Aaron Robinson*Director of Secondary Education & Accountability*

Social Circle Schools

William Rowland*Shift Supervisor*

Walton County Emergency Medical Services

Kenny Sergeant*Director*

Keep Walton Beautiful Recycling Center

David Shanks*Targeted Violence Prevention Homeland Security Coordinator*

Georgia Emergency Management and Homeland Security Agency

Henry Shirley*Director*

Walton County Facilities & Risk Management

Joseph Stancil*Field Manager*

City of Loganville

Bradley G. Stanley*CERT Volunteer*

Walton County Emergency Management Agency

Jeremiah Still*Director*

City of Social Circle Streets and Transportation

Tim Tallant*Captain – Uniform Patrol Division*

Walton County Sheriff's Office

Sheri Traylor*Nurse Manager*

Walton County Health Department

Helen Dana Tripp*CERT Volunteer; Secretary*

Walton County Citizen's Corps Council

Vashun Tuggle-Hill*Utilities Administrative Assistant*

City of Monroe

Payton Turner*Chief Ranger III*

Georgia Forestry Commission

Steve Wagner*EMA Specialist*

Newton County Emergency Management Agency

John Ward*County Manager*

Walton County Board of Commissioners

Sabrina Westbrook*Volunteer*

Jasper County 911 Authority

Larry Westmoreland*EMA Tech*

Newton County Emergency Management Agency

Joseph Whelchel*Emergency Management Specialist*

Walton County Emergency Management Agency

Casey Williams
Safety Coordinator
NUCOR Warehouse Systems

Joseph Witcher
Water Treatment Plant Manager
City of Monroe

Kenneth Zaydel
Chief
City of Social Circle Fire Department

The Plan Update Committee relied on their consultant to guide them through the update process. During meetings, the participants had productive discussions, expanded their professional networks, asked thoughtful questions, made important decisions, and provided critical input during key stages in the update process.

Efforts were made to involve all county and municipal departments, as well as community organizations and local businesses, which may have a role in the implementation of mitigation actions and/or policies. These efforts included sending invitations via email to attend the Kick-off Meeting, sending reminder emails before each upcoming meeting, emailing pertinent information throughout the process, and requesting the review and critique of each chapter in the updated Plan.

All neighboring counties – Barrow, Gwinnett, Morgan, Newton, Oconee, and Rockdale – were asked to peer review the 2025 Mitigation Plan draft. The Plan was sent to each County EMA office. Walton County had significant support and contribution to the Hazard Mitigation Plan Update process from surrounding jurisdictions. Additionally, the EMA Directors from surrounding counties were asked to attend Plan Update Committee meetings in hopes they would share mitigation ideas from their own counties.

Public Participation

Requirement §201.6(b)(1)

State Requirement Element F2

Public awareness is a key component of any community's overall mitigation strategy. As citizens become more involved in decisions that affect their safety, they may develop a greater respect for the natural hazards present in their community, and thus, may take the steps necessary to reduce potential impacts of those hazards.

The following local organizations and businesses participated in the update of Walton County's 2021 Mitigation Plan: American Red Cross, Hitachi Astemo, Meta, Piedmont Walton Hospital, Walton County Citizen's Corps Council, and Walton EMC

The Plan Update Committee took it upon themselves to ensure the processes undertaken for the development, implementation, and maintenance of the 2025 Hazard Mitigation Plan adequately considered public needs and viewpoints.

A list of public outreach initiatives can be found below:


- Email reminders were sent to all Plan Update Committee members, as well as other stakeholders, prior to every meeting. Recipients were encouraged to share the meeting invitation with anyone they thought would be an asset to the Plan Update process or anyone who may want to learn more about what a Hazard Mitigation Plan is.
- The Walton County Hazard Mitigation Plan Update Committee provided the general public with an opportunity to attend all committee meetings. The meetings were held in the Walton County Administrative Building in an area heavily used by the public. All meetings were open to the public. Additionally, stakeholders and committee members shared information with the public regarding the meetings by posting information in their office areas utilized by the public as well as spreading information by word of mouth. No members of the public attended any meetings of the Walton County Plan Update Committee and no public feedback was provided.

Multi-Jurisdictional Considerations

FEMA does not require cities and Walton to adopt a local Hazard Mitigation Plan. However, the Federal DMA 2000 requires that all municipalities, wishing to be eligible to receive Hazard Mitigation Grants through FEMA, must adopt a local multi-hazard mitigation plan and must update that plan every five years. 2024 Mitigation Plan is the third five-year update. This FEMA-approved 2024 Hazard Mitigation Plan makes Walton County, the City of Loganville, the City of Monroe, the City of Social Circle, the City of Walnut Grove, the Town of Between, the Town of Good Hope, and the Town of Jersey eligible for FEMA's Hazard Mitigation Grant Program, Flood Assistance Mitigation Grants, and Pre-Disaster Mitigation Grants.

As set forth by Georgia House Bill 489, the Emergency Management Agency is the implementing agency for projects pertaining to hazard mitigation. Walton County is dedicated to work in the best interests of the County, as well as its municipalities. A few mitigation strategies in Walton County's 2024 Mitigation Plan apply to a specific municipality. Unless noted otherwise, mitigation strategies apply equally to all jurisdictions. During the creation and update of this Plan, Walton County Emergency Management Agency solicited and received participation from the following Walton County municipalities: Loganville, Monroe, Social Circle, Walnut Grove, Between, Good Hope, and Jersey.

Distribution of Buildings in Walton County



Source: 2024 Walton County HAZUS Report

Incorporation of Existing Plans, Studies, and Resources

Requirement §201.6(b)(3)

State Requirement Element F3

Existing Plans

2021 Walton County Pre-Disaster Hazard Mitigation Plan
 2024 State of Georgia Hazard Mitigation Plan
 Walton County Local Emergency Operations Plan
 Georgia Forestry Commission's Walton Co. Community Wildfire Protection Plan
 Walton County Joint Comprehensive Plan

Studies

2024 Hazard Risk Analyses (HAZUS Report)
 2017 United States Department of Agriculture Ag Census
 2010 United States Census
 2020 United States Census
 2009 Walton County Flood Insurance Study
 Radeloff, V. C., R. B. Hammer, S. I. Stewart, J. S. Fried, S. S. Holcomb, and J. F. McKeefry. 2005. *The Wildland Urban Interface in the United States*. *Ecological Applications* 15:799-805.

Resources

2014 City of Boston Natural Hazard Mitigation Plan Update
 2010 Camden County Joint Hazard Mitigation Plan Update
 2010 Northern Virginia Hazard Mitigation Plan Update
 National Climactic Data Center
 National Weather Service
 Walton County Tax Assessor's Data
 Walton County Website
 Georgia Mitigation Information System Database
 Colorado State University (Hurricane mapping)
 United States Geological Survey
 FEMA Flood Insurance Rate Maps
 National Flood Insurance Program
 United States Coast Guard National Response Center Data
 Georgia Department of Transportation
 Georgia Safe Dams Program
 Southern Group of State Foresters Wildfire Risk Assessment

Application of Existing Plans and Studies

Existing Planning Mechanism	Reviewed? Yes/No	Incorporation into 2022 Mitigation Plan
2021 Walton County Hazard Mitigation Plan	Yes	Baseline for the 2022 Plan; updated mitigation strategies; updated hazards; updated Walton County information
2024 State of Georgia Hazard Mitigation Plan	Yes	Hazard descriptions; potential hazards; mapping mechanisms; potential mitigation strategies that could be adopted on a local level
Walton County Local Emergency Operations Plan (LEOP)	Yes	Identification of current resources; identification of current capabilities
Georgia Forestry's Walton County Community Wildfire Protection Plan (CWPP)	Yes	Mitigation strategies for wildfire and drought; historical data
2017 USDA Agriculture Census	Yes	Agricultural data regarding potential losses for drought and wildfire
2020 United States Census	Yes	To update Walton County's profile information
2009 Walton County Flood Insurance Study	Yes	Identify potential flood prone areas; prioritization of flood-related mitigation strategies
Walton County Comprehensive Plan	Yes	To identify future development trends; identify mitigation strategies to curb trends in a direction that considers the hazards of the area
Walton County Flood Mitigation Assistance Plan	No	No such plan exists
2024 Walton County HAZUS Report	Yes	Hazard Analysis

CHAPTER TWO – COUNTY PROFILE

Summary of Updates for Chapter Two

The following table provides a description of each section of this chapter and a summary of the changes that have been made to the Walton County Hazard Mitigation Plan 2021.

<u>Chapter 2 Section</u>	<u>Updates</u>
Past Hazards	• This information involved a review of the hazards listed in the previous plan. • Information was updated for the last 50 years
History	• Expanded and updated from previous plan
Past Events	• Identification of major hazard events in Walton County for the last 50 years • Focus on Federal Declarations and events since the last Hazard Mitigation Plan Update
Demographics	• Updated data to the 2020 Census information
Social Vulnerability	• New Section – Not in 2021 Plan
Economy	• Expanded and updated from previous plan
Government	• Expanded and updated from previous plan
Municipalities	• Expanded and updated from previous plan
Transportation	• Expanded and updated from previous plan
Climate	• Expanded and updated from previous plan
Utilities	• Expanded and updated from previous plan
NFIP Compliance	• Expanded and updated from previous plan


History

Walton County was established on December 15, 1818, and is the State of Georgia's 43rd county. Covering 329 square miles, it was named after George Walton, one of three Georgians to sign the Declaration of Independence and briefly Georgia's governor.

Initially, Walton County's settlers were mainly farmers, growing cotton, grains, potatoes, and tobacco. Cotton mills were the first industries, starting in the 1840s, followed by gristmills and steam mills. After the Civil War, industry grew. The textile industry boomed in the 1890s but was later hurt by the boll weevil, soil erosion, and the Great Depression. Following World War II, the county's economy diversified, with manufacturing playing a significant role.

The county boasts 27 sites on the National Register of Historic Places, many of which are in Monroe, including nine historic districts. Other notable sites include the McDaniel-Tichenor House and the Briscoe House and Mill Site in Between.

Walton County is historically significant, having been the birthplace or residence of several Georgia governors, including Alfred H. Colquitt, Henry McDaniel, and Clifford Walker. Two notable figures from Walton County are Mary Ethel Creswell, the University of Georgia's first female baccalaureate graduate, and Moina Belle Michael, the originator of the memorial poppy, which she used to raise funds for wounded soldiers during World War I.



Past Hazards

Walton County, Georgia, has faced many natural hazards in its Walton history. Severe thunderstorms have been the most prevalent of these hazards. In the last 50 years, Walton County has been subjected to 360 documented severe thunderstorm events. These events include torrential rainfall, hail, thunderstorm-force winds, and lightning.

Tornadoes, which can sometimes spawn from severe thunderstorms, have also occurred, although with much less frequency. In Walton County, there have been 8 documented tornados in the last 50 years.

Because of heavy rainfall, either within Walton County or upstream, flooding has also occurred. In the National Climactic Data Center (NCEI) databases of the National Weather Service, there is documentation of 25 flooding events for Walton County.

Winter storms and heavy snowfall have affected Walton County on 23 occasions over the last 50 years, according to the NCEI record. Because these natural events are barely an annual occurrence, the pre-planning and preparedness component of emergency management is not as robust as northern or western states that routinely see this type of weather.

Walton County has also been impacted by the following: drought, excessive heat, tropical cyclones, earthquakes, and wildfires.

Walton County has had 12 Presidential Disaster Declarations (FEMA-declared major disasters) – three of which have occurred since the adoption of the 2019 Hazard Mitigation Plan (two for COVID-19 in 2020 and one for Hurricane Helene in 2024).

Notable Past Events

- **2024, Hurricane Storm Helene (Federal Declaration)**
- 2021, Tornado (EF0)
- 2021, Hail
- **2020, Covid-19 (Federal Declaration x2)**
- 2020, Thunderstorm Wind
- 2018, Tornado (EF1)
- 2018, Thunderstorm Wind
- **2017, Hurricane Irma (Federal Declaration x2)**
- 2017, Tornado (EF1)
- **2014, Severe Winter Storm (Federal Declaration)**
- 2011, Hail
- 2009, Hail
- 2008, Hail
- 2005, Tornado (F0)
- **2000, Severe Winter Storm (Federal Declaration)**
- 1997, Thunderstorm Wind
- 1994, Tornado (F1)
- 1994, Tornado (F0)
- 1994, Tornado (F1)
- **1993, Severe Snowfall, Winter Storm (Federal Declaration)**
- **1993, Tornadoes, High Winds, Heavy Rains (Federal Declaration)**
- 1993, Thunderstorm Wind
- 1990, Tornado (F1)
- **1977, Drought (Federal Declaration)**
- **1973, Tornadoes, Flooding (Federal Declaration)**

Demographics

Walton County

	2000 Census	2010 Census	2020 Census	2023 US Estimated Census
Population	60,687	83,768	96,673	106,702
White	83.0%	80.1%	72.0%	68.3%
African American	14.4%	15.6%	17.9%	20.9%
Hispanic/Latino	1.9%	3.2%	5.4%	7.2%
Asian	0.7%	1.1%	1.5%	1.9%
American Indian	0.3%	0.3%	0.3%	0.1%
Two or More Races	0.9%	1.5%	5.6%	5.1%
Median Age	33.9	37.4	39.7	39.8
Median Household Income	\$46,479	\$52,747	\$71,390	\$77,346
Persons in Poverty	9.7%	15.3%	12.3%	9.1%
Homeowners	72.5%	78.4%	76.2%	79.5%

Municipalities – Population

	2000 Census	2010 Census	2020 Census	2022 US Estimated Census
Between	148	296	402	494
Good Hope	209	274	339	479
Jersey	155	137	146	146
Loganville	5,472	10,458	14,127	15,336
Monroe	11,570	13,234	14,928	15,336
Social Circle	3,329	4,262	4,974	5,113
Walnut Grove	1,241	1,330	1,322	1,594

Social Vulnerability Information

Social vulnerability refers to a community's capacity to prepare for and respond to the stress of hazardous events ranging from natural disasters, such as tornadoes or disease outbreaks, to human-caused threats, such as a toxic chemical spill. The Center for Disease Control and Prevention and the Agency for Toxic Substances and Disease Registry (CDC/ATSDR) rates social vulnerability on 16 variables.

These variables are:


- Percentage below the poverty level
- Unemployment rate
- Per capita income
- Percentage of population 25+ without a high school diploma
- Percentage of population below 65 without insurance
- Percentage of population under 18 years of age
- Percentage of population age 65 and over
- Percentage of the population age 5 or older with a disability
- Percentage of households with a single parent
- Percentage of population that is Hispanic or non-Walton race
- Percentage of population over the age of 5 who speak English less than “well”
- Number of large apartment buildings (10 or more housing units per building)
- Percentage of mobile homes
- Number of housing units with more than one person per room
- Number of households with no vehicle available
- Percentage of population living in group quarters

These 16 variables are aggregated into four overall factors: Socioeconomic Status, Household Characteristics, Racial and Ethnic Minority Status, and Household Type/Transportation. Each census tract is then mapped based upon each of these four factors and the overall SVI based upon the full 16 variables. A score is assigned based upon these variables from 0 (no social vulnerability) to 1 (very high social vulnerability).


Walton County has an Overall SVI score of 0.1392, which indicates a low level of vulnerability. Walton County has a low level of vulnerability for Socioeconomic Status (0.2468), Household Characteristics (0.1962), and Housing Type/Transportation (0.0633). Walton County has a low to medium level of vulnerability for Racial/Ethnic Minority Status (0.2595).

Walton County does have particular areas that score higher on the SVI Index and higher on each of the four factors. The area surrounding the City of Monroe score slightly higher on the Overall SVI and one each of the four factors.


Overall Social Vulnerability




Socioeconomic Status




Household Characteristics



Racial and Ethnic Minority Status



Housing Type/Transportation



Economy

Walton County's economy is primarily agriculture with some light industry. Walton County's cost of living is 1.8% above the national average. The unemployment rate in Walton County is 3.1%, which is below the State average of 3.7% and below the National average of 4.0%. Walton County has a median household income of \$77,356, which is below the national average of \$80,610. The list of the ten largest private employers is from the Georgia Department of Labor (2024) and is listed in alphabetical order – not in order of company size or impact on the community.

The largest private employers in Walton County are:

Company	Product/Service
Hitachi Automotive Products, Inc	Manufacturing: Automotive
Huey Magoo's	Restaurant
Piedmont Walton Hospital, Inc	Healthcare
Pike Electric, LLC	Utilities
Publix Super Markets, Inc	Retail: Groceries
Ridgeview Institute	Healthcare
Standridge Color Corp	Manufacturing: Thermoplastics
The Goodyear Tire & Rubber Co	Manufacturing: Tires
Tucker Door & Trim LLC	Manufacturing: Construction
Walmart	Retail: General

Utilities

Walton County's utility needs are met by a variety of public and private entities.

Electrical power in Walton County is provided by Georgia Power, Walton EMC, and the City of Monroe.

Water in Walton County is provided by Walton County, the City of Social Circle, the City of Monroe, and the City of Loganville.

Natural Gas is supplied in Walton County by the City of Social Circle, the City of Monroe, the City of Lawrenceville, and Walton Gas.

Transportation

Walton County's transportation system consists primarily of state highways and county-maintained roads. Interstate 20, US Highways 78 and 278, as well as State highways 10, 11, 12, 20, 81, 83, 138, and 186 are major transportation routes that carry the majority of passenger and commercial traffic in and out of Walton County.

Government

The form of government specified in the County Charter is known as a commissioner/manager form of government, which provides for six district elected Commissioners and one county at-large, elected chairperson. The Board of Commissioners appoints a County Manager to oversee the day-to-day operations of the county.

The main duties of the commissioners is to pass local laws, known as ordinances, that regulate a variety of things that promote the health, safety and welfare of the citizens covered by them; to pass a balanced budget each year that funds its own operations as well as to allocate funds to the Constitutional Officers, other elected officials, the courts and a variety of programs put in place by the State but funded locally; to ensure that necessary services are funded and provided; to set the millage rate for the County government and many other secondary duties.

The commissioners set the County millage rate each year to fund a portion of the County budget. They also receive the millage rate that is set by the Board of Education and an assessment by the State which is submitted to the Georgia Department of Revenue each year.

The commissioners receive, deliberates, and passes local ordinances each year and amends many others to reflect the changing times. Both require that a public hearing be held, and these are normally held during the regular Commission meetings. They also pass several resolutions and proclamations throughout the year. Generally, with some exceptions, the commissioner can pass any local law and ordinance they feel is needed for the County so long as it does not violate the laws of the State or Federal government or the Constitutional rights of any individual. These are researched thoroughly by legal staff before ever being brought to a hearing.

The commissioners provide many services that citizens expect through the revenues that are raised annually. These include Fire and Ambulance protection; E-911 dispatch services; Zoning and Planning; Inspections; Code Enforcement; Animal Control; Public Library; Parks and Recreation; Public Works; Waste Management Collection Centers; and agencies that service all these such as Building Maintenance, Vehicle Maintenance, and Emergency Management Services. The budget also funds state mandated services such as Law Enforcement and Detention; Superior, Probate, Magistrate and Juvenile courts; Tax Assessment and Tax Collection services; Elections management; District Attorney (shared with other counties) and some smaller funding for local agencies under the State of Georgia.

Climate

Walton County, like much of Georgia, enjoys a temperate climate with four well-defined seasons: warm to hot summers; brisk fall temperatures; relatively brief, cool winters; and a warm spring season. As a result, there exists a Walton growing season in Georgia, perfect for ornamental and economic-boosting agricultural plants.

AVERAGE MONTHLY TEMPERATURES IN GEORGIA (FAHRENHEIT)

	Average Georgia Temperature	Average Walton County Temperature
January	46	44
February	49	47
March	56	55
April	63	62
May	70	70
June	77	77
July	80	80
August	79	78
September	74	73
October	64	63
November	56	54
December	48	46

National Flood Insurance Program Compliance

JURISDICTION	PARTICIPATING?	PARTICIPATION DATE	EFFECTIVE MAP DATE
WALTON COUNTY	YES	2/15/90	12/15/22
BETWEEN	YES	7/1/10	12/15/22
GOOD HOPE	YES	6/17/86	12/15/22
JERSEY	NO	-----	-----
LOGANVILLE	YES	7/16/82	12/8/16
MONROE	YES	2/16/90	12/15/22
SOCIAL CIRCLE	YES	3/31/10	12/15/22
WALNUT GROVE	YES	11/15/10	12/8/16

**** The Town of Jersey does not participate in NFIP due to there being no 1% annual risk floodplain area within the city limits.**

Municipalities

Town of Between



The Town of Between is governed by a Mayor/City Council form of government. All city councilmembers are elected by the citizens of Between. The Town of Between provides the following services to the citizens: Administrative.

The Town of Between was incorporated in 1908, but the area had been settled during the 1850s. The town received its name since it is located halfway between the City of Monroe and the City of Loganville.

Town of Good Hope



The Town of Good Hope is governed by a Mayor/City Council form of government. The Mayor and all council members are elected by the citizens of Good Hope. The Town of Good Hope provides the following services to its citizens: Administration and Planning/Zoning.

The Town of Good Hope was incorporated in 1905. The name of the town is a testament to the aspirations of the first settlers who founded the area.

Town of Jersey



The Town of Jersey is governed by a Mayor/City Council form of government. All city councilmembers are elected by the citizens of Jersey. The Town of Jersey provides the following services to the citizens: Administrative.

The Town of Jersey was incorporated in 1905. Jersey was originally called Centerville due to being equidistance from the City of Monroe, the City of Covington, and the City of Social Circle. However, it was discovered during the 1880s that another Centerville already existed in the state. This prompted the name to be changed. It was at this same time that local merchant, T.M. Abercrombie, had recently brought in a Jersey bull which had caused quite a stir. He jokingly suggested they name the town after the bull and the name stuck.

City of Loganville



The City of Loganville is governed by a Mayor/City Council form of government. All city councilmembers are elected by the citizens of Loganville. The City of Loganville provides the following services to the citizens: Administrative, Economic Development, Planning/Zoning, Utilities, Sanitation, Fire Department, Law Enforcement, and Public Works.

The City of Loganville was named after James H. Logan, who in 1842 purchased 62.5 acres of land in what was then known as Buncombe. In 1851, the area was renamed Loganville in honor of Logan.

Loganville's first town charter was issued in 1887, with the city's limits defined as a half-mile radius from the Justice of the Peace Courthouse. A fire destroyed the original land marker for the city limits, prompting a second charter in 1905 that expanded the city limits to a mile in every direction from the downtown water well.

Two key events shaped Loganville before the 20th century: the first charter and the arrival of the railroad. In 1897, after nearly 20 years of effort, Loganville secured a branch of the Lawrenceville and Loganville Railroad. The railroad, which began operation in 1898, helped connect Loganville to Lawrenceville but ceased operations in 1932 due to the Great Depression. By that time, cotton farming had declined, and Loganville began to re-invent itself.

Today, Loganville is considered to be one of the fastest growing communities in Georgia.

City of Monroe



The City of Monroe is governed by a Mayor/City Council form of government. All city councilmembers are elected by the citizens of Monroe. The City of Monroe provides the following services to the citizens: Administrative, Parks/Recreation, Planning/Development, Fire Department, Law Enforcement, Public Works, and Utilities.

When discussions about establishing a county seat arose, Elisha Betts advocated for "Spring Place" to be established as the county seat. Ms. Betts donated land for county buildings and cemeteries, and the town was renamed Monroe in honor of President James Monroe. It officially became the county seat in 1820 and was incorporated in 1821.

The City of Monroe developed slowly until after the Civil War but grew significantly in the early 20th century, becoming a thriving cotton and textile mill town. Despite a devastating fire in 1857 that destroyed much of downtown, the city rebuilt with brick buildings, many of which remain today. Monroe is known for its strong sense of community and culture, earning the nickname "City of Governors" for producing seven Georgia governors. It also proudly claims a native son who became Governor of Texas.

City of Social Circle



The City of Social Circle is governed by a Mayor/City Council form of government. All city councilmembers are elected by the citizens of Social Circle. The City of Social Circle provides the following services to the citizens: Administrative, Development Authority, Historic Preservation, Library, Planning/Zoning, Housing Authority, Utilities, Fire Department, Law Enforcement, and Public Works.

In 1824, John P. Blackmon purchased shares to the land which today comprises a large portion of the City of Social Circle. Blackmon was drawn to the land's excellent spring and its location at the intersection of two major roads, making it an ideal site for a settlement. He added a dwelling, donated land for a Methodist Church, and established a store and meeting house, which led to the growth of a small village.

The City of Social Circle is said to have earned its name from a traveler impressed by the hospitality of the pioneers. However, a previous community by the same name may have also influenced the name. In 1826, Blackmon and Augustine B. Pope created a site for a post office, with Blackmon becoming Social Circle's first postmaster.

Social Circle was incorporated in 1832, and new settlers continued to arrive. The arrival of the Georgia Railroad in 1845 was a major milestone, establishing the town as the county's first rail center. A Masonic Lodge was founded in 1848, and in 1869, the town was reincorporated, with ordinances regulating public behavior, including curfews, prohibition of liquor sales on election days, and even fines for marbles on Sundays.

The town surrendered its 1869 charter in 1904 and was reincorporated as a city, expanding its limits to one mile from the public well at the intersection of key streets.

City of Walnut Grove



The City of Walnut Grove is governed by a Mayor/City Council form of government. All city councilmembers are elected by the citizens of Walnut Grove. The City of Walnut Grove provides the following services to the citizens: Administrative and Sanitation.

Walnut Grove began as a small crossroads community. The site was marked by a group of walnut trees where Thomas Evans established a store. The area became known as "the walnut grove," a name that stuck when a post office was later established.

Between 1860 and 1870, Ezra Hoffman, a wheelwright, expanded the community with his cabinet-making shop, creating pine chests that were highly prized by local brides.

Walnut Grove was officially incorporated in 1905, with a town charter defining its boundaries as a half-mile from the Brodnax Banking Company.

By 1907, the town had five granite buildings and a population of 125. Business establishments included general merchants, a drug store, and a ginnery.

While the walnut grove and early business area have largely disappeared due to highway construction, Walnut Grove remains a community with deep historical ties. The town retains much of the charm that attracted its early residents.

Notable residents include Robert Hicks, also known as Barbecue Bob. Barbecue Bob was a prominent blue musician who became a key figure in the development of the Atlanta blues style. Another notable resident was Bazoline Estelle Usher who was one of the first African-American women to serve as a school principal. She also was instrumental in founding the first African-American Girl Scout troop in Atlanta.

CHAPTER THREE – COUNTY PROFILE

Summary of Updates for Chapter Three

The following table provides a description of each section of this chapter, and a summary of the changes that have been made to the Walton County Hazard Mitigation Plan 2021.

Chapter 3 Section	Updates
Risk Assessment	- Expanded the explanation of the Risk Assessment - Added an explanation of each part of the Hazard Information
Natural Hazard Severe Thunderstorm	- Updated and consolidated hazard profile with new data - Incorporated Hailstorm into Severe Thunderstorm Hazard - Incorporated Lighting into Severe Thunderstorm Hazard - Content revised
Natural Hazard Winter Storm	- Updated and consolidated hazard profile with new data - Content revised
Natural Hazard Flooding	- Updated and consolidated hazard profile with new data - Land Use and Development trends updated to include municipal NFIP information - Content revised
Natural Hazard Tornado	- Updated and consolidated hazard profile with new data - Content revised
Natural Hazard Drought	- Updated and consolidated hazard profile with new data - Content revised
Natural Hazard Wildfire	- Updated and consolidated hazard profile with new data - Content revised
Natural Hazard Geologic Hazards	- New Section – Not in 2021 Plan - Incorporated Earthquakes into Geologic Hazards - Content revised
Natural Hazard Tropical Cyclone	- Updated and consolidated hazard profile with new data - Content revised
Technological Hazard Hazardous Materials	Updated hazard description

	• Updated and consolidated hazard profile data • Content revised
Technological Hazard Dam Failure	• Updated hazard description • Updated and consolidated hazard profile data • Content revised
Technological Hazard Transportation Incident	• Updated hazard description • Updated and consolidated hazard profile data • Content revised
Technological Hazard Terrorism	• Updated hazard description • Updated and consolidated hazard profile data • Content revised
Technological Hazard Infrastructure Failure	• New Section – Not in 2021 Plan
Technological Hazard Emergent Infectious Diseases	• Updated hazard description • Updated and consolidated hazard profile data • Content revised

Risk Assessment

Requirement §201.6(c)(2)(i and ii)

Requirement §201.6(d)(3)


The Walton County Hazard Mitigation Planning Committee conducted a comprehensive Threat and Hazard Identification and Risk Assessment (THIRA) for Walton County and all municipalities. This assessment developed the hazard basis for this plan. The assessment includes the following components for each hazard:

1. *Hazard Identification:* The Walton County Hazard Mitigation Planning Committee identified nine natural hazards and seven technological/manmade hazards for this Hazard Mitigation Plan. This is an increase of one technological/manmade hazard from the previous iteration of the plan. Each hazard was identified using statistical data and records from a variety of sources. The list of hazards is based upon frequency, severity of impact, probability, potential losses, and vulnerability.
2. *Hazard Description:* Each hazard was described in detail. Many hazard descriptions came from the Georgia Hazard Mitigation Plan since many of the hazards that could impact the state could also potentially impact Walton County.
3. *Profile of Hazards:* Each hazard was profiled as to how it could potentially impact the County.
4. *Assets Exposed to the Hazard:* The plan considers critical facilities and infrastructure as part of the vulnerability assessment. This assessment determines the vulnerability of the municipalities and attempts to identify populations most vulnerable to each hazard, although many have potential countywide impacts.
5. *Estimated Potential Losses:* Using critical facility and past history data, an estimation of potential losses due to a particular hazard event were determined.
6. *Land Use and Development Trends:* Land use trends were considered when determining the potential future impacts of each hazard. This is of importance regarding flooding and dam failure events.
7. *Multi-Jurisdictional Concerns:* Each jurisdiction was considered when determining the potential hazard impact.

The National Risk Index was utilized as a database of risk potential for how natural hazards have impacted Walton County in the past and for how they could impact Walton County in the future. The National Risk Index is a dataset and online tool to help illustrate the United States communities most at risk for 18 natural hazards: Avalanche, Coastal Flooding, Cold Wave, Drought, Earthquake, Hail, Heat Wave, Hurricane, Ice Storm, Landslide, Lightning, Riverine Flooding, Strong Wind, Tornado, Tsunami, Volcanic Activity, Wildfire, and Winter Weather.

The National Risk Index leverages available source data for Expected Annual Loss due to these 18 hazard types, Social Vulnerability, and Community Resilience to develop a baseline relative risk measurement for each United States county and Census tract. These measurements are calculated using average past conditions, but they cannot be used to predict future outcomes for a community. The National Risk Index is intended to fill gaps in available data and analyses to better inform federal, state, local, tribal, and territorial decision makers as they develop risk reduction strategies.

Here is how Walton County scored in each category overall:



These scores indicate that Walton County has relatively low overall risk and expected annual loss. It also indicates relatively moderate values of social vulnerability and community resilience.

In addition to the overall scores, a matrix for each hazard is also produced by the National Risk Index.

Hazard Type	Risk Index Rating	Risk Index Score	National Percentile
Avalanche	Not Applicable	--	
Coastal Flooding	Not Applicable	--	
Cold Wave	No Rating	0	0 100
Drought	Relatively Low	57.6	0 100
Earthquake	Relatively Low	77.6	0 100
Hail	Relatively Moderate	92.7	0 100
Heat Wave	Relatively Low	49.3	0 100
Hurricane	Very Low	62.6	0 100
Ice Storm	Relatively Moderate	78.8	0 100
Landslide	Relatively Low	38.8	0 100
Lightning	Relatively Moderate	84.6	0 100
Riverine Flooding	Very Low	25.5	0 100
Strong Wind	Relatively Low	41.2	0 100
Tornado	Relatively Moderate	77.9	0 100

At the first meeting of the Walton County Hazard Mitigation Plan Update Committee, the attendees participated in a risk assessment of hazard for Walton County. This risk assessment was based upon two primary factors: 1. How likely is a hazard to occur; 2. How prepared the committee meeting participants felt the community was for each hazard. This risk assessment relied on the committee meeting attendees to identify the hazards and then rank them by those two factors. As a result, the risk assessment could be skewed by the meeting participants, recency bias, and/or how the hazard would directly impact the organizations represented at this meeting. After additional discussion with the Walton County Hazard

Mitigation Plan Update committee at future meetings, the hazards in this chapter were the agreed upon list. Several of the hazards identified by the committee members were consolidated into expanded hazard descriptions. Those incorporations are notated in the below hazard ranking.

Hazard	Likelihood Score	Preparedness Score	Impact Score	Total Score
Severe Thunderstorms	182	12	18	212
Nuclear Incident*	1	54	87	142
Utility Failure**	61	8	62	131
Terrorism	12	42	68	122
Severe Winter Weather	60	3	26	79
Hazardous Materials Incident	16	37	17	70
Drought	19	16	17	52
Communications Failure**	6	20	25	51
Water Contamination***	3	28	19	50
Tornado	21	9	14	44
Flooding	18	7	17	42
Transportation Incident	27	9	3	39
Civil Unrest	0	10	25	35
Solar Interference/EMP****	4	13	17	34
Infrastructure Failure/Incident**	7	6	9	22
Earthquake	0	16	5	21
Pandemic/Epidemic	2	6	6	14
Industrial Incident***	3	5	5	13
Tropical Cyclone	12	0	0	12
Wildfire	4	6	2	12
Dam Failure	0	10	0	10
Pipeline Incident*****	1	5	0	6
Extreme Temperatures	3	0	2	5
Agricultural Incident*****	0	3	1	4
Fog/Low Visibility*****	0	1	1	2
Ethylene Oxide Plumes***	1	1	0	2

* Nuclear Incident was incorporated into Terrorism and Hazardous Materials Incident

** Utility Failure, Communications Failure and Infrastructure Failure/Incident were incorporated under Critical Infrastructure Failure

***Water Contamination, Industrial Incident, and Ethylene Oxide Plumes were incorporated under Hazardous Materials Incident

****Solar Interference/EMP was incorporated into Terrorism and Critical Infrastructure Failure

*****Pipeline Incident was incorporated into Hazardous Materials Incident and Critical Infrastructure Failure

*****Agricultural Incident was incorporated into Hazardous Materials Incident and Emergent Infectious Disease

*****Fog/Low Visibility was incorporated into Transportation Incident

Hazard Type	EAL Value	Social Vulnerability	Community Resilience	CRF	Risk Value	Risk Index Score
Tornado	\$3,017,771	Relatively Moderate	Relatively Moderate	1.14	\$3,428,219	77.9
Hail	\$1,339,949	Relatively Moderate	Relatively Moderate	1.14	\$1,523,081	92.7
Earthquake	\$724,684	Relatively Moderate	Relatively Moderate	1.14	\$863,944	77.6
Hurricane	\$567,966	Relatively Moderate	Relatively Moderate	1.14	\$649,330	62.6
Lightning	\$390,550	Relatively Moderate	Relatively Moderate	1.14	\$443,028	84.6
Strong Wind	\$260,884	Relatively Moderate	Relatively Moderate	1.14	\$295,526	41.2
Ice Storm	\$234,181	Relatively Moderate	Relatively Moderate	1.14	\$266,649	78.8
Winter Weather	\$124,290	Relatively Moderate	Relatively Moderate	1.14	\$141,164	72.3
Riverine Flooding	\$106,218	Relatively Moderate	Relatively Moderate	1.14	\$122,340	25.5
Heat Wave	\$73,039	Relatively Moderate	Relatively Moderate	1.14	\$82,925	49.3
Drought	\$50,203	Relatively Moderate	Relatively Moderate	1.14	\$52,189	57.6
Landslide	\$21,900	Relatively Moderate	Relatively Moderate	1.14	\$24,418	38.8
Wildfire	\$19,991	Relatively Moderate	Relatively Moderate	1.14	\$22,556	40.4

As the above graphics indicate, Tornadoes have the highest expected annual loss score of any potential hazard with over \$3 million in expected annual loss. As far as overall risk score, hail has the highest score with lightning second. These two hazards, along with strong wind, are combined in the Walton County Hazard Mitigation Plan under Severe Thunderstorms.


Natural Hazard: **Severe Thunderstorm**

Hazard Description

This section provides general and historical information about thunderstorms, including high wind, lightning, and hail. Other elements of thunderstorms, such as tornadoes and flooding, are addressed in their own sections.

Thunderstorms are formed when moist air near the earth's surface is forced upward through some catalyst (convection or frontal system). As the moist air rises, the air condenses to form clouds. Because condensation is a warming process, the cloud continues to expand upward. When the initial updraft is halted by the upper troposphere, both the anvil shape and a downdraft form. This system of up-drafting and down-drafting air columns is termed a "cell."

As the process of updrafts and downdrafts feeds the cell, the interior particulates of the cloud collide and combine to form rain and hail, which falls when the formations are heavy enough to push through the updraft. The collision of water and ice particles within the cloud creates a large electrical field that must discharge to reduce charge separation. This discharge is the lightning that occurs from cloud to ground or cloud to cloud in the thunderstorm cell. In the final stage of development, the updraft weakens as the downdraft-driven precipitation continues until the cell dies.



Each thunderstorm cell can extend several miles across its base and to reach 40,000 feet in altitude. Thunderstorm cells may compound and move abreast to form a squall line of cells, extending farther than any individual cell's potential.

In terms of temporal characteristics, thunderstorms exhibit no true seasonality in that occurrences happen throughout the year. Convectively, driven systems dominate the summer while frontal driven systems dominate during the other seasons. The rate of onset is rapid in that a single cell endures only 20 minutes.

However, various cells in different stages of development may form a thunderstorm that lasts up to a few hours as it moves across the surface.

In terms of magnitude, the National Weather Service defines thunderstorms in terms of severity as a severe thunderstorm that produces winds greater than 57 mph and/or hail of at least 1 inch in diameter and/or a tornado. The National Weather Service chose these measures of severity as parameters more capable of producing considerable damage. Therefore, these are measures of magnitude that may project intensity.

Natural Hazard: **Severe Thunderstorm**

Lightning

Lightning occurs when the difference between the positive and negative charges of the upper layers of the cloud and the earth's surface becomes great enough to overcome the resistance of the insulating air. The current flows along the forced conductive path to the surface (in cloud to ground lightning) and reaches up to 100 million volts of electrical potential. In Georgia, lightning strikes peak in July, with June and August being second highest in occurrence.

Hail

Hail is a form of precipitation that forms during the updraft and downdraft-driven turbulence within the cloud. The hailstones are formed by layers of accumulated ice (with more layers creating larger hailstones) that can range from the size of a pea to the size of a grapefruit. Hailstones span a variety of shapes but usually take a spherical form. Hailstorms mostly endanger cars but have been known to damage aircraft and structures.

Hazard Profile

Severe thunderstorms, including high winds, hail, and lightning, are a serious threat to the residents and infrastructure of Walton County. Severe thunderstorms are the most frequently occurring natural hazard in Walton County. Many of these storms include high winds, lightning, and hail. Hail up to 3.00 inches was recorded in Walton County on several occasions, most recently in 2009. Thunderstorm winds over 100 mph have been reported on a few occasions in Walton County, with the most recent occurring in 1993. While there have been dozens of documented thunderstorm events affecting Walton County over the last 50 years, it is likely that the official number is a low estimate due to poor record keeping in decades past. For example, only 44 thunderstorm events were recorded between 1975 and 1995, likely a vast underestimation of actual events.

Most of the available information relating to severe thunderstorm events in Walton County fails to describe damage estimates in any detail. With each thunderstorm event, there are likely unreported costs related to infrastructure costs, public safety response costs, utility repair costs, and personal home and business repair costs. Thunderstorms have occurred during all parts of the day and night and in every month in Walton County.


The Walton County Hazard Mitigation Plan Update Committee utilized data from the National Centers for Environmental Information, the National Weather Service, numerous weather-related news articles, and the Walton County LEOP in researching severe thunderstorms and their potential impacts on the county. All information has been gathered on a countywide basis. All thunderstorm hazard data included for Walton County is limited to countywide data and is not broken down by jurisdiction.

During the last 50 years, 198 thunderstorm events were recorded in Walton County, with 154 of those occurring in the last 30 years. According to these records, Walton County has a 1.4% daily chance of a thunderstorm event based upon data from the last 30 years. Over the last 10 years, Walton County has averaged 6.2 thunderstorm events per year (62 events). Due to improved record keeping protocols, the Walton County Hazard Mitigation Plan Update Committee believes the data from the last ten years provides a more accurate representation of the thunderstorm threat to the county. The Walton County Hazard Mitigation Plan Update Committee has also determined that the lightning threat is severely under-reported, as shown in the NCEI data numbers.

Natural Hazard: Severe Thunderstorm

Hailstone size	Measurement		Updraft Speed	
	in.	cm.	mph	km/h
bb	< 1/4	< 0.64	< 24	< 39
pea	1/4	0.64	24	39
marble	1/2	1.3	35	56
dime	7/10	1.8	38	61
penny	3/4	1.9	40	64
nickel	7/8	2.2	46	74
quarter	1	2.5	49	79
half dollar	1 1/4	3.2	54	87
walnut	1 1/2	3.8	60	97
golf ball	1 3/4	4.4	64	103
hen egg	2	5.1	69	111
tennis ball	2 1/2	6.4	77	124
baseball	2 3/4	7.0	81	130
tea cup	3	7.6	84	135
grapefruit	4	10.1	98	158
softball	4 1/2	11.4	103	166

As indicated by the below graphics, Walton County averages around 16 flashes of cloud to ground lightning per square kilometer per year. That equals a 4.4% chance of a cloud-to-ground lightning strike on any given day. This shows a much higher indication of lightning occurrences than has been reported to the National Weather Service and the National Centers for Environmental Information. It is the determination of the Walton County Hazard Mitigation Plan Update Committee that this data shows a more accurate representation of the scope of the threat that lightning poses to the citizens and infrastructure of Walton County.



Natural Hazard: Severe Thunderstorm

Severe thunderstorm winds, which are defined as winds of at least 58 mph in conjunction with a convective event, have occurred with many thunderstorms that have affected Walton County. These winds can exceed 100 mph and cause damage comparable to weak tornadoes.

Hazard Score	Wind Speeds
1	<90 mph gust
2	91 – 100 mph gust
3	101 – 110 mph gust
4	111 – 120 mph gust
5	>120 mph gust

<i>Municipality</i>	<i># of Thunderstorms</i>	<i>Annual Risk</i>
MONROE	35	100%
LOGANVILLE	34	100%
SOCIAL CIRCLE	23	92%
WALNUT GROVE	24	96%
BETWEEN	13	52%
GOOD HOPE	15	60%
JERSEY	16	64%

This Table identifies the number of Thunderstorms for municipalities over the last 25 years


Assets Exposed to the Hazard

In evaluating assets that are susceptible to severe thunderstorms, the Walton County HMPC determined that all public and private property is at threat by severe thunderstorms, including all critical facilities. This is due to the lack of spatially prejudice of severe thunderstorm events.

Estimated Potential Losses

Estimates of damage for the past events of the last 50 years are over \$57.8 million, or \$1,151,180 annually. However, all estimated damages reported have occurred over the last 35 years. When extrapolated over 30 years, the annual average increases significantly to \$1,651,686. These numbers are thought to be a gross underestimation of actual past damages. According to the National Risk Index, Walton County has an estimated annual loss of \$1,991,383 for lightning, hail, and strong winds.

Natural Hazard: Severe Thunderstorm



Source: 2024-2029 State of Georgia Hazard Mitigation Strategy and Enhanced Plan


Land Use & Development Trends

Walton County currently has no land use trends related to Thunderstorms beyond continued population growth, which is occurring in most areas of Walton County. However, the greatest amount of growth has occurred in areas near the Gwinnett County line.

Multi-Jurisdictional Considerations


Thunderstorm events have occurred across all areas of Walton County. Crop damage from thunderstorm events would likely have the greatest impact in the rural areas of Walton County. However, property damage numbers would be highest in more heavily populated areas due to greater population density. Thunderstorms have the potential to impact all areas of Walton County.

Natural Hazard: **Severe Thunderstorm**



Source: 2024-2029 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

Natural Hazard: Severe Thunderstorm



Source: 2024-2029 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

Hazard Summary

Thunderstorm events pose one of the greatest threats of property damage, injuries, and loss of life in Walton County. Thunderstorm events are the most frequently occurring weather event that threatens Walton County. As a result, the Walton County HMPC recommends that the mitigation measures identified in this plan for thunderstorms should be aggressively pursued due to the frequency of this hazard and the ability for this hazard to affect any part of Walton County.

Natural Hazard: **Severe Thunderstorm***Thunderstorm Events Since 2020 in Walton County*

<u>Location</u>	<u>County/Zone</u>	<u>St.</u>	<u>Date</u>	<u>Time</u>	<u>Type</u>	<u>Mag</u>	<u>Dth</u>	<u>Inj</u>	<u>PrD</u>	<u>CrD</u>
Totals:							0	0	1.344M	0.00K
YOUTH	WALTON CO.	GA	02/06/2020	09:58	Thunderstorm Wind	50 kts. EG	0	0	10.00K	0.00K
BOLD SPGS	WALTON CO.	GA	04/13/2020	02:07	Thunderstorm Wind	50 kts. EG	0	0	6.00K	0.00K
BOLD SPGS	WALTON CO.	GA	04/13/2020	02:12	Thunderstorm Wind	50 kts. EG	0	0	6.00K	0.00K
BETWEEN	WALTON CO.	GA	04/13/2020	02:18	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
YOUTH	WALTON CO.	GA	06/15/2020	15:20	Thunderstorm Wind	60 kts. EG	0	0	15.00K	0.00K
BOLD SPGS	WALTON CO.	GA	06/24/2020	14:35	Thunderstorm Wind	50 kts. EG	0	0	6.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/27/2020	16:03	Thunderstorm Wind	50 kts. EG	0	0	25.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	08/03/2020	13:58	Thunderstorm Wind	50 kts. EG	0	0	50.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	08/09/2020	20:10	Thunderstorm Wind	45 kts. EG	0	0	1.00K	0.00K
SPLIT SILK	WALTON CO.	GA	05/03/2021	10:55	Thunderstorm Wind	50 kts. EG	0	0	15.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	05/03/2021	13:19	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	05/04/2021	13:47	Thunderstorm Wind	50 kts. EG	0	0	8.00K	0.00K
YOUTH	WALTON CO.	GA	06/14/2021	15:55	Lightning		0	0	50.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/14/2021	15:55	Thunderstorm Wind	50 kts. EG	0	0	30.00K	0.00K
YOUTH	WALTON CO.	GA	06/14/2021	16:07	Hail	1.00 in.	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	06/14/2021	16:07	Hail	1.75 in.	0	0	900.00K	0.00K
YOUTH	WALTON CO.	GA	07/08/2021	19:41	Thunderstorm Wind	45 kts. EG	0	0	10.00K	0.00K
JERSEY	WALTON CO.	GA	08/10/2021	16:35	Thunderstorm Wind	45 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	08/25/2021	18:19	Thunderstorm Wind	50 kts. EG	0	0	9.00K	0.00K

LOGANVILLE	WALTON CO.	GA	12/11/2021	14:20	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
PANNELL	WALTON CO.	GA	05/30/2022	16:56	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
WHITNEY	WALTON CO.	GA	05/30/2022	16:58	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
GOOD HOPE	WALTON CO.	GA	05/30/2022	17:03	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
WHITNEY	WALTON CO.	GA	05/30/2022	17:13	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	06/08/2022	22:55	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	06/08/2022	23:00	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	06/08/2022	23:06	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
SPLIT SILK	WALTON CO.	GA	06/17/2022	17:15	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
SPLIT SILK	WALTON CO.	GA	06/17/2022	17:20	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	06/17/2022	17:20	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
GOOD HOPE	WALTON CO.	GA	07/03/2022	17:40	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	07/19/2022	16:51	Thunderstorm Wind	50 kts. EG	0	0	0.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	07/19/2022	16:57	Thunderstorm Wind	45 kts. EG	0	0	2.00K	0.00K
MONROE	WALTON CO.	GA	07/19/2022	17:00	Thunderstorm Wind	50 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	07/19/2022	17:02	Thunderstorm Wind	45 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	07/19/2022	17:24	Thunderstorm Wind	50 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	07/19/2022	17:25	Thunderstorm Wind	50 kts. EG	0	0	0.00K	0.00K
SPLIT SILK	WALTON CO.	GA	01/12/2023	16:34	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	01/12/2023	16:39	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K

YOUTH	WALTON CO.	GA	01/12/2023	16:41	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
GRATIS	WALTON CO.	GA	01/12/2023	16:42	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
BETWEEN	WALTON CO.	GA	01/12/2023	16:45	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
BETWEEN	WALTON CO.	GA	01/12/2023	16:47	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
BETWEEN	WALTON CO.	GA	01/12/2023	16:49	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	01/12/2023	16:50	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	01/12/2023	16:50	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	01/12/2023	16:53	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	01/12/2023	16:56	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	01/12/2023	16:57	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
BRADLEY	WALTON CO.	GA	01/12/2023	16:58	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	01/12/2023	17:03	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
WALKER PARK	WALTON CO.	GA	01/12/2023	17:04	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	01/12/2023	17:04	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
BOLD SPGS	WALTON CO.	GA	01/12/2023	17:05	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
EBENEZER	WALTON CO.	GA	01/12/2023	17:05	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
EBENEZER	WALTON CO.	GA	01/12/2023	17:08	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	01/12/2023	17:08	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
CAMPTON	WALTON CO.	GA	03/03/2023	18:18	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
EBENEZER	WALTON CO.	GA	03/03/2023	18:40	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K

SOCIAL CIRCLE	WALTON CO.	GA	04/01/2023	08:27	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	04/30/2023	04:35	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	04/30/2023	05:20	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	05/16/2023	16:58	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	05/16/2023	16:58	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	05/16/2023	17:00	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	05/16/2023	17:40	Thunderstorm Wind	35 kts. EG	0	0	1.00K	0.00K
YOUTH	WALTON CO.	GA	06/06/2023	17:27	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	06/06/2023	17:29	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	06/06/2023	17:29	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	06/06/2023	17:30	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/14/2023	14:10	Hail	1.00 in.	0	0	0.00K	0.00K
GRATIS	WALTON CO.	GA	06/25/2023	17:13	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
BOLD SPGS	WALTON CO.	GA	06/25/2023	17:27	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:27	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
YOUTH	WALTON CO.	GA	06/25/2023	17:28	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:30	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:30	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:30	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:30	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K

WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:31	Lightning		0	0	10.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:32	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:35	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:39	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
YOUTH	WALTON CO.	GA	06/25/2023	17:41	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:42	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
SNOWS MILL	WALTON CO.	GA	06/25/2023	17:44	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	06/25/2023	17:45	Thunderstorm Wind	52 kts. EG	0	0	3.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:45	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:51	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
JERSEY	WALTON CO.	GA	06/25/2023	17:51	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:57	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:57	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	06/25/2023	17:57	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
EBENEZER	WALTON CO.	GA	06/25/2023	18:00	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
BETWEEN	WALTON CO.	GA	06/25/2023	18:03	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
BOLD SPGS	WALTON CO.	GA	06/25/2023	18:03	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	07/01/2023	18:04	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
CAMPTON	WALTON CO.	GA	07/01/2023	18:08	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
SPLIT SILK	WALTON CO.	GA	07/01/2023	19:02	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K

BOLD SPGS	WALTON CO.	GA	07/14/2023	20:19	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	07/20/2023	17:22	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
GRATIS	WALTON CO.	GA	07/20/2023	17:27	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	07/20/2023	17:33	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
BRADLEY	WALTON CO.	GA	07/20/2023	17:35	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
MT VERNON	WALTON CO.	GA	07/20/2023	17:42	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
GRATIS	WALTON CO.	GA	07/20/2023	17:42	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	07/20/2023	17:45	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WHITNEY	WALTON CO.	GA	07/21/2023	17:09	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
PANNELL	WALTON CO.	GA	08/03/2023	15:45	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	08/06/2023	12:10	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	08/06/2023	12:30	Thunderstorm Wind	48 kts. EG	0	0	2.00K	0.00K
MT VERNON	WALTON CO.	GA	08/06/2023	12:35	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
BRADLEY	WALTON CO.	GA	08/06/2023	12:37	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
YOUTH	WALTON CO.	GA	08/07/2023	17:10	Thunderstorm Wind	61 kts. EG	0	0	10.00K	0.00K
LOGANVILLE	WALTON CO.	GA	08/07/2023	17:12	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
MONROE	WALTON CO.	GA	08/07/2023	17:15	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
BOLD SPGS	WALTON CO.	GA	08/07/2023	17:16	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	08/07/2023	17:23	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MT VERNON	WALTON CO.	GA	08/07/2023	17:23	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K

GRATIS	WALTON CO.	GA	08/07/2023	17:30	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	08/12/2023	16:25	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
JERSEY	WALTON CO.	GA	08/12/2023	16:41	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	08/12/2023	16:41	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
YOUTH	WALTON CO.	GA	08/12/2023	16:41	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
GOOD HOPE	WALTON CO.	GA	08/12/2023	16:46	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
GRATIS	WALTON CO.	GA	08/12/2023	17:00	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	01/09/2024	09:08	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	02/12/2024	21:15	Thunderstorm Wind	43 kts. EG	0	0	2.00K	0.00K
LOGANVILLE	WALTON CO.	GA	02/28/2024	15:46	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
SPLIT SILK	WALTON CO.	GA	02/28/2024	15:50	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	02/28/2024	16:22	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	04/02/2024	23:06	Thunderstorm Wind	56 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	04/02/2024	23:10	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	04/02/2024	23:10	Thunderstorm Wind	56 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	04/02/2024	23:12	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	04/02/2024	23:16	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	04/02/2024	23:20	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	04/02/2024	23:20	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	04/02/2024	23:22	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K

BOLD SPGS	WALTON CO.	GA	08/17/2024	18:15	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	08/29/2024	17:50	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	08/29/2024	17:50	Thunderstorm Wind	65 kts. EG	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	08/29/2024	17:52	Thunderstorm Wind	61 kts. EG	0	0	20.00K	0.00K
SPLIT SILK	WALTON CO.	GA	08/29/2024	18:00	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	08/29/2024	18:05	Thunderstorm Wind	56 kts. EG	0	0	7.00K	0.00K
JERSEY	WALTON CO.	GA	08/29/2024	18:10	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
YOUTH	WALTON CO.	GA	08/29/2024	18:18	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
SPLIT SILK	WALTON CO.	GA	08/29/2024	18:25	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
LOGANVILLE	WALTON CO.	GA	08/29/2024	18:30	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	02/16/2025	05:03	Thunderstorm Wind	48 kts. EG	0	0	2.00K	0.00K
BETWEEN	WALTON CO.	GA	02/16/2025	05:04	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
YOUTH	WALTON CO.	GA	02/16/2025	05:04	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
NICHOLASVILLE	WALTON CO.	GA	02/16/2025	05:06	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
WALKER PARK	WALTON CO.	GA	02/16/2025	05:07	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
CAMPTON	WALTON CO.	GA	02/16/2025	05:08	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	02/16/2025	05:10	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	02/16/2025	05:10	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	02/16/2025	05:10	Thunderstorm Wind	52 kts. EG	0	0	10.00K	0.00K
MT VERNON	WALTON CO.	GA	02/16/2025	05:13	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K

SOCIAL CIRCLE	WALTON CO.	GA	02/16/2025	05:17	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	02/16/2025	05:18	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K

Natural Hazard: **Winter Storm**

Hazard Description

Severe winter storms bring the threat of ice and snow. There are many types of frozen precipitation that could create a severe winter weather event. Freezing rain consists of super cooled falling liquid precipitation freezing on contact with the surface when temperatures are below freezing. This results in an ice glazing on exposed surfaces including buildings, roads, and power lines. Sleet is easily discernable from freezing rain in that the precipitation freezes before hitting the surface. Often this sleet bounces when hitting a surface and does not adhere to the surface. However, sleet can compound into enough depths to pose some threat to motorists and pedestrians.

A heavy accumulation of ice, which is often accompanied by high winds, can devastate infrastructure and vegetation. Destructiveness in the southern states is often amplified due to the lack of preparedness and response measures. Also, the infrastructure was not designed to withstand certain severe weather conditions such as weight build-up from snow and ice. Often, sidewalks and streets become extremely dangerous to pedestrians and motorists. Primary industries, such as farming and fishing, suffer losses through winter seasons that produce extreme temperatures and precipitation.

Within Georgia, the impacts of winter storms are often contained within the northern part of the State. However, events like the 1993 “storm of the century” illustrated the vast impacts that one storm can have on the entire state. The winter storms with the greatest impacts on Georgia are the result of coastal storms coming up from the Gulf of Mexico, including the winter storms in 1973 and 1993. The 1973 storm produced snowfalls of up to 19 inches in parts of Central Georgia including the City of Thomaston in Upson County. Also, a major ice storm occurred in 2014, bringing up to 1 inch of ice to the eastern portion of the State near Augusta.

Severe winter weather exhibits seasonal qualities in that most occur within the months of January to March, with the highest probability of occurrence in February. The rate of onset and duration varies from storm to storm, depending on the weather system driving the storm. Severe winter weather rarely frequents the State of Georgia. However, the impacts of the storms substantiate severe winter weather’s inclusion in the risk assessment.

Hazard Profile


While winter storms are not as frequent of an occurrence in Walton County as they are in areas in the Northern US, they still have the potential to wreak havoc on the community when they do occur. Winter storms in Walton County typically cause drastic damage to infrastructure, such as roads, power lines, and bridges. The elevation changes, steepness of major roads, and lack of easy accessibility to some areas make winter weather particularly problematic for Walton County.

They also can cause damage to private property, businesses, and trees throughout the county. The large number of trees in Walton County can also become a hazard when the tree limbs become weighed down with snow and ice and begin to break and fall to the ground, potentially damaging private property, public property, or injuring people and animals.

During the past thirty years, documentation exists for 23 winter storm events in Walton County. This equates to a winter storm every 1.3 years in Walton County. No consolidated data can be located prior to this timeframe. All winter storm data has been gathered on a countywide basis. For additional historic data, please see Appendix B. All winter storm hazard data included for the Walton County is limited to

Natural Hazard: **Winter Storm**


countywide data and is not broken down by jurisdiction.



Source: 2024-2029 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

Individual events of Winter Weather can be drastically different depending on many factors, including the duration of the event, the type of precipitation involved, and the depth of the precipitation. Winter Storm events can be a light dusting of snow, $\frac{1}{4}$ inch of ice, or over a foot of snow. During the 1993 snow event, parts of Walton County reported up to 10 inches of snow and all areas received at least 3 inches of snow. Ice events are another type of winter storm that has impacted Walton County in the past. These types of winter storms can be particularly crippling due to the increased threat of tree falls related to the weight of accumulated ice and subsequent utility infrastructure failure.

Natural Hazard: Winter Storm



Source: 2024-2029 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

During the 2014 Ice Storm event, parts of eastern Walton County received up to ½ inch of ice and all areas received at least a 0.15 inch of ice.


Assets Exposed to the Hazard

Since winter storms are indiscriminate regarding location, the Walton County HMPC determined that all public and private property, including all critical infrastructure, are susceptible to impacts from winter storms with areas of higher elevation more likely to receive direct impacts.

Estimated Potential Losses

Over the last 50 years, nearly \$1.2 million in damages have been reported in Walton County from winter storm events. This equates to \$23,880 annually in damages. However, all reported damages have been from the last 25 years. When extrapolated over 25 years, the annual damage amount doubles to \$47,760. However, this is likely a gross underestimation of the damages winter storms have caused in Walton County in the past. According to the National Risk Index, Walton County has an estimated annual loss of \$358,471 related to severe winter weather.

Natural Hazard: **Winter Storm**




Source: 2024-2029 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

Land Use & Development Trends

Walton County currently has no land use trends related to Winter Storms beyond continued population growth, which is occurring in nearly all areas of Walton County and particularly near the Gwinnett County line.

Natural Hazard: Winter Storm



Source: 2024-2029 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

Assets Exposed to the Hazard

Since winter storms are indiscriminate regarding location, the Walton County HMPC determined that all public and private property, including all critical infrastructure, are susceptible to impacts from winter

Multi-Jurisdictional Considerations

All portions of Walton County could potentially be impacted by a winter storm, including freezing rain, sleet, and snow. Therefore, all mitigation actions identified regarding winter storms should be pursued on a countywide basis and including all municipalities.

Natural Hazard: **Winter Storm**

Hazard Summary

Winter storms, which can include freezing rain, sleet, or snow, typically afford communities some advance warning, which is different from many other severe weather phenomena. The National Weather Service issues winter storm watches, advisories, and warnings as much as a day before the storm's impacts begin. Unfortunately, communities in the Southern United States are not equipped to handle winter storms due to their relative infrequent nature. Oftentimes, communities can face severe impact from these storms. The Walton County HMPC recognizes the potential threats winter storms could have on the community and have identified specific mitigation actions as a result.

Winter Storm Events since 2020

<u>Location</u>	<u>County/Zone</u>	<u>St.</u>	<u>Date</u>	<u>Time</u>	<u>Type</u>	<u>Mag</u>	<u>Dth</u>	<u>Ini</u>	<u>PrD</u>	<u>CrD</u>
WALTON (ZONE)	WALTON (ZONE)	GA	01/16/2022	08:00	Winter Weather		0	0	0.00K	0.00K

Natural Hazard: **Flooding**

Requirement §201.6(c)(2)(ii)

Requirement §201.6(c)(3)(ii)

Hazard Description

Flooding is a temporary overflow of water on normally dry lands adjacent to the source of water, such as a river, stream, or lake. The causes of flooding include mass sources of precipitation, such as tropical cyclones, frontal systems, and isolated thunderstorms combined with other environmental variables, such as changes to the physical environment, topography, ground saturation, soil types, basin size, drainage patterns, and vegetative cover. Adverse impacts may include structural damages, temporary backwater effects in sewers and drainage systems, death of livestock, agricultural crop loss, loss of egress and access to critical facilities due to roads being washed-out or over-topped and unsanitary conditions by deposition of materials during recession of the floodwaters.

Floods are loosely classified as either coastal or riverine. Coastal flooding occurs when normally dry, low-lying land is flooded by sea water. Coastal flooding is usually associated with tropical cyclones in Georgia. Riverine flooding occurs from inland water bodies such as streams and rivers. Riverine flooding is often classified based on rate of onset. The first is slow to build, peak, and recede, often allowing enough time for evacuations. The other type of riverine flood is referred to as a “flash” flood, which rapidly peaks and recedes, thus giving insufficient time for evacuations. Flash floods are typically considered the most dangerous of these types.

On a broad scale, flooding can occur around any body of water or low-lying surface given enough precipitation or snowmelt. The spatial extent of the flooding event depends on the amount of water overflow but can usually be mapped because of existing floodplains (areas already prone to flooding).

Flooding in Georgia is highly dependent on precipitation amounts and is highly variable. Certain seasons are more prone to flooding to a greater likelihood of excessive precipitation. Typically, the wet seasons are during the winter, early spring, and midsummer. Late spring and fall are usually drier seasons.

Hazard Profile

The Walton County HMPC researched flooding information for the last fifty years. The main sources of information used by the Walton County HMPC came from the National Centers for Environmental Information, the Walton County Emergency Operations Plan, and news media sources. It was determined that flooding has caused significant damage on many occasions over the last 25 years.

One significant flooding event that affected Walton County occurred in September 2009. This flood event impacted a wide area across Metro Atlanta, including Walton County. While damage estimates within Walton County are difficult to estimate, areawide damage estimates topped \$250 million.

Flood events within Walton County are typically associated with areas of special flood hazard as identified on Flood Rate Insurance Maps (FIRMS) published by FEMA. With each flooding event, it is likely that significant costs arose related to road repair, infrastructure repair, and public safety response operations. Most of the flood damage in Walton County’s history appears to be related to roads and culverts washing out because of flood waters. Walton County’s significant elevation changes also increases the impact of short duration, heavy rain events leading to flash flooding.

Natural Hazard: **Flooding**

Walton County has one flood gage that provides recent historical data and potential flood levels. This gage is located on Cornish Creek at Lower Jersey Road. Flood stage at this location begins at 11 feet. At this level, minor flooding of agricultural and pasture lands upstream and downstream from the gage begins. At 17 feet, moderate flood level is reached and water will reach the top of the large culvert system on Lower Jersey Road and reach the road itself. At 18 feet, Lower Jersey Road would be under 1 foot of water and significant erosion around the culvert system is likely. At 19 feet, major flood stage is reached and 2 feet of water will cover Lower Jersey Road. The USGS gage house will begin to be impacted at this stage.

For the City of Monroe, a tributary of Jack's Creek would flood several homes on Walton Road and Hickory Drive in a 100-year (1% annual risk) flood event. Homes in this area could see up to 1 foot of water inundation in a 100-year (1% annual risk) flood event. Additionally, Mountain Creek would flood several homes in western Monroe, as well. One home on Mountain View Drive could see up to 2 feet of water inundation in a 100-year (1% annual risk) flood event. A tributary of Mountain Creek could also impact homes on Country Club Drive.

For the City of Walnut Grove, there are a few residential structures that could see some direct impacts in a 100-year (1% annual risk) flood event. The home of most concern would be on Georgia Highway 138 very close to the jurisdictional limits of Walnut Grove. This residence could see up to 1 foot of water inundation. Most other structures would see less than 3 inches of water in a 100-year (1% annual risk) flood event.

Loganville is the jurisdiction in Walton County with the greatest concern for flooding. Little Haynes Creek could cause minor flooding of many homes in the southwest portion of the city, although most would see less than 3 inches of water inundation in a 100-year (1% annual risk) flood event. Additionally, Big Flat Creek could cause flooding of up to 18 inches for several homes off Lee Byrd Road and Bay Creek Road. Overall, there are 146 residences in the floodplain in the City of Loganville with the vast majority at risk for less than 3 inches of water.

In Social Circle, several homes on Oak Drive and Sweetgum Street could see direct impacts from a 100-year (1% annual risk) flood event. Many of these homes could see up to 6 inches of water and some homes on Sweetgum Street could see up to 18 inches of water inundation in a 100-year (1% annual risk) flood event.

In Good Hope, there are a few residential structures that could see impacts from a 100-year (1% annual risk) flood event. A few homes on Pleasant Valley Road would be inaccessible during this magnitude event. Some homes could even see up to 6 inches of water inundation on Pleasant Valley Road.

There are no structures located within the 100-year (1% annual risk) floodplain in the Town of Between. The Town of Between would be more likely to see impacts from a flash flood event with the ponding of water in low-lying areas. Some low-lying areas that could see such impacts include New Hope Church Road on the southwest and northeast areas of the Between jurisdictional boundaries.

There is no 100-year (1% annual risk) floodplain within the Town of Jersey. Additionally, the Town of Jersey is almost completely built on a raised area, leaving little to no low-lying areas that are susceptible to flash flood events. The most significant flood event impacts for the Town of Jersey would be the

Natural Hazard: **Flooding**

blocking of roads accessing the jurisdiction from the east (Big Flat Creek) and west (Cornish Creek) in a 100-year (1% annual risk) flood event.

There are 15 documented flood events over the last 50 years. Based on the 50-year record, it can be inferred that such an event is likely to occur every 3.3 years in Walton County. This relates to a 30% chance of a flood event occurring in a given year. However, all identified flood events have occurred over the last 25 years. When extrapolated over 25 years, Walton County has averaged a flood event every 1.7 years and has a 60% annual chance of a flood event of some magnitude occurring. For additional historical data, please see Appendix B.

Assets Exposed to the Hazard

To evaluate the assets that would potentially be impacted by flooding, the Walton County HMPC attempted to identify known structures within, or close to, the 100-year floodplain. There are approximately 790 buildings identified in the flood plain. Of the buildings identified as being in the floodplain, 773 of them are residential properties.


<i>Municipality</i>	<i># of Flood Events</i>	<i>Annual Risk</i>
<i>MONROE</i>	5	20%
<i>LOGANVILLE</i>	5	20%
<i>SOCIAL CIRCLE</i>	5	20%
<i>WALNUT GROVE</i>	6	24%
<i>BETWEEN</i>	4	16%
<i>GOOD HOPE</i>	6	24%
<i>JERSEY</i>	4	16%

The above information is for the last 25 years


Estimated Potential Losses

Based upon the estimations from the 2024 Walton County HAZUS Report, a flood equivalent to the 1% riverine flood levels could result in estimated losses of more than \$37.2 million (790 buildings). However, it is possible that some areas may not experience total losses while others not designated in the 1% annual risk areas may be inundated with flood water. According to the National Risk Index, Walton County has an estimated annual loss of \$106,218 related to Riverine Flooding events.

Natural Hazard: **Flooding**




Source: 2024-2029 State of Georgia Hazard Mitigation Strategy and Enhanced Plan



Source: 2024 Walton County HAZUS Report

Natural Hazard: **Flooding**



Source: 2019-2024 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

Land Use & Development Trends

Walton County participates in the National Flood Insurance Program (NFIP) and follows the program's guidelines to ensure future development is carried out in the best interests of the public. Walton County (CID No. 130185C) first entered the NFIP on February 16, 1990. According to the NFIP guidelines, the County has executed a Flood Damage Prevention Ordinance. This ordinance attempts to minimize the loss of human life and health as well as minimize public and private property losses due to flooding. The ordinance requires any potential flood damage be evaluated at the time of initial construction and that certain uses be restricted or prohibited based on this evaluation. The ordinance also requires that potential homebuyers be notified that a property is located in a flood area. In addition, all construction must adhere to the Georgia State Minimum Standard Codes and the International Building Codes of 2018. Currently, the Walton County municipalities of Monroe, Loganville, Social Circle, Walnut Grove, Between, and Good Hope also participate in NFIP through the application of appropriate NFIP-compliant ordinances and regulations. There are no 100-year (1% annual risk) floodplain areas within the Town of Jersey.

Natural Hazard: **Flooding**

The Walton County ordinance that governs flood damage prevention can be found in Article 11, Part 11-4 of the Walton County Code of Ordinances. Within this code, the Walton County Planning and Development Director is tasked as the floodplain management program administrator. The administrator roles are:

1. Review proposed development to assure that the permit requirements of this Ordinance have been satisfied.
2. Review proposed development to assure that all necessary permits have been received from governmental agencies from which approval is required by Federal or State law, including Section 404 of the Federal Water Pollution Control Act Amendments of 1972, 33 U.S.C. 1334. Require that copies of such permits be provided and maintained on file.
3. Review all permit applications to determine whether proposed building sites will be reasonably safe from flooding.
4. When Base Flood Elevation data or floodway data have not been provided in accordance with Section 11-4-110 B, then the administrator shall obtain, review and reasonably utilize any base flood elevation and floodway data available from a Federal, State or other sources in order to administer the provisions of Section 11-4-130.
5. Review and record the actual elevation in relation to mean sea level (or highest adjacent grade) of the lowest floor, including basement, of all new or substantially improved structures in accordance with Section 11-4-120 B.2.
6. Review and record the actual elevation, in relation to mean sea level to which any new or substantially improved structures have been flood-proofed, in accordance with Section 11-4-120 B.2.
7. When flood-proofing is utilized for a structure, the administrator shall obtain certification of design criteria from a registered professional engineer or architect in accordance with Section 11-4-120 B.1.c and Section 11-4-130 B.2 or D.2.
8. Make substantial damage determinations following a flood event or any other event that causes damage to structures in flood hazard areas.
9. Notify adjacent communities and the Georgia Department of Natural Resources prior to any alteration or relocation of a watercourse and submit evidence of such notification to the Federal Emergency Management Agency (FEMA).
10. For any altered or relocated watercourse, submit engineering data/analysis within six (6) months to the FEMA to ensure accuracy of community flood maps through the Letter of Map Revision process. Assure flood carrying capacity of any altered or relocated watercourse is maintained.
11. Where interpretation is needed as to the exact location of boundaries of the Areas of Special Flood Hazard (for example, where there appears to be a conflict between a mapped boundary and actual field conditions) the administrator shall make the necessary interpretation. Any person contesting the location of the boundary shall be given a reasonable opportunity to appeal the interpretation as provided in this Ordinance.
12. All records pertaining to the provisions of this Ordinance shall be maintained in the office of the administrator and shall be open for public inspection.

In Monroe, the Code Enforcement Officer is the person designated as the administrator of the floodplain ordinance. In Loganville, this responsibility falls to the city manager. In Social Circle, the Community Development Director is designated as the administrator of the floodplain ordinance. Walnut Grove defaults to the Walton County Planning Commission for enforcement of the floodplain ordinance.

Natural Hazard: **Flooding**

This role is filled by the Mayor in both Between and Good Hope.

For the substantial damage portion of the flood prevention ordinance, the floodplain administrator will utilize tax assessor's data to determine market value for all damaged structures. Substantial damage will be determined by assessing whether the repairs needed to bring a structure back to pre-damage conditions exceeds 50% of the market value of the structure. If so, then the structure will be determined to be of "substantial damage." This determination will be communicated to the property owners and any appeals will be held in accordance with established appeals procedures for permit applications. Once appeals are resolved, permitting will commence and inspections will occur as normally scheduled. Any technical assistance needed will be requested from the State of Georgia and/or the Federal Emergency Management Agency.

There are three repetitive loss residential properties in Walton County. Two of these properties are in unincorporated Walton County and have a reported repetitive loss of \$81,975. One property is located within the City of Monroe and has a reported repetitive loss of \$22,719. One of the residential properties in unincorporated Walton County has been determined to be a severe repetitive loss property.

Multi-Jurisdictional Considerations

During a large-scale flood event, many portions of Walton County would potentially be impacted by flooding. However, the area's most prone to flooding have historically been those areas located within the 100-year floodplain – particularly those areas along the Alcovy River, Apalachee River, Shoal Creek, Jack's Creek, Big Sandy Creek, Hard Labor Creek, Cornish Creek, Big Flat Creek, Little Flat Creek, Gum Creek, Little Haynes Creek, and their tributaries and distributaries. All of Walton County, including all municipalities, could potentially be impacted.

Hazard Summary

Flooding has the potential to inflict significant damage within Walton County, particularly along the Alcovy River, Apalachee River, Shoal Creek, Jack's Creek, Big Sandy Creek, Hard Labor Creek, Cornish Creek, Big Flat Creek, Little Flat Creek, Gum Creek, Little Haynes Creek, and their tributaries and distributaries. Mitigation of flood damage requires the community to be aware of flood-prone areas, including roads, bridges, and critical facilities. The Walton County HMPC identified flooding as a hazard requiring mitigation measures and identified specific goals, objectives, and action items they deemed necessary to lessen the impact of flooding for their communities.


Flood Events in Walton County since 2020

<u>Location</u>	<u>County/Zone</u>	<u>St.</u>	<u>Date</u>	<u>Time</u>	<u>Type</u>	<u>Mag</u>	<u>Dth</u>	<u>Inj</u>	<u>PrD</u>	<u>CrD</u>
Totals:							0	0	20.00K	0.00K
<u>BOLD SPGS</u>	WALTON CO.	GA	02/06/2020	11:30	Flash Flood		0	0	0.00K	0.00K
<u>GOOD HOPE</u>	WALTON CO.	GA	02/06/2020	14:30	Flash Flood		0	0	0.00K	0.00K
<u>LOGANVILLE</u>	WALTON CO.	GA	02/06/2020	14:30	Flash Flood		0	0	0.00K	0.00K

<u>MT VERNON</u>	WALTON CO.	GA	02/06/2020	14:30	Flash Flood		0	0	0.00K	0.00K
<u>BOLD SPGS</u>	WALTON CO.	GA	02/06/2020	14:30	Flash Flood		0	0	0.00K	0.00K
<u>SPLIT SILK</u>	WALTON CO.	GA	02/06/2020	14:30	Flash Flood		0	0	0.00K	0.00K
<u>CLEATON</u>	WALTON CO.	GA	09/17/2020	06:00	Flash Flood		0	0	20.00K	0.00K
<u>BOLD SPGS</u>	WALTON CO.	GA	09/17/2020	06:00	Flash Flood		0	0	0.00K	0.00K
<u>NICHOLASVILLE</u>	WALTON CO.	GA	01/04/2023	09:30	Flash Flood		0	0	0.00K	0.00K
<u>CLEATON</u>	WALTON CO.	GA	01/04/2023	09:30	Flash Flood		0	0	0.00K	0.00K
<u>GOOD HOPE</u>	WALTON CO.	GA	08/28/2023	05:00	Flash Flood		0	0	0.00K	0.00K
<u>WALKER PARK</u>	WALTON CO.	GA	01/09/2024	09:30	Flash Flood		0	0	0.00K	0.00K
<u>NICHOLASVILLE</u>	WALTON CO.	GA	01/09/2024	09:45	Flash Flood		0	0	0.00K	0.00K


Natural Hazard: **Flooding**


Walton County





Natural Hazard: Flooding


Between




Natural Hazard: Flooding**Good Hope**

Natural Hazard: Flooding**Jersey**

Natural Hazard: Flooding**Loganville**

Natural Hazard: Flooding**Monroe**

Natural Hazard: Flooding**Social Circle**

*Note: All “light blue” shaded areas indicate the extent of the 100-year (or 1% annual) flood risk
All Flood Maps are from the Georgia DFIRM Flood Map Program*

Natural Hazard: **Tornado**

Hazard Description

A tornado is a violently rotating column of air (seen only when containing condensation, dust, or debris) that is in contact with the surface of the ground. Exceptionally large tornadoes may not exhibit the classic “funnel” shape, but may appear as a large, turbulent cloud near the ground or a large rain shaft. Destructive because of strong winds and windborne debris, tornadoes can topple buildings, roll mobile homes, uproot vegetation, and launch objects hundreds of yards.

Most significant tornadoes (excluding some weak tornadoes and waterspouts) stem from the right rear quadrant of large thunderstorm systems where the circulation develops between 15,000 and 30,000 feet. As circulation develops, a funnel cloud, a rotating air column aloft, or tornado descends to the surface. These tornadoes are typically stronger and longer-lived. The weaker, shorter-lived tornadoes can develop along the leading edge of a singular thunderstorm. Although tornadoes can occur in most locations, most of the tornado activity in the United States is in the Midwest and Southeast. Tornadoes can occur anywhere within the State of Georgia.

Enhanced Fujita Scale for Tornadoes		
The Enhanced Fujita Scale (EF), introduced in 2007, provides estimates of tornado strength based on damage surveys. The original scale was developed by Dr. Theodore Fujita and implemented in 1971.		
Wind Speed	EF Scale	Typical Damage
65-85 mph	0	Peels surface off some roofs, some damage to gutters or siding
86-110 mph	1	Roof severely stripped, mobile homes overturned or badly damaged, loss of exterior doors, windows and other glass broken
111-135 mph	2	Roofs torn off well-constructed homes; foundations of frame homes shifted; mobile homes completely destroyed
136-165 mph	3	Entire stories of well-constructed homes destroyed; severe damage to large buildings such as shopping malls
166-200 mph	4	Well-constructed houses and whole-frame homes completely leveled
200+ mph	5	Strong frame houses leveled off foundations and swept away; high-rise buildings have significant structural deformation

Source: International Code Council

In terms of the continuum of area of impact for hazard events, tornadoes are fairly isolated. Typically ranging from a few hundred to one or two miles across, tornadoes affect far less area than larger

Natural Hazard: **Tornado**

meteorological events such as tropical cyclones, winter storms and severe weather events. An exact season does not exist for tornadoes. However, most occur between early spring to mid-summer (February-June). The rate of onset of tornado events is rapid. Typically, the appearance of the first signs of the tornado is the descending funnel cloud. This sign may be only minutes from the peak of the event, giving those in danger minimal sheltering time. However, meteorological warning systems attempt to afford those in danger more time to shelter. The frequency of specific tornado intensities is undetermined because no pattern seems to exist in occurrence. Finally, the duration of tornado events ranges from the few minutes of impact on a certain location to the actual tornado lasting up to a few hours.

Tornadoes are measured after the occurrence using the subjective intensity measures. The Enhanced Fujita Scale describes the damage and then gives estimates of magnitude of peak 3-second gusts in miles per hour.

Hazard Profile

All areas within Walton County are vulnerable to the threat of a tornado. Due to the indiscriminate and unpredictable nature of tornadoes, there is no reliable method to determine where or when a tornado will strike. There have been 8 documented tornadoes in the last 50 years in Walton County. It is likely that other tornadoes have occurred within this timeframe, but available records are limited in nature.

Based on the 50-year information available for Walton County, a tornado occurs every 6.25 years. On an annual basis, Walton County has an 16% chance of being impacted from a tornado event. When only the last twenty years are considered, the likelihood of a tornado affecting Walton County increases slightly to 20% (4 tornadoes since 2005).

Individual tornado events can cause extreme damage to an area. This holds true for Walton County, as well. The costliest and, likely, strongest documented tornado to impact Walton County was a F1 in 1994. This storm caused significant damage between Conyers in Rockdale County and Walnut Grove in Walton County. In total, thirty homes were damaged and six were destroyed from this storm. This storm also injured three people in Walton County. Overall, this storm caused more than \$5 million in damages.

All tornado hazard data included for Walton County is limited to countywide data and is not broken down by jurisdiction.

Assets Exposed to the Hazard


In evaluating assets that are susceptible to tornadoes, the Walton County HMPC determined that all public and private property is threatened by tornadoes, including all critical facilities. This is due to the lack of spatial prejudice of tornadoes.

Estimated Potential Losses

Estimates of damage for the past events of the last 50 years are over \$6.5 million, or \$131,800 annually. However, singular events can cause a significant impact in the amount of losses. Documented damage estimates for tornado events in Walton County have varied wildly depending on what was damaged. According to the National Risk Index, Walton County has an estimated annual loss of over \$3.02 million related to tornado events.

Natural Hazard: **Tornado**

Within the 2024 Walton County HAZUS report, a theoretical tornado path for an EF3 was identified that would inflict maximum damage. HAZUS estimated that this theoretical tornado would cause damage to approximately 835 buildings and result in losses more than \$63 million with the City of Monroe suffering the greatest economic impacts.



Source: 2024 Walton County HAZUS Report


Land Use & Development Trends

Walton County main land use trend related to Tornadoes involves continued population growth, which is occurring in nearly all areas of Walton County.

Multi-Jurisdictional Considerations


All portions of Walton County could potentially be impacted by a tornado due to the indiscriminate nature of tornadic events. Therefore, all mitigation actions identified regarding tornadoes should be pursued on a countywide basis and included all municipalities.

Natural Hazard: Tornado



Source: 2024-2029 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

Natural Hazard: **Tornado**



Source: 2024-2029 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

Hazard Summary

Walton County remains at risk to potential damage from tornadoes, especially considering the average of one tornado every 6.25 years over the last 50 years. Should a tornado strike in densely populated areas of the county, significant damage or loss of life could occur. Due to the destructive power of tornadoes, it is essential that the mitigation measures identified in this plan regarding tornado activity receive full consideration.

Tornado Events in Walton County since 2020

Location	County/Zone	St.	Date	Time	T.Z.	Type	Mag	Dth	Inj	PrD	CrD
GRATIS	WALTON CO.	GA	05/03/2021	11:39	EST-5	Tornado	EF0	0	0	100.00K	0.00K

Natural Hazard: **Drought**

Hazard Description

Drought is a normal, recurrent feature of climate consisting of a deficiency of precipitation over an extended period (usually a season or more). This deficiency results in a water shortage for some social or environmental sector. Drought should be judged relative to some long-term average condition of balance between precipitation and evapotranspiration in a particular area that is considered “normal.” Drought should not be viewed as only a natural hazard because the demand people place on water supply affects perceptions of drought conditions. From limited water supplies in urban areas to insufficient water for farmland, the impacts of drought are vast.


Droughts occur in virtually every climatic zone and on every continent. Because the impacts of drought conditions are largely dependent on the human activity in the area, the spatial extent of droughts can span a few counties to an entire country.

Temporal characteristics of droughts are drastically different from other hazards due to the possibility of extremely lengthy durations as well as a sluggish rate of onset. Drought conditions may endure for years or even decades. This factor implicates drought as having a high potential to cause devastation on a given area. The duration characteristic of droughts is so important that droughts are classified in terms of length of impact. Droughts lasting 1 to 3 months are considered short term, while droughts lasting 4 to 6 months are considered intermediate and droughts lasting longer than 6 months are long term. With the slow rate of onset, most populations have some inkling that drought conditions are increasingly present. However, barring drastic response measures, most only have to adapt to the changing environment.

Seasonality has no general impact on droughts in terms of calendar seasons. However, “wet” and “dry” seasons obviously determine the severity of drought conditions. In other words, areas are less susceptible to drought conditions if the area is experiencing a wet season. The frequency of droughts is undetermined, because the hazard spans such a long period of time. However, climatologists track periods of high and low moisture content similarly to the tracking of cooling and warming periods.

Hazard Profile


The Walton County HMPC reviewed data for the last 50 years regarding drought conditions. Historically, agricultural losses have accounted for the vast amount of losses related to drought conditions. Due to poor record keeping and the unpredictable nature of drought conditions, reliability of historical data for the last 50 years is low. Walton County has been impacted by 11 drought events in the last 25 years, according to data from the National Centers for Environmental Information. This amounts to a 44% chance of a drought for a given year over the last 25 years. The economic impact of these droughts, including crop damage, is not available.



Natural Hazard: Drought

All drought hazard data included for Walton County is limited to countywide data and is not broken down by jurisdiction.

There have been two recent examples of “exceptional” drought events affecting Walton County. These events occurred in 2016 and 2007. Both events reached the D4 (Exceptional Drought) designation, according to data from the United States Drought Monitor. Below are maps of these two events.



Source: USDA Drought Monitor – University of Nebraska-Lincoln

Natural Hazard: **Drought**

Events of this extent can cause water shortages for residential and corporate needs, as well as affecting the ability for firefighting operations to be properly effective. Of particular concern to Walton County is the impact drought can have on wildfire. Drought can exacerbate the impacts of a wildfire by increasing fire load and overall fire danger. Drought conditions of this extent can have devastating effects on the local agricultural industries, which has occurred in previous D4 level droughts.


Assets Exposed to the Hazard

While drought conditions do not typically pose a direct threat to structures, secondary hazards from drought such as increased wildfire threat, does pose a significant threat to all public and private property in Walton County, including all critical facilities. Water resources could also become scarce during a drought, a condition that would potentially affect all Walton County residences and critical facilities.

Estimated Potential Losses

No damage to structures or critical facilities is expected as a direct result of drought conditions. However, crop damage and subsequent losses can be expected to occur because of drought conditions. The degree of losses would depend on the duration of the drought, severity of the drought, temperatures during the drought, season in which the drought occurs, and the specific needs of the involved crops. Water system shortages and need for supply assistance for those systems could also lead to economic losses associated with the drought.

According to the National Risk Index, Walton County has an estimated annual loss of \$50,203 related to drought events. Additionally, according to the 2022 Agriculture Census data, Walton County's market value of products sold was \$37,354,000.



Source: United States Drought Monitor (University of Nebraska-Lincoln)

Natural Hazard: **Drought**

Land Use & Development Trends

As growth continues, drought can become a larger threat for Walton County due to the increased reliance on water infrastructure countywide. This increased pull on these resources in Walton County could quicken or deepen the impacts of a drought for residential, commercial, and industrial areas.

Multi-Jurisdictional Considerations

All portions of Walton County could potentially be impacted by a drought, but agricultural areas of the county are potentially more at risk. Therefore, all mitigation actions identified regarding drought should be pursued on a countywide basis and include all municipalities.

Hazard Summary

Drought conditions can cause significant economic stress on the agriculture and forestry interests of Walton County. The potential negative secondary impacts of drought are numerous. They include increased wildfire threat, decreased water supplies for residential and industrial needs, stream-water quality, and water recreation facilities. The Walton County HMPC recognizes the potential threats drought conditions could have on the community and have identified specific mitigation actions as a result.

Natural Hazard: **Wildfire**

Hazard Description

A wildfire is an uncontained fire that spreads through the environment. Wildfires can consume large areas, including infrastructure, property, and resources. When massive fires, or conflagrations, develop near populated areas, evacuations could possibly ensue. Not only do the flames impact the environment, but the massive volumes of smoke spread by certain atmospheric conditions also impact the health of nearby populations.

Wildfires result from the interaction of three crucial elements: fuel, ignition (heat), and oxygen. Natural and manmade forces cause the three crucial elements to coincide in a manner that produces wildfire events. Typically, fuel consists of natural vegetation. However, as the urban and suburban footprint expands, wildfires may utilize other means of fuel, such as buildings. In terms of ignition or source of heat, the primary source is lightning. However, humans are more responsible for wildfires than lightning. Manmade sources vary from the unintentional, such as fireworks, campfires, or machinery, to intentional arson. With these two elements provided, the wildfires may spread as long as oxygen is present.

Weather is the most variable factor affecting wildfire behavior. Strong winds propel wildfires quickly across most landscapes unless firebreaks are present. Shifting winds create erratic wildfires, which can complicate fire management efforts. Dry conditions provide faster-burning fuels, either making the area more vulnerable to wildfire or increasing the mobility of preexisting wildfires.

Wildfires are notorious for spawning secondary hazards, such as flash flooding and landslides, long after the original fire is extinguished. Both flash flooding and landslides result from fire consuming the natural vegetation that provides precipitation interception and infiltration as well as slope stability.

All of Georgia is prone to wildfire due to the presence of wildland fuels associated with wildfires. Land cover associated with wildland fuels includes coniferous, deciduous, and mixed forest; shrubland; grassland and herbaceous; transitional; and woody and emergent herbaceous wetlands. The spatial extent of wildfire events greatly depends on both the factors driving the fire as well as the efforts of fire management and containment operations.

In terms of seasonality, wildfires can occur during any season of the year. However, drier seasons, which vary within the State of Georgia, are more vulnerable to severe wildfires because of weather patterns and the abundant quick-burning fuels. In terms of rate of onset and duration, wildfires vary depending on the available fuels and weather patterns. Some wildfires can engulf an area in a matter of minutes from the first signs whereas others may be slower burning and moving. The frequency of wildfires is not typically measured because of the high probability of human ignition being statistically unpredictable. Magnitude and intensity are typically only measured by size of the wildfire and locations of burning.

Three classes of fires include understory, crown, and ground fires. Naturally induced wildfires burn at relatively low intensities, consuming grasses, woody shrubs, and dead trees. These understory fires often play an important role in plant reproduction and wildlife habitat renewal and self-extinguish due to low fuel loads or precipitation. Crown fires, which consist of fires consuming entire living trees, are low probability but high consequence events due to the creation of embers that can be spread by the wind. Crown fires typically match perceptions of wildfires. In areas with high concentrations of organic materials in the soil, ground fires may burn, sometimes persisting undetected for long periods until the surface is ignited.

Natural Hazard: **Wildfire**

Hazard Profile

Wildfires pose a serious threat to Walton County. This is a result of the high amount of forestland and vegetation available to fuel potential wildfires, the significant elevation changes within the county, and the high percentage of inaccessible areas. The latter two make wildland firefighting operations significantly more difficult. Also, there is an increasing amount of wildland-urban interface (WUI) in Walton County, which is defined as areas where structures and other human development meets undeveloped wildland properties. 25% of Walton County's acreage has direct WUI exposure. All wildfire hazard data included for Walton County is limited to countywide data and is not broken down by jurisdiction.

Wildfire statistics were not available for the 50-year timeframe at the time of this profile. Georgia Forestry Commission, Walton County had 115 wildfires from 2012 to 2025 that consumed a total of 340.3 acres. This equates to an average of 8.2 wildfires per year and these fires consume an average of 24.31 acres per year. Walton County has a 2.3% daily chance of a wildfire. Historically, debris burning has been the top reason for wildfires in Walton County. In March of 2014, a single large fire burned a total of 27.3 acres – accounting for 8% of all acreage burned in Walton County since 2012. This single fire was the result of a campfire that got out of control. It took approximately three hours for Walton County Fire Department and Georgia Forestry Commission units to get the fire under control.

Assets Exposed to the Hazard

All public and private property located within the Wildland-Urban Interface, including critical infrastructures, are susceptible to impacts from wildfires. Due to the large area of wildland area in Walton County and the large amount of WIU, all public and private property, including critical infrastructures, could be directly or indirectly impacted by the threat of wildfire.

Jurisdiction	Percentage of Area with Direct WUI Exposure
Walton County	29%
Between	36%
Good Hope	30%
Jersey	41%
Loganville	28%
Monroe	28%
Social Circle	22%
Walnut Grove	49%

Estimated Potential Losses


Little information is available regarding damages, in terms of dollars, for wildfire losses in Walton County. According to the 2022 Ag Census by the USDA, Walton County has just over \$37 million in annual agriculture sales. According to the National Risk Index, Walton County has an estimated annual loss of \$19,991 related to wildfire events.

Natural Hazard: **Wildfire**

Land Use & Development Trends

With the continued increase in population, Wildland-Urban Interface (WUI) is increasing in Walton County. The WUI creates areas where fire can easily move from wildland areas into developed areas and threaten structures and human life. The expansion of the WUI in Walton County complicated wildland fire management operations and planning initiatives. This development trend is expected to continue in the future.

Georgia Wildfire Exposure



Source: Southern Group of State Foresters Wildfire Risk Assessment Portal

Multi-Jurisdictional Considerations


All portions of Walton County, including all municipalities, could potentially be impacted by a wildfire due to the large amount of Wildland-Urban Interface, but the less developed areas of the county are more vulnerable. Therefore, all mitigation actions identified regarding wildfires should be pursued on a countywide basis and include all municipalities.

Hazard Summary

Wildfire is a significant threat to Walton County due to the increased amount of Wildland-Urban Interface. The increasing amount of area where structures and other human development meets undeveloped, wildland property is of concern. The mitigation measures identified in this plan should be aggressively pursued based on the high frequency of this hazard and the ability for wildfires to inflict devastation anywhere in Walton County.


Natural Hazard: **Wildfire**

Walton County Wildfire Hazard Potential




Natural Hazard: **Wildfire**

Walton County Functional WUI




Natural Hazard: **Wildfire**

Walton County Suppression Difficulty Index




Natural Hazard: **Wildfire**

Monroe Wildfire Hazard Potential




Natural Hazard: **Wildfire**


Monroe Functional WUI



Natural Hazard: **Wildfire**


Monroe Suppression Difficulty Index



Natural Hazard: **Wildfire***Between Wildfire Hazard Potential*


Natural Hazard: **Wildfire**

Between Functional WUI




Natural Hazard: **Wildfire**


Between Suppression Difficulty Index



Natural Hazard: **Wildfire**


Good Hope Wildfire Hazard Potential




Natural Hazard: **Wildfire***Good Hope Functional WUI*

Natural Hazard: **Wildfire**


Good Hope Suppression Difficulty Index



Natural Hazard: **Wildfire***Jersey Wildfire Hazard Potential*


Natural Hazard: **Wildfire**

Jersey Functional WUI




Natural Hazard: **Wildfire**

Jersey Suppression Difficulty Index




Natural Hazard: **Wildfire**

Loganville Wildfire Hazard Potential




Natural Hazard: **Wildfire**

Loganville Functional WUI




Natural Hazard: **Wildfire**

Loganville Suppression Difficulty Index





Social Circle Wildfire Hazard Potential



Natural Hazard: **Wildfire**


Social Circle Functional WUI



Natural Hazard: **Wildfire***Social Circle Suppression Difficulty Index*


Natural Hazard: **Wildfire**


Walnut Grove Wildfire Hazard Potential



Natural Hazard: **Wildfire**

Walnut Grove Functional WUI



Natural Hazard: **Wildfire***Walnut Grove Suppression Difficulty Index*

*All maps in this section are from the
Southern Group of State Foresters Wildfire Risk Assessment Portal*

Natural Hazard: **Geologic**

Hazard Description

Geologic hazards for this plan include both earthquakes and sinkholes. Earthquakes are generally defined as the sudden motion or trembling of the Earth's surface caused by an abrupt release of slowly accumulated strain. This release typically manifests on the surface as ground shaking, surface faulting, tectonic uplifting and subsidence, or ground failures, and tsunamis. In the United States, earthquake activity east of the Rocky Mountains is relatively low compared to the Western states because it is away from active plate boundaries and the plate interior strain rates are known to be very low.

The physical property of earthquakes that causes most of the damage within the United States is ground shaking. The vibrations from the seismic waves that propagate outward from the epicenter may cause failure in structures not adequately designed to withstand earthquakes. Because the seismic waves have different frequencies of vibration, the waves disseminate differently through sub-surface materials. For example, high frequency compression and shear waves arrive first, whereas lower frequency Rayleigh and love waves arrive later. Not only are the speeds varied between seismic waves, but also the types of movement. The surface vibration may be horizontal, vertical, or a combination of the two, which causes a wider array of structures to collapse.

Another manifestation of earthquakes is surface faulting. This phenomenon is defined as the offset or tearing of the earth's surface by a differential movement across a fault. Structures built across active faults tend to sustain damage regularly. There are no active faults within or near Georgia. Distinct inactive faults are known within the state north of the Columbus to Macon to Augusta fall line and running generally northeast-southwest.

The third earthquake phenomenon that causes damage is tectonic uplift and subsidence. Tectonic uplift can cause shallowing of the harbors and waterways while tectonic subsidence can cause permanent or intermittent inundation. Due to the association of tectonic uplift and subsidence with active faults, Georgia is not at risk to these phenomena.


The fourth earthquake damage-causing phenomena are earthquake-induced ground failures, including liquefaction and landslides. During an earthquake, the areas that are rich in sand and silt have groundwater within 30 feet of the surface temporarily behave as viscous fluids during strong ground shaking. Structures built on these materials can settle, topple, or collapse as the ground "liquefies" beneath it. Landslides can also form when earthquake shaking or seismic activity dislodges rock and debris on steep slopes, triggering rock falls, avalanches, and slides.

Also, unstable, or nearly unstable, slopes consisting of clay soils may lose shear strength when disturbed by ground shaking and fail, resulting in a landslide. Georgia is at very low risk of seismic induced liquefaction or landslides. The last of the earthquake-induced phenomena are tsunamis, which are large, gravity-driven waves triggered by the sudden displacement of a large volume of water. The waves produced travel in all directions from the origin at speeds of up to 600 miles per hour. In deep water, tsunamis normally have small wave heights. However, as the waves reach shallower water near land, the wave speed diminishes, and the amplitude drastically increases. Upon impact with a shoreline, the waves can inundate land rapidly, engulfing everything in its path. Successive wave crests follow, typically arriving minutes to hours later, frequently with later arrivals being more dominant. Frequently, the first tsunami waves are downward, causing dramatic exposure of the beach. Because of this, people are often killed trying to collect newly exposed seashells when the positive waves then arrive.

Natural Hazard: **Geologic**

Although large tsunamis are rare in the eastern coast of the US, the possibility of such events occurring anywhere along the Atlantic and Gulf coast exists.

Sinkholes are generally associated with limestone areas where underground water has dissolved rock underneath the surface of the earth and created a chasm that is then unable to support the ground above it, which then collapses. Little information is available on the threat of sinkholes outside of the north Georgia mountains.



Two-percent probability of exceedance in 50 years map of 0.2 second spectral response acceleration

Source: 2019-2024 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

Hazard Profile


Walton County is not one of the 37 Georgia counties with the highest earthquake risk, according to Georgia Emergency Management Agency. In reviewing data of the last 50 years, no earthquakes have originated from within Walton County. The earthquake that originated the closest to Walton County occurred on November 7, 1979 and originated in Gwinnett County 5 km south-southeast of Dacula, GA and measured 2.2 on the Richter Scale. Overall, 38 earthquakes have originated within 75 kilometers of Monroe, GA in the last 50 years. The strongest earthquake to occur within the 75-kilometer radius was a 2.6 that occurred 13km south-southeast of Eatonton, GA in 2015. Walton County averages an earthquake every 1.32 years occurring within 75 kilometers of Monroe, GA. This equates to a 76% chance of an earthquake occurring within 75 kilometers of Monroe, GA in any given year. The most recent earthquake to occur within this area occurred on June 13, 2024 near Buford, GA. According to the National Risk Index, Walton County has a 0.056% annual chance of an earthquake. Historically, the 1886 Charleston, SC earthquake, estimated to be between 6.6 and 7.3 on the modern Richter Scale, likely caused impacts to Walton County. Although no historical records exist exhibiting any damages, Walton County was estimated to be in a level VI area of the Modified Mercalli Intensity scale for this event. This would indicate strong shaking felt by everyone inside and outside at the time of the event and characterized by broken windows, movement of heavy furniture, and slight to moderate damage for poorly built buildings. Even with this low number of occurrences, it was determined that if earthquakes occur within or close to the jurisdiction of Walton County, significant damage could occur. Therefore, the Walton County HMPC has determined the threat of earthquakes to be higher than the statistics would indicate. All earthquake hazard data included for Walton County is limited to countywide data and is not broken down by jurisdiction.

Natural Hazard: **Geologic**

Instrumental Intensity	Acceleration (%g)	Velocity (cm/s)	Perceived Shaking	Potential Damage
I	< 0.17	< 0.1	Not Felt	None
II-III	0.17 - 1.4	0.1 - 1.1	Weak	None
IV	1.4 - 3.9	1.1 - 3.4	Light	None
V	3.9 - 9.2	3.4 - 8.1	Moderate	Very light
VI	9.2 - 18	8.1 - 16	Strong	Light
VII	18 - 34	16 - 31	Very Strong	Moderate
VIII	34 - 65	31 - 60	Severe	Moderate to Heavy
IX	65 - 124	60 - 116	Violent	Heavy
X+	> 124	> 116	Extreme	Very Heavy

Assets Exposed to the Hazard

The Walton County HMPC determined that all critical facilities and all public and private property within Walton County are susceptible to the impacts of an earthquake due to the lower building codes with regards to earthquakes when compared to other parts of the country. This includes all municipalities.



Source: United States Geological Survey (USGS) Earthquake Hazards Program


Natural Hazard: **Geologic**

Estimated Potential Losses

Little information is available regarding damages, in terms of dollars, for earthquake losses in Walton County. According to the National Risk Index, Walton County has an estimated annual loss of \$724,684 related to earthquake events.

Land Use and Development Trends

Walton County currently has no land use trends related to earthquakes.



Source: 2019-2024 State of Georgia Hazard Mitigation Strategy and Enhanced Plan

Natural Hazard: **Geologic**

Multi-Jurisdictional Considerations

All of Walton County, including all municipalities, potentially could be threatened by earthquakes. As such, all earthquake mitigation actions should be pursued on a countywide basis and include all municipalities.

Hazard Summary

Even with the infrequency of earthquake impacts in Walton County, the potential losses and impacts associated with the event would severely damage the infrastructure and economic viability of the County and all municipalities. Secondary impacts, such as landslides during or after an earthquake, are also of a great concern and are detailed in a separate section of this plan. The mitigation measures identified in this plan should be pursued based on the high impact potential of this hazard and the ability for earthquakes to inflict widespread devastation anywhere in Walton County.

Natural Hazard: Tropical Cyclone

Hazard Description

The National Weather Service describes tropical cyclones systems in the Atlantic Basin, including the Gulf of Mexico and Caribbean Sea, into four types based on strength.

Tropical Disturbance: A discrete tropical weather system of apparently organized thunderstorms – generally 100 to 300 nautical miles in diameter – originating in the tropics or subtropics, and maintaining its identity for 24 hours or more.

Tropical Depression: An organized system of clouds and thunderstorms with a defined circulation and maximum sustained winds of 38 mph (33 knots) or less.

Tropical Storm: An organized system of strong thunderstorms with a defined circulation and maximum sustained winds of 39 mph to 73 mph (34-63 knots).

Hurricane: An intense tropical weather system with a well-defined circulation, producing maximum sustained winds of 74 mph (64 knots) or greater. Hurricane intensity is classified into five categories using the Saffir-Simpson Hurricane scale. Winds in a hurricane range from 74-95 mph for a Category 1 hurricane to greater than 156 mph for a Category 5 hurricane.

Saffir-Simpson Scale for Hurricane Classification				
Strength	Wind Speed (Kts)	Wind Speed (MPH)	Pressure (Millibars)	Pressure
Category 1	64- 82 kts	74- 95 mph	>980 mb	28.94 "Hg
Category 2	83- 95 kts	96-110 mph	965-979 mb	28.50-28.91 "Hg
Category 3	96-113 kts	111-130 mph	945-964 mb	27.91-28.47 "Hg
Category 4	114-135 kts	131-155 mph	920-944 mb	27.17-27.88 "Hg
Category 5	>135 kts	>155 mph	919 mb	27.16 "Hg
Tropical Cyclone Classification				
Tropical Depression		20-34kts		
Tropical Storm		35-63kts		
Hurricane		64+kts or 74+mph		

Tropical cyclones can cause catastrophic damage to coastlines and areas several hundred miles inland. Tropical cyclones can produce sustained high winds and spawn tornadoes and microbursts. Additionally, tropical cyclones can create storm surges along the coast and cause extensive damage from heavy rainfall. Floods and flying debris from the excessive winds are often the deadly and destructive results of these weather events.


Slow moving tropical cyclones traveling into mountainous regions tend to produce especially heavy rain. Excessive rain can trigger landslides or mudslides. Flash flooding can also occur due to intense rainfall. Each of these hazards present unique characteristics and challenges; therefore, the following have been separated and analyzed as individual hazards: Tropical cyclones, Thunderstorms, Tornadoes, and Flooding. This section will focus on the direct effects of tropical cyclones.

Natural Hazard: Tropical Cyclone

Hazard Profile

Tropical cyclones have directly impacted Walton County on a frequent basis over the last 50 years. According to the National Centers for Environmental Information, there have been 17 documented impacts from Tropical Cyclones in Walton County over the last 25 years, with Hurricane Helene in 2024 being the most recent. This equates to an 68% chance of a tropical cyclone impacting Walton County in any given year. The more likely impacts of a tropical cyclone on Walton County would be secondary impacts, such as flooding, tornadoes, and severe thunderstorms.

Only three tropical cyclones – Tropical Storm Claudette in 2021, Tropical Storm Jerry in 1995, and Tropical Storm Beryl in 1994 – have had a track that directly dissected Walton County in the last 50 years. All tropical cyclone hazard data included for Walton County is limited to countywide data and is not broken down by jurisdiction. In 2017, Hurricane Irma dropped 3-3.5 inches of rain on Walton County and wind gusts up to 40 mph were reported in the county. In 2024, Hurricane Helene dropped 4-8 inches of rain across Walton County with areas of western Walton County seeing the highest rainfall amounts.




Source: NOAA Office for Coastal Management

Assets Exposed to the Hazard

The Walton County HMPC determined that all critical facilities and all public and private property within Walton County are susceptible to the direct and indirect impacts of a tropical cyclone. This includes all municipalities.

Natural Hazard: Tropical Cyclone



Source: National Weather Service

Estimated Potential Losses

Little information is available regarding damages, in terms of dollars, is available for tropical cyclone losses in Walton County. Most losses for these events have been labeled under other impacts, such as tornadoes and flooding. According to the National Risk Index, Walton County has an estimated annual loss of \$567,966 related to hurricane events.

According to the 2024 Walton County HAZUS Report, a 1% annual risk tropical cyclone event would produce winds up to 66 mph in Walton County, which would be a Tropical Storm. A storm of this magnitude would create more than \$3.9 million in damages, which equates to a 0.06% loss ratio. A storm of this magnitude would create over 12,000 tons of debris.



Land Use and Development Trends

Walton County currently has no land use trends related to Tropical Cyclones beyond continued population growth, which is happening in most parts of Walton County and particularly near the Gwinnett County line.


Multi-Jurisdictional Considerations

All of Walton County, including all municipalities, could potentially be threatened by tropical cyclones. As such, all tropical cyclone mitigation actions should be pursued on a countywide basis and include all municipalities.

Natural Hazard: Tropical Cyclone




Natural Hazard: Tropical Cyclone



Source: 2019-2024 Georgia Hazard Mitigation Strategy and Enhanced Plan



Natural Hazard: Tropical Cyclone



Source: 2024 Walton County HAZUS Report

Hazard Summary

Even with the relative infrequency of tropical cyclone impacts in Walton County in the recent past, the potential losses and impacts associated with the event would severely damage the infrastructure and economic viability of Walton County and all municipalities. The mitigation measures identified in this plan for tropical cyclones should be pursued based on the high impact potential of this hazard and the ability for tropical cyclones to inflict widespread devastation anywhere in Walton County.

Technological Hazard: **Hazardous Materials**

Hazard Description


Hazardous materials, or hazmat, refers to any materials that may pose a real hazard to human health and/or the environment because of its quantity, concentration, and/or physical or chemical characteristics. Hazardous materials include explosives, flammables, combustibles, oxidizers, toxic materials, radioactive substances, and corrosives. Specific federal and state regulations exist regarding the transport and storage of hazardous materials.

A hazardous materials spill or release occurs when a hazardous material gets into the environment in an uncontrolled fashion. Response to a hazmat spill or release depends greatly on the type of material involved and the subsequent physical and chemical characteristics. Major sources of hazardous materials spills include transportation accidents on roadways and railways, pipeline breaches, and spills into rivers and creeks. Jurisdictions with facilities that produce, process, or store hazardous materials are at risk, as are facilities that treat or dispose of hazardous materials.

Hazard Profile

Data from the Pipeline and Hazardous Materials Safety Administration was reviewed regarding hazardous materials spill history in Walton County. Data is available from 1989 to 2024 and all available data was reviewed. There were 11 PHMSA reported hazardous materials spills or releases in Walton County over a 35-year period. It is anticipated that many more hazardous materials incidents have occurred over the last 35 years but have not been reported. According to the NRC data, Walton County averages a hazardous materials incident of a reportable amount every 3.2 years. This equates to a 31.4% chance of a hazardous materials spill of a reportable amount each year.

According to the Georgia Department of Natural Resources Environmental Protection Division, there is one Hazardous Site Inventory location in Walton County. This site is the Walton County landfill, which is located northwest of the City of Monroe. Hazardous Site Inventory locations are areas where a known or suspected release of a regulated substance has occurred that was above a reportable quantity and which has you to properly show that state clean-up standards have been met.



Source: Georgia Department of Natural Resources Environmental Protection Division

Technological Hazard: **Hazardous Materials**

Hazardous materials releases can also be the result of railway or fixed facility incidents. Fixed facilities continue to be an increasing concern due to Walton County's growing industrial footprint. Hazardous materials spills during transport is of particular concern to Walton County, especially considering the location of Interstate 20 dissecting Walton County from west to east. In particular, the Walton County Hazard Mitigation Plan Update Committee expressed concern about a radiological/nuclear incident along Interstate 20 as this is the route for WIPP shipments leaving the Savannah River Site and Plant Vogtle on their way to New Mexico. Walton County has participated in multiple exercises regarding an incident with one of the WIPP shipments passing through the jurisdiction. Additionally, there is significant concern about incident along US Highway 78, which connects eastern portions of Atlanta and Gwinnett County to the City of Athens.

Additionally, Walton County is home to two railroad lines. One line passes through the far southern corner of Walton County, including the City of Social Circle. This line is owned and operated by CSX Transportation. A second line extends from Social Circle to Monroe. This line is owned by the Great Walton Railroad. The CSX line serves as a major connector between Atlanta and Augusta.

Of concern to the Walton County Hazard Mitigation Committee is the exposure of water sources to potential hazardous materials incidents. A hazardous materials incident at or near drinking water sources could have devastating effects on a large population in Walton County. Walton County is home to the Hard Labor Creek Regional Reservoir, which supplies water to multiple counties. These locations being in other jurisdictions certainly heightens concerns within Walton County.

Assets Exposed to Hazard

The environment is particularly vulnerable to the threat posed by hazardous materials. Waterways are at a high risk for contamination from hazardous materials. Water contamination is of concern to the Walton County HMPC. Public and private property located near fixed hazardous materials facilities are also a greater risk than the general population of Walton County. Water contamination from a hazardous materials release is of particular concern to the Walton County Hazard Mitigation Planning Committee.

Estimated Potential Losses

Estimation of potential losses is difficult regarding hazardous materials due to the vast array of potential types of hazardous materials that could be involved in the incident and unknown costs regarding environmental damages. No recorded information was found regarding the losses associated with hazardous materials incidents in Walton County. However, a hazardous materials release, whether in transport or at a fixed facility, would incur significant costs regarding emergency response, potential road closures, evacuations, watershed protection measures, expended man-hours, and cleanup materials, equipment, and personnel.

Land Use and Development Trends

Walton County currently has no land use trends related to Hazardous Materials beyond continued population growth, which is occurring in all areas of Walton County.

Multi-Jurisdictional Considerations

All of Walton County, including all municipalities, are vulnerable to both fixed facility and transportation-related hazardous materials releases. However, areas along the Interstate 20 and US Highway 78 corridors, including the municipalities of Social Circle, Loganville, and Monroe, are of particular concern.

Technological Hazard: Hazardous Materials*Hazard Summary*

Hazardous materials incidents pose a significant threat to the citizens, infrastructure, and critical facilities of Walton County. Unknown quantities of hazardous materials are transported daily through Walton County and all municipalities. These materials are often transported via highways. Water contamination because of a hazardous materials spill is of significant concern to the Walton County HMPC. As a result of the threat posed by hazardous materials, the Walton County HMPC has identified mitigation actions directly related to this threat.

Technological Hazard: **Dam Failure**

Hazard Description

Georgia law defines a dam as any artificial barrier, which impounds or diverts water, is 25 feet or more in height from the natural bed of a stream or has an impounding capacity at maximum water storage evaluation of 100 acre-feet or more. Dams are generally constructed to provide a ready supply of water for drinking, irrigation, recreation, and other purposes. Dams can be constructed from earth, rock, masonry, concrete or any combination of these materials.

Dam failure is a term used to describe a significant breach of a dam and the subsequent loss of contained water. Dam failure can cause significant damages downstream to structures, roads, utilities, and crops. Dam failure can also put human and animal lives at risk. National statistics indicate that one-third of all dam failures in the United States are caused by overtopping due to inadequate spillway design, debris blocking spillways, or settlement of the dam crest. Another third of all US dam failures are the result of foundation defects, including settlement and slope instability.

Hazard Profile

There are 3 category I and 27 category II dams located within Walton County. Category I dams are those that would pose a possible threat to human life if a failure were to occur. All category I dams must be inspected annually according to Georgia's Safe Dams Act.

The threat of a dam failure in Walton County could potentially lead to downstream flooding. This downstream flooding would have many of the same hazards as a flood event, but with the onset of such an event being much quicker than in a typical flood event.

The dam of greatest concern in Walton County is the 97-foot Hard Labor Creek Reservoir Dam located north of North High Shoals. This dam, which holds back over 76,000 acre-feet of water, could have significant downstream impacts if a breach were to occur. In particular, the water from this dam could flood several residences on Browning Shoals Road with little to no warning. A breach at this location could also have devastating impacts on Hard Labor Creek State Park in Morgan County.

Assets Exposed to Hazard

To evaluate the assets that would potentially be impacted by a dam failure, the Walton County HMPC attempted to identify known structures within, or close to, the 100-year floodplain. All municipalities could be exposed to the hazards of other dams or face secondary hazards from the dams.

Estimated Potential Losses

Loss estimations are not applicable since it is not known which dam will fail and how significant of failure will occur.

Land Use and Development Trends


Walton County participates in the National Flood Insurance Program (NFIP) and follows the program's guidelines to ensure future development is carried out in the best interests of the public. Walton County (CID No. 130185C) first entered the NFIP on February 16, 1990. According to the NFIP guidelines, the County has executed a Flood Damage Prevention Ordinance. This ordinance attempts to minimize the loss of human life and health as well as minimize public and private property losses due to flooding. The ordinance requires any potential flood damage be evaluated at the time of initial construction and that

Technological Hazard: **Dam Failure**

certain uses be restricted or prohibited based on this evaluation. The ordinance also requires that potential homebuyers be notified that a property is located in a flood area. In addition, all construction must adhere to the Georgia State Minimum Standard Codes and the International Building Codes of 2018.

Multi-Jurisdictional Considerations

During a dam failure event, many portions of Walton County would potentially be impacted by flooding. However, the area's most prone to flooding have historically been those areas located within the 100-year floodplain and downstream from dams.



Source: National Inventory of Dams – US Army Corps of Engineers

Hazard Summary

Dam failure poses a threat to Walton County and its citizens, infrastructure, and critical facilities. A dam failure could prove catastrophic for areas downstream of the dam, particularly if the failure were to occur at any of the Category I dams located in Walton County. As a result, mitigation efforts for dam failure should be focused in this potentially affected area.

Technological Hazard: **Transportation Incident**

Hazard Description

There are many secondary hazards that could be associated with transportation incidents. Injuries or deaths can occur as a result of the impact of a transportation accident, by a hazardous materials release because of a transportation incident, or by other related transportation hazards. Transportation can occur via roadways, highways, interstates, railways, air, or navigable waterways. Each transportation type poses their own unique hazard issues and consequences.

Roadway hazards are most likely to be caused by a motor vehicle accident involving one or more cars, trucks, vans, or transport vehicles. These incidents can have injuries because of the impact of the MVA or a hazardous materials release into the local environment, including waterways. Railway incidents pose many of the same dangers as motor vehicle accidents. However, the threat of a hazardous materials release is greatly increased when railway transportation incidents are considered.

Air accidents can include commercial airplanes, private airplanes, hot air balloons, helicopters, or other forms of air travel. Each of these incidents can cause a significant threat to human life as well as posing a hazardous material threat due to the cargo being transported or the fuel being used. Navigable waterway incidents can create formidable incidents for response organizations. Because of the waterway, technical expertise is needed to carry out rescue operations, especially in swift-moving waterways. Also, any incident in a waterway is likely to have environmental impacts.

Hazard Profile

Transportation incidents are of a significant concern in Walton County. Passing through Walton County are Interstate 20, US Highways 78 and 278, and Georgia Highways 10, 11, 12, 20, 81, 83, 138, and 186. Interstate 20 and US Highways 78 and 278 is of particular concern. US Highway 78 serves as a major connection between Atlanta and Athens. Additionally, Interstate 20 connects Atlanta to Augusta and, eventually, Interstate 95. This increases the risk to Walton County of a transportation incident, especially from individuals who are unfamiliar with the area.

Assets Exposed to Hazard

All assets and critical facilities located along or near any transportation route could potentially be impacted by a transportation incident. Areas within Walton County that are not located along or near a transportation route could still face residual impacts.

Estimated Potential Losses

Estimated potential losses cannot be anticipated with this event due to the vast number of differing scenarios regarding transportation incidents.

Land Use and Development Trends

Walton County currently has no land use trends related to Transportation Incidents beyond an increase in overall population which, in turn, increases the likelihood and potential impact of a transportation incident. Population growth in Walton County has occurred throughout the county. However, for transportation incidents, areas along US Highways 78 and Interstate 20 are of greatest concern. This includes the Cities of Loganville, Monroe, and Social Circle.

Technological Hazard: Transportation Incident*Multi-Jurisdictional Considerations*

Walton County as well as all municipalities could potentially be impacted by a transportation incident. However, for transportation incidents, areas along US Highways 78 and Interstate 20 are of greatest concern. This includes the Cities of Loganville, Monroe, and Social Circle..

Hazard Summary

The Walton County HMPC has determined that transportation incidents pose a high risk to their jurisdictions due to the unpredictable nature and likelihood of the incident. As a result, the Walton County HMPC has developed mitigation strategies and actions with transportation incidents in mind.

Technological Hazard: **Terrorism**

Hazard Description

The Federal Bureau of Investigation (FBI) defines terrorism as violent acts or acts dangerous to human life that violate federal or state law, appear to be intended to intimidate or coerce a civilian population, affect the conduct of a government by mass destruction, assassination, or kidnapping, and is calculated to influence or affect the conduct of a government by intimidation or retaliate against government conduct. Terrorism is usually referenced as being premeditated and politically motivated.

Terrorist acts are, by their very nature, designed and carried out with the intention of inflicting mass casualties and extensive property damage. When an act of terrorism is carried out in a jurisdiction, it will likely be necessary to implement multiple aspects of the emergency management system and summon additional resources from local, state, and federal partners.

Terrorism is generally divided into two types: domestic terrorism and international terrorism. Domestic terrorism is defined as terroristic acts focused on facilities and populations without foreign direction. International terrorism involves activities that are foreign-based and/or sponsored by organizations outside of the United States.

Terrorists often use threats to create fear among the public, to convince citizens that government is powerless to prevent terrorism and to get immediate publicity for their causes. Weapons of Mass Destruction (WMDs), including incendiary, explosive, chemical, biological, radiological, and nuclear agents, have the capability to cause death or serious bodily injury to a significant number of people, thus posing the threat of a catastrophic incident. Terrorism can also include arson, agro-terrorism, armed attack, intentional hazardous materials release, water or food contamination, and attacks on infrastructure and electronic information systems.

Hazard Profile

Terrorism targets have historically been facilities that make a large economic or social impact on the targeted government or jurisdiction. In Walton County, all critical facilities could be potential targets. Terrorism includes a multitude of potential approaches, including agro-terrorism, which is terrorism targeted toward agriculture. Due to the high economic impact (over \$37 million in annual agriculture-related sales) of agriculture in Walton County, agro-terrorism could be of particular concern. Additionally, a terrorist contamination of the water sources is of concern.

Within Walton County, there are many areas that could be viewed as potential targets for terrorism due to their economic impact on the area. This includes tourist-friendly areas throughout Walton County.

While active shooter situations are not always classified as terrorism, for this plan, the Walton County HMPC has chosen to classify them as such. Active shooter situations can occur in any location, including businesses, schools, government buildings, and public spaces. Schools are seen as particularly vulnerable to these types of situations due to the high publicity of recent active shooter events. The Walton County HMPC spent considerable time discussing the active shooter event that occurred at Apalachee High School in Barrow County on September 4, 2024. Walton County provided considerable resources in Support of Barrow County's response to this event. In this event, 4 people were killed and 11 total people were shot by a student on campus at Apalachee High School. This incident heightened awareness throughout Walton County regarding how such an incident would impact the county. It was determined

Technological Hazard: **Terrorism**

that considerable resources would be needed for a response and recovery for this type of situation. While active shooter events and other acts of terrorism occur worldwide, they have low probability for Walton County but would have devastating impacts if they were to occur. To help mitigate some of these impacts, Walton County has exercised an active shooter response in the past to better prepare for any such event.

Assets Exposed to the Hazard

Due to the unpredictable nature of terrorism, all public and private structures are threatened by the terrorism hazard. This includes all critical facilities.

Estimated Potential Losses

Losses due to terrorism are difficult to estimate due to the unpredictable nature of terrorism. The type of terrorist act carried out, location of the act, and the impact of the act would all affect the potential losses. Please see the critical facilities information for estimated potential losses for each critical facility.

Land Use and Development Trends

Walton County currently has no land use trends related to Terrorism.

Multi-Jurisdictional Considerations

All of Walton County, including all municipalities, are vulnerable to potential acts of terrorism. However, critical facilities and their surrounding areas are considered to be at the greatest risk.

Hazard Summary

Terrorism, while a low-probability hazard, would have devastating effects on Walton County and all municipalities. These impacts would be immediate and long-lasting and could be potentially economically crippling to Walton County and surrounding communities.

Technological Hazard: Critical Infrastructure Failure


Hazard Description

Infrastructures are particularly vulnerable to both natural and technological hazards. These include electrical utilities, water utilities, gas pipelines, fuel supplies, and other infrastructures that supply vital supplies and services to the community. While an infrastructure failure would most likely be a secondary hazard of one of the other hazards identified in this plan, an infrastructure failure could be a solo incident itself.

A lack of connection with outside sources could lead to public panic, poor emergency response capabilities, and other domino hazards. These events pose a significant threat to many jurisdictions.

Hazard Profile

In case of any failure of a utility infrastructure, general difficulties would be exacerbated for both emergency responders and for the public. The reliance on wireless communications, particularly for the public safety sector, increases the vulnerability of Walton County's emergency response agencies to a communications failure. A failure in the communications sector could have significant impacts to Walton County's radio system, telephone systems, and internet infrastructure. Each of these would be devastating to both public safety and the general public.



Source: National Pipeline Mapping System

Technological Hazard: **Critical Infrastructure Failure**

Additionally, a utility infrastructure failure is also of significant concern to the Walton County Hazard Mitigation Planning Committee. This includes water, power, and natural gas utility failures. This type of failure would have significant impacts to the citizens of Walton County. There are two gas transmission lines that pass through Walton County that are of particular concern. One line dissects Walton County from southwest to northeast and could impact Walnut Grove and/or Monroe. A second line connects to this line northeast of the City of Monroe and travels to the northwest towards Gwinnett County.

Assets Exposed to Hazard

All assets and critical facilities within Walton County could potentially be impacted by an infrastructure failure.

Estimated Potential Losses

Estimated potential losses cannot be anticipated with this event due to the vast number of differing scenarios regarding utility failure.

Land Use and Development Trends

Walton County currently has no land use trends related to infrastructure failures beyond continued population growth and an ever-increasing industrial footprint.

Multi-Jurisdictional Considerations

All areas of Walton County could potentially be impacted by an infrastructure failure.

Hazard Summary

The Walton County HMPC has determined that utility failures pose a high risk to their jurisdictions due to the unpredictable nature of the incident. As a result, the Walton County HMPC has developed mitigation strategies and actions with infrastructure failures in mind.

Technological Hazard: **Civil Unrest**

Hazard Description

Civil Unrest has been evident in society from the earliest recordings. Most civil unrest disturbances throughout history have been directly related to political or social issues. In recent years, most of the publicized disturbances have been protests. Some of the protests have devolved into more violent situations. Marches and protests for or against certain causes are common near prominent locations and government buildings. On rare occasions, these may develop into civil unrest situations that cause damage to public and private property.

Hazard Profile

Civil unrest could occur at any location within Walton County. Areas most likely to be subjected to civil unrest are the areas that most likely to be the site of protests or marches. This includes government buildings, government complexes, and prominent locations throughout Walton County. This includes all municipalities.

In Walton County, concerns exist of how civil unrest situations in other jurisdictions, such as Gwinnett County, could impact Walton County. Walton County serves as a primary transportation route for people entering southern portions of Gwinnett County from the Athens area. Additionally, the City of Loganville has jurisdictional areas in both Walton and Gwinnett Counties. In the case of a Civil Unrest situation, there would likely be a considerable influx of people traversing Walton County to access Gwinnett County or even Atlanta or Athens.

Assets Exposed to the Hazard

Due to the unpredictable nature of civil unrest, all public and private structures are threatened by the civil unrest hazard. This includes all critical facilities. If unrest in Gwinnett County were to spill over into Walton County, areas along US Highway 78, such as Loganville, Between, and Monroe, along with areas in western Walton County would be the most likely to see impacts.

Estimated Potential Losses

Losses due to civil unrest are difficult to estimate due to the unpredictable nature of civil unrest incidents. The location, duration, and level of unrest would all affect the potential losses.

Land Use and Development Trends

Walton County currently has no land use trends related to civil unrest.

Multi-Jurisdictional Considerations

All of Walton County, including all municipalities, are vulnerable to potential acts of civil unrest. However, critical facilities and their surrounding areas are considered to be at the greatest risk.

Hazard Summary

Civil unrest, while a low-probability hazard, could have devastating effects on Walton County and all municipalities. These impacts would be immediate and long-lasting and could be potentially economically crippling to Walton County and surrounding communities.

Technological Hazard: **Emergent Infectious Diseases**

Hazard Description

Microorganisms, such as bacteria, viruses, parasites, fungi, or prions, surround us within the environment. They can even be found within our own bodies. Most microorganisms are completely harmless, and many are actually beneficial. However, some of these organisms are pathogenic, meaning they cause or can cause disease. Infectious diseases are caused by these pathogenic organisms and are communicable – meaning they can be spread from person to person either directly or indirectly. Direct transmission of the disease occurs through actual physical contact with an infected person or their bodily fluids. Indirect transmission of a disease occurs when an infected person contaminates a surface by sneezing, coughing, etc., and a non-infected person comes into contact with that infected surface. Another means of indirect transmission includes vectors, such as mosquitos, flies, mites, ticks, fleas, rodents, or dogs, which may carry the pathogenic microorganism and transmit it to people via a bite. Infectious diseases can also impact animal populations, particularly livestock and other farm animals. Even though these diseases may not directly affect humans, the economic impact of these diseases can be just as harmful, if not more so, to the community.

Infectious diseases can occur as primary events or they may occur as a cascading result of another disaster, such as a tornado, flood, or winter weather. Infectious diseases can vary greatly in severity and magnitude. According to the World Health Organization, infectious diseases account for three of the ten leading causes of death worldwide – HIV/AIDS, lower respiratory infections, and diarrheal disease. These three events, combined with tuberculosis and malaria, account for 20% of deaths globally.

In Western countries, the impact of infectious diseases has diminished greatly over the last 75 years due to improved sanitation, personal hygiene, vaccinations, and the use of antibiotics. In the United States, only two infectious diseases – seasonal influenza and pneumonia – rank in the top ten leading causes of death. Annually, there are 1,500 deaths in the United States from seasonal influenza and another 52,000 from pneumonia. Children and older adults are the greatest at risk for both.

Emergent infectious diseases are those that are appearing in a population for the first time. Re-emergent infectious diseases are those that may have previously existed in a population, but levels had dropped to the point where it was no longer considered a public health problem until levels once again began increasing.

During the last 25 years, emergent and re-emergent infectious diseases have been on the rise. The below table outlines some of the contributing factors to this rise:

Contributing Factors to Increasing Occurrence of Emergent Diseases
Agent-Related Factors
Evolution of pathogenic infectious agents
Development of resistance to drugs
Resistance of disease carriers to pesticides
Host-Related Factors
Human demographic changes (humans inhabiting new areas)
Human behavior (sexual practices and drug use)
Human susceptibility to infection
Environment-Related Factors
Economic development and land use patterns
International travel and commerce
Deterioration of surveillance systems

Technological Hazard: Emergent Infectious Diseases


Due to a lack of ready-made vaccines for these diseases and a lack of immunity in the population, emergent and re-emergent infectious diseases are much more likely to escalate to pandemic levels rapidly.

CDC-Identified Emergent and Re-Emergent Infectious Diseases	
Drug-resistant Infections	Mad Cow/Variant Creutzfeldt-Jakob Diseases
Campylobacteriosis	Chagas Disease
Cholera	Cryptococcosis
Cryptosporidiosis (Crypto)	Cyclosporiasis
Cysticercosis	Dengue Fever
Diphtheria	Ebola Hemorrhagic Fever
Group B Streptococcal Infection	Hantavirus Pulmonary Syndrome
Hepatitis C	Hendra Virus Infection
Histoplasmosis	HIV/AIDS
Influenza	Lassa Fever
Legionnaires' Disease and Pontiac Fever	Leptospirosis
Listeriosis	Lyme Disease
Malaria	Marburg Hemorrhagic Fever
Measles	Meningitis
Monkeypox	MRSA
Nipah Virus Infection	Norovirus Infection
Pertussis	Plague
Polio	Rabies
Rift Valley Fever	Rotavirus Infection
Salmonellosis	SARS and COVID-19
Shigellosis	Smallpox
Sleeping Sickness (Trypanosomiasis)	Tuberculosis
Tularemia	Valley Fever (Coccidioidomycosis)
VISA/VRSA	Staphylococcus Aureus
West Nile Virus Infection	Yellow Fever

Hazard Profile

Emergent Infectious diseases are of significant concern to the Walton County HMPC, particularly those that would have an impact on the human population or animal population of Walton County. Walton County would likely see significant economic impacts from an outbreak involving animal populations, such as an Avian Flu, due to the large economic base agriculture provides (over \$120 million in annual sales). The lack of current vaccines and preparatory activities for these diseases has created a situation where the potential impact to Walton County of a pandemic or epidemic could be catastrophic. The most recent pandemic scare in the Central Georgia area was the 2009-2010 H1N1 Swine Flu. There were 1286 cases of H1N1 in Georgia in 2009-2010 and 33 deaths. Most registered cases occurred with people between the ages of 5 and 29. This equates to a mortality rate of just over 2.5% - which is slightly lower than the 3% rate of the 1918-1919 Spanish Flu Pandemic. The 2019-2021 COVID-19 Pandemic, which was caused by SARS-CoV2, spread worldwide in a matter of weeks. As of February 21, 2023, there were over 674 million cases reported worldwide with nearly 7 million deaths. In Walton County, as of March 20, 2024, there had been 20,496 confirmed cases and 444 deaths. The COVID-19 Pandemic was a Federally Declared Disaster.

Technological Hazard: Emergent Infectious Diseases



Source: Georgia Department of Public Health

Over the last 25 years, emergent infectious disease outbreaks have occurred in other parts of the country. These include:

- 1993 Cryptosporidium Outbreak (Milwaukee, Wisconsin – 403,000 people ill and 100 deaths)
- 2010 Whooping Cough Outbreak (California – 9,500 people ill and 10 infant deaths)
- 2015 H5N2 Avian Flu Outbreak (Midwest – over 25 million chickens and turkeys destroyed as a precautionary measure at 83 locations)

Technological Hazard: **Emergent Infectious Diseases**

Assets Exposed to the Hazard

Due to the unpredictable nature of emergent infectious diseases, all public and private structures are threatened by the hazard. This includes all critical facilities.

Estimated Potential Losses

Losses due to emergent infectious diseases are difficult to estimate due to the unpredictable nature of the hazard. The type of emergent infectious disease, location of the outbreak, and the impact of the outbreak would all affect the potential losses. Please see the critical facilities information for estimated potential losses for each critical facility.

Land Use and Development Trends

Walton County has no land use trends directly related to Emergent Infectious Diseases.

Multi-Jurisdictional Considerations

All of Walton County, including all municipalities, are vulnerable to emergent infectious diseases. However, livestock and other farm animals are considered to be the greatest at risk, along with areas that have a large, concentrated human population, such as schools.

Hazard Summary

An emergent infectious disease would have devastating effects on Walton County and all municipalities. These impacts would be immediate and long-lasting and could be potentially economically crippling. Because of these considerations, the Walton County HMPC has developed mitigation actions with emergent infectious diseases in mind.

CHAPTER FOUR–HAZARD MITIGATION STRATEGIES

Summary of Updates to Chapter Four

The following table provides a description of each section of this chapter, and a summary of the changes that have been made to the Walton County Hazard Mitigation Plan 2020.

Chapter 4 Section	Updates
Goals and Objectives	Updated goals to match the needs of the Walton County
Identification and Analysis of Mitigation Techniques	Content Revised Reviewed mitigation strategies identified in the 2020 plan and made updates Identified mitigation strategies that were completed Identified mitigation strategies to be removed

Goals and Objectives

Requirement §201.6(c)(3)

Requirement §201.6(c)(3)(i)

It is important that State and local government, public-private partnerships, and the average citizen can see the results of these mitigation efforts, therefore, the goals and strategies need to be achievable. The mitigation goals and objectives form the basis for the development of specific mitigation actions. Walton County officials should consider the listed goals before making community policies, public investment programs, economic development programs, or community development decisions for their communities. The goals of Walton County have changed slightly in the last five years (since 2020) due to specific threat events. Because of the recentness of the impacts of these hazards and the devastation that occurred, these types of events have taken a greater priority, particularly in the increased priority of mitigation strategies directly related to these events and the development of new mitigation strategies related to these hazards.

Each jurisdiction covered by the Walton County Hazard Mitigation plan update – Walton County, Loganville, Monroe, Social Circle, Walnut Grove, Between, Good Hope, and Jersey – has limited ability to fully implement the mitigation actions described in this plan. Walton County and its municipalities lack the needed financial strength and staffing to implement all the actions described in this plan. Many of the actions will be pursued through grant programs and by partnering with public and private organizations who can supplement the needed resources to accomplish the goals outlined in this plan. For actions where grant funding or partnerships are not available, the Walton County and municipal revenue streams may be supplemented through Special Purpose Local Option Sales Tax (SPLOST) funds, which are voted on by the electorate.

- | | |
|--------|---|
| GOAL 1 | Maximize the use of all resources by promoting intergovernmental coordination and partnerships in the public and private sectors |
| GOAL 2 | Harden communities against the impacts of disasters through the development of new mitigation strategies and strict enforcement of current regulations that have proven effective |
| GOAL 3 | Reduce and, where possible, eliminate repetitive damage, loss of life and property from disasters |
| GOAL 4 | Bring greater awareness throughout the community about potential hazards and the need for community preparedness |

These objectives state a more specific outcome that Walton County strives to accomplish over the next five years. Action steps are the specific steps necessary to achieve these objectives. Objectives are not listed in order of importance.

- | | |
|-------------|---|
| OBJECTIVE 1 | Reduce damage to property and loss of life through the utilization of preventative activities |
| OBJECTIVE 2 | Minimize the damage to property and loss of life through property protection measures |
| OBJECTIVE 3 | Minimize the damage to property and loss of life through natural resource protection activities |

OBJECTIVE 4	Reduce damage to property and loss of life through the utilization of structural mitigation projects
OBJECTIVE 5	Increase the ability of Walton County and its citizens to respond to natural and manmade hazards through emergency service measures
OBJECTIVE 6	Increase public education and awareness of natural hazards
OBJECTIVE 7	Minimize the impacts on local citizens, industry, and infrastructure of a dam breach
OBJECTIVE 8	Implement additional protective measures and capabilities in response to manmade incidents
OBJECTIVE 9	Increase public awareness of local manmade hazards and proper response to those hazards

Identification and Analysis of Mitigation Techniques

Requirement §201.6(c)(3)(iv)

Requirement §201.6(c)(3)(iii)

In updating Walton County's mitigation strategy, a wide range of activities were considered to help achieve the mitigation goals and objectives. This includes the following activities as by the Emergency Management Accreditation Program (EMAP):

- 1) The use of applicable building construction standards;
- 2) Hazard avoidance through appropriate land-use practices;
- 3) Relocation, retrofitting, or removal of structures at risk;
- 4) Removal or elimination of the hazard;
- 5) Reduction or limitation of the amount or size of the hazard;
- 6) Segregation of the hazard from that which is to be protected;
- 7) Modification of the basic characteristics of the hazard;
- 8) Control of the rate of release of the hazard;
- 9) Provision of protective systems or equipment for both cyber and/or physical risks;
- 10) Establishment of hazard warning and communication procedures; and
- 11) Redundancy or duplication of essential personnel, critical systems, equipment, and information materials.

Part of the prioritization includes a general assessment according to the STAPLEE criteria, which stands for Social, Technical, Administrative, Political, Legal, Economic and Environmental. This process led to three designated priorities: High, Medium, and Low. Most items that require grant funding must undergo a full Benefit Cost Analysis to determine the action's actual cost effectiveness prior to funding. This process will be completed as part of the grant opportunity application process.

Strategy Priority	Priority Description	Strategies within this priority
LOW	Low priority strategies are those strategies that will have less direct impact on mitigating Walton County's hazards, are in the early stages of strategy development, or score poorly on a preliminary cost-benefit analysis	4.e; 4.j; 5.k; 5.l; 5.z; 5.aa; 5.gg; 5.hh; 5.xx; 5.zz; 5.bbb
MEDIUM	Medium priority strategies are those strategies that will have a direct impact on mitigating Walton County's hazards but will not have as large of an anticipated impact as High Priority strategies or may be focused on hazards that are not as potentially impactful or prevalent for Walton County. These strategies may be in the earlier stages of development or score mediocre on a preliminary cost-benefit analysis	1.a; 2.a; 2.b; 2.c; 2.d; 2.e; 2.f; 2.g; 2.h; 2.i; 2.j; 2.k; 2.o; 3.a; 4.c; 4.d; 4.f; 4.g; 4.h; 5.f; 5.g; 5.m; 5.p; 5.v; 5.w; 5.x; 5.y; 5.bb; 5.cc; 5.dd; 5.ee; 5.fff; 5.ii; 5.jj; 5.kk; 5.ll; 5.uu; 5.vv; 5.ww; 5.yy; 5.aaa; 5.ccc; 5.ddd; 5.eee; 5.fff; 6.a; 6.c; 7.a; 8.a; 8.f
HIGH	High priority strategies are those strategies that would have a direct, large impact on mitigating Walton County's hazards. These strategies are oftentimes well-established needs of Walton County and have score high on a preliminary cost-benefit analysis	1.b; 1.c; 1.d; 1.e; 1.f; 1.g; 2.l; 2.m; 2.n; 4.a; 4.b; 4.i; 5.a; 5.b; 5.c; 5.d; 5.e; 5.h; 5.i; 5.j; 5.n; 5.o; 5.q; 5.r; 5.s; 5.t; 5.u; 5.mm; 5.nn; 5.oo; 5.p; 5.qq; 5.rr; 5.ss; 5.tt; 6.b; 8.b; 8.c; 8.d; 8.e; 8.g; 9.a

The lead agency listed in the Mitigation Strategy charts will be responsible for the jurisdictional administration and implementation of the mitigation strategy prioritization. Prioritization was determined based on many factors. These include the likelihood of the event, the potential impact of the event, the current readiness posture of Walton County for the event, the all-hazard impact of the mitigation strategy, and a cost-benefit analysis for the mitigation action. For example, mitigation actions that address high-likelihood, high-impact events with a low cost would rate higher than low-likelihood, high-impact events with a high cost.

The Walton County Hazard Mitigation Planning Committee also attempted to identify potential funding sources outside of Walton County budgets for the mitigation strategies that were identified. This is particularly helpful for future grant planning and for items with significant costs that are beyond the capabilities of Walton County to procure without grant assistance.

Grant Name	Grant Description	Strategies that could be potentially funded
Hazard Mitigation Grant Program	The purpose of the HMGP is to provide funds to State agencies and local governments in the aftermath of a disaster for projects that reduce or eliminate long-term risk to human life and property	1.b; 2.a; 2.b; 2.c; 2.d; 2.e; 2.f; 2.g; 2.h; 2.i; 2.j; 2.k; 2.l; 2.m; 2.n; 2.o; 5.d
Flood Mitigation Assistance Program	The FMA program provides funding to assist States and communities in implementing measures to reduce or eliminate the long-term risk of flood damage to buildings, manufactured homes, and other structures insurable under the NFIP.	1.b; 3.a; 4.b
Community Development Block Grant	Provides communities with resources to address a wide range of unique community development needs	2.e; 2.f; 2.g; 2.l; 2.m; 2.n; 4.a; 5.d
Assistance to Firefighters Grant	This program provides funding to meet the firefighting and emergency response needs of fire departments and nonaffiliated emergency medical service organizations	2.o; 5.s; 5.kk; 8.g

The following Mitigation Charts meet:

[Requirement §201.6\(c\)\(3\)\(ii\)](#)

[Requirement §201.6\(d\)\(3\)](#)

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
OBJECTIVE ONE: Reduce damage to property and loss of life through the utilization of preventative activities															
1.a	Make application to participate in FEMA's NFIP Community Rating System (CRS)	Planning and Development	✓								Local budgets	Staff time	60 months	CRS requirements under research	1.a
1.b	Explore possibility of acquiring and/or relocating repetitive losses in Walton County	EMA and Board of Commissioners	✓								Public and private grants and/or local budgets	\$1 million	60 months	Potential buyout locations identified; funding under research	1.b
1.c	Maintain NFIP Compliance for Between	Between Town Council	✓								Local budgets	Staff time	12 months	NEW	NEW
1.d	Maintain NFIP Compliance for Good Hope	Good Hope Town Council	✓								Local budgets	Staff time	12 months	NEW	NEW
1.e	Maintain NFIP Compliance for the Social Circle	Social Circle City Council	✓								Local budgets	Staff time	12 months	NEW	NEW
1.f	Maintain NFIP Compliance for Monroe	Monroe City Council	✓								Local budgets	Staff time	12 months	NEW	NEW
1.g	Maintain NFIP Compliance for Walnut Grove	Walnut Grove City Council	✓								Local budgets	Staff time	12 months	NEW	NEW
OBJECTIVE TWO: Minimize the damage to property and loss of life through property protection measures															

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
2.a	Install additional backup generators, as needed, at Social Circle Schools and Walton County Schools	EMA, Walton County Schools, Social Circle Schools		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$1 million	60 months	New elementary school will have a generator	2.d
2.b	Install generator at City of Loganville wastewater treatment facility	City of Loganville Wastewater	✓	✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$350,000	48 months	Generator grants awarded; Install in 2026	2.e
2.c	Purchase fixed generator for fuel pump for schools	Social Circle Schools		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$200,000	48 months	Walton County purchased in 2019	2.f (mod)
2.d	Purchase generator for Walnut Grove City Hall and downtown area	EMA and Walnut Grove City Council		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$250,000	48 months	None; other projects have taken priority	2.g
2.e	Purchase all needed generator for the City of Monroe water and wastewater treatment facilities and pump stations	Monroe water and wastewater departments	✓	✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$4 million	60 months	None; other projects have taken priority	2.h
2.f	Purchase generator for the City of Loganville booster stations	EMA and Loganville water	✓	✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$90,000	42 months	None; other projects have taken priority	2.j (mod)
2.g	Purchase generator for Health Department in the City of Loganville	EMA and Health Department		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$50,000	48 months	None; other projects have taken priority	2.k

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
2.h	Purchase generator for Walton County Sheriff's Office precincts	EMA and Sheriff's Office		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$300,000	60 months	None; other projects have taken priority	2.k
2.i	Purchase generator for Walton County Recreation Centers	EMA and Recreation Department		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$1 million	60 months	None; other projects have taken priority	2.l
2.j	Purchase generator for Walton County EMS Office	EMA and EMS		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$100,000	60 months	None; other projects have taken priority	2.n
2.k	Purchase generator for Walton County Animal Control	EMA and Animal Control		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$100,000	60 months	None; other projects have taken priority	2.o
2.l	Purchase generator for all critical facilities in Walton County and all municipalities	EMA and critical facility operators		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$50 million	60 months	NEW	NEW
2.m	Purchase generators for the Social Circle water treatment and wastewater plants	EMA and Social Circle Water	✓	✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$350,000	60 months	Water treatment plant generator purchased in 2025	2.q
2.n	Replace generators at Social Circle lift stations	EMA and Social Circle Water	✓	✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$750,000	60 months	None; other projects have taken priority	2.r

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
2.o	Purchase generators for Loganville Fire Department stations 15 and 16	EMA and Loganville Fire Department		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$350,000	48 months	NEW	NEW
OBJECTIVE THREE: Minimize the damage to property and loss of life through natural resource protection activities															
3.a	Create a diversion of the Apalachee River	Walton County Water and Sewer Authority	✓				✓				Public and private grants and/or local budgets	\$12 million	60 months	Phase II of a 3-phase plan; Phase I was completed	3.a
OBJECTIVE FOUR: Reduce damage to property and loss of life through the utilization of structural mitigation projects															
4.a	Build a new water treatment plant in conjunction with the diversion in 3.a	Walton County Water and Sewer Authority	✓				✓				Public and private grants and/or local budgets	\$375 million	36 months	Began in 2025; Estimated completion in 2027	3.b
4.b	Perform a hydrology study at each culvert site to determine best option for flood and flash flood management	Walton County Public Works	✓		✓		✓				Public and private grants and/or local budgets	\$5 million	48 months	BRIC grant utilized to replace some	4.a
4.c	Build an above ground fuel storage location	Walton County Public Works	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$3 million	60 months	NEW	NEW
4.d	Build a 2 million gallon round storage water tank	City of Monroe Water						✓			Public and private grants and/or local budgets	\$10 million	60 months	NEW	NEW

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
4.e	Create a second and third entrance to Piedmont Walton Hospital	Piedmont Walton Hospital and Walton County Public Works	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$10 million	60 months	Researching properties; Easements are biggest issue	4.b
4.f	Install outdoor warning sirens with targeting areas where cell service is poor and in densely populated areas	EMA				✓					Public and private grants and/or local budgets	\$250,000	60 months	Potential areas researched	5.d
4.g	Build 3 additional water towers for Walton County	Walton County Water and Sewer Authority						✓			Public and private grants and/or local budgets	\$750,000	60 months	NEW	NEW
4.h	Build a permanent Emergency Operations Center with backup communications for 911 Center, generator, and enough space for all ESFs	EMA	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$2 million	60 months	None; other projects have taken priority	5.k
4.i	Replace the following culverts: Thurman Baccus, Wildwood, Lakewood, Cannon Drive	Social Circle Public Works	✓		✓		✓				Public and private grants and/or local budgets	\$1.5 million	48 months	NEW	NEW
4.j	Build a storage building/pole barn for the storage of sand and gravel	Social Circle Public Works		✓							Public and private grants and/or local budgets	\$100,000	36 months	NEW	NEW
OBJECTIVE FIVE: Increase the ability of Walton County and the citizens to respond to natural and manmade hazards through emergency services measures															

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
5.a	Purchase stationary bypass pumps for the City of Loganville	Loganville wastewater	✓				✓				Public and private grants and/or local budgets	\$200,000	48 months	NEW	NEW
5.b	Schedule maintenance and needed repairs for generators at critical county and municipal government facilities and other infrastructure locations	EMA, Walton County Facilities; critical facility operators		✓	✓	✓	✓		✓		Local budgets	Staff time	24 months	Twice annually by WC facilities; City of Monroe and Good Hope have contract	2.a (mod)
5.c	Inventory and load test backup generators at Walton County and Social Circle Schools	Walton County and Social Circle Schools; EMA		✓	✓	✓	✓		✓		Local budgets	Staff time	24 months	None; other projects have taken priority	2.b
5.d	Repair and replace old generators in county and municipalities	EMA		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$5 million	60 months	NEW	NEW
5.e	Inspect all county and municipal critical facilities for power grounding every couple of years	EMA and Facilities		✓	✓	✓	✓		✓		Local budgets	Staff time	24 months	Each done every two years at minimum	2.p
5.f	Identify and implement supply shelter locations for winter storm response – one on each side of Walton County	Public Works		✓							Public and private grants and/or local budgets	\$50,000	36 months	One location identified at water department	4.c
5.g	Formalize a Stormwater Management Plan and update it every five years	Public Works	✓		✓		✓				Local budgets	Staff time	60 months	Report done annually	5.a

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
5.h	Update the Water Strategic Plan every 3 years	Walton County Water and Sewer Authority						✓			Local budgets	Staff time	36 months	Last updated in 2022; Update in progress	5.b
5.i	Update the Debris Management Plan every 3 years	Public Works and EMA	✓	✓	✓	✓	✓		✓	✓	Local budgets	Staff time	36 months	NEW	NEW
5.j	Provide incident command training for all officials in county and municipal department leadership positions	EMA	✓	✓	✓	✓	✓	✓	✓	✓	Local budgets	Staff time	36 months	NEW	NEW
5.k	Purchase 2 fuel trucks	Public Works		✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$150,000	48 months	NEW	NEW
5.l	Encourage cellular service providers to increase coverage in Walton County – with particular emphasis on Walnut Grove and other municipalities	EMA	✓	✓	✓	✓	✓		✓	✓	Local budget	Staff time	24 months	NEW	NEW
5.m	Create a policy stating that if any private entity builds a new stadium or event space, there must also have a means to alert the participants at the venue	Planning and Development	✓	✓	✓	✓	✓	✓	✓	✓	Local budgets	Staff time	18 months	None; Other projects have taken priority	5.e

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
5.n	Expand the mass notification system to use additional modules to increase functionality	EMA	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$20,000	48 months	IPAWS integration in 2024; Additional modules being researched	5.f
5.o	Encourage businesses and complaints in the community to purchase NOAA weather radios	EMA	✓	✓	✓	✓	✓				Local budgets	Staff time	12 months	Heavily promoted by Red Cross	5.g
5.p	Map all county and municipal critical facilities using GPS and provide access to all municipal and county departments and utilities	Planning and Development; Tax Assessors; Public Works	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$150,000	48 months	Social Circle and Monroe have partially completed; Contracting out being researched	5.h
5.q	Maintain StormReady designation	EMA			✓	✓	✓				Local budgets	Staff time	36 months	Last renewed in 2024	5.i
5.r	Update the Community Wildfire Protection Plan every five years	Georgia Forestry Commission								✓	State budgets	Staff time	60 months	Last completed in 2020	5.j
5.s	Purchase ladder truck for fire department	Walton County Fire Rescue							✓	✓	Public and private grants and/or local budgets	\$3 million	60 months	NEW	NEW

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
5.t	Fund training and training aids for emergency preparedness training (STB, CPR, AED, etc.)	Walton County Citizens Corps Council and EMA	✓		✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$25,000	48 months	NEW	NEW
5.u	Review and update the Walton County LEOP	EMA	✓	✓	✓	✓	✓	✓	✓	✓	Local budgets	Staff time	36 months	Updated in 2023; Next update due in 2027	5.l
5.v	Continue to institute additional CERT Basic Training Courses	EMA	✓	✓	✓	✓	✓		✓		Local budgets	\$10,000	36 months	Last classes in 2022 and 2025	5.m
5.w	Institute additional advanced CERT classes	EMA	✓	✓	✓	✓	✓		✓		Local budgets	\$5,000	36 months	None; other projects have taken priority	5.n
5.x	Encourage private schools throughout Walton County to develop and implement an EOP	EMA	✓	✓	✓	✓	✓	✓	✓	✓	Local and private budgets	Staff time	24 months	In process currently	5.o
5.y	Purchase Starlinks	EMA	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$15,000	36 months	NEW	NEW
5.z	Purchase mobile and transportable cross-band repeaters in buildings	911	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$150,000	60 months	None; other projects have taken priority	5.r
5.aa	Create an Animal Emergency Response Plan	Animal Control and EMA	✓	✓	✓	✓	✓	✓	✓	✓	Local budgets	Staff time	36 months	None; other projects have taken priority	5.s

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
5.bb	Purchase electronic signage to be deployed during emergencies	Public Works and EMA	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$80,000	36 months	Grant applied for to purchase 6 signs	5.t
5.cc	Purchase electronic signage for the City of Walnut Grove	Walnut Grove Town Council	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$25,000	36 months	None; other projects have taken priority	5.u
5.dd	Research concept of transportable satellite-linked alternative communication system with push-to-talk, phone, and internet capabilities	EMA	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$10,000	60 months	None; other projects have taken priority	5.v
5.ee	Purchase electronic signage for the City of Monroe	Monroe City Council	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$25,000	36 months	NEW	NEW
5.ff	Purchase electronic signage for the City of Social Circle	Social Circle City Council	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$25,000	36 months	NEW	NEW
5.gg	Upgrade ARES Equipment at Piedmont Walton Hospital	ARES and Piedmont Walton		✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$20,000	60 months	Some upgrades ongoing with PH funding	5.x
5.hh	Exercise ARES communications with Piedmont Walton Hospital monthly	ARES and Piedmont Walton		✓	✓	✓	✓		✓		Local budgets	Staff time	12 months	1 st Sunday of each month currently	5.y

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
5.ii	Expand the Walton County fuel tanks in the Walnut Grove area	Public Works and EMA		✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$500,000	48 months	In discussion for west side of the county	5.z
5.jj	Expand the Board of Education fuel tanks and provide a backup location	Walton County and Social Circle Schools		✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$500,000	60 months	None; other projects have taken priority	5.aa
5.kk	Purchase two fuel trucks for the Walton County Fire Rescue	Walton County Fire Rescue		✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$600,000	60 months	None; other projects have taken priority	5.bb (mod)
5.ii	Secure funding to update the Master Transportation Plan	Planning and Development	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$150,000	36 months	Last completed in 2018 by Public Works; Due in 2028	5.cc
5.m m	Create a Continuity of Operations Plan for Walton County	Walton County Board of Commissioners	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$25,000	36 months	Many lessons learned from COVID-19	5.dd
5.nn	Create a Continuity of Operations Plan for the City of Social Circle	Social Circle City Council	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$10,000	36 months	Many lessons learned from COVID-19	5.ff
5.oo	Create a Continuity of Operations Plan for the City of Loganville	Loganville City Council	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$10,000	36 months	Many lessons learned from COVID-19	5.gg

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
5.pp	Create a Continuity of Operations Plan for the Town of Between	Between Town Council	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$5,000	36 months	Many lessons learned from COVID-19	5.hh
5.qg	Create a Continuity of Operations Plan for the Town of Good Hope	Good Hope Town Council	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$5,000	36 months	Many lessons learned from COVID-19	5.ii
5.rr	Create a Continuity of Operations Plan for the Town of Walnut Grove	Walnut Grove Town Council	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$7,500	36 months	Many lessons learned from COVID-19	5.jj
5.ss	Create a Continuity of Operations Plan for the Town of Jersey	Jersey Town Council	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$5,000	36 months	Many lessons learned from COVID-19	5.kk
5.tt	Update the City of Monroe's Continuity of Operations Plan	Monroe City Council	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$2,000	36 months	NEW	NEW
5.uu	Purchase and outfit additional salt and brine trucks for winter weather response	Public Works		✓							Public and private grants and/or local budgets	\$250,000	48 months	None; Other projects have taken priority	5.mm
5.vv	Purchase traffic control devices, such as barricades, cones, etc.	Public Works, Monroe Public Works, and Sheriff's Office	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$40,000	30 months	None; other projects have taken priority	5.oo

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
5.w	Purchase P25 digital vehicular repeater system	911 and each municipality	✓	✓	✓	✓	✓		✓	✓	Public and private grants and/or local budgets	\$250,000	60 months	None; other projects have taken priority	5.pp
5.xx	Purchase mobile animal emergency response equipment and animal control emergency response supplies	Animal Control	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$150,000	60 months	None; other projects have taken priority	5.qq; 5.vv
5.yy	Update Volunteer Management Plan by 2027	EMA	✓	✓	✓	✓	✓		✓		Local budgets	Staff time	24 months	NEW	NEW
5.zz	Host a CERT Train-the-Trainer Course	EMA	✓	✓	✓	✓	✓		✓		Local budgets	Staff time	24 months	Aiming to host in 2026-27	5.tt
5.aa	Secure a facility to store Citizens Corps Council supplies	Citizens Corps Council	✓	✓	✓	✓	✓	✓	✓	✓	Local budgets	\$15,000	36 months	None; other projects have taken priority	5.aa
5.bb	Purchase supplies for an MRC training course	Citizens Corps Council	✓	✓	✓	✓	✓		✓		Local budgets	\$5,000	36 months	NEW	NEW
5.cc	Purchase supplies to operate a Point of Distribution site	EMA	✓	✓	✓	✓	✓	✓	✓	✓	Public and private grants and/or local budgets	\$100,000	48 months	Public Health has purchased supplies annually for dispensing	7.c

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Flood	Winter Weather	Thunderstorm	Tornado	Tropical Cyclone	Drought/Ex Temp	Geologic	Wildfire	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
5.dd	Purchase brine spreader and two trucks with plows	Social Circle Public Works		✓							Public and private grants and/or local budgets	\$150,000	60 months	NEW	NEW
5.ee	Purchase two plows to attached to F-350s	Social Circle Public Works		✓							Public and private grants and/or local budgets	\$75,000	60 months	NEW	NEW
5.fff	Purchase debris management equipment, including tractor, bush hog, sidearm tractor, skid loader, and multiple F-350s	Public Works	✓	✓	✓	✓	✓		✓		Public and private grants and/or local budgets	\$750,000	60 months	NEW	NEW
OBJECTIVE SIX: Increase public education and awareness of natural disasters															
6.a	Establish a “Severe Weather/Weather Education” and “Community and Individual Disaster Preparedness” section within each unit of the Walton County Public Library	EMA and Walton County Public Library	✓	✓	✓	✓	✓				Public and private grants and/or local budgets	\$5,000	60 months	Established in 1 library so far	6.b
6.b	Utilize social media to provide public information	Walton County PIO and Citizens Corps Council	✓	✓	✓	✓	✓	✓	✓	✓	Local budgets	Staff time	12 months	In place currently; Active on Social Media	6.c
6.c	Add information regarding mass notification system to utility and tax bills	EMA, Tax Commissioners Office, and Utility Providers		✓	✓	✓	✓				Local budgets	Staff time	18 months	City of Loganville has done this twice in last 5 years	6.d and 6.g

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Dam Failure	Hazardous Materials	Terrorism/Civil	Transportation	Infrastructure Failure	Emer. Disease	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
OBJECTIVE SEVEN: Minimize the impact of a dam breach on local citizens, industry, and infrastructure													
7.a	Install cameras and electronic warning system at local dams to improve off-site monitoring capabilities	EMA and dam owners/operators	✓		✓				Public and private grants and/or local budgets	\$1 million	60 months	Hard Labor Creek dam identified as priority	7.a
OBJECTIVE EIGHT: Implement additional protective measures and capabilities in response to manmade incidents													
8.a	Install an antenna with connections to existing digi-repeater located at the HD Atha Road Tower site	EMA		✓	✓		✓		Public and private grants and/or local budgets	\$5,000	36 months	Researching Cost information	5.w
8.b	Provide Operations level Hazardous Materials training for all first responders	EMA and all public safety agencies		✓	✓	✓		✓	Local budgets	Staff time	48 months	Fire Department trains to Ops level currently	8.a
8.c	Provide Technician level Hazardous Materials training for HazMat team members	EMA and Fire Departments		✓	✓	✓		✓	Local budgets	Staff time	18 months	Fire Department offers a Technician class annually	8.b

Strategy #	Mitigation Action	Lead and Supporting Agency, Department, Organization	Dam Failure	Hazardous Materials	Terrorism/Civil	Transportation	Infrastructure Failure	Emer. Disease	Funding Source	Estimated Cost	Completion Timeframe	Progress/ Status	Previous Strategy #
8.d	Hold multi-jurisdictional mass casualty/active shooter/terrorism exercise	EMA, emergency response agencies, Walton County Schools, Social Circle Schools		<	<			<	Public and private grants and/or local budgets	\$3,000	24 months	Mass Casualty TTX in 2025; Active Shooter training every year; Terrorism exercise planned for 2026/27	8.c
8.e	Maintain participation in the East Georgia Local Emergency Planning Committee (LEPC)	EMA and LEPC	✓	✓	✓	✓	✓	✓	Local budgets	Staff time	12 months	In place; Meet monthly	8.d
8.f	Install camera software in the EOC for mobile traffic monitoring during mass events	EMA and DOT			✓		✓		Public and private grants and/or local budgets	\$500,000	60 months	Have a GDOT account to see their cameras	8.e
8.g	Supply HazMat Team with training and emergency response resources	Fire Departments and EMA		✓	✓	✓		✓	Public and private grants and/or local budgets	\$300,000	60 months	HazMat team established	8.f
OBJECTIVE NINE: Increase public awareness of local manmade hazards and proper response to those hazards													
9.a	Develop a public awareness campaign for technological hazards	EMA	✓	✓	✓	✓	✓	✓	Local budget	Staff time	12 months	NEW	NEW

Completed Mitigation Strategies

Previous Strategy #	Strategy Description	Status
2.i	Purchase generators for five Walton County Fire Stations	COMPLETE; Completed in 2023 and 2024 with county funds
5.c	Create a debris management	COMPLETE
5.p	Complete an HSEEP-compliant full-scale exercise with county and municipal agencies	COMPLETE; Completed in 2023
5.ee	Create a Continuity of Operations Plan for Monroe	COMPLETE
5.nn	Purchase computers for EOC Operations	COMPLETE; Completed in 2023 with county funds
5.rr	Develop a Volunteer Management Plan	COMPLETE; Completed in 2023
5.ss	Purchase supplies, backpacks, and helmets for CERT students	COMPLETE; Grant acquired
6.a	Develop a functional website for the Walton County EMA	COMPLETE
6.h	Purchase road signs to let public know about StormReady designation	COMPLETE; In 2024
7.b	Develop a full After Action Review of the COVID-19 response in Walton County	COMPLETE; in 2023

Deleted Mitigation Strategies

Previous Strategy #	Strategy Description
2.c	Correct deficiencies identified in 2.a (generator inventory)
5.ii	Build a new fuel station in the county to serve Walton County and Walton County Schools
6.e	Mail out flyers/pamphlets regarding the mass notification system to all zip codes
6.f	Add information regarding mass notification system in City of Monroe quarterly newsletter
7.d	Install State-of-the-art HVAC protective measures in all county and municipal buildings to manage the spread of any potential airborne pathogens

CHAPTER FIVE – MAINTENANCE AND IMPLEMENTATION

Summary of Updates for Chapter Five

The following table provides a description of each section of this chapter, and a summary of the changes that have been made to the Walton County Hazard Mitigation Plan 2021.

Chapter 5 Section	Updates
Maintenance	Content Revised
Plan Distribution	Content Revised
Implementation	Content Revised
Evaluation	Content Revised
Peer Review	Content Revised
Plan Update	Content Revised
Conclusion	Content Revised

Maintenance

Requirement §201.6(c)(4)(iii)

To adhere to best practices, state and federal guidelines, and lessons learned, the Walton County Hazard Mitigation Plan Update Committee has developed a method to ensure the regular review and update of the Plan occurs. Plan maintenance protocols identified during the 2021 Walton County Hazard Mitigation Plan was followed, to the best abilities of Walton County and its municipalities. This most importantly included an increased attempt for public participation and inclusion in the planning process. The Walton County Hazard Mitigation Plan Update Committee will reconvene annually in February to monitor and evaluate the progress of the mitigation strategies in the Plan. Walton County's Homeland Security and Emergency Management Director, Carl Morrow, will be responsible for implementing this meeting. The Committee will discuss the following questions annually:

- Do the goals address current and expected hazards and conditions?
- Are the goals and objectives still relevant to Walton County?
- Has the nature or magnitude of risks changed?
- Does the risk assessment portion of the Plan need to be updated or modified?
- Are the goals and objectives meeting changes in state and federal policy?
- Are the current resources appropriate for implementing the Plan?
- Are there local implementation problems, such as technical, political, legal, or coordination issues with other agencies?
- Did the jurisdictions, agencies, and other partners participate in the plan implementation process as proposed?

The responsible parties for various mitigation strategies will provide a report during this annual meeting regarding the following:

- How well did the implementation processes work?
- Were any difficulties encountered during implementation?
- How successful was the coordination of efforts?
- Are there any suggestions for revision of any strategies?

Walton County's Emergency Management Director will send the minutes from this annual meeting to the Walton County Board of Commissioners for review.

If there are any updates or modifications to the Walton County Hazard Mitigation Plan, the Emergency Management Director will forward the changes to the Georgia Emergency Management Agency's Hazard Mitigation Officer. All annual reviews of the Walton County Hazard Mitigation Plan will be open to the public. These meetings will be advertised both in the local newspapers, but also on signage in the publicly used facility hosting the meeting.

Maintenance Log

Revision Date	Revised Section	Reason for Revision	Revised By
2025-2026	Five Year Hazard Mitigation Plan Update	FEMA Requirement	Walton County Hazard Mitigation Planning Committee with assistance from Lux Mitigation and Planning

Plan Distribution

This Plan will be distributed, but not limited, to the following departments and organizations within Walton County:

Walton County Board of Commissioners
Walton County Emergency Management Agency
Walton County Sheriff's Office
Walton County Public Works
Walton County Planning & Development
Walton County Fire Rescue
City of Loganville
City of Monroe
City of Social Circle
City of Walnut Grove
Town of Between
Town of Good Hope
Town of Jersey

A printed copy of the approved Plan will be available for viewing at the Walton County Emergency Management Agency.

Implementation

Requirement §201.6(c)(4)(ii)

Each jurisdiction participating in the Walton County Hazard Mitigation Plan is responsible for implementing specific mitigation actions as prescribed in this plan. In the Mitigation Strategies section, every proposed strategy is assigned to a specific local department or agency to assign responsibility and accountability and increase the likelihood of subsequent implementation.

In addition to the designation of a local lead department or agency, some strategies have secondary or assisting department or agencies listed as well. This allows for a sharing of responsibility and coordination of effort for some of the identified strategies that cross lines of departmental responsibility. The completion date has been assigned to assess whether identified mitigation strategies are being implemented in a timely fashion.

Walton County will seek outside funding sources to implement mitigation projects in both the pre-disaster and post-disaster environments. When applicable, potential funding sources have been identified and targeted for the proposed actions listed in the mitigation strategies. It will be the responsibility of each participating jurisdiction to determine additional implementation procedures beyond those listed within the Walton County Hazard Mitigation Plan.

This plan, as a joint within Walton County and will serve as a comprehensive mitigation plan. The mitigation strategies, hazard identification, and other information identified in this plan will be integrated into all comprehensive Walton County plans in the future. Incorporation of these strategies will occur, as necessary, throughout this planning cycle covered by this Hazard Mitigation Plan Update. Aspects of this plan will be integrated into the Walton County Comprehensive Plan during the next planning cycle.

Identified hazards and mitigation strategies of the 2021 Walton County Hazard Mitigation plan were integrated into the Local Emergency Operations Plan, multiple County and City SOPs and SOGs, and future planning and zoning plans. Walton County and the municipalities of Loganville, Monroe, Social Circle, Walnut Grove, Between, Good Hope, and Jersey will integrate mitigation strategies identified in this plan into the Walton County Comprehensive Plan, Community Wildfire Protection Plan, Continuity of Operations Plan, and other future plans. Strategies identified in the previous plan were applied to grant applications, building and zoning requirements, and development planning considerations for Walton County and all municipalities. Once this plan is approved, it will be used by the consultants and planning committees responsible for the update process for the County and City Comprehensive Plans, Short-Term Work Programs, and all other plans that could incorporate the requirements of this plan. To facilitate the inclusion of this Plan, the Walton County Board of Commissioners and the Municipalities of Loganville, Monroe, Social Circle, Walnut Grove, Between, Good Hope, and Jersey will provide a copy to the persons and/or committees responsible for writing and updating plans. Many of these strategies will be applied using previously identified policies and ordinances, including the NFIP compliance ordinances and water-use ordinances, which have now been applied countywide. All jurisdictions have the authority to adopt locally binding ordinances and policies to enhance the mitigation strategies in their jurisdiction.

The Legal and Regulatory Capability survey documents authorities available to the jurisdiction and/or enabling legislation at the state level affecting planning and land management tools that support local hazard mitigation planning efforts. The identified planning and land management tools are typically used by states and local jurisdictions to implement hazard mitigation activities.

Regulatory Tools/Plans	Regulatory Type: Ordinance, Resolution, Codes, Plans, Etc.	Local Authority	State Prohibited	Higher Authority
Building Codes	Walton County Code; Loganville, Monroe, Social Circle, Walnut Grove, Between, Good Hope, and Jersey codes and ordinances	Yes	No	No
Capital Improvements Plan		Yes	No	No
Comprehensive Plan	Walton County Joint Comprehensive Plan (Includes Loganville, Monroe, Social Circle, Walnut Grove, Between, Good Hope, and Jersey)	Yes	No	No
Economic Development Plan	Walton County Joint Comprehensive Plan (Includes Loganville, Monroe, Social Circle, Walnut Grove, Between, Good Hope, and Jersey)	Yes	No	Yes
Emergency Management Accreditation Program		No	No	Yes
Emergency Response Plan	Walton County Local Emergency Operations Plan (LEOP)	Yes	No	Yes
Flood Management Plan		Yes	No	No
Historic Preservation		Yes	No	No
National Flood Insurance Program Participation		Yes	No	Yes
Continuity of Government/ Operations Plan		No	No	No
Post-Disaster Ordinance		Yes	No	No
Zoning Ordinances	Walton County Code; Loganville, Monroe, Social Circle, Walnut Grove, Between, Good Hope, and Jersey codes and ordinances	Yes	No	No

Opportunities to integrate the requirements of this Plan into other local planning mechanisms shall continue to be identified. Although it is recognized that there are many possible benefits to integrating components of this Plan into other local planning mechanisms, the development and maintenance of this stand-alone Hazard Mitigation Plan is deemed by the Walton County Hazard Mitigation Planning Committee to be the most effective and appropriate method to implement local hazard mitigation actions at this time.

Evaluation

Requirement §201.6(c)(4)(i)

Periodic revisions and updates of the Walton County Hazard Mitigation Plan may be required to ensure that the goals of this plan are kept current with federal, state, and local regulations. These revisions should also consider any potential changes in the hazard vulnerability and mitigation priorities of Walton County.

The Walton County Hazard Mitigation Plan Update Committee will meet annually to review the Walton County Hazard Mitigation Plan. During this annual review, mitigation strategies will be reviewed to evaluate the progress that has occurred for each identified mitigation strategy. The Walton County Hazard Mitigation Plan Update Committee will also meet following any disaster event to review the identified mitigation strategies for that hazard and determine if timelines should be adjusted or additional mitigation strategies should be identified and added to the plan. These steps will ensure that the Walton County Hazard Mitigation Plan is continuously updated to allow for changes in hazard vulnerabilities and identified mitigation strategies. The Walton County Hazard Mitigation Plan Update Committee will complete all evaluations of the Walton County Hazard Mitigation Plan.

Peer Review

State Requirement Element F1

To maintain standards of quality, improve performance, and provide credibility to the Walton County Hazard Mitigation Plan Update, representatives of local emergency management agencies bordering Walton County conducted a peer review of the Plan. The peer review of this Plan constitutes a form of self-regulation, accountability, and new insights offered by qualified professionals in neighboring communities, which face many of the same natural and man-made hazards.

The Walton County Hazard Mitigation Plan Update was peer reviewed by:

Wendy Patterson	Date
Director	
Newton County Emergency Management Agency	

Amanda Proctor	Date
Director	
Morgan County Emergency Management Agency	

Sharon Courson	Date
Director	
Barrow County Emergency Management Agency	

CJ Worden	Date
Director	
Oconee County Emergency Management Agency	

Sharon Webb	Date
Director	
Rockdale County Emergency Management Agency	

Michael Shaw	Date
Director	
Gwinnett County Emergency Management Agency	

Plan Update

Requirement §201.6(c)(4)(i)

The Federal Disaster Mitigation Act of 2000 requires that the Hazard Mitigation Plan be updated at least once every five years. The Walton County Emergency Management Agency is the department responsible with ensuring this requirement is met. The Walton County Hazard Mitigation Plan Update Committee will be involved in this future process and will aid the Walton County Emergency Management Agency in ensuring that all jurisdictions provide input into the planning process. The public will be invited to participate in the planning process through public hearings to be held whenever major updates to this plan are needed and during annual review meetings. This plan will expire in the second quarter of 2030; therefore, the approval and adoption of the next plan update must be completed before that time.

In the first quarter of 2029, Walton County plans to begin the Hazard Mitigation Plan Update process for the fourth time. This planning process will include bi-monthly meetings to accomplish the identified goals of the Walton County Hazard Mitigation Plan Update. This process will be headed up by the Walton County Emergency Management Agency. The Walton County Hazard Mitigation Planning Committee will follow a similar process as was undertaken during this planning cycle to complete all FEMA and GEMA requirements for the Hazard Mitigation Plan Update. This process will be completed by the first quarter of 2030 to meet all identified planning deadlines.

Conclusion

As a result of the hazard mitigation planning process Walton County, as well as additional participating organizations have gained significant information and knowledge regarding Walton County's disaster history, natural and technological hazards, vulnerabilities, and potential strategies to lessen the impacts of the identified hazards.

One consistent theme identified by the Walton County Hazard Mitigation Planning Committee was the inability to consistently identify geographic locations that were more vulnerable to most hazards due to the widespread potential effects and random impact areas of each hazard. This was exceedingly true for most natural hazards. Recognizing this challenge, the Walton County Hazard Mitigation Plan Update Committee determined it was best to identify many mitigation goals, objectives, and strategies that were both general and specific in nature. These strategies allow the Walton County Hazard Mitigation Plan Update Committee to adopt strategies that will have the greatest positive effect on the greatest amount of the population.

The Walton County Hazard Mitigation Planning Committee adopted strategies in all six of the major mitigation categories: Prevention, Property Protection, Natural Resource Protection, Structural Projects, Emergency Services, and Public Education and Awareness. Emergency Services comprised the greatest number (61.7%) of the mitigation strategies identified by Walton County.

Appendix A – Walton County Hazard Mitigation Plan Update Committee Sign-In Sheets

**Walton County Hazard Mitigation Plan Update
Committee Workshop #1**

Sign-In Sheet

Tuesday, February 18, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Craig League		cleague@co.walton.ga.us	Walton Fire
Matt McClung		mccclung@monroe.ga.gov	Monroe PD
Jack Armstrong		Jack.Armstrong.r.f@acemid.com	HiTech!
Bradley Stanley		bradley.stanley1124@gmail.com	LEET Walton Co
Vashon Hill		Vhuggle@monroe.gov	City of Monroe
Rennie Fulcher		Rennie.Fulcher@monroe.gov	City of Monroe
Kenny Sargent		Kenny.Sargent@co.walton.ga.us	Walton Co. Recycling Center
Josh GARNER		josh.garner@co.walton.ga.us	Walton County Sheriff's Office
Matthew George		MGeorge@monroe.ca.gov	City of Monroe
TaShia Brist		TGUEST@SPECIALSERVICES.CALIF.	SPECIAL SERVICES PD
Carl Morrow		Carl.Morrow@co.walton.ga.us	WCFMA
J. Garrett Polston		james.polston@piedmont.org	Piedmont Walton-Triunion
JOSEPH WHEELER		JOSEPH.WHEELER@CO.WALTON.GA.US	WALTON CO. EMA

**Walton County Hazard Mitigation Plan Update
Committee Workshop #1**

Sign-In Sheet

Tuesday, February 18, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Randy Garnett Mayor		townofgoodhope@windstream.net	City of Good Hope
Sheri Traylor PW		Sheri.traylor@dph.ga.gov	Walton Co. Health Dept
Charlie Dalton		Bigcountry4413@gmail.com	WC S.O.
Kevin Jones		Kevin.M.Jones.cmr@hickoryhills.com	Hickory Hills Astoria
Doug Brown		doug.brown@co.walton.ga.us	WCFR
Tim Allant		tim.tallante@co.walton.ga.us	WCSO
Michael Moore		mmoores@logansville-fa.gov	LFD
Wayne Harper		WAYNE.HARPER@WHITEFOXRUN.COM	LEPC
Steen Edwards		Wm4dyd@gmail.com	Citizen / ARES
Wm H. Ayres / MASS CARE		William.Ayres@redcross.org	Red Cross
Julie DeVera		jmk400@yahoo.com	WCCC
Janil Adair		vjanlad@yahoo.com	Michelin
Ray Johnson		johnsr@co.walton.ga.us	Walton County

Walton County Hazard Mitigation Plan Update
Committee Workshop #1


Sign-In Sheet
Tuesday, February 18, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Lee Cochran ANALYST Security Manager		LeeCochran@meta.com	Meta
Hank Shirley Facilities Manager		hshirley@co.walton.ga.us	
Jody Carter HSE Analyst		jody.carter.p@hickokistano.com	Hickokistano
Charles Hammond PIO		Ben.Hammond@co.walton.ga.us	WCSO
Tad Amistead		tamistead@monroega.gov	City of Monroe
Ronda Beel		rdbeel@socialcirclega.gov	Social Circle
Kathy Pharrill		KPharrill@socialcirclega.gov	Social Circle
ANDY LATIMER Facilities Director Walton County		andy.latimer@piedmont.org	Piedmont Walton Hospital
Jessica deBenedictis Manager		deBenedictis@monroega.gov	City of Monroe
Monalis Jordan		monalis.jordan@co.walton.ga.us	Walton Co
Ken Baydel Fire Chief City of Monroe		kbaydel@socialcirclega.gov	Social Circle
Jim Holbrook City of Monroe Electric		Jholbrook@monroega.gov	City of Monroe
Jonathan Jones Gen/HLS		jjonathan.jones@gen.ga.gov	GEN/HLS

**Walton County Hazard Mitigation Plan Update
Committee Workshop #1**

Sign-In Sheet

Tuesday, February 18, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Carol Patchell ^{HRC} Carol Patchell		cpatchell@wpcc.com	Walton County HRC
Brad Adcock Loss Control		brad.adcock@waltonemc.com	Walton EMC
Andrew Dykes		adykes@waltonemc.com	Walton EMC
Joey Witcher		jwitcher@waltonemc.com	Walton EMC
Jeremiah Gill		jst11@waltonemc.com	City of Monroe
Jacky Johnson		jjohnson@co.walton.ga.gov	Walton Public Safety
Kelvin Hancey		khancey@co.walton.ga.gov	Walton Fire
Payton Turner		pturner@ge.state.ga.us	GFC
David Westmoreland		westmoreland@co.walton.ga.us	Walton
David Shanks TUPHSC		dmshanks@waltonemc.com	Walton EMC
Elisabeth Wilson, HRC		Elisabeth.Wilson@ph-ga.gov	DPH/NEHD
Ashley Casar		casar@waltonemc.com	Traffic Operations
Jeff Adams		adamsj23@waltonemc.com	

Walton County Hazard Mitigation Plan Update
Committee Workshop #1

Sign-In Sheet

Tuesday, February 18, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Dana T. Tipp Secretary		dana@clara-tipp.com	WCCC
Robert Post		betweengamajor@gmail.com	Panel of Peewee
John Alderman		ALDERMAN HUBER@gmail.com	←
Sabrina Westbrook		shadydalefec@bellsouth.net	Vesper Co. 911 Authority
John Allman		john.allman@walton.gal.us	Walton Co.

**Walton County Hazard Mitigation Plan Update
Committee Workshop #2**

Sign-In Sheet

Tuesday, March 18, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Ben Hammond / PIO		Ben.Hammond@Co.walton.fl.us	Walton County
Andrew Dyer		adryes@monroe.gov	Monroe Fire
Bill Ayers		W-H-Ayres@redcross.org	Red Cross
Celia Tatalona		cobdean@yahoo.com	WCCC/MRC/OERT
John W. Langley		john.wulfe@waltonfla.gov	Walton Co. Board of Comm
J. Garrett Polston		james.polston@pielawent.org	Piedmont Walker
Lee Cochran Arbor Security Manager		LeeCochran@meta.com	Meta
Jos Witcher		jwitcher@munroe.gov	City of Munroe
Aaron Robinson		aaron.robinson@socialwiredschools.org	
Tad Armstrong		tarmistad@munroegov.org	City of Monroe
Vashun Ethel		Vthugle@munroegov.org	City of Monroe
Fannie Fulcher		Fannie.Fulcher@munroegov.org	City of Monroe
Brian Collins		Brian.Collins@co.walton.fl.us	Walton County

**Walton County Hazard Mitigation Plan Update
Committee Workshop #2**

Sign-In Sheet

Tuesday, March 18, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Carl Morrow		Carl.Morrow@co.walton.ga.us	Walton EMA
John Allmon/Pls Director		j.allmon@co.walton.ga.us	Walton County
Randy Gannett		gannett@waltonfla.net	Walton County
Brad Shriver		bradley.shriver@waltonfla.net	Walton County
Greg Westmoreland		westmoreland@co.walton.ga.us	NCEMA
Sam		subigner@co.newton.ga.us	NCEMA
Wendy Patterson		wendy.patterson@wilmington-nc.gov	NCEMA
Robert Post		post@wilmington-nc.gov	Town of Betts
Charlie Dalton		charlie.dalton@co.walton.ga.us	Walton County Dept.
Jody Carter		jody.carter@waltonhvac.com	HVAC
Casey Williams		casey.williams@nucor.com	NUCOR WAREHOUSE SYSTEMS
Rhonda Beel		rhonda.beel@socialcircle.ga.gov	City Social Circle
Dana Tripp		dana@danetripp.com	CERT

**Walton County Hazard Mitigation Plan Update
Committee Workshop #2**

Sign-In Sheet

Tuesday, March 18, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Ray Johnson Assoc F Die		johnson@cr.walton.ga.us	Walton County
Jamie Peters		j.peters@monroe.ga.gov	City of Monroe
Lee Branch		lbranch@monroe.ga.gov	City of Monroe
Greg Boyd		gregboyd@co.walton.ga.us	Walton County
Doug Brown		doug.brown@403egmail.com	WCFR
Kellie Haney		khanev@co.walton.ga.us	WCFR
Patsack Maculloy		Clay.Maculloy@co.walton.ga.us	WCFR
William Rowland		William.Rowland@co.walton.ga.us	EMS
W. K. HARP		W. K. HARP W. K. HARP W. K. HARP	LEPC
Craig League		c.league@co.walton.ga.us	Walton Fire
Stan Edwards		StanEdwards@gmail.com	W/CARES
Ashley Cason		acason@co.walton.ga.us	Traffic Operations
Kath Marell		Kath.Marell@SocialCivicga.gov	Street Signs

Walton County Hazard Mitigation Plan Update
Committee Workshop #2

Sign-In Sheet

Tuesday, March 18, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Jessica de Benedichs WWTP Manager		Jdebenedichs@monroega.gov	city of Monroe
JOSEPH WHISCHIEL EMA SPEC.		JOSEPH.WHISCHIEL@ CO.WALTON.FL.US	WALTON CO. EMA
Sabrina Westbrook		sbradydalefc@bellisecity.net	Jasper Co. 911 Authority

Walton County Hazard Mitigation Plan Update
Committee Workshop #2


Sign-In Sheet
Tuesday, March 18, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Julie DeVries		JuliaA00@yahoo.com	Walton County Citizens Corps Council

**Walton County Hazard Mitigation Plan Update
Committee Workshop #3**

Sign-In Sheet

Tuesday, April 22, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Steve Edwards		WALTON@ymail.com	WRES
CARLA TATCHEL		cdbdean@yahoo.com	MRC/CERT/WCCC
Craig League		cleague@co.walton.ga.us	Walton Fire
Charma Parker		C Parker @ Co. Walton. ga. us	Walton Co P+D
Kristi Parr		Kparr @ Co. Walton. ga. us	Walton Co P+D
Kerlin HANEY		Khaney@co.walton.ga.us	Walton Fire
Logan Lob...		carol.robinson@scsccs.net	SCCS
Donna Bree		donna.bree@socialwilde.com	Social Wilde
J. Garrett Polston		janes.polston@ Piedmont. org	Piedmont Walton
Joey Witche		jwiche@muniegn.gov	City of Munroe
Staren Ernie		searn@munroe.gov	City of Munroe
Joseph Starnil Utilities Field Manager		Jstarnil@logansville-ga.gov	City of Logansville
JOSEPH WHELOHEL		JOSEPH.WHELOHEL@CO.WALTON.GA.US	WALTON EMA

Walton County Hazard Mitigation Plan Update
Committee Workshop #3

Sign-In Sheet
Tuesday, April 22, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Julie DeVries		JulieDeVries@walton.fl.gov	WCCCC
Sabrina Westbrook		sabradel@walton.fl.gov	Jasper Co 911 Authority

**Walton County Hazard Mitigation Plan Update
Committee Workshop #3**

Sign-In Sheet

Tuesday, April 22, 2025

Name/Title	Signature	E-mail Address	Agency/Organization
Patty Grant / Mayor		trung.south@waltoncountynv.com	City of Good Hope
Mollie Spain		mollie.jordan@co.walton.ga.us	WC Boc - Water
Andrew Dykes Fire Chief		adykes@waltonfire.org	Walton Fire Dept.
Charles Hannell		Brian.Hannell@co.walton.ga.us	WC Boc
Lee Cochran / Area Security Manager		leecochran@meta.com	Meta
Josh Bowman / EP Director		joshua.bowman@delphi.ga.gov	Northeast Health District
Carle Morrison		Carle.Morrison@co.walton.ga.us	Walton EMA
Joshua Mosley		Joshua.Mosley@co.walton.ga.us	Walton EMS
Derek Marshall		Lawrence.Saunders@co.walton.ga.us	City of Social Circle
Robbie Groves Public Works Dir.		rgroves@socialcirclega.gov	City of Social Circle
Wm Ayers		William.Ayers@redcross.org	Red Cross
Timothy Johnson Fire Chief		timjohnson@laganville-ga.gov	Laganville Fire Dept.
JOHN WARD		john.ward@co.walton.ga.us	Walton County

Appendix B – Natural Hazard Data Tables

Thunderstorms

Location	County/Zone	St.	Date	Time	T.Z.	Type	Mag	Dth	Inj	PrD	CrD
Totals:								0	2	57.846M	0.00K
WALTON CO.	WALTON CO.	GA	03/13/1975	18:00	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	08/17/1978	14:25	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	07/05/1979	11:25	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	05/14/1981	21:45	CST	Hail	1.75 in.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	05/30/1982	16:00	CST	Hail	1.75 in.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	05/30/1982	20:30	CST	Hail	0.75 in.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	06/12/1982	11:30	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	07/13/1982	21:45	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	05/29/1983	15:00	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	03/28/1984	14:50	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	05/02/1984	17:08	CST	Hail	1.00 in.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	05/02/1984	17:50	CST	Hail	1.00 in.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	05/02/1984	17:50	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	05/02/1984	18:30	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	05/03/1984	14:35	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	11/10/1984	18:15	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	04/05/1985	19:40	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	06/07/1985	16:10	CST	Thunderstorm Wind	52 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	03/13/1986	07:40	CST	Thunderstorm Wind	51 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	06/08/1986	14:15	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K

WALTON CO.	WALTON CO.	GA	11/20/1986	09:05	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	06/17/1988	15:00	CST	Thunderstorm Wind	0 kts.	0	2	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	06/18/1988	15:50	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	07/09/1988	16:22	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	04/04/1989	13:22	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	06/05/1989	13:40	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	08/25/1989	20:45	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	10/01/1989	19:30	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	11/01/1989	19:50	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	01/25/1990	09:00	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	02/10/1990	05:33	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	03/16/1990	18:05	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	04/10/1990	17:25	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	04/28/1990	13:16	CST	Hail	0.88 in.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	05/28/1990	14:00	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	08/05/1990	16:12	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	08/22/1990	18:45	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	03/01/1991	17:15	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	03/01/1991	17:30	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	04/27/1991	17:50	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	04/29/1991	12:50	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K

WALTON CO.	WALTON CO.	GA	05/05/1991	14:00	CST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	02/26/1992	01:00	PST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	03/06/1992	19:30	CST	Hail	2.00 in.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	03/06/1992	20:00	PST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
WALTON CO.	WALTON CO.	GA	07/05/1992	16:52	PST	Thunderstorm Wind	0 kts.	0	0	0.00K	0.00K
Monroe	WALTON CO.	GA	02/21/1993	22:25	EST	Thunderstorm Wind	100 kts.	0	0	50.000M	0.00K
Loganville	WALTON CO.	GA	05/13/1993	11:35	EST	Hail	1.00 in.	0	0	0.00K	0.00K
Social Circle	WALTON CO.	GA	05/31/1993	14:05	EST	Thunderstorm Wind	0 kts.	0	0	5.00K	0.00K
Watkinsville	WALTON CO.	GA	06/27/1994	05:30	EST	Hail	1.75 in.	0	0	0.00K	0.00K
Mount Vernon	WALTON CO.	GA	06/10/1995	21:30	EST	Hail	1.75 in.	0	0	0.00K	0.00K
WALTON AND OCONEE CO.	WALTON AND OCONEE CO.	GA	06/10/1995	22:00	EST	Thunderstorm Wind	0 kts.	0	0	0.75K	0.00K
Loganville	WALTON CO.	GA	09/01/1995	16:30	EST	Thunderstorm Wind	0 kts.	0	0	1.00K	0.00K
Monroe	WALTON CO.	GA	09/01/1995	16:30	EST	Thunderstorm Wind	0 kts.	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	03/15/1996	16:00	EST	Hail	0.75 in.	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	03/15/1996	17:15	EST	Hail	0.75 in.	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	04/13/1996	16:22	EST	Hail	1.75 in.	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	02/21/1997	14:30	EST	Thunderstorm Wind		0	0	100.00K	0.00K
MONROE	WALTON CO.	GA	03/05/1997	19:25	EST	Thunderstorm Wind		0	0	2.00K	0.00K
MONROE	WALTON CO.	GA	03/25/1997	19:10	EST	Hail	0.75 in.	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	04/19/1997	19:15	EST	Thunderstorm Wind		0	0	0.50K	0.00K
MONROE	WALTON CO.	GA	04/22/1997	14:15	EST	Hail	1.00 in.	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	04/22/1997	18:05	EST	Thunderstorm Wind		0	0	2.50K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/1997	00:59	EST	Lightning		0	0	50.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/1997	19:50	EST	Thunderstorm Wind	68 kts.	0	0	15.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/1997	19:50	EST	Hail	1.75 in.	0	0	0.00K	0.00K

WALNUT GROVE	WALTON CO.	GA	07/28/1997	18:05	EST	Hail	1.00 in.	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	09/10/1997	21:05	EST	Hail	1.75 in.	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	09/10/1997	21:22	EST	Hail	1.00 in.	0	0	0.00K	0.00K
GRATIS	WALTON CO.	GA	04/03/1998	17:30	EST	Hail	0.75 in.	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	04/03/1998	21:25	EST	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	04/08/1998	19:24	EST	Hail	1.00 in.	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	04/23/1998	15:08	EST	Hail	1.00 in.	0	0	0.00K	0.00K
BOLD SPGS	WALTON CO.	GA	05/03/1998	20:15	EST	Hail	1.00 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	05/07/1998	21:20	EST	Hail	1.75 in.	0	0	2.00K	0.00K
MONROE	WALTON CO.	GA	05/08/1998	00:10	EST	Hail	1.00 in.	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	06/16/1998	00:30	EST	Thunderstorm Wind		0	0	5.00K	0.00K
MONROE	WALTON CO.	GA	06/16/1998	16:59	EST	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/19/1998	11:42	EST	Hail	1.00 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/30/1998	20:12	EST	Thunderstorm Wind		0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	04/15/1999	05:10	EST	Hail	1.00 in.	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	06/02/1999	18:20	EST	Hail	1.75 in.	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	06/02/1999	18:30	EST	Thunderstorm Wind		0	0	0.50K	0.00K
MONROE	WALTON CO.	GA	06/30/1999	16:00	EST	Thunderstorm Wind		0	0	1.50K	0.00K
GOOD HOPE	WALTON CO.	GA	02/14/2000	00:30	EST	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2000	13:00	EST	Hail	1.25 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2000	13:00	EST	Thunderstorm Wind		0	0	2.00K	0.00K
MONROE	WALTON CO.	GA	06/25/2000	13:38	EST	Thunderstorm Wind		0	0	1.50K	0.00K
LOGANVILLE	WALTON CO.	GA	07/12/2000	16:54	EST	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	07/12/2000	16:55	EST	Thunderstorm Wind		0	0	3.00K	0.00K
LOGANVILLE	WALTON CO.	GA	07/23/2000	14:05	EST	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	07/23/2000	14:35	EST	Hail	1.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	07/23/2000	14:35	EST	Thunderstorm Wind		0	0	3.00K	0.00K
MONROE	WALTON CO.	GA	09/04/2000	20:15	EST	Thunderstorm Wind		0	0	5.00K	0.00K

LOGANVILLE	WALTON CO.	GA	02/16/2001	19:05	EST	Thunderstorm Wind		0	0	3.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/14/2001	17:10	EST	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/14/2001	17:10	EST	Lightning		0	0	5.00K	0.00K
LOGANVILLE	WALTON CO.	GA	04/28/2002	21:25	EST	Hail	0.88 in.	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	02/22/2003	07:35	EST	Hail	0.75 in.	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	02/22/2003	07:35	EST	Thunderstorm Wind	50 kts. EG	0	0	0.50K	0.00K
LOGANVILLE	WALTON CO.	GA	03/19/2003	23:50	EST	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	05/01/2003	18:27	EST	Hail	1.00 in.	0	0	0.00K	0.00K
COUNTYWIDE	WALTON CO.	GA	05/02/2003	17:45	EST	Thunderstorm Wind	50 kts. EG	0	0	3.00K	0.00K
MONROE	WALTON CO.	GA	05/02/2003	17:45	EST	Hail	0.88 in.	0	0	0.00K	0.00K
COUNTYWIDE	WALTON CO.	GA	05/02/2003	19:40	EST	Thunderstorm Wind	50 kts. EG	0	0	25.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	07/16/2003	17:40	EST	Hail	0.75 in.	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	07/22/2003	13:30	EST	Thunderstorm Wind	52 kts. EG	0	0	35.00K	0.00K
MONROE	WALTON CO.	GA	08/16/2003	15:50	EST	Hail	0.75 in.	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	08/16/2003	15:50	EST	Thunderstorm Wind	45 kts. EG	0	0	0.25K	0.00K
JERSEY	WALTON CO.	GA	06/27/2004	19:00	EST	Thunderstorm Wind	39 kts. EG	0	0	0.25K	0.00K
LOGANVILLE	WALTON CO.	GA	07/04/2004	15:50	EST	Thunderstorm Wind	50 kts. EG	0	0	10.00K	0.00K
MONROE	WALTON CO.	GA	07/07/2004	23:00	EST	Thunderstorm Wind	50 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	07/14/2004	18:00	EST	Thunderstorm Wind	50 kts. EG	0	0	2.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	11/24/2004	11:00	EST	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
LOGANVILLE	WALTON CO.	GA	02/21/2005	13:50	EST	Hail	0.75 in.	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	02/21/2005	19:30	EST	Lightning		0	0	25.00K	0.00K
LOGANVILLE	WALTON CO.	GA	02/21/2005	19:40	EST	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	02/21/2005	20:03	EST	Hail	1.00 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	02/21/2005	20:30	EST	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	04/22/2005	13:00	EST	Hail	0.88 in.	0	0	0.00K	0.00K

COUNTYWIDE	WALTON CO.	GA	04/22/2005	13:22	EST	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
COUNTYWIDE	WALTON CO.	GA	07/01/2005	16:50	EST	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
MONROE	WALTON CO.	GA	08/17/2005	20:54	EST	Lightning		0	0	250.00K	0.00K
MONROE	WALTON CO.	GA	04/08/2006	03:50	EST	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	05/25/2006	17:05	EST	Thunderstorm Wind	35 kts. EG	0	0	0.25K	0.00K
LOGANVILLE	WALTON CO.	GA	05/25/2006	17:15	EST	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/23/2006	18:10	EST	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	01/05/2007	12:11	EST-5	Thunderstorm Wind	50 kts. EG	0	0	3.00K	0.00K
MONROE	WALTON CO.	GA	06/12/2007	18:35	EST-5	Hail	0.75 in.	0	0	0.00K	0.00K
BETWEEN	WALTON CO.	GA	06/12/2007	18:45	EST-5	Thunderstorm Wind	56 kts. EG	0	0	1.00K	0.00K
MT VERNON	WALTON CO.	GA	08/17/2007	14:40	EST-5	Hail	1.25 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	02/26/2008	07:03	EST-5	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	03/15/2008	15:20	EST-5	Hail	0.88 in.	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	03/15/2008	15:34	EST-5	Hail	2.75 in.	0	0	2.000M	0.00K
GOOD HOPE	WALTON CO.	GA	05/11/2008	02:20	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
CAMPTON	WALTON CO.	GA	05/20/2008	18:38	EST-5	Lightning		0	0	250.00K	0.00K
MONROE	WALTON CO.	GA	05/20/2008	18:39	EST-5	Hail	0.75 in.	0	0	0.00K	0.00K
GRATIS	WALTON CO.	GA	07/21/2008	18:10	EST-5	Thunderstorm Wind	50 kts. EG	0	0	3.00K	0.00K
LOGANVILLE	WALTON CO.	GA	07/22/2008	18:30	EST-5	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	08/02/2008	18:30	EST-5	Hail	0.75 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	02/18/2009	18:03	EST-5	Hail	3.00 in.	0	0	2.500M	0.00K

WALNUT GROVE	WALTON CO.	GA	03/28/2009	15:45	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
JERSEY	WALTON CO.	GA	04/10/2009	20:28	EST-5	Hail	0.75 in.	0	0	0.00K	0.00K
GRATIS	WALTON CO.	GA	04/10/2009	21:00	EST-5	Lightning		0	0	10.00K	0.00K
BOLD SPGS	WALTON CO.	GA	04/23/2009	20:10	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	07/23/2009	18:40	EST-5	Thunderstorm Wind	36 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	08/04/2009	20:08	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	01/21/2010	22:10	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	06/15/2010	17:37	EST-5	Thunderstorm Wind	50 kts. EG	0	0	20.00K	0.00K
BETWEEN	WALTON CO.	GA	06/25/2010	17:40	EST-5	Thunderstorm Wind	38 kts. EG	0	0	1.50K	0.00K
MONROE	WALTON CO.	GA	07/31/2010	17:38	EST-5	Thunderstorm Wind	50 kts. EG	0	0	4.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	08/27/2010	02:05	EST-5	Thunderstorm Wind	43 kts. EG	0	0	5.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	08/27/2010	02:05	EST-5	Hail	0.88 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	04/04/2011	23:15	EST-5	Thunderstorm Wind	50 kts. EG	0	0	7.00K	0.00K
MONROE	WALTON CO.	GA	04/04/2011	23:37	EST-5	Lightning		0	0	300.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	05/26/2011	17:45	EST-5	Thunderstorm Wind	52 kts. EG	0	0	30.00K	0.00K
MONROE	WALTON CO.	GA	06/09/2011	15:28	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/15/2011	20:35	EST-5	Hail	0.88 in.	0	0	0.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	06/18/2011	16:20	EST-5	Hail	1.75 in.	0	0	400.00K	0.00K
MONROE	WALTON CO.	GA	06/18/2011	17:15	EST-5	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	06/18/2011	17:15	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K

WALNUT GROVE	WALTON CO.	GA	06/22/2011	15:49	EST-5	Thunderstorm Wind	39 kts. EG	0	0	4.00K	0.00K
MONROE	WALTON CO.	GA	12/22/2011	19:20	EST-5	Thunderstorm Wind	36 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	07/16/2012	16:44	EST-5	Thunderstorm Wind	50 kts. EG	0	0	4.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	07/17/2012	13:15	EST-5	Thunderstorm Wind	50 kts. EG	0	0	1.50K	0.00K
LOGANVILLE	WALTON CO.	GA	05/19/2013	05:15	EST-5	Thunderstorm Wind	50 kts. EG	0	0	3.00K	0.00K
BETWEEN	WALTON CO.	GA	06/02/2013	15:51	EST-5	Thunderstorm Wind	45 kts. EG	0	0	1.00K	0.00K
BOLD SPGS	WALTON CO.	GA	06/13/2013	19:10	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/18/2013	16:35	EST-5	Thunderstorm Wind	60 kts. EG	0	0	10.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	05/14/2014	18:15	EST-5	Thunderstorm Wind	60 kts. EG	0	0	2.50K	0.00K
MT VERNON	WALTON CO.	GA	05/25/2014	17:01	EST-5	Thunderstorm Wind	60 kts. EG	0	0	3.00K	0.00K
MONROE	WALTON CO.	GA	05/25/2014	17:01	EST-5	Lightning		0	0	50.00K	0.00K
BOLD SPGS	WALTON CO.	GA	06/17/2014	16:15	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	06/19/2014	19:10	EST-5	Thunderstorm Wind	50 kts. EG	0	0	2.00K	0.00K
MONROE	WALTON CO.	GA	08/08/2014	15:12	EST-5	Thunderstorm Wind	50 kts. EG	0	0	2.50K	0.00K
GOOD HOPE	WALTON CO.	GA	08/20/2014	14:50	EST-5	Thunderstorm Wind	50 kts. EG	0	0	1.50K	0.00K
PANNELL	WALTON CO.	GA	08/20/2014	15:00	EST-5	Thunderstorm Wind	50 kts. EG	0	0	2.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	08/20/2014	15:15	EST-5	Thunderstorm Wind	50 kts. EG	0	0	0.50K	0.00K
GOOD HOPE	WALTON CO.	GA	10/14/2014	06:10	EST-5	Thunderstorm Wind	55 kts. EG	0	0	10.00K	0.00K
JERSEY	WALTON CO.	GA	06/09/2015	15:47	EST-5	Thunderstorm Wind	55 kts. EG	0	0	12.00K	0.00K
MT VERNON	WALTON CO.	GA	06/18/2015	17:35	EST-5	Thunderstorm Wind	65 kts. EG	0	0	40.00K	0.00K

BETWEEN	WALTON CO.	GA	06/24/2015	14:50	EST-5	Thunderstorm Wind	50 kts. EG	0	0	6.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	06/24/2015	15:43	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	08/17/2015	18:45	EST-5	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
MONROE	WALTON CO.	GA	07/05/2016	14:00	EST-5	Thunderstorm Wind	50 kts. EG	0	0	3.00K	0.00K
JERSEY	WALTON CO.	GA	07/11/2016	17:55	EST-5	Thunderstorm Wind	50 kts. EG	0	0	6.00K	0.00K
BOLD SPGS	WALTON CO.	GA	07/18/2016	15:46	EST-5	Thunderstorm Wind	50 kts. EG	0	0	2.00K	0.00K
MONROE	WALTON CO.	GA	07/21/2016	17:15	EST-5	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	04/05/2017	23:00	EST-5	Thunderstorm Wind	50 kts. EG	0	0	15.00K	0.00K
BETWEEN	WALTON CO.	GA	06/15/2017	17:24	EST-5	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/15/2017	18:24	EST-5	Thunderstorm Wind	45 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	07/26/2017	17:08	EST-5	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	06/25/2018	14:26	EST-5	Thunderstorm Wind	50 kts. EG	0	0	3.00K	0.00K
CAMPTON	WALTON CO.	GA	07/21/2018	06:05	EST-5	Thunderstorm Wind	55 kts. EG	0	0	50.00K	0.00K
WALKER PARK	WALTON CO.	GA	08/07/2018	13:30	EST-5	Thunderstorm Wind	50 kts. EG	0	0	3.00K	0.00K
JERSEY	WALTON CO.	GA	09/27/2018	16:02	EST-5	Thunderstorm Wind	50 kts. EG	0	0	20.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	02/12/2019	14:30	EST-5	Thunderstorm Wind	45 kts. EG	0	0	1.00K	0.00K
BETWEEN	WALTON CO.	GA	04/14/2019	11:38	EST-5	Thunderstorm Wind	50 kts. EG	0	0	30.00K	0.00K
YOUTH	WALTON CO.	GA	04/19/2019	06:00	EST-5	Thunderstorm Wind	50 kts. EG	0	0	8.00K	0.00K
JERSEY	WALTON CO.	GA	04/19/2019	07:44	EST-5	Thunderstorm Wind	50 kts. EG	0	0	6.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/23/2019	15:33	EST-5	Thunderstorm Wind	50 kts. EG	0	0	10.00K	0.00K

BRADLEY	WALTON CO.	GA	09/13/2019	20:02	EST-5	Thunderstorm Wind	50 kts. EG	0	0	4.00K	0.00K
YOUTH	WALTON CO.	GA	02/06/2020	09:58	EST-5	Thunderstorm Wind	50 kts. EG	0	0	10.00K	0.00K
BOLD SPGS	WALTON CO.	GA	04/13/2020	02:07	EST-5	Thunderstorm Wind	50 kts. EG	0	0	6.00K	0.00K
BOLD SPGS	WALTON CO.	GA	04/13/2020	02:12	EST-5	Thunderstorm Wind	50 kts. EG	0	0	6.00K	0.00K
BETWEEN	WALTON CO.	GA	04/13/2020	02:18	EST-5	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
YOUTH	WALTON CO.	GA	06/15/2020	15:20	EST-5	Thunderstorm Wind	60 kts. EG	0	0	15.00K	0.00K
BOLD SPGS	WALTON CO.	GA	06/24/2020	14:35	EST-5	Thunderstorm Wind	50 kts. EG	0	0	6.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/27/2020	16:03	EST-5	Thunderstorm Wind	50 kts. EG	0	0	25.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	08/03/2020	13:58	EST-5	Thunderstorm Wind	50 kts. EG	0	0	50.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	08/09/2020	20:10	EST-5	Thunderstorm Wind	45 kts. EG	0	0	1.00K	0.00K
SPLIT SILK	WALTON CO.	GA	05/03/2021	10:55	EST-5	Thunderstorm Wind	50 kts. EG	0	0	15.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	05/03/2021	13:19	EST-5	Thunderstorm Wind	50 kts. EG	0	0	5.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	05/04/2021	13:47	EST-5	Thunderstorm Wind	50 kts. EG	0	0	8.00K	0.00K
YOUTH	WALTON CO.	GA	06/14/2021	15:55	EST-5	Lightning		0	0	50.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/14/2021	15:55	EST-5	Thunderstorm Wind	50 kts. EG	0	0	30.00K	0.00K
YOUTH	WALTON CO.	GA	06/14/2021	16:07	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	06/14/2021	16:07	EST-5	Hail	1.75 in.	0	0	900.00K	0.00K
YOUTH	WALTON CO.	GA	07/08/2021	19:41	EST-5	Thunderstorm Wind	45 kts. EG	0	0	10.00K	0.00K
JERSEY	WALTON CO.	GA	08/10/2021	16:35	EST-5	Thunderstorm Wind	45 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	08/25/2021	18:19	EST-5	Thunderstorm Wind	50 kts. EG	0	0	9.00K	0.00K

LOGANVILLE	WALTON CO.	GA	12/11/2021	14:20	EST-5	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
PANNELL	WALTON CO.	GA	05/30/2022	16:56	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
WHITNEY	WALTON CO.	GA	05/30/2022	16:58	EST-5	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
GOOD HOPE	WALTON CO.	GA	05/30/2022	17:03	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
WHITNEY	WALTON CO.	GA	05/30/2022	17:13	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	06/08/2022	22:55	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	06/08/2022	23:00	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	06/08/2022	23:06	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
SPLIT SILK	WALTON CO.	GA	06/17/2022	17:15	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
SPLIT SILK	WALTON CO.	GA	06/17/2022	17:20	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	06/17/2022	17:20	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
GOOD HOPE	WALTON CO.	GA	07/03/2022	17:40	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	07/19/2022	16:51	EST-5	Thunderstorm Wind	50 kts. EG	0	0	0.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	07/19/2022	16:57	EST-5	Thunderstorm Wind	45 kts. EG	0	0	2.00K	0.00K
MONROE	WALTON CO.	GA	07/19/2022	17:00	EST-5	Thunderstorm Wind	50 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	07/19/2022	17:02	EST-5	Thunderstorm Wind	45 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	07/19/2022	17:24	EST-5	Thunderstorm Wind	50 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	07/19/2022	17:25	EST-5	Thunderstorm Wind	50 kts. EG	0	0	0.00K	0.00K
SPLIT SILK	WALTON CO.	GA	01/12/2023	16:34	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	01/12/2023	16:39	EST-5	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K

YOUTH	WALTON CO.	GA	01/12/2023	16:41	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
GRATIS	WALTON CO.	GA	01/12/2023	16:42	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
BETWEEN	WALTON CO.	GA	01/12/2023	16:45	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
BETWEEN	WALTON CO.	GA	01/12/2023	16:47	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
BETWEEN	WALTON CO.	GA	01/12/2023	16:49	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	01/12/2023	16:50	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	01/12/2023	16:50	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	01/12/2023	16:53	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	01/12/2023	16:56	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	01/12/2023	16:57	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
BRADLEY	WALTON CO.	GA	01/12/2023	16:58	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	01/12/2023	17:03	EST-5	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
WALKER PARK	WALTON CO.	GA	01/12/2023	17:04	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	01/12/2023	17:04	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
BOLD SPGS	WALTON CO.	GA	01/12/2023	17:05	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
EBENEZER	WALTON CO.	GA	01/12/2023	17:05	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
EBENEZER	WALTON CO.	GA	01/12/2023	17:08	EST-5	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	01/12/2023	17:08	EST-5	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
CAMPTON	WALTON CO.	GA	03/03/2023	18:18	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
EBENEZER	WALTON CO.	GA	03/03/2023	18:40	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K

SOCIAL CIRCLE	WALTON CO.	GA	04/01/2023	08:27	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	04/30/2023	04:35	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	04/30/2023	05:20	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	05/16/2023	16:58	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	05/16/2023	16:58	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
YOUTH	WALTON CO.	GA	05/16/2023	17:00	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	05/16/2023	17:40	EST-5	Thunderstorm Wind	35 kts. EG	0	0	1.00K	0.00K
YOUTH	WALTON CO.	GA	06/06/2023	17:27	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	06/06/2023	17:29	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	06/06/2023	17:29	EST-5	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	06/06/2023	17:30	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/14/2023	14:10	EST-5	Hail	1.00 in.	0	0	0.00K	0.00K
GRATIS	WALTON CO.	GA	06/25/2023	17:13	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
BOLD SPGS	WALTON CO.	GA	06/25/2023	17:27	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:27	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
YOUTH	WALTON CO.	GA	06/25/2023	17:28	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:30	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:30	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:30	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:30	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K

WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:31	EST-5	Lightning		0	0	10.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:32	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:35	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:39	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
YOUTH	WALTON CO.	GA	06/25/2023	17:41	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:42	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
SNOWS MILL	WALTON CO.	GA	06/25/2023	17:44	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	06/25/2023	17:45	EST-5	Thunderstorm Wind	52 kts. EG	0	0	3.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:45	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:51	EST-5	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
JERSEY	WALTON CO.	GA	06/25/2023	17:51	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
LOGANVILLE	WALTON CO.	GA	06/25/2023	17:57	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	06/25/2023	17:57	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	06/25/2023	17:57	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
EBENEZER	WALTON CO.	GA	06/25/2023	18:00	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
BETWEEN	WALTON CO.	GA	06/25/2023	18:03	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
BOLD SPGS	WALTON CO.	GA	06/25/2023	18:03	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	07/01/2023	18:04	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
CAMPTON	WALTON CO.	GA	07/01/2023	18:08	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
SPLIT SILK	WALTON CO.	GA	07/01/2023	19:02	EST-5	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K

BOLD SPGS	WALTON CO.	GA	07/14/2023	20:19	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	07/20/2023	17:22	EST-5	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
GRATIS	WALTON CO.	GA	07/20/2023	17:27	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	07/20/2023	17:33	EST-5	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
BRADLEY	WALTON CO.	GA	07/20/2023	17:35	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
GRATIS	WALTON CO.	GA	07/20/2023	17:42	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
MT VERNON	WALTON CO.	GA	07/20/2023	17:42	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	07/20/2023	17:45	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WHITNEY	WALTON CO.	GA	07/21/2023	17:09	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
PANNELL	WALTON CO.	GA	08/03/2023	15:45	EST-5	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	08/06/2023	12:10	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	08/06/2023	12:30	EST-5	Thunderstorm Wind	48 kts. EG	0	0	2.00K	0.00K
MT VERNON	WALTON CO.	GA	08/06/2023	12:35	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
BRADLEY	WALTON CO.	GA	08/06/2023	12:37	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
YOUTH	WALTON CO.	GA	08/07/2023	17:10	EST-5	Thunderstorm Wind	61 kts. EG	0	0	10.00K	0.00K
LOGANVILLE	WALTON CO.	GA	08/07/2023	17:12	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
MONROE	WALTON CO.	GA	08/07/2023	17:15	EST-5	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
BOLD SPGS	WALTON CO.	GA	08/07/2023	17:16	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	08/07/2023	17:23	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MT VERNON	WALTON CO.	GA	08/07/2023	17:23	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K

GRATIS	WALTON CO.	GA	08/07/2023	17:30	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	08/12/2023	16:25	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
JERSEY	WALTON CO.	GA	08/12/2023	16:41	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	08/12/2023	16:41	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
YOUTH	WALTON CO.	GA	08/12/2023	16:41	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
GOOD HOPE	WALTON CO.	GA	08/12/2023	16:46	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
GRATIS	WALTON CO.	GA	08/12/2023	17:00	EST-5	Thunderstorm Wind	56 kts. EG	0	0	0.00K	0.00K
LOGANVILLE	WALTON CO.	GA	01/09/2024	09:08	EST-5	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	02/12/2024	21:15	EST-5	Thunderstorm Wind	43 kts. EG	0	0	2.00K	0.00K
LOGANVILLE	WALTON CO.	GA	02/28/2024	15:46	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
SPLIT SILK	WALTON CO.	GA	02/28/2024	15:50	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	02/28/2024	16:22	EST-5	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	04/02/2024	23:06	EST-5	Thunderstorm Wind	56 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	04/02/2024	23:10	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	04/02/2024	23:10	EST-5	Thunderstorm Wind	56 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	04/02/2024	23:12	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	04/02/2024	23:16	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	04/02/2024	23:20	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	04/02/2024	23:20	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	04/02/2024	23:22	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K

YOUTH	WALTON CO.	GA	05/09/2024	07:40	EST-5	Thunderstorm Wind	35 kts. EG	0	0	1.00K	0.00K
BRADLEY	WALTON CO.	GA	05/09/2024	07:41	EST-5	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	05/25/2024	10:20	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
CAMPTON	WALTON CO.	GA	05/25/2024	10:20	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	05/25/2024	10:20	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	05/25/2024	10:27	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	05/25/2024	10:30	EST-5	Thunderstorm Wind	48 kts. EG	0	0	3.00K	0.00K
GOOD HOPE	WALTON CO.	GA	05/25/2024	10:30	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
EBENEZER	WALTON CO.	GA	05/25/2024	10:35	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
BOLD SPGS	WALTON CO.	GA	08/17/2024	18:15	EST-5	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	08/29/2024	17:50	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	08/29/2024	17:50	EST-5	Thunderstorm Wind	65 kts. EG	0	0	0.00K	0.00K
MONROE	WALTON CO.	GA	08/29/2024	17:52	EST-5	Thunderstorm Wind	61 kts. EG	0	0	20.00K	0.00K
SPLIT SILK	WALTON CO.	GA	08/29/2024	18:00	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	08/29/2024	18:05	EST-5	Thunderstorm Wind	56 kts. EG	0	0	7.00K	0.00K
JERSEY	WALTON CO.	GA	08/29/2024	18:10	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
YOUTH	WALTON CO.	GA	08/29/2024	18:18	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
SPLIT SILK	WALTON CO.	GA	08/29/2024	18:25	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
LOGANVILLE	WALTON CO.	GA	08/29/2024	18:30	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	02/16/2025	05:03	EST-5	Thunderstorm Wind	48 kts. EG	0	0	2.00K	0.00K

BETWEEN	WALTON CO.	GA	02/16/2025	05:04	EST-5	Thunderstorm Wind	52 kts. EG	0	0	2.00K	0.00K
YOUTH	WALTON CO.	GA	02/16/2025	05:04	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
NICHOLASVILLE	WALTON CO.	GA	02/16/2025	05:06	EST-5	Thunderstorm Wind	52 kts. EG	0	0	5.00K	0.00K
WALKER PARK	WALTON CO.	GA	02/16/2025	05:07	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
CAMPTON	WALTON CO.	GA	02/16/2025	05:08	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
JERSEY	WALTON CO.	GA	02/16/2025	05:10	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	02/16/2025	05:10	EST-5	Thunderstorm Wind	52 kts. EG	0	0	0.00K	0.00K
MONROE MUNI ARPT	WALTON CO.	GA	02/16/2025	05:10	EST-5	Thunderstorm Wind	52 kts. EG	0	0	10.00K	0.00K
MT VERNON	WALTON CO.	GA	02/16/2025	05:13	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	02/16/2025	05:17	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
GOOD HOPE	WALTON CO.	GA	02/16/2025	05:18	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	03/31/2025	12:35	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	03/31/2025	12:40	EST-5	Thunderstorm Wind	39 kts. EG	0	0	1.00K	0.00K
LOGANVILLE	WALTON CO.	GA	03/31/2025	12:40	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
BETWEEN	WALTON CO.	GA	03/31/2025	12:48	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
WALKER PARK	WALTON CO.	GA	03/31/2025	12:50	EST-5	Thunderstorm Wind	52 kts. EG	0	0	1.00K	0.00K
PANNELL	WALTON CO.	GA	03/31/2025	12:57	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
SPLIT SILK	WALTON CO.	GA	05/21/2025	00:42	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
MT VERNON	WALTON CO.	GA	05/21/2025	00:54	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
MONROE	WALTON CO.	GA	06/07/2025	17:15	EST-5	Thunderstorm Wind	56 kts. EG	0	0	14.00K	0.00K

YOUTH	WALTON CO.	GA	06/17/2025	17:46	EST-5	Thunderstorm Wind	43 kts. EG	0	0	1.00K	0.00K
BOLD SPGS	WALTON CO.	GA	06/17/2025	17:56	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
BOLD SPGS	WALTON CO.	GA	06/17/2025	17:56	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K
BRADLEY	WALTON CO.	GA	06/17/2025	17:59	EST-5	Thunderstorm Wind	48 kts. EG	0	0	1.00K	0.00K

Winter Weather

<u>Location</u>	<u>County/Zone</u>	<u>St.</u>	<u>Date</u>	<u>Time</u>	<u>T.Z.</u>	<u>Type</u>	<u>Dth</u>	<u>Ini</u>	<u>PrD</u>	<u>CrD</u>
Totals:							0	0	1.194M	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/18/1996	18:00	EST	Heavy Snow	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/22/2000	13:00	EST	Ice Storm	0	0	980.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/28/2000	19:00	EST	Ice Storm	0	0	32.79K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/17/2000	07:30	EST	Winter Storm	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/19/2000	00:00	EST	Winter Storm	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/02/2002	06:00	EST	Heavy Snow	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/04/2002	14:00	EST	Ice Storm	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/25/2004	05:00	EST	Ice Storm	0	0	5.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	02/26/2004	00:00	EST	Winter Storm	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/28/2005	20:00	EST	Winter Storm	0	0	150.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/15/2005	00:00	EST	Ice Storm	0	0	1.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	02/01/2007	04:00	EST-5	Winter Weather	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	03/01/2009	13:00	EST-5	Heavy Snow	0	0	25.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/07/2010	16:00	EST-5	Winter Weather	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	02/12/2010	14:30	EST-5	Heavy Snow	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/25/2010	16:00	EST-5	Winter Weather	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/09/2011	22:00	EST-5	Heavy Snow	0	0	0.00K	0.00K

WALTON (ZONE)	WALTON (ZONE)	GA	02/09/2011	23:00	EST-5	Heavy Snow	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/28/2014	12:00	EST-5	Winter Storm	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	02/11/2014	07:00	EST-5	Winter Storm	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/09/2017	02:00	EST-5	Winter Weather	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/16/2018	20:00	EST-5	Winter Weather	0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/16/2022	08:00	EST-5	Winter Weather	0	0	0.00K	0.00K

Flooding

<u>Location</u>	<u>County/Zone</u>	<u>St.</u>	<u>Date</u>	<u>Time</u>	<u>T.Z.</u>	<u>Type</u>	<u>Dth</u>	<u>Inj</u>	<u>PrD</u>	<u>CrD</u>
Totals:							0	0	29.00K	0.00K
<u>WALNUT GROVE</u>	WALTON CO.	GA	09/13/2002	18:58	EST	Flood	0	0	0.00K	0.00K
<u>COUNTYWIDE</u>	WALTON CO.	GA	03/20/2003	04:00	EST	Flash Flood	0	0	0.00K	0.00K
<u>COUNTYWIDE</u>	WALTON CO.	GA	07/01/2003	16:30	EST	Flash Flood	0	0	0.00K	0.00K
<u>SOCIAL CIRCLE</u>	WALTON CO.	GA	07/22/2003	09:02	EST	Flash Flood	0	0	0.00K	0.00K
<u>WALTON (ZONE)</u>	WALTON (ZONE)	GA	09/07/2004	04:00	EST	Flood	0	0	0.00K	0.00K
<u>MONROE</u>	WALTON CO.	GA	03/31/2005	07:00	EST	Flash Flood	0	0	0.00K	0.00K
<u>WALTON (ZONE)</u>	WALTON (ZONE)	GA	07/11/2005	00:00	EST	Flood	0	0	0.00K	0.00K
<u>SNOWS MILL</u>	WALTON CO.	GA	09/16/2009	11:05	EST-5	Flood	0	0	1.00K	0.00K
<u>BOLD SPGS</u>	WALTON CO.	GA	09/21/2009	08:00	EST-5	Flash Flood	0	0	3.00K	0.00K
<u>BOLD SPGS</u>	WALTON CO.	GA	09/21/2009	08:30	EST-5	Flood	0	0	5.00K	0.00K
<u>WALNUT GROVE</u>	WALTON CO.	GA	07/05/2019	22:10	EST-5	Flash Flood	0	0	0.00K	0.00K
<u>SPLIT SILK</u>	WALTON CO.	GA	07/05/2019	22:15	EST-5	Flash Flood	0	0	0.00K	0.00K
<u>BOLD SPGS</u>	WALTON CO.	GA	02/06/2020	11:30	EST-5	Flash Flood	0	0	0.00K	0.00K
<u>GOOD HOPE</u>	WALTON CO.	GA	02/06/2020	14:30	EST-5	Flash Flood	0	0	0.00K	0.00K
<u>LOGANVILLE</u>	WALTON CO.	GA	02/06/2020	14:30	EST-5	Flash Flood	0	0	0.00K	0.00K
<u>MT VERNON</u>	WALTON CO.	GA	02/06/2020	14:30	EST-5	Flash Flood	0	0	0.00K	0.00K
<u>BOLD SPGS</u>	WALTON CO.	GA	02/06/2020	14:30	EST-5	Flash Flood	0	0	0.00K	0.00K
<u>SPLIT SILK</u>	WALTON CO.	GA	02/06/2020	14:30	EST-5	Flash Flood	0	0	0.00K	0.00K
<u>CLEATON</u>	WALTON CO.	GA	09/17/2020	06:00	EST-5	Flash Flood	0	0	20.00K	0.00K
<u>BOLD SPGS</u>	WALTON CO.	GA	09/17/2020	06:00	EST-5	Flash Flood	0	0	0.00K	0.00K
<u>NICHOLASVILLE</u>	WALTON CO.	GA	01/04/2023	09:30	EST-5	Flash Flood	0	0	0.00K	0.00K

CLEATON	WALTON CO.	GA	01/04/2023	09:30	EST-5	Flash Flood	0	0	0.00K	0.00K
GOOD HOPE	WALTON CO.	GA	08/28/2023	05:00	EST-5	Flash Flood	0	0	0.00K	0.00K
WALKER PARK	WALTON CO.	GA	01/09/2024	09:30	EST-5	Flash Flood	0	0	0.00K	0.00K
NICHOLASVILLE	WALTON CO.	GA	01/09/2024	09:45	EST-5	Flash Flood	0	0	0.00K	0.00K

Drought

<u>Location</u>	<u>County/Zone</u>	<u>St.</u>	<u>Date</u>	<u>Time</u>	<u>Type</u>	<u>Mag</u>	<u>Dth</u>	<u>Inj</u>	<u>PrD</u>	<u>CrD</u>
Totals:							0	0	0.00K	6.030M
WALTON (ZONE)	WALTON (ZONE)	GA	09/01/1997	00:00	Drought		0	0	0.00K	1.670M
WALTON (ZONE)	WALTON (ZONE)	GA	05/01/1999	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	08/01/1999	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	02/01/2000	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	04/01/2000	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	05/01/2000	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	06/01/2000	00:00	Drought		0	0	0.00K	4.360M
WALTON (ZONE)	WALTON (ZONE)	GA	07/01/2000	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	10/01/2000	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	10/01/2001	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	11/01/2001	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/01/2001	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	04/01/2002	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	08/01/2002	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/01/2003	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	03/01/2004	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	05/01/2007	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	09/01/2007	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	10/01/2007	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	11/01/2007	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/01/2007	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	06/01/2016	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	07/01/2016	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	08/01/2016	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	09/01/2016	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	10/01/2016	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	11/01/2016	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/01/2016	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	01/01/2017	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	02/01/2017	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	03/01/2017	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	09/24/2019	00:00	Drought		0	0	0.00K	0.00K

WALTON (ZONE)	WALTON (ZONE)	GA	10/01/2019	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	11/01/2019	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	11/21/2023	00:00	Drought		0	0	0.00K	0.00K
WALTON (ZONE)	WALTON (ZONE)	GA	12/01/2023	00:00	Drought		0	0	0.00K	0.00K

Tornadoes

<u>Location</u>	<u>County/Zone</u>	<u>St.</u>	<u>Date</u>	<u>Time</u>	<u>T.Z.</u>	<u>Type</u>	<u>Mag</u>	<u>Dth</u>	<u>Inj</u>	<u>PrD</u>	<u>CrD</u>
Totals:								0	12	6.590M	0.00K
WALTON CO.	WALTON CO.	GA	02/10/1990	05:15	EST	Tornado	F1	0	0	250.00K	0.00K
Bold Springs	WALTON CO.	GA	06/27/1994	02:40	EST	Tornado	F1	0	9	500.00K	0.00K
Monroe to	WALTON CO.	GA	06/27/1994	05:30	EST	Tornado	F0	0	0	500.00K	0.00K
Conyers	WALTON CO.	GA	06/27/1994	07:00	EST	Tornado	F1	0	3	5.000M	0.00K
SOCIAL CIRCLE	WALTON CO.	GA	08/29/2005	21:25	EST	Tornado	F0	0	0	25.00K	0.00K
WALNUT GROVE	WALTON CO.	GA	04/05/2017	11:10	EST-5	Tornado	EF1	0	0	15.00K	0.00K
HERNDONVILLE	WALTON CO.	GA	08/01/2018	18:32	EST-5	Tornado	EF1	0	0	200.00K	0.00K
GRATIS	WALTON CO.	GA	05/03/2021	11:39	EST-5	Tornado	EF0	0	0	100.00K	0.00K

Appendix C – Worksheet 3As

GEMA Worksheet #3a

Inventory of Assets

Jurisdiction: Walton County

Hazard: Non-Spatially Defined Hazard

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	54,128	54,128	100.000%	9,254,891,473	9,254,891,473	100.000%	108,702	108,702	100%
Commercial	3,479	3,479	100.000%	635,070,925	635,070,925	100.000%	0	0	#DIV/0!
Industrial	549	549	100.000%	356,587,102	356,587,102	100.000%	0	0	#DIV/0!
Agricultural	2,542	2,542	100.000%	319,285,617	319,285,617	100.000%	0	0	#DIV/0!
Religious/ Non-profit	933	933	100.000%	165,011,400	165,011,400	100.000%	0	0	#DIV/0!
Government	1,179	1,179	100.000%	437,923,035	437,923,035	100.000%	0	0	#DIV/0!
Education	314	314	100.000%	199,680,237	199,680,237	100.000%	0	0	#DIV/0!
Utilities	60	60	100.000%	327,630,922	327,630,922	100.000%	0	0	#DIV/0!
Total	63,182	63,182	100.000%	11,695,880,711	11,695,880,711	100.000%	108,702	108,702	100%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | | N |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | | N |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | | N |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a
Jurisdiction: Walton County
Hazard: Wildfire Hazard

Inventory of Assets

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	54,126	15,749	29.097%	9,254,891,473	2,662,830,359	29.097%	106,702	31,047	29%
Commercial	3,479	477	13.711%	635,070,925	87,073,538	13.711%	0	0	#DIV/0!
Industrial	549	33	6.011%	356,587,102	21,434,197	6.011%	0	0	#DIV/0!
Agricultural	2,542	1,745	68.647%	319,265,617	219,165,422	68.647%	0	0	#DIV/0!
Religious/ Non-profit	933	195	20.900%	165,011,400	34,487,913	20.900%	0	0	#DIV/0!
Government	1,179	202	17.133%	437,923,035	75,030,070	17.133%	0	0	#DIV/0!
Education	314	41	13.057%	199,880,237	26,072,897	13.057%	0	0	#DIV/0!
Utilities	60	12	20.000%	327,830,922	65,526,184	20.000%	0	0	#DIV/0!
Total	63,182	18,454	29.208%	11,695,880,711	3,221,820,579	27.546%	106,702	31,047	29%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a**Inventory of Assets****Jurisdiction: Walton County****Hazard: Flood Hazard**

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	54,128	789	1.421%	9,254,891,473	36,756,897	0.397%	108,702	1,516	1%
Commercial	3,479	9	0.259%	635,070,925	228,875	0.036%	0	0	#DIV/0!
Industrial	549	5	0.911%	368,587,102	63,156	0.018%	0	0	#DIV/0!
Agricultural	2,542	0	0.000%	319,265,617	0	0.000%	0	0	#DIV/0!
Religious/ Non-profit	933	2	0.214%	185,011,400	22,897	0.014%	0	0	#DIV/0!
Government	1,179	1	0.085%	437,923,035	4,996	0.001%	0	0	#DIV/0!
Education	314	0	0.000%	199,680,237	0	0.000%	0	0	#DIV/0!
Utilities	60	0	0.000%	327,630,922	0	0.000%	0	0	#DIV/0!
Total	63,182	796	1.244%	11,695,880,711	37,074,421	0.317%	108,702	1,516	1%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | Y | |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | Y | |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a Inventory of Assets**Jurisdiction: Loganville (Walton County)****Hazard: Wildfire Hazard****Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.**

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	3,965	1,098	27.692%	965,526,947	272,915,155	27.692%	15,336	4,247	28%
Commercial	741	71	9.582%	230,563,165	22,091,747	9.582%	0	0	#DIV/0!
Industrial	20	1	5.000%	782,920	39,146	5.000%	0	0	#DIV/0!
Agricultural	1	1	100.000%	189,600	189,600	100.000%	0	0	#DIV/0!
Religious/ Non-profit	95	12	12.632%	25,003,500	3,158,337	12.632%	0	0	#DIV/0!
Government	137	11	8.029%	31,505,032	2,529,601	8.029%	0	0	#DIV/0!
Education	63	3	4.762%	30,495,770	1,462,180	4.762%	0	0	#DIV/0!
Utilities	7	0	0.000%	9,896,850	0	0.000%	0	0	#DIV/0!
Total	5,029	1,197	23.802%	1,313,963,784	302,375,765	23.012%	15,336	4,247	28%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a **Inventory of Assets**
Jurisdiction: Loganville (Walton County)
Hazard: Non-Spatially Defined Hazard

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community or State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	3,965	3,965	100.000%	985,528,947	985,528,947	100.000%	15,336	15,336	100%
Commercial	741	741	100.000%	230,563,165	230,563,165	100.000%	0	0	#DIV/0!
Industrial	20	20	100.000%	782,920	782,920	100.000%	0	0	#DIV/0!
Agricultural	1	1	100.000%	189,600	189,600	100.000%	0	0	#DIV/0!
Religious/ Non-profit	95	95	100.000%	25,003,500	25,003,500	100.000%	0	0	#DIV/0!
Government	137	137	100.000%	31,505,032	31,505,032	100.000%	0	0	#DIV/0!
Education	63	63	100.000%	30,495,770	30,495,770	100.000%	0	0	#DIV/0!
Utilities	7	7	100.000%	9,896,850	9,896,850	100.000%	0	0	#DIV/0!
Total	5,029	5,029	100.000%	1,313,963,784	1,313,963,784	100.000%	15,336	15,336	100%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | Y | N |
|---|---|---|
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | | N |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | | N |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | | N |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a **Inventory of Assets**
Jurisdiction: Loganville (Walton County)
Hazard: Flood Hazard

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	3,965	146	3.682%	965,526,947	3,178,956	0.323%	15,336	565	4%
Commercial	741	0	0.000%	230,563,166	0	0.000%	0	0	#DIV/0!
Industrial	20	0	0.000%	782,920	0	0.000%	0	0	#DIV/0!
Agricultural	1	0	0.000%	189,600	0	0.000%	0	0	#DIV/0!
Religious/ Non-profit	95	0	0.000%	25,003,500	0	0.000%	0	0	#DIV/0!
Government	137	0	0.000%	31,505,032	0	0.000%	0	0	#DIV/0!
Education	63	0	0.000%	30,495,770	0	0.000%	0	0	#DIV/0!
Utilities	7	0	0.000%	9,896,850	0	0.000%	0	0	#DIV/0!
Total	5,029	146	2.903%	1,313,963,784	3,178,956	0.242%	15,336	565	4%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | Y | |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | Y | |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a**Inventory of Assets****Jurisdiction: Monroe (Walton County)****Hazard: Non-Spatially Defined Hazard****Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.**

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community or State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	5,888	5,888	100.000%	961,745,057	961,745,057	100.000%	15,336	15,336	100%
Commercial	1,320	1,320	100.000%	255,804,952	255,804,952	100.000%	0	0	#DIV/0!
Industrial	161	161	100.000%	74,315,145	74,315,145	100.000%	0	0	#DIV/0!
Agricultural	12	12	100.000%	2,550,060	2,550,060	100.000%	0	0	#DIV/0!
Religious/ Non-profit	227	227	100.000%	40,355,907	40,355,907	100.000%	0	0	#DIV/0!
Government	430	430	100.000%	113,484,865	113,484,865	100.000%	0	0	#DIV/0!
Education	64	64	100.000%	38,123,707	38,123,707	100.000%	0	0	#DIV/0!
Utilities	11	11	100.000%	22,163,165	22,163,165	100.000%	0	0	#DIV/0!
Total	8,113	8,113	100.000%	1,508,542,858	1,508,542,858	100.000%	15,336	15,336	100%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | | N |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | | N |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | | N |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a**Inventory of Assets****Jurisdiction: Monroe (Walton County)****Hazard: Wildfire Hazard**

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community or State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	5,888	1,641	27.870%	961,745,057	268,040,699	27.870%	15,336	4,274	28%
Commercial	1,320	194	14.697%	255,804,952	37,595,576	14.697%	0	0	#DIV/0!
Industrial	161	12	7.453%	74,315,145	5,539,017	7.453%	0	0	#DIV/0!
Agricultural	12	11	91.667%	2,550,060	2,337,555	91.667%	0	0	#DIV/0!
Religious/ Non-profit	227	18	7.930%	40,355,907	3,200,028	7.930%	0	0	#DIV/0!
Government	430	43	10.000%	113,484,885	11,348,487	10.000%	0	0	#DIV/0!
Education	64	3	4.688%	38,123,707	1,787,049	4.688%	0	0	#DIV/0!
Utilities	11	1	9.091%	22,183,166	2,014,833	9.091%	0	0	#DIV/0!
Total	8,113	1,923	23.703%	1,508,542,858	331,863,244	21.999%	15,336	4,274	28%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a**Inventory of Assets****Jurisdiction: Monroe (Walton County)****Hazard: Flood Hazard**

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	5,888	42	0.713%	981,745,057	2,146,477	0.223%	15,336	109	1%
Commercial	1,320	2	0.152%	255,804,952	51,356	0.020%	0	0	#DIV/0!
Industrial	161	5	3.106%	74,315,145	63,156	0.085%	0	0	#DIV/0!
Agricultural	12	0	0.000%	2,550,060	0	0.000%	0	0	#DIV/0!
Religious/ Non-profit	227	0	0.000%	40,355,907	0	0.000%	0	0	#DIV/0!
Government	430	0	0.000%	113,484,865	0	0.000%	0	0	#DIV/0!
Education	64	0	0.000%	38,123,707	0	0.000%	0	0	#DIV/0!
Utilities	11	0	0.000%	22,163,165	0	0.000%	0	0	#DIV/0!
Total	8,113	49	0.604%	1,508,542,858	2,261,029	0.150%	15,336	109	1%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | Y | |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | Y | |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a Inventory of Assets**Jurisdiction: Social Circle (Walton County)****Hazard: Non-Spatially Defined Hazard****Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.**

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	2,573	2,573	100.000%	366,583,392	366,583,392	100.000%	5,113	5,113	100%
Commercial	206	206	100.000%	27,336,932	27,336,932	100.000%	0	0	#DIV/0!
Industrial	165	165	100.000%	84,654,202	84,654,202	100.000%	0	0	#DIV/0!
Agricultural	58	58	100.000%	5,936,965	5,936,965	100.000%	0	0	#DIV/0!
Religious/ Non-profit	61	61	100.000%	11,165,940	11,165,940	100.000%	0	0	#DIV/0!
Government	177	177	100.000%	19,698,830	19,698,830	100.000%	0	0	#DIV/0!
Education	51	51	100.000%	21,652,550	21,652,550	100.000%	0	0	#DIV/0!
Utilities	11	11	100.000%	11,087,880	11,087,880	100.000%	0	0	#DIV/0!
Total	3,302	3,302	100.000%	538,116,691	538,116,691	100.000%	5,113	5,113	100%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | | N |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | | N |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | | N |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a **Inventory of Assets**
Jurisdiction: Social Circle (Walton County)
Hazard: Wildfire Hazard

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	2,573	574	22.309%	366,583,392	79,548,724	22.309%	5,113	1,141	22%
Commercial	206	25	12.136%	27,336,932	3,317,589	12.136%	0	0	#DIV/0!
Industrial	165	12	7.273%	84,654,202	6,156,669	7.273%	0	0	#DIV/0!
Agricultural	58	47	81.034%	5,936,966	4,810,989	81.034%	0	0	#DIV/0!
Religious/ Non-profit	61	4	6.557%	11,165,940	732,193	6.557%	0	0	#DIV/0!
Government	177	17	9.605%	19,698,830	1,891,978	9.605%	0	0	#DIV/0!
Education	51	4	7.843%	21,652,550	1,698,239	7.843%	0	0	#DIV/0!
Utilities	11	1	9.091%	11,087,880	1,007,989	9.091%	0	0	#DIV/0!
Total	3,302	694	20.715%	538,116,691	99,164,370	18.428%	5,113	1,141	22%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a Inventory of Assets**Jurisdiction: Social Circle (Walton County)****Hazard: Flood Hazard****Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.**

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	2,573	7	0.272%	358,583,392	281,293	0.073%	5,113	14	0%
Commercial	208	0	0.000%	27,338,932	0	0.000%	0	0	#DIV/0!
Industrial	165	0	0.000%	84,854,202	0	0.000%	0	0	#DIV/0!
Agricultural	58	0	0.000%	5,935,965	0	0.000%	0	0	#DIV/0!
Religious/ Non-profit	81	0	0.000%	11,185,940	0	0.000%	0	0	#DIV/0!
Government	177	0	0.000%	19,698,830	0	0.000%	0	0	#DIV/0!
Education	51	0	0.000%	21,852,550	0	0.000%	0	0	#DIV/0!
Utilities	11	0	0.000%	11,087,880	0	0.000%	0	0	#DIV/0!
Total	3,302	7	0.212%	538,116,691	281,293	0.049%	5,113	14	0%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | Y | |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a Inventory of Assets**Jurisdiction: Walnut Grove (Walton County)****Hazard: Non-Spatially Defined Hazard****Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.**

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community or State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	828	828	100.000%	127,032,180	127,032,180	100.000%	1,594	1,594	100%
Commercial	78	78	100.000%	6,483,190	6,483,190	100.000%	0	0	#DIV/0!
Industrial	26	26	100.000%	1,911,590	1,911,590	100.000%	0	0	#DIV/0!
Agricultural	10	10	100.000%	785,880	785,880	100.000%	0	0	#DIV/0!
Religious/ Non-profit	20	20	100.000%	3,851,560	3,851,560	100.000%	0	0	#DIV/0!
Government	52	52	100.000%	4,894,270	4,894,270	100.000%	0	0	#DIV/0!
Education	13	13	100.000%	20,782,200	20,782,200	100.000%	0	0	#DIV/0!
Utilities	5	5	100.000%	2,563,212	2,563,212	100.000%	0	0	#DIV/0!
Total	1,032	1,032	100.000%	188,284,062	188,284,062	100.000%	1,594	1,594	100%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | | N |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | | N |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | | N |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a Inventory of Assets**Jurisdiction: Walnut Grove (Walton County)****Hazard: Wildfire Hazard****Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.**

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community or State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	828	408	49.275%	127,032,180	62,595,557	49.275%	1,594	785	49%
Commercial	78	24	30.769%	6,463,190	1,968,874	30.769%	0	0	#DIV/0!
Industrial	26	7	26.923%	1,911,590	514,859	26.923%	0	0	#DIV/0!
Agricultural	10	8	80.000%	785,880	628,704	80.000%	0	0	#DIV/0!
Religious/ Non-profit	20	6	30.000%	3,851,560	1,155,468	30.000%	0	0	#DIV/0!
Government	52	7	13.462%	4,894,270	658,844	13.462%	0	0	#DIV/0!
Education	13	2	15.385%	20,782,200	3,197,282	15.385%	0	0	#DIV/0!
Utilities	5	1	20.000%	2,583,212	512,642	20.000%	0	0	#DIV/0!
Total	1,032	483	44.894%	188,284,082	71,251,810	42.340%	1,594	785	49%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a **Inventory of Assets**
Jurisdiction: Walnut Grove (Walton County)
Hazard: Flood Hazard

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	828	0	0.000%	127,032,160	0	0.000%	1,594	0	0%
Commercial	78	0	0.000%	6,463,190	0	0.000%	0	0	#DIV/0!
Industrial	26	0	0.000%	1,911,590	0	0.000%	0	0	#DIV/0!
Agricultural	10	0	0.000%	785,880	0	0.000%	0	0	#DIV/0!
Religious/ Non-profit	20	0	0.000%	3,851,560	0	0.000%	0	0	#DIV/0!
Government	52	0	0.000%	4,894,270	0	0.000%	0	0	#DIV/0!
Education	13	0	0.000%	20,782,200	0	0.000%	0	0	#DIV/0!
Utilities	5	0	0.000%	2,563,212	0	0.000%	0	0	#DIV/0!
Total	1,032	0	0.000%	168,284,062	0	0.000%	1,594	0	0%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a**Inventory of Assets****Jurisdiction: Between (Walton County)****Hazard: Non-Spatially Defined Hazard****Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.**

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community or State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	228	228	100.000%	48,615,717	48,615,717	100.000%	494	494	100%
Commercial	29	29	100.000%	4,854,850	4,854,850	100.000%	0	0	#DIV/0!
Industrial	0	0	#DIV/0!	0	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!
Agricultural	9	9	100.000%	834,720	834,720	100.000%	0	0	#DIV/0!
Religious/ Non-profit	20	20	100.000%	4,340,000	4,340,000	100.000%	0	0	#DIV/0!
Government	20	20	100.000%	2,961,000	2,961,000	100.000%	0	0	#DIV/0!
Education	0	0	#DIV/0!	0	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!
Utilities	1	1	100.000%	70,190	70,190	100.000%	0	0	#DIV/0!
Total	307	307	100.000%	61,676,477	#DIV/0!	#DIV/0!	494	#DIV/0!	#DIV/0!

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | | N |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | | N |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | | N |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a**Inventory of Assets****Jurisdiction: Between (Walton County)****Hazard: Wildfire Hazard**

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	228	82	35.96%	48,815,717	17,484,800	35.96%	494	178	36%
Commercial	29	8	20.89%	4,854,850	1,004,452	20.89%	0	0	#DIV/0!
Industrial	0	0	#DIV/0!	0	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!
Agricultural	9	9	100.00%	834,720	834,720	100.00%	0	0	#DIV/0!
Religious/ Non-profit	20	1	5.00%	4,340,000	217,000	5.00%	0	0	#DIV/0!
Government	20	4	20.00%	2,981,000	592,200	20.00%	0	0	#DIV/0!
Education	0	0	#DIV/0!	0	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!
Utilities	1	0	0.00%	70,190	0	0.00%	0	0	#DIV/0!
Total	307	102	33.22%	61,676,477	#DIV/0!	#DIV/0!	494	#DIV/0!	#DIV/0!

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a **Inventory of Assets**
Jurisdiction: Between (Walton County)
Hazard: Flood Hazard

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	228	0	0.000%	48,815,717	0	0.000%	494	0	0%
Commercial	29	0	0.000%	4,854,850	0	0.000%	0	0	#DIV/0!
Industrial	0	0	#DIV/0!	0	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!
Agricultural	9	0	0.000%	834,720	0	0.000%	0	0	#DIV/0!
Religious/ Non-profit	20	0	0.000%	4,340,000	0	0.000%	0	0	#DIV/0!
Government	20	0	0.000%	2,961,000	0	0.000%	0	0	#DIV/0!
Education	0	0	#DIV/0!	0	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!
Utilities	1	0	0.000%	70,190	0	0.000%	0	0	#DIV/0!
Total	307	0	0.000%	61,876,477	#DIV/0!	#DIV/0!	494	#DIV/0!	#DIV/0!

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a **Inventory of Assets**
Jurisdiction: Good Hope (Walton County)
Hazard: Non-Spatially Defined Hazard

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community or State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	272	272	100.000%	38,541,855	38,541,855	100.000%	478	478	100%
Commercial	15	15	100.000%	1,302,020	1,302,020	100.000%	0	0	#DIV/0!
Industrial	4	4	100.000%	213,210	213,210	100.000%	0	0	#DIV/0!
Agricultural	5	5	100.000%	1,787,232	1,787,232	100.000%	0	0	#DIV/0!
Religious/ Non-profit	10	10	100.000%	1,076,840	1,076,840	100.000%	0	0	#DIV/0!
Government	7	7	100.000%	350,400	350,400	100.000%	0	0	#DIV/0!
Education	2	2	100.000%	0	153,900	#DIV/0!	0	0	#DIV/0!
Utilities	1	1	100.000%	113,855	113,855	100.000%	0	0	#DIV/0!
Total	318	318	100.000%	43,385,412	43,539,312	100.355%	478	478	100%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | | N |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | | N |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | | N |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a Inventory of Assets**Jurisdiction: Good Hope (Walton County)****Hazard: Wildfire Hazard****Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.**

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	272	81	29.779%	38,541,855	11,477,538	29.779%	479	143	30%
Commercial	15	2	13.333%	1,302,020	173,603	13.333%	0	0	#DIV/0!
Industrial	4	0	0.000%	213,210	0	0.000%	0	0	#DIV/0!
Agricultural	5	5	100.000%	1,787,232	1,787,232	100.000%	0	0	#DIV/0!
Religious/ Non-profit	10	0	0.000%	1,076,840	0	0.000%	0	0	#DIV/0!
Government	7	2	28.571%	350,400	100,114	28.571%	0	0	#DIV/0!
Education	2	0	0.000%	0	153,900	#DIV/0!	0	0	#DIV/0!
Utilities	1	0	0.000%	113,855	0	0.000%	0	0	#DIV/0!
Total	318	90	28.461%	43,385,412	13,692,387	31.560%	479	143	30%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a Inventory of Assets**Jurisdiction: Good Hope (Walton County)****Hazard: Flood Hazard****Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.**

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	272	2	0.735%	38,541,855	78,698	0.204%	479	4	1%
Commercial	15	0	0.000%	1,302,020	0	0.000%	0	0	#DIV/0!
Industrial	4	0	0.000%	213,210	0	0.000%	0	0	#DIV/0!
Agricultural	5	0	0.000%	1,787,232	0	0.000%	0	0	#DIV/0!
Religious/ Non-profit	10	0	0.000%	1,076,840	0	0.000%	0	0	#DIV/0!
Government	7	0	0.000%	350,400	0	0.000%	0	0	#DIV/0!
Education	2	0	0.000%	0	153,900	#DIV/0!	0	0	#DIV/0!
Utilities	1	0	0.000%	113,855	0	0.000%	0	0	#DIV/0!
Total	318	2	0.633%	43,385,412	232,598	0.536%	479	4	1%

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | Y | |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a**Inventory of Assets****Jurisdiction: Jersey (Walton County)****Hazard: Non-Spatially Defined Hazard****Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.**

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community or State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	124	124	100.000%	8,537,887	8,537,887	100.000%	148	148	100%
Commercial	18	18	100.000%	1,471,040	1,471,040	100.000%	0	0	#DIV/0!
Industrial	0	0	#DIV/0!	0	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!
Agricultural	14	14	100.000%	635,060	635,060	100.000%	0	0	#DIV/0!
Religious/ Non-profit	5	5	100.000%	288,250	288,250	100.000%	0	0	#DIV/0!
Government	8	8	100.000%	196,510	196,510	100.000%	0	0	#DIV/0!
Education	2	2	100.000%	0	153,900	#DIV/0!	0	0	#DIV/0!
Utilities	1	1	100.000%	9,775	9,775	100.000%	0	0	#DIV/0!
Total	172	172	100.000%	11,138,522	#DIV/0!	#DIV/0!	148	#DIV/0!	#DIV/0!

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | | N |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | | N |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | | N |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a**Inventory of Assets****Jurisdiction: Jersey (Walton County)****Hazard: Wildfire Hazard**

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community or State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	124	51	41.129%	8,537,887	3,511,550	41.129%	148	60	41%
Commercial	18	3	16.667%	1,471,040	245,173	16.667%	0	0	#DIV/0!
Industrial	0	0	#DIV/0!	0	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!
Agricultural	14	12	85.714%	635,060	544,337	85.714%	0	0	#DIV/0!
Religious/ Non-profit	5	3	60.000%	288,250	171,750	60.000%	0	0	#DIV/0!
Government	8	2	25.000%	196,510	49,128	25.000%	0	0	#DIV/0!
Education	2	2	100.000%	0	153,900	#DIV/0!	0	0	#DIV/0!
Utilities	1	1	100.000%	9,775	9,775	100.000%	0	0	#DIV/0!
Total	172	74	43.023%	11,136,522	#DIV/0!	#DIV/0!	148	#DIV/0!	#DIV/0!

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

GEMA Worksheet #3a **Inventory of Assets**
Jurisdiction: Jersey (Walton County)
Hazard: Flood Hazard

Task A. Determine the proportion of buildings, the value of buildings, and the population in your community or state that are located in hazard areas.

Type of Structure (Occupancy Class)	Number of Structures			Value of Structures			Number of People		
	# in Community of State	# in Hazard Area	% in Hazard Area	\$ in Community or State	\$ in Hazard Area	% in Hazard Area	# in Community or State	# in Hazard Area	% in Hazard Area
Residential	124	0	0.000%	8,537,887	0	0.000%	146	0	0%
Commercial	18	0	0.000%	1,471,040	0	0.000%	0	0	#DIV/0!
Industrial	0	0	#DIV/0!	0	#DIV/0!	#DIV/0!	0	#DIV/0!	#DIV/0!
Agricultural	14	0	0.000%	635,060	0	0.000%	0	0	#DIV/0!
Religious/ Non-profit	5	0	0.000%	288,250	0	0.000%	0	0	#DIV/0!
Government	8	0	0.000%	198,510	0	0.000%	0	0	#DIV/0!
Education	2	0	0.000%	0	153,900	#DIV/0!	0	0	#DIV/0!
Utilities	1	0	0.000%	9,775	0	0.000%	0	0	#DIV/0!
Total	172	0	0.000%	11,138,522	#DIV/0!	#DIV/0!	146	#DIV/0!	#DIV/0!

Task B. Determine whether (and where) you want to collect additional inventory data.

- | | | |
|---|----------|----------|
| | Y | N |
| 1. Do you know where the greatest damages may occur in your area? | | N |
| 2. Do you know whether your critical facilities will be operational after a hazard event? | | N |
| 3. Is there enough data to determine which assets are subject to the greatest potential damages? | Y | |
| 4. Is there enough data to determine whether significant elements of the community are vulnerable to potential hazards? | Y | |
| 5. Is there enough data to determine whether certain areas of historic, environmental, political, or cultural significance are vulnerable to potential hazards? | Y | |
| 6. Is there concern about a particular hazard because of its severity, repetitiveness, or likelihood of occurrence? | | N |
| 7. Is additional data needed to justify the expenditure of community or state funds for mitigation initiatives? | | N |

Appendix D – Documentation of Peer Review

Barrow County

Morgan County

Newton County

Oconee County

Rockdale County

Appendix E – Walton County HAZUS Report



MEMORANDUM

To: County Chairman, Sole Commissioners and CEOs
Mayors of Consolidated Governments
c/o County Clerks, Managers or Administrators

From: Dave Wills, Executive Director

Date: **July 16, 2026**

Subject: Legislative Leadership Conference Business Session

This is the official call for the business session at the ACCG Legislative Leadership Conference scheduled for Thursday, October 8th at The Classic Center, 300 N. Thomas St., Athens, Georgia 30601. The purpose of this session is to consider 2027 Policy Priorities to be adopted by the membership and other business that may come before the body. Each county governing authority may appoint a voting delegate (*commissioner or county staff*) to cast its county's vote on matters coming before the membership at the business session.

Please note that cellular devices will be used to cast votes and delegates must be able to access their email accounts onsite.

In order for ACCG staff to conduct the voting process as smoothly as possible, we need the name of your county's delegate before the conference convenes. Credentials pickup will be announced once the conference agenda is finalized.

Please complete and return this page via email as a pdf attachment no later than Friday, August 28th to Stephanie Wright at swright@accg.org. Your prompt attention to this matter is greatly appreciated.

2026 LEGISLATIVE LEADERSHIP CONFERENCE VOTING DELEGATE FORM

Lee Bradford
Name (First & Last Name)

Commissioner, Dist 4
Title & email address

Walton
County

Walton County Department Agenda Request

Department Name: **Fire Rescue**

Department Head/Representative: **Kevin Haney**

Meeting Date Request: **10/6/2026**

Has this topic been discussed at past meetings? **no**

If so, When?

TOPIC: **Donated equipment**

Wording For Agenda: **Equipment donation from Takeda**

This Request: **Informational Purposes Only**

Needs Action by Commissioners* **Yes**

*What action are you seeking from the Commissioners? **Accept and approve**

Department Comments/Recommendation: **approve**

Additional Documentation Attached? **Letter to the board of the equipment donated and estimated cost.**

Is review of this request or accompanying documentation by the County Attorney required? **no**

If so, has a copy of the documentation been forwarded to County Attorney?

Date forwarded to County Attorney:

Has the County Attorney review been completed?

If this request involves the expenditure of county funds, please answer the following:

Approved in current budget?

Budget information attached?

Comments: **N/A**

Purchasing Department Comments:

County Attorney Comments:

Chairman's Comments:



303 South Hammond Dr.
Dept. 460
Monroe, Georgia 30655

Office 770.267.1315
770.267.1311
Fax 770.267.1405

Walton County Fire Rescue

To: Walton County Board of Commission

From: Kevin Haney, Fire Chief

Ref: Donated Equipment

Walton County Fire Rescue recently received a donation of equipment and firefighting turnout gear from Takeda Pharmaceuticals in Social Circle, Georgia. The following equipment was donated:

- 1 Turnout Gear Washer
- 18 Turnout Gear Lockers
- 10 sets of new firefighting turnout gear.
- 13 sets of used firefighting turnout gear
- 18 pairs of firefighting turnout boots
- 6 fire helmets
- 4 pairs of firefighting gloves

Altogether the donated equipment has an approximate value of nearly \$100,000 dollars.

The equipment and gear donated will be utilized by our training division for our fire recruit class and for our High School Intern class.

A handwritten signature in blue ink, appearing to read "Kevin Haney".

Walton County Department Agenda Request

Department Name: **Walton County Sheriff's Office**

Department Head/Representative: **Kim McCord**

Meeting Date Request: **10/06/2026**

Has this topic been discussed at past meetings? **Yes**

If so, When? **June 2025, April 2026 and July 2026**

TOPIC: **Requesting to Donate 2027 Ford Expedition w/ equipment (Fire Dept.) as Capital Asset**

Wording For Agenda: **DBB Donation of 2027 Ford Expedition**

This Request: Informational Purposes Only Needs Action by Commissioners* **Yes**

*What action are you seeking from the Commissioners? **Acceptance**

Department Comments/Recommendation: **Deputies Beyond the Badge non-profit purchased a 2027 Ford Expedition with equipment and is requesting the vehicle to be donated to the Walton County Board of Commissioners for use at the Walton County Fire Department**

Additional Documentation Attached? **Letter from Deputies Beyond the Badge and Loganville Ford Purchase Agreement**

Is review of this request or accompanying documentation by the County Attorney required? **No**

If so, has a copy of the documentation been forwarded to County Attorney?

Date forwarded to County Attorney:

Has the County Attorney review been completed?

If this request involves the expenditure of county funds, please answer the following:

Approved in current budget?

Budget information attached?

Comments:

Purchasing Department Comments:

County Attorney Comments:

Chairman's Comments:



DEPUTIES BEYOND THE BADGE

350 Georgia Ave, Monroe GA 30655

September 24, 2026

To: Walton County Board of Commissioners
303 South Hammond Drive, Suite 330
Monroe, GA 30655

Dear Board of Commissioners,

Deputies Beyond the Badge is pleased to continue its mission of supporting the Walton County Sheriff's Office along with all other First Responders that serve Walton County. In this support, please accept the donation of a 2027 Ford Expedition VIN 1FMJU1G89VEA16410 for the sole use of the Walton County Fire Department to further assist them in serving the citizens of Walton County.

Regards,

Ashley Knight
President

LOGANVILLE FORD

3460 ATLANTA HWY
LOGANVILLE GA 30052
770-554-9994

W.C.F.D. - FM#2604

RETAIL PURCHASE AGREEMENT

Dealership License #: N/A

Cust#: XHA86526

Deal #: 77896Purchaser's Name(s): WALTON COUNTY BD OF COMMISSIONERSDate: 08/27/2026Address: 303 S HAMMOND DR STE 330 MONROE GA 30655-2904County: WALTONTelephone (1): 770-267-6557

Telephone (2): _____

DOB: _____

E-mail: kim.mccord@co.walton.ga.us

D.L./State I.D.#: _____

Issuing State: _____

Exp. Date: _____

The above information has been requested so that we may verify your identity. By signing below, you represent that you are at least 18 years of age and have authority to enter into this Agreement. The Odometer Reading for the Vehicle you are purchasing is accurate unless indicated otherwise. Please refer to the Federal Mileage Statement for full disclosure.

YEAR 2027	MAKE FORD	MODEL EXPEDITION	COLOR OXFORD WHITE	STOCK NO. VEA16410
VIN/SERIAL NO. 1FMJU1G89VEA16410		ODOMETER READING ☐ Not Accurate 11	SALESPERSON DAVID A GUNTER	
THE VEHICLE IS: ☒ NEW ☐ USED		PRIOR USE DISCLOSURE: ☐ DEMONSTRATOR ☐ FACTORY OFFICIAL ☐ RENTAL ☐ OTHER		
WARRANTY STATEMENT			CASH PRICE OF VEHICLE	55910.00
We are selling this Vehicle to you AS-IS and we expressly disclaim all warranties, express and implied, including any implied warranties of merchantability and fitness for a particular purpose, unless the box beside the "Used Vehicle Limited Warranty Applies" is marked below, or we enter into a service contract with you at the time of, or within 90 days of, the date of this transaction. Any warranties by a manufacturer or supplier other than our Dealership are theirs, <u>not</u> ours, and only such manufacturer or supplier shall be liable for performance under such warranties. We neither assume nor authorize any other person to assume for us any liability in connection with the sale of the Vehicle and the related goods and services. CONTRACTUAL DISCLOSURE STATEMENT (USED VEHICLES ONLY) The information you see on the window form for this Vehicle is part of this contract. Information on the window form overrides any contrary provisions in the contract of sale. Guía para compradores de vehículos usados. La información que ve en el formulario de la ventanilla para este vehículo forma parte del presente contrato. La información del formulario de la ventanilla deja sin efecto toda disposición en contrario contenida en el contrato de venta. ☐ We are providing a Used Vehicle Limited Warranty in connection with this transaction. Any implied warranties apply for the duration of the Limited Warranty.			N/A	N/A
			WINDOW TINT	650.00
			N/A	N/A
			N/A	N/A
			N/A	N/A
			N/A	N/A
			N/A	N/A
			N/A	N/A
			N/A	N/A
			TRADE-IN VEHICLE INFORMATION	
Year:	Make:	Model:	Color:	
N/A	N/A	N/A	N/A	
VIN/Serial No.:	Odometer Reading:			
N/A	☐ Not Accurate		N/A	
Trade-In Allowance:	Balance Owed & Lienholder:			
N/A	N/A			
OTHER MATERIAL UNDERSTANDINGS AND INTEGRATED DOCUMENTS			N/A	N/A
☐ IF BOX IS MARKED, PLEASE SEE THE DELIVERY CONFIRMATION			N/A	N/A
☐ IF BOX IS MARKED, PLEASE SEE THE CONDITIONAL (SPOT) DELIVERY AGREEMENT			TOTAL DUE	56560.00
The Deposit/Down Payment received from you is <u>not</u> refundable, except as set forth in this Retail Purchase Agreement. In the case of a Deposit, we will hold the Vehicle for <u>N/A</u> days. X _____			LESS DEPOSIT/DOWN PAYMENT	N/A
			LESS REBATE	N/A
			N/A	N/A
			LESS CASH DUE AT DELIVERY	N/A
☐ If this box is marked, the Vehicle you are purchasing must pass an Emissions Inspection. Please see the attached Certificate of Emission Inspection or Waiver.			AMOUNT TO BE FINANCED (See Paragraphs 11 and 14)	56560.00

This agreement and any documents which are part of this transaction or incorporated herein comprise the entire agreement affecting this Retail Purchase Agreement and no other agreement or understanding of any nature concerning the same has been made or entered into or will be recognized. I have read and accept all of the terms and conditions of this Agreement, and agree to them as if they were printed above my signature. I further acknowledge receipt of a copy of this Agreement. This Agreement shall not become binding until signed and accepted by an Authorized Dealership Representative.

Kim McCord

Purchaser

Accepted by Authorized Dealership Representative

N/A

Purchaser

DealerCAP

53187*1*LOG-FI
CATALOG #8963182

08/27/2026 09
© 2015 CDK Global, LLC Georgia

336

**CONTRIBUTION AGREEMENT GACD-02-24-007
AMENDMENT NO 1**

PURPOSE: The purpose of this amendment is to extend the current Contribution Agreement between Georgia Association of Conservation Districts (GACD) and the Walton County Board of Commissioners, entered on August 6, 2024 ("Agreement") which is currently due to expire on September 30, 2026, so that said Agreement will expire on September 30, 2027.

NOW, THEREFORE the Agreement is amended to change Section V thereof to now read as follows:

"V. PERIOD OF PERFORMANCE

- A. The expiration date of the Agreement is September 30, 2027. The Agreement is effective from the later of: 1) the date signed by both parties or 2) the 12 month period preceding the expiration date."

All other terms of the Agreement shall remain in full force and effect: IN WITNESS WHERE OF the parties have executed this amendment on _____, 2026.

Name & Title of GACD Rep

Signature

Date

David G. Thompson
Name & Title of Provider (County)

County Comm. Chair

[Signature]
Signature

9/30/2026
Date

CONTRIBUTION AGREEMENT
GACD-02-20-007
BETWEEN THE
GEORGIA ASSOCIATION OF CONSERVATION DISTRICTS, INCORPORATED
AND THE
WALTON COUNTY BOARD OF COMMISSIONERS

THIS AGREEMENT, made and entered into this 6th day of August, 2024, by and between the WALTON COUNTY BOARD OF COMMISSIONERS (hereinafter referred to as the "Provider"); and the Georgia Association Of Conservation Districts, Incorporated (hereinafter referred to as the "GACD").

I. PURPOSE:

This long-term conservation partnership serves to facilitate the implementation of planned conservation practices. This "partnership" is to assist interested landowners with the NRCS application process and conservation practice implementation. The Provider is responsible for providing technical support to participants for planned conservation as outlined in this agreement. The task involves the following technical support:

- Assisting landowners with Farm Bill Program application process
- Design and layout of conservation practices.
- Activities associated with various Farm Bill conservation programs contract development and management
- Contract planning
- Eligibility determinations
- Processing applications

All technical assistance provided must meet USDA-Natural Resources Conservation Service (NRCS) standards and specifications as set forth in its Departmental manuals, handbooks, and Field Office Technical Guide, conservation planning, conservation practice application, and other areas of technical assistance.

II. OBJECTIVES:

Under the provisions of this agreement NRCS is assigned responsibility of managing the technical assistance supplied by the Provider to landowners to plan and implement conservation practices on eligible land, manage easements, and complete evaluation and monitoring of completed practices. This agreement will support the objectives of both organizations and will leverage their capabilities to efficiently and effectively implement conservation activities as outlined in the Agriculture Improvement Act of 2018 and subsequent Farm Bills.

III. RESPONSIBILITIES OF THE PARTIES

A. GACD will

- Provide a list of program participants to county personnel contracted through the Provider, that have scheduled conservation practices, as identified in Part IV, Section

A, **Expected Accomplishments and Deliverables**, and identify and prioritize work assignments at the field office level.

- Provide technical guidance to the Provider and the county personnel maintained through this agreement when requested and provide clarity on work plan and other agreement details.
- Provide working materials and equipment needed to perform duties and to bear the cost of operation, maintenance and repair of equipment except for cost due to gross negligence by the Provider. NRCS accident reporting procedures will be followed.
- Coordinate reimbursement of the Provider on a quarterly basis upon receipt of properly completed required documentation. Documentation must include a detailed list of accomplishments utilizing the Deliverable Tracking Report as referenced in Part IV, Section A, **Expected Accomplishments and Deliverables**. GACD costs share shall not exceed the total obligation as identified in Part VI, **Resources Required**, equal to no more than **\$40,000.00**
- Review all new technologies and innovative practices, including applicable standards and specifications, prior to initiating those technologies and practices.
- Provide quality assurance for services provided under the agreement.

B. PROVIDER will:

- Provide employees to perform technical services in the State of Georgia.
- As identified in this Statement of Work, Part IV, Section A, **Expected Accomplishments and Deliverables** and Part VI, **Resources Required**, provide administrative and technical assistance to private landowners in conserving, improving, and enhancing their natural resources as well as in-kind supplies and services. The total cash supplied by the Provider will be **\$40,000.00**
- Provide technical assistance to participants as described in this Statement of Work and Part IV, Section A, **Expected Accomplishments and Deliverables**. Ensure personnel meet the GACD qualification standards for assigned responsibilities and for operation of equipment to perform those responsibilities.
- Ensure the Provider personnel maintained through this agreement, remain current with all training and certification requirements, to obtain and keep USDA NRCS Level II Computer Access current and up to date. This includes reporting changes to records and completing required Ag Learn courses when appropriate.
- Use existing NRCS policy, training procedures, and supervisory guidelines to ensure that all provided assistance meets NRCS standards.

- Comply with the special provisions included in this agreement and to work within this agreed-to **Statement of Work** and Part VI, **Resources Required**. Meet applicable NRCS standards, specifications, and program requirements. Be consistent with the conservation program goals and objectives in the agreement; and incorporate, where appropriate, low cost alternatives that would address the resource issues and meet the objectives of both the program and program participants for which assistance is provided.
- Limit request for reimbursement for technical assistance provided as described in this **Statement of Work**, Part IV, Section A, **Expected Accomplishments and Deliverables** and Part VI, **Resources Required**.
- Be responsible for gross negligence during use of any NRCS property and to reimburse the NRCS for such costs. Gross negligence is defined as willful destruction of NRCS property.
- If applicable, the Provider shall carry liability insurance to operate a government vehicle in the amount of a minimum of \$500,000 and provide a certificate of insurance to GACD. Nongovernment employees will not drive government vehicles unless proof of insurance is made available to GACD.
- Provide at least fifty (50) percent of the cost of the technical assistance listed in Part IV, Section A, **Expected Accomplishments and Deliverables**. The Provider must match the USDA funds awarded on dollar-for-dollar basis from non-Federal sources.
- Request reimbursement from GACD for GACD's share as referenced in this Statement of Work, and the **General Terms and Conditions of this Agreement**. Total reimbursement shall not exceed the GACD portion referenced in Part VI, **Resources Required**. Reimbursement shall be requested through the use of:
 - Documentation must include a detailed list of accomplishments utilizing the Deliverable Tracking Report as referenced in Part IV, Section of A, **Expected Accomplishments and Deliverables**.
 - **Deliverables Tracking Report** must be certified, signed, and dated by the appropriate Walton County official and the NRCS District Conservationist with the following statement: *"I certify that, to the best of my knowledge, this bill has not been previously submitted and that program accomplishments will meet planned activities under this agreement. I have examined and certify that this request is correct for payment."*
- Requests for Reimbursement shall be no more often than every 30 days for the period this agreement is in force
- Requests for Reimbursement shall be submitted via email to an address given.
- Warrant that the technical services provided:

- Comply with all applicable Federal, State, and Tribal and local laws and requirements;
- Are consistent with the conservation program goals and objectives in the agreement
- Incorporate, where appropriate, low-cost alternatives that would address the resource issues and meet the objectives of both the program and program participants for which assistance is provided.
- Be subject to the same rules and regulations that apply to NRCS and other USDA employees when using Government owned property or equipment.

IV. EXPECTED ACCOMPLISHMENTS AND DELIVERABLES

A. Deliverables associated with this agreement include item listed in table A.1 and the following:

- o Submit the Deliverables Tracking Report when requesting any payment.

Table A.1 Lists the Practice Development, Review and Certification deliverables associated with this agreement

Practice Description	Practice Code
Agrichemical Handling Facility (NO) (309)	309
Amendments for the Treatment of Agricultural Waste (591)	591
Animal Mortality Facility (NO.) (316)	316
Brush Management (314)	314
Closure of Waste Impoundments (NO) (360)	360
Combustion System Improvement (NO) (372)	372
Composting Facility (NO.) (317)	317
Conservation Cover (AC) (327)	327
Conservation Crop Rotation (AC) (328)	328
Cover Crop (AC) (340)	340
CNMP Development (102)	102
Critical Area Planting (AC) (342)	342
Diversion (FT) (362)	362
Early Successional Habitat Development/Management (AC) (647)	647
Farmstead Energy Improvement (NO) 374	374
Fence (FT) (382)	382
Filter Strip (AC) (393)	393
Forage and Biomass Planting (512)	512
Forest Stand Improvement (AC) (666)	666
Forest Trails and Landings (AC) (655)	655
Grade Stabilization Structure (NO.) (410)	410
Grassed Waterway (AC) (412)	412
Heavy Use Area Protection (AC) (561)	561
Hedgerow Planting (FT) (422)	422
Herbaceous Weed Control (Ac.) 315	315
Integrated Pest Management (AC) (595)	595
Irrigation Pipeline (FT) (430)	430
Irrigation Reservoir (NO. AND AC-FT) (436)	436

Irrigation System (NO. AND AC), Micro irrigation (441)	441
Irrigation System (NO. AND AC), Sprinkler (442)	442
Irrigation Water Management (AC)(449)	449
Mulching (AC) (484)	484
Nutrient Management (AC) (590)	590
Pipeline (FT) (516)	516
Prescribed Burning (AC) (338)	338
Prescribed Grazing (AC) (528)	528
Pumping Plant (NO.) (533)	533
Riparian Forest Buffer (AC) (391)	391
Riparian Herbaceous Cover (AC) (390)	390
Roof Runoff Structure (NO) (558)	558
Seasonal High Tunnel System for Crops (SF) (798)	798
Silvopasture Establishment (AC) 381	381
Solids/Liquid Waste Separation Facility (632)	632
Spring Development (NO.) (574)	574
Stream Crossing (NO.) (578)	578
Streambank and Shoreline Protection (FT) (580)	580
Terrace (FT) (600)	600
Tree/Shrub Establishment (AC) (612)	612
Tree/Shrub Site Preparation (AC) (490)	490
Underground Outlet (FT) (620)	620
Waste Storage Facility (NO.) (313)	313
Waste Transfer (634)	634
Waste Treatment Lagoon (NO.) (359)	359
Waste Utilization (AC) (633)	633
Water and Sediment Control Basin (NO.) (638)	638
Watering Facility (NO.) (614)	614
Well (NO.) (642)	642
Wildlife Upland Habitat Management (AC) (645)	645

Deliverables Tracking: Table B.1 provides a sample Deliverables Tracking Report. Use this report to identify the specific work performed during each payment period. The Deliverables Tracking Report tracks and totals reimbursement requirements based on the deliverable's cost rates based on practice and task level performed. Actual Deliverables Tracking Report will be provided to the Provider in Excel format.

Table B.1 Sample Deliverables Tracking Report

Separate Deliverable Tracking Report must be submitted for each individual county working in support of this agreement.

Appling County

1st Quarter

Customer Name	Date of Service	Task Level	Program	Description	Amount Paid to County per Deliverable
John Doe	10/23/2012	Administrative	EQIP	Farm Bill Program Applications & their processing	\$ 20.00
Jane's Farm	10/24/2012	Technician	CTA	Fence (FT) (382)	\$ 90.00

sample

Actual Deliverables Tracking Report will be provided to the Provider in Excel format by GACD

V. PERIOD OF PERFORMANCE

- A. The expiration date of the Agreement is **September 30, 2026**. The Agreement is effective from the later of: 1) the date signed by both parties, or 2) the 24 month period preceding the expiration date.

VI. RESOURCES REQUIRED

- A. WALTON COUNTY and GACD requirements are outlined in the following tables

Table A.1 GACD AND WALTON COUNTY COST SHARE

AGENCY	FY25 TOTAL COST	FY26TOTAL COST	TOTAL COST
WALTON COUNTY	\$20,000.00	\$20,000.00	\$40,000.00
GACD	\$20,000.00	\$20,000.00	\$40,000.00

Table A.2 2 YEAR BUDGET SUMMARY

Category	GACD Funds	WALTON COUNTY Funds	Total
Conservation Program Practice Development, Review and Certification (Administrative, Technical, Easement Development, and CNMP Development)	\$40,000.00	\$40,000.00	\$80,000.00

- B. GACD costs share for this agreement is fixed at \$40,000.00.

Katie Sponberger- Executive Director Katie Sponberger 8-9-24
 Name/Title of Authorized GACD Rep Signature Date

David G. Thompson 8/6/24
 Name /Title of Authorized Provider Rep Signature Date

A RESOLUTION OF THE BOARD OF COMMISSIONERS OF WALTON COUNTY, GEORGIA TO AMEND THE WALTON COUNTY FINANCIAL POLICIES TO INCREASE THE REQUIRED WORKING CAPITAL IN THE GENERAL FUND FROM AN AMOUNT EQUIVALENT TO APPROXIMATELY TWO MONTHS OF OPERATING AND DEBT EXPENDITURES TO AN AMOUNT EQUIVALENT TO APPROXIMATELY THREE MONTHS OF OPERATING AND DEBT EXPENDITURES; TO RECOMMEND THAT THE COUNTY HOLD IN RESERVE, FOR ACCOUNTING PURPOSES, THE UNFUNDED LIABILITY BALANCE OF ITS PENSION PLAN; AND TO PROVIDE FOR RELEATED MATTERS

WHEREAS, the Board of Commissioners of Walton County, Georgia (hereinafter the “Board”) adopted Resolution 2009-19 on November 3, 2009 whereby it established various financial policies for the Walton County Government (hereinafter the “Financial Policies”);

WHEREAS, Section I, Subsection II, Paragraph (Q) of the Financial Policies addresses Pension Plan Funding;

WHEREAS, Section I, Subsection III, Paragraph (B) of the Financial Policies addresses Budget Stabilization Resources;

WHEREAS, the Board desires to amend Section I, Subsection II, Paragraph (Q) of the Financial Policies to include a recommendation that the Walton County Government hold in reserve, for accounting purposes, the unfunded liability balance of its pension plan; and

WHEREAS, the Board desires to amend Section I, Subsection III, Paragraph (B) of the Financial Policies to provide that Walton County shall maintain in its General Fund working capital equivalent to approximately three (3) months of operating and debt expenditures, instead of two months of operating and debt expenditures;

NOW BE IT HEREBY RESOLVED BY THE BOARD OF COMMISSIONERS OF WALTON COUNTY, GEORGIA that:

1.

Section I, Subsection II, Paragraph (Q) of the Financial Policies is hereby amended to include the following additional sentence at the end of said paragraph: “Further, it is recommended that the County hold in reserve, for accounting purposes, the unfunded liability balance of its pension plan.”

2.

Section I, Subsection III, Paragraph (B) is hereby amended to replace the last sentence in said Paragraph with the following sentence: "This designation shall accumulate and then be maintained at an amount which represents the equivalent of approximately three (3) months of operating and debt expenditures."

3.

All other provisions of the Financial Policies, as adopted by the Board, shall remain in full force and effect.

4.

If any provision of this Resolution is held to be invalid or unenforceable for any reason, the invalidity or unenforceability of such provision shall not affect any of the other provisions of this Resolution, which shall remain in full force and effect.

5.

Any resolutions or portions of resolutions of the Board which conflict with any of the provisions of this Resolution are hereby repealed to the extent of such conflict.

6.

This Resolution shall take effect upon its adoption.

SO RESOLVED and ADOPTED this ____ day of _____, 2026.

BOARD OF COMMISSIONERS OF WALTON COUNTY, GEORGIA

David Thompson
Chair

Attest: _____

Rhonda Hawk
County Clerk

[COUNTY SEAL]

RESOLUTION

WHEREAS, the budgets of Walton County for Fiscal Year 2027 for the General Fund, all special revenue funds, debt service funds, and capital funds were adopted on June 2, 2026, and

WHEREAS, to maintain compliance with the state of Georgia budget requirements per O.C.G.A. sections 36-81, it is necessary to amend said budgets, now

THEREFORE, BE IT RESOLVED BY THE Board of Commissioners of Walton County, amends the Fiscal Year 2027 budget to make changes to the Fiscal Year 2027 budget as presented in the attached summary schedule.

Adopted this 6th day of October, 2026

Chairman, David G. Thompson

Attest:

County Clerk Rhonda R. Hawk

AMENDMENT SUMMARY
October 2026 Agenda

1. **Multiple Budget Units Sheriffs Dept:** Budget transfer to move funds from Criminal Investigation temporary and personnel accounts in the amount of \$ 27,754.45 to Criminal Investigation, Uniform Patrol, and Youth Inv. regular and personnel accounts in the amount \$ 27,754.45. Approval of position changes and step increases that was approved during Sept 1st board meeting. This transfer would have no effect on fund balance.

Walton County Department Agenda Request

Department Name: Administration/County Manager

Department Head/Representative: **John Ward**

Meeting Date Request: **10/6/2026**

Has this topic been discussed at past meetings? **Yes**

If so, When? **During FY2027 budget adoption and during multiple County Manager updates**

TOPIC: Capital Equipment/Building Funds Request

Wording For Agenda: **Funding allocation request for FY27 Capital Vehicles/Equipment/Site Improvements**

This Request: Needs Action by Commissioners*

*What action are you seeking from the Commissioners? **Approval of \$2,925,063 from the General Fund Reserve Fund to fund the purchase of the recommended vehicles/equipment/site improvements outlined in the attached master list.**

Department Comments/Recommendation: **During the process of preparing and adopting the FY26 General Fund budget it was determined that it was appropriate to use savings from the prior year budget for one time expenses for vehicles/equipment/site improvements. Initial requests from various departments totaled \$5,168,919. That number has been reduced to \$2,925,063.00 with an itemized list of vehicles/equipment/site improvements attached.**

Additional Documentation Attached? **Yes**

Is review of this request or accompanying documentation by the County Attorney required? **No**

If so, has a copy of the documentation been forwarded to the County Attorney?

Date forwarded to County Attorney:

Has the County Attorney review been completed?

If this request involves the expenditure of county funds, please answer the following:

Approved in the current budget?

Budget information attached?

Comments: **The funds being requested were not included in the the approved FY27 budget but are now being requested as previously discussed.**

Purchasing Department Comments:

County Attorney Comments:

Chairman's Comments:

1565 Gen Gov Buildings	E350	(2)	54.2200	131,000.00
1552 Tax Assessors	2026 Ford Maverick		54.2200	31,000.00
3300 Sheriff	Patrol Vehicles	(5)	54.2200	
3910 Animal Control	F-250 Regular Cab		54.2200	60,000.00
4220 Roadways & Walkways	2027 Mack Flatbed Steel Dump		54.2200	130,358.00
4220 Roadways & Walkways	2027 Mack Pinnacle Lowboy		54.2200	-
4220 Roadways & Walkways	2027 Crew Cab 4x4		54.2200	50,750.00
4220 Roadways & Walkways	2027 Crew Cab 4x4		54.2200	44,254.00
6220 Parks & Rec	F-150 4X4 Supercrew		54.2200	60,000.00
7132 County Extension	Ford Maverick		54.2200	31,500.00
3610 EMS	Dodge 3500 Ambulance Prep	(2)	54.2200	134,000.00
3610 EMS	Ambulance Box	(2)	54.2200	390,000.00
1320 County Manager	2 Updated 911 Radios		54.2500	10,000.00
1535 IT	Dell PowerStore 500T		54.2500	98,000.00
1535 IT	2 HPE DL360 GEN10 Server		54.2500	20,000.00
1565 Facilities	Various Bldg - HVAC units		54.2500	40,000.00
2200 District Attorney			54.2500	
3300 Sheriff	Forensic Imager TX2 - CID		54.2500	
3700 Coroner	4 Portable Radios		54.2500	
3810 Comm/E911	HVAC		54.2500	12,000.00
3910 Animal Control	Adoption Trailer 18.1		54.2500	60,000.00
3910 Animal Control	SWAB Animal Carrier		54.2500	19,050.00
3920 EMA	8.5 X 24 Enclosed Trailer		54.2500	10,000.00
3920 EMA	ATV		54.2500	10,000.00
3920 EMA	HVAC		54.2500	5,000.00
4220 Roadways & Walkways	Gradall		54.2500	
4220 Roadways & Walkways	Boom Axe		54.2500	228,684.00
4220 Roadways & Walkways	(2) Bush Hog Bat Wing Mowers		54.2500	52,692.00
4220 Roadways & Walkways	Zero Turn Mower		54.2500	15,415.00
4220 Roadways & Walkways	Skid Steer		54.2500	63,348.00
4220 Roadways & Walkways	Asphalt Roller		54.2500	185,794.00
4910 Fleet Maint	Big Joe Pallet Jack		54.2500	12,218.00
5170 Health Centers & Clinics	HVAC Units		54.2500	12,000.00
6220 Parks & Rec	Floor Machine		54.2500	6,500.00
6220 Parks & Rec	Tractor		54.2500	47,500.00
6220 Parks & Rec	Grapple Bucket - Skid Steer		54.2500	6,000.00
6220 Parks & Rec	Soccer Goals		54.2500	11,000.00
6220 Parks & Rec	Fencing		54.2500	50,000.00
6220 Parks & Rec	Splash Park Motor		54.2500	6,500.00
6220 Parks & Rec	72" Zero Turn Mower		54.2500	18,000.00
6220 Parks & Rec	Sod Cutter		54.2500	6,000.00
6220 Parks & Rec	Dingo		54.2500	42,500.00
6220 Parks & Rec	Pull Behind Lift		54.2500	

6220 Parks & Rec	Yamaha Concierge	54.2500	
6220 Parks & Rec	Stand On Mower	54.2500	10,000.00
6220 Parks & Rec	HVAC Units	54.2500	12,000.00
3800 E-911/Towers	HVAC	54.2500	24,000.00
3610 EMS	Power Stretcher	54.2500	50,000.00
4530 Solid Waste	3 40 Yard Cans	54.2500	21,647.00
4550 KWB/ Recycling	Skid Steer Loader	54.2500	68,918.00
1565 Facilities	Unlimited Services Re-Roof LR Anderso	54.1200	100,000.00
6220 Parks & Rec	Ag Center Re-Roof	54.1200	160,000.00
6220 Parks & Rec	Criswell Park - Automated Lights	54.1200	25,000.00
6220 Parks & Rec	West Walton Park - Field Lights	54.1200	
6220 Parks & Rec	South Walton Park - Field Lights	54.1200	
6220 Parks & Rec	Meridian CC Floor Replacement	54.1350	
6220 Parks & Rec	Felker CC Floor Replacement	54.1350	28,500.00
4900 Heavy Equipment Shop	Tool Room	54.1350	
	Initial Requests Vehicles and Equipment		3,683,919.00
	Initial Requests Impr and Bldg Impr		1,485,000.00
	Total		5,168,919.00
Recommended	total on Vehicles and Equipment		2,297,628.00
Recommended	total on Site Impr and Bldg Impr		313,500.00
	Contingency @ 12%		313,935.00
	Total		2,925,063.00

* Contingency is calculated due to initial costs being obtained during the original budget process. Contingency will only be utilized due to costs increases associated with delayed purchase.

Walton County Department Agenda Request

Department Name: **Walton County Sheriff's Office**

Department Head/Representative: **Kim McCord**

Meeting Date Request: **10/06/2026**

Has this topic been discussed at past meetings? **No**

If so, When?

TOPIC: **LeadsOnline, LLC / Total Track Investigations System**

Wording For Agenda: **LeadsOnline/Total Track Investigations System**

This Request: Informational Purposes Only Needs Action by Commissioners* **Yes**

*What action are you seeking from the Commissioners? **Acceptance**

Department Comments/Recommendation: **New Investigations System to be utilized in CID**

Additional Documentation Attached? **Agreement**

Is review of this request or accompanying documentation by the County Attorney required? **Yes**

If so, has a copy of the documentation been forwarded to County Attorney? **Yes**

Date forwarded to County Attorney: **09/25/2026**

Has the County Attorney review been completed? **No**

If this request involves the expenditure of county funds, please answer the following:

Approved in current budget? **Yes, approved in the FY27 Budget Process**

Budget information attached?

Comments:

Purchasing Department Comments:

County Attorney Comments:

Chairman's Comments:

SUBSCRIPTION SERVICES AGREEMENT

This Subscription Services Agreement (**Agreement**) No. LO-11889 is between LeadsOnline, LLC, a Delaware limited liability company (**LeadsOnline**), Walton County GA Sheriff (**Customer**), and is effective as of the date of the last signature below. This Agreement contemplates one or more Order Forms for Services, which are governed by the terms of this Agreement.

1. SERVICE

- a. This Agreement and the applicable Order Form provide Customer access to and usage of solution services involving hardware devices provided by LeadsOnline with accompanying software needed to operate such hardware and/or an Internet-based software service, including, without limitation, its features, functions, and user interface, and underlying software, which may be limited to a set number of Eligible Users, as defined and specified on an Order Form (**Service**).

2. USE OF SERVICE

- a. **Customer Owned Data.** All data, information, images, and files uploaded or otherwise entered by Customer into the Service remains the property of Customer, as between LeadsOnline and Customer (**Customer Property**), unless otherwise specified in the applicable Order Form regarding licensing terms for the Service offered under said Order Form.
- b. **Responsibilities for Customer Property.** Customer represents and warrants to LeadsOnline that Customer has provided all required notices and has obtained all required licenses, permissions, and consents regarding Customer Property for use within the Service under this Agreement. Customer grants LeadsOnline the right to use the Customer Property solely for Purposes of performing under this Agreement (which includes, without limitation, the right for LeadsOnline to enhance its technology and offerings). LeadsOnline will purge any or all Customer Property upon Customer's written request. Customer may export its Customer Property as allowed by functionality within the Service.
- c. **General Responsibilities.** Customer must (i) ensure that access to Service and information produced by or derived from it is limited to the Purpose defined in the Order Form, (ii) maintain any data accessed, received or otherwise derived from Service according to all applicable statutes, laws and regulations for use and disclosure of non-public personal information, (iii) connect to Service only using devices and browsers with proper encryption, (iv) promptly notify LeadsOnline (within the Service or by email to support@leadsonline.com) when an Eligible User is no longer employed by Customer or is no longer authorized to access Service, (v) ensure that each Eligible User is acting within the bounds of their authority from Customer and within their legal rights to search, possess, enter, analyze and use, all information and data submitted to and received from the Service, (vi) refrain from any use, misuse or actions related to Service or Data that infringe, misappropriate, or otherwise violate any right of anyone, or that violate any applicable law, and ensure that any instructions or directives Customer gives to or regarding anyone do not conflict with applicable laws, (vii) use any hardware provided by LeadsOnline solely for the Purpose defined in the Order Form and in accordance with all applicable instructions, policies, and documentation provided by LeadsOnline, (viii) ensure that the hardware is used only by Eligible Users authorized under this Agreement and is not transferred, loaned, or sublicensed to any unauthorized person or entity, (ix) keep all hardware provided as part of the Service in good working condition, refrain from any unauthorized repairs, modifications, or tampering, and promptly notify LeadsOnline of any malfunction, damage, or loss, and (x) verify the accuracy, timeliness, context and relevance of information or communication from Service or personnel prior to taking action. Customer acknowledges that LeadsOnline does not enforce laws, does not provide legal advice, and does not claim to have authority or expertise in legal or law enforcement matters.
- d. **Governmental Agency Public Records Clause.** If Customer is a government agency and is required by law to permit the inspection and copying of public records, Customer acknowledges the Service contains information protected by exemptions to public disclosure laws in many states, and if Customer searches the Service in response to a request for Public Records, Customer is acting on its own accord. LeadsOnline does not grant Customer access to the Service for the Purpose of searching for or creating records to respond to a public records request when Customer did not have the record in its possession at the time of the request.
- e. **Customer Responsibilities.** Customer: (i) must keep its passwords secure and confidential and use industry-standard password management practices, and ensure that any credentials related to the hardware under the Service are protected from unauthorized access; (ii) is responsible for its access control policies and administration of access rights to its account within the Service, the acts and omissions of its users, and the legality and accuracy of any data submitted to the Service, may not share any access credentials and must also prevent unauthorized access, tampering, or misuse of any hardware provided under the Service; (iii) must use commercially reasonable efforts to prevent unauthorized access to its account, and notify LeadsOnline promptly of any such unauthorized access; (iv) may use the Service and any associated hardware only in accordance with the Service's technical documentation (including without limitation, video tutorials) and applicable law; and (v) must follow all provided guidelines for hardware setup, maintenance, and operation to ensure compliance and functionality under the Service.

- f. **LeadsOnline Support.** Unless otherwise specified in the applicable Order Form, LeadsOnline must provide Customer support for the Service under the terms of LeadsOnline's Customer Support Policy (**Support**), which is located at leadsonline.com/customer-support.

3. WARRANTY DISCLAIMER

- a. **EXCEPT WHERE EXPLICITLY STATED IN WRITING, THE SERVICE IS PROVIDED 'AS IS' WITHOUT WARRANTY. LEADSONLINE DISCLAIMS ALL WARRANTIES, INCLUDING, WITHOUT LIMITATION, THE IMPLIED WARRANTIES OF MERCHANTABILITY, TITLE, AND FITNESS FOR A PARTICULAR PURPOSE. WHILE LEADSONLINE TAKES REASONABLE PHYSICAL, TECHNICAL, AND ADMINISTRATIVE MEASURES TO SECURE THE SERVICE, CUSTOMER UNDERSTANDS THAT THE SERVICE MAY NOT BE ERROR FREE, AND USE MAY BE INTERRUPTED.**
- b. While Customer acknowledges that the Service may not be error-free and may not fully meet Customer's expectations, LeadsOnline does warrant that the Service is free from defects that will substantially affect performance, and that it has used commercially available tools designed to discern that no viruses or other security defects are present. LeadsOnline further warrants that the Service will function substantially in accordance with the Order Form. LeadsOnline will not intentionally introduce any virus, Trojan horse, spyware, malware, or other malicious code designed to erase, damage, or unlawfully interfere with Customer's equipment, data, or other programs. Notwithstanding the foregoing, Customer acknowledges and agrees that the Service may contain functionality that allows LeadsOnline to remotely disable or limit the hardware's operation in accordance with this Agreement, including but not limited to instances of non-payment or material breach by Customer.
- c. LeadsOnline cannot control the decisions and actions of Customer. LeadsOnline expressly disclaims and does not undertake or assume any duty, obligation or responsibility for any decisions, actions, reactions, responses, inaction by Customer or any other party as a result of or reliance on, in whole or in part, any use of the Service or information derived from it, or for any consequences or outcomes including death, injury, loss or damage to any property arising from or caused by any such actions decisions, reactions, responses, or inaction.

4. PAYMENT

- a. **Fees and Payment.** Customer must pay all fees as specified on the Order Form, but if not specified, then within thirty (30) days of receipt of an invoice. The fees are exclusive of sales, use, withholding, VAT, TPT, and other similar taxes, and if required by law Customer is responsible for payment of such taxes.
- b. **Nonpayment.** LeadsOnline will provide electronic notice (within the Service) and notice to the email registered with LeadsOnline (Customer is responsible for maintaining an updated email address with LeadsOnline) of the non-payment of an open invoice. If the payment is not made within seven (7) days of the first notice, then LeadsOnline may suspend Service and Support until the amount is paid in full or terminate the Service upon 30 days' notice under Section 9(c).

5. MUTUAL CONFIDENTIALITY

- a. **Definition of Confidential Information.** Confidential Information means all non-public information disclosed by a party (**Discloser**) to the other party (**Recipient**), whether orally, visually, or in writing, that is designated as confidential or that reasonably should be understood to be confidential given the nature of the information and the circumstances of disclosure (**Confidential Information**). LeadsOnline's Confidential Information includes, without limitation, the Service. Customer's Confidential Information includes, without limitation, the Customer Property.
- b. **Protection of Confidential Information.** Recipient must use the same degree of care that it uses to protect the confidentiality of its own confidential information of like kind (but not less than reasonable care) to: (i) not use any Confidential Information of Discloser for any Purpose outside the scope of this Agreement; and (ii) limit access to Confidential Information of Discloser to those of its and its Affiliates' employees and contractors who need that access for Purposes consistent with this Agreement, and who have a legal obligation under law or policy regarding confidentiality or have signed confidentiality Agreements with Recipient containing protections not materially less protective of the Confidential Information than those in this Agreement.
- c. **Exclusions.** Confidential Information *excludes* information that: (i) is or becomes generally known to the public without breach of any obligation owed to Discloser; (ii) was known to the Recipient before its disclosure by the Discloser without breach of any obligation owed to the Discloser; (iii) is received from a third party without breach of any obligation owed to Discloser; or (iv) is independently developed by the Recipient without use of or access to the Confidential Information. The Recipient may disclose Confidential Information to the extent required by law or court order but will provide Discloser with advance notice to seek a protective order unless otherwise directed by the court.

6. INFORMATION SECURITY

- a. Data Security Measures.** To protect Customer Property from unauthorized disclosure, alteration, or misuse, LeadsOnline shall:
- i. Agree to the terms of the Federal Bureau of Investigation Criminal Justice Information Services (FBI CJIS) Security Addendum.
 - ii. Ensure that LeadsOnline personnel with unescorted access to unencrypted Customer Property and/or physically secure locations have:
 - Completed CJIS Security Awareness Training and have passed the Level Four CJIS Security Test designed for Information technology personnel (system administrators, security administrators, network administrator).
 - Submitted to and successfully passed state of residency and national fingerprint-based record checks.
 - iii. Apply appropriate controls according to the AICPA Trust Services Criteria for Security so as to maintain a secure environment for all Customer Property.
 - iv. Maintain proper encryption of data in transit using 256-Bit Transport Layer Security (TLS) and at rest using FIPS 140-2 standards.
 - v. Maintain advanced firewall and intrusion protection, database partitioning, patch management, account management, identification and authentication, configuration management and third-party application and network penetration tests.
 - vi. Log events relative to access and use of the Services; maintain and protect logs from disclosure, alteration, or misuse.
 - vii. Respond to security incidents; In the event of a data breach (as defined by applicable law), of Customer Property, LeadsOnline will act to eliminate the breach, preserve forensic evidence, and notify Customer without undue delay. LeadsOnline shall have no obligation to notify consumers or regulatory authorities of a breach of Customer data that was not the result of a data security incident experienced by LeadsOnline.
 - viii. Purge any Customer Property upon Customer's written request.

7. INSURANCE

- a. Insurance Policies.** LeadsOnline shall maintain insurance policies for property, general liability, auto, workers compensation, errors and omissions/cyber liability insurance.
- b. Additional Insured.** For the purposes of this Agreement, Customer, its officers, officials, employees, and volunteers shall be deemed additional insureds on the general liability policy with respect to liability arising out of work or operations performed by or on behalf of LeadsOnline. Additional insured coverage shall be evidenced in the form of Blanket Certificate of Endorsement upon Customer's request.

8. PROPERTY

- a. Reservation of Rights.** LeadsOnline and its licensors are the sole owners of the Service, including all associated intellectual property rights, and they remain only with LeadsOnline. Title to any hardware provided under this Agreement passes to Customer upon full payment as specified in the Order Form; however, LeadsOnline retains all intellectual property rights related to any software, firmware, or proprietary technology embedded in or used to operate the hardware. Customer may not remove or modify any proprietary marking or restrictive legends in the Service. LeadsOnline reserves all rights that are not expressly granted in this Agreement.
- b. Restrictions.** Customer *may not*: (i) share, provide, sell, resell, rent, or lease the Service or use it in a service-provider capacity or allow access to the Service, its output, or any associated hardware, software, firmware, or proprietary technology by a third party, except as expressly permitted in this Agreement; (ii) use the Service or any hardware provided as part of the Service, to store or transmit unsolicited marketing emails, libelous, or otherwise objectionable, unlawful, or tortious material, or to store or transmit infringing material in violation of third party rights; (iii) interfere with or disrupt the integrity or performance of the Service, including but not limited to tampering with, modifying, or attempting to bypass any security, tracking, or management features within any software or hardware provided as part of the Service; (iv) attempt to gain unauthorized access to the Service or its related systems or networks or use any automated means to monitor, access or copy any data from the Service; (v) reverse engineer, decompile, disassemble, or otherwise attempt to discover the underlying technology, software, or firmware of the Service or hardware, or modify, alter, or remove any proprietary markings or security features; (vi) resell, transfer, or dispose of the hardware in a manner inconsistent with this Agreement, including attempting to sublicense or lease it to a third party without LeadsOnline's prior written consent; the Service; or (vii) access the Service to build a competitive service or product, or copy any feature, function, or graphic. LeadsOnline may suspend Service to Customer if LeadsOnline believes in good faith that Customer's use of the Service poses threat to the security, availability,

or legality of the Service; in such event, LeadsOnline will work with Customer to address the issue and restore Service as quickly as possible.

- c. **Audit Information.** LeadsOnline logs events related to user registration, contacts, access, and use of the Services for legal, audit, security, and support Purposes (**Audit Information**). Audit Information is not Customer Property.

9. TERM & TERMINATION

- a. **Term.** This Agreement continues until the thirtieth (30th) day after all Order Forms have expired or earlier terminated as provided below.
- b. **Term of Order Forms.** The term of each Order Form is specified in the Order Form.
- c. **Mutual Termination for Material Breach.** If either party is in material breach of this Agreement, the other party may terminate this Agreement at the end of a written thirty (30) day notice/cure period if the breach has not been cured.
- d. **Termination by Mutual Consent.** This Agreement and/or any Order Form may be terminated by the mutual consent of both parties.
- e. **Termination of an Order Form Due to Non-Appropriation of Funds.** Government Customers may terminate services in an Order Form by providing sixty (60) days' written notice to LeadsOnline prior to the next contract year if funding to make the next scheduled payment is not duly appropriated and authorized.
- f. **Return of Customer Property:**
 - Within sixty (60) days after termination, upon written or electronic request LeadsOnline will make the Service available for Customer to export Customer Property as provided in **Section 2(a)**.
 - After such a sixty (60) day period, LeadsOnline has no obligation to maintain the Customer Property and may destroy it.

10. LIABILITY LIMIT

- a. **Indemnification for Third-Party Claims.** LeadsOnline will defend or settle any third-party claim against Customer to the extent that such claim alleges that the LeadsOnline technology used to provide the Service violates a copyright, patent, or trademark (**IP Indemnity Claim**), if Customer: promptly notifies LeadsOnline of the claim in writing; cooperates with LeadsOnline in the defense; and allows LeadsOnline to solely control the defense or settlement of the claim. Costs. LeadsOnline will pay infringement claim defense costs it incurs in defending Customer, and LeadsOnline-negotiated settlement amounts, and court awarded damages. Process. If such a claim appears likely, then LeadsOnline may modify the Service, procure the necessary rights, or replace it with the functional equivalent. If LeadsOnline determines that none of these are reasonably available, then LeadsOnline may terminate the Service and refund any prepaid and unused fees. Exclusions. LeadsOnline has no obligation for any claim arising from: Customer's misuse of the Services, LeadsOnline's compliance with Customer's designs, specification, instructions, or technical information; a combination of the Service with other technology or aspects where the infringement would not occur but for the combination; Customer's directives, access or use of, or laws or policies applicable to Customer regarding the information and sources thereof accessible via the Services including Customer Property; or technology or aspects not provided by LeadsOnline. **THIS SECTION CONTAINS CUSTOMER'S EXCLUSIVE REMEDIES AND LEADSONLINE'S SOLE LIABILITY FOR INTELLECTUAL PROPERTY INFRINGEMENT CLAIMS.**
- b. **EXCLUSION OF INDIRECT DAMAGES.** TO THE MAXIMUM EXTENT ALLOWED BY LAW, LEADSONLINE IS NOT LIABLE FOR ANY INDIRECT, SPECIAL, INCIDENTAL, OR CONSEQUENTIAL DAMAGES ARISING OUT OF OR RELATED TO THIS AGREEMENT (INCLUDING, WITHOUT LIMITATION, COSTS OF DELAY; LOSS OF OR UNAUTHORIZED ACCESS TO DATA OR INFORMATION; AND LOST PROFITS, REVENUE, OR ANTICIPATED COST SAVINGS), EVEN IF IT KNOWS OF THE POSSIBILITY OR FORESEEABILITY OF SUCH DAMAGE OR LOSS.
- c. **TOTAL LIMIT ON LIABILITY.** TO THE MAXIMUM EXTENT ALLOWED BY LAW, EXCEPT FOR LEADSONLINE'S INDEMNITY OBLIGATIONS RELATING TO IP INDEMNITY CLAIMS, LEADSONLINE'S TOTAL LIABILITY ARISING OUT OF OR RELATED TO THIS AGREEMENT (WHETHER IN CONTRACT, TORT, OR OTHERWISE) DOES NOT EXCEED THE AMOUNT PAID BY CUSTOMER WITHIN THE 12-MONTH PERIOD PRIOR TO THE EVENT THAT GAVE RISE TO THE LIABILITY, EXCEPT THAT THE ABOVE LIMITATION DOES NOT APPLY TO CUSTOMER'S PAYMENT OBLIGATIONS FOR THE SERVICE.

11. GOVERNING LAW & FORUM

- a. **Government Customers.** This Agreement is governed by the laws of the State of Georgia (without regard to conflicts of law principles) for any dispute between the parties or relating in any way to the subject matter of this Agreement. Any suit or legal proceeding must be brought in the federal or state courts for the County where Customer is located in the State of Georgia, and each party submits to this personal jurisdiction and venue. Nothing in this Agreement prevents either party from seeking injunctive relief in a court of competent jurisdiction.

12. OTHER TERMS

- a. **Entire Agreement and Changes.** This Agreement and the Order Form constitute the entire Agreement between the parties and supersede any prior or contemporaneous negotiations or Agreements, whether oral or written, related to this subject matter. Customer is not relying on any representation concerning this subject matter, oral or written, not included in this Agreement. No representation, promise, or inducement not included in this Agreement is binding. No modification or waiver of any term of this Agreement is effective unless both parties sign an amendment to this Agreement.
- b. **No Assignment.** Neither party may assign or transfer this Agreement to a third party, except that the Agreement and all Order Forms may be assigned without the consent of the other party as part of a merger or sale of all or substantially all a party's businesses, assets, not involving a competitor of the other party, or at any time to an Affiliate.
- c. **Export Compliance.** The Service and Confidential Information may be subject to export laws and regulations of the United States and other jurisdictions. Each party represents that it is not named on any U.S. government denied-party list. Neither party will permit its personnel or representatives to access any Service in a U.S.-embargoed country or in violation of any applicable export law or regulation.
- d. **Independent Contractors.** The parties are independent contractors with respect to each other, and neither party is an employee, or partner of the other party or the other party's Affiliates.
- e. **Enforceability and Force Majeure.** If any term of this Agreement is invalid or unenforceable, the other terms remain in effect. Neither party is liable for its non-performance due to events beyond its reasonable control, including but not limited to natural weather events and disasters, labor disruptions, and disruptions in the supply of utilities.
- f. **Money Damages Insufficient.** Any breach by a party of this Agreement or violation of the other party's intellectual property rights could cause irreparable injury or harm to the other party. The other party may seek a court order to stop any breach or avoid any future breach of this Agreement.
- g. **No Additional Terms.** LeadsOnline rejects additional or conflicting terms of any Customer form-purchasing document.
- h. **Order of Precedence.** If there is an inconsistency between this Agreement and an Order Form, the Order Form prevails.
- i. **Survival of Terms.** All provisions of this Agreement regarding payment, confidentiality, indemnification, limitations of liability, proprietary rights, and such other provisions that by fair implication require performance beyond the term of this Agreement shall survive expiration or termination of this Agreement until fully performed or otherwise are inapplicable.
- j. **Feedback.** If Customer provides feedback or suggestions about the Service, then LeadsOnline (and those it allows to use its technology) may use such information without obligation to Customer.

<< REMAINDER OF PAGE LEFT INTENTIONALLY BLANK—SIGNATURE PAGE TO FOLLOW >>

13. SUBSCRIPTION SERVICES AGREEMENT NO. LO-11889 SIGNATURES

a. Each representative identified below represents and warrants that it has the full power, right and authority to enter into this Agreement on behalf of its respective party.

LEADSONLINE, LLC (LeadsOnline)	
SIGNATURE:	
NAME:	Alexander Finley
TITLE:	President & CEO
DATE:	
ADDRESS:	6900 Dallas Parkway, Suite 825, Plano, Texas 75024, United States

WALTON COUNTY GA SHERIFF (Customer)	
SIGNATURE:	
NAME:	
TITLE:	
DATE:	
ADDRESS:	1425 S Madison Ave, Monroe, Georgia 30655, United States

LEADS ONLINE TOTALTRACK™ INVESTIGATIONS SYSTEM SUBSCRIPTION

ORDER FORM No. Q-12244-LO | AGENCY ID: 7308

CUSTOMER:

WALTON COUNTY GA SHERIFF

UNIT:

SHERIFF

1. SERVICE

- a. **Service.** LeadsOnline TotalTrack™ Investigations System Subscription for Law Enforcement Agency users (**Service**).

b. **Authority.** Customer represents that it is a law enforcement agency or governing body of a law enforcement agency, an entity duly authorized by municipal, state county or federal government to enforce laws or investigate crimes, and the Eligible Users are employed by Customer in the Unit listed at the top of this Order Form.

2. PURPOSE

- a. **Law Enforcement Use.** Exclusively for the official law enforcement agency duties of Customer's Unit; information retrieved from the Service is for the exclusive use of Eligible Users with the exception of disclosure necessary to investigate and prosecute crimes within the jurisdiction of and investigated by Customer's Unit.

3. DEFINITIONS

- a. **Audit Records** means records audit records retained for administrative, legal, audit, or other operational purposes. Audit Records are protected from modification, deletion and unauthorized access and are retained for a minimum of one (1) year.

b. **Deconfliction Data** means the subset of data provided to be made aware of activity by another Law Enforcement Official or Law Enforcement Customer regarding a matching person, person of interest, phone number, device identifier, item of property, location, vehicle or other data element to facilitate the benefits of coordinated investigative efforts by Law Enforcement Officials.

c. **Law Enforcement Official** means a person employed by and authorized by a Law Enforcement Customer to, in their official duties, access or submit data according to the terms of this agreement.

d. **Reporting Business** means any entity that records Transaction Data regarding the receipt or other disposition of merchandise or materials and reports such Transaction Data for access by Law Enforcement Officials according to official request, statutory requirement or otherwise.

e. **Repository Data** means data and any other information LeadsOnline has received from entities other than the Customer.

f. **Transaction Data** means information provided by Reporting Businesses and Law Enforcement Agencies about transactions, including, but not limited to, the transaction number, make, model, property description, serial number, name, address, identification number, telephone number, date of birth and any images recorded during the course of a transaction according to official request, statutory requirement or otherwise.

g. **Analysis Files** means records electronically submitted by a Customer to the Service for automated analysis. Analysis Files include but are not limited to unstructured images, video, audio or text submitted, and data related to communications or movements of devices, vehicles and other entities, which reference data for identifying locations including cell site lists, landmarks, and locations related to crimes. Analysis Files are Customer Property.

4. SERVICE RECIPIENT AND ELIGIBLE USERS

- a. **Service Recipient.** An unlimited number of authorized personnel of Customer in its Sheriff, each with a unique login (**Eligible Users**).

i. Eligible User logins may not be shared and individuals who are not Eligible Users may not access the Service.

ii. During initial onboarding, Customer may provide LeadsOnline with the names and email addresses of Eligible Users.

5. TERM, SERVICE PERIODS AND SUBSCRIPTION FEES

- a. Order Term.** This Order Form will become effective as of the Effective Date and remain in effect through the Service Periods listed below (**Initial Term**) and any renewal Service Periods or until termination by LeadsOnline or Customer as described below. The Effective Date shall be defined as the date of the last signature below.
- b. Payment Terms.** Payment shall be made on or before each anniversary during the Initial Term and any renewal term thereafter.

START DATE	END DATE	RATE	QTY	TOTAL DUE
October 1, 2026	June 30, 2027	\$11,872.50	1	\$11,872.50
July 1, 2027	June 30, 2028	\$16,304.90	1	\$16,304.90

- c. Renewals.** Neither party is obligated to renew this Order Form. Prior to the expiration of the Initial Term or any renewal term, the parties may renew this Order Form for additional one-year terms by LeadsOnline's submission of a valid invoice to Customer for the renewal Service Period at then-current pricing and Customer's payment of such invoice within thirty (30) days of renewal.
- d. Applicable Taxes.** Fees are exclusive of sales, use, withholding, VAT, TPT, and other similar taxes, and if required by law Customer is responsible for payment of such taxes. Any taxes referenced and/or quoted are estimates only, and not all services may be subject to taxation. Final tax amounts will be determined based on applicable laws at the time of invoicing. Customer may provide a Tax Exemption Certificate if applicable.

6. FEATURES

TOTALTRACK™ KEY FEATURES AND CHARACTERISTICS	
TotalTrack™ Unlimited Nationwide Search	Nationwide search access through pawn shop and secondhand store transactions. Unlimited accounts/searches for your personnel working your cases. Continuous saved searches alert investigators to persons or property after. Results include images of property, sellers, vehicles, thumbprints, etc. as reported. Robust identity resolution to spot suspect activity when identifiers are incorrect or out of date. Possible associates report identifying other leads in cases. Advanced property identification to overcome incomplete descriptions and missing information. Daily Stats (hits and statistics for each user).
Nationwide Inter-Agency Deconfliction System	Benefit from coordinated investigative efforts through pointers to the records of other Law Enforcement Agencies when users match persons, property, devices, vehicles, and other entities.
NCIC Stolen Property Notification	Automated alerts on property including guns, articles and vehicles from your cases found within and outside your jurisdiction.
Person / Property Notification	Automatic alerts on suspects, wanted persons and stolen property.
Compliance Management	Free online reporting system for all pawn/secondhand stores. Easy reporting for businesses. Compatible with point-of-sale systems. Property hold management system. Message Inbox for alerts and communication to and from businesses in your jurisdiction. Unlimited technical support for reporting businesses.
OfferUp & eBay Marketplace Access	Identify persons in your cases when evidence is found in online listings.
Unlimited Support	Updates, training and support for Customer personnel and businesses.
LeadsOnline Toolbox	Automated search warrant generation, automated phone lookups, repository of training materials, video tutorials, templates, resources, software, process guides, carrier and network specifications, contacts, subject matter assistance and other content relevant to criminal investigations.
Citizen Property Inventory System	Community engagement for improved reporting of property crimes via LeadsOnline ReportIt.

7. ONBOARDING, TRAINING AND TECHNICAL SUPPORT

- a. Registration.** Eligible Users register for a user account at www.leadsonline.com; Customer may provide lists of Eligible Users for expedited processing.

- b. Training.** LeadsOnline Support will activate Eligible Users and provide training via in-app instructions, videos, and live support.
- c. Support.** Technical support services for non-critical issues, training and general assistance are provided to end-users in the form of unlimited email and/or telephone support, Monday through Friday 7:00 AM – 5:30 PM CST via toll-free at (800) 311-2656 or support@leadsonline.com.

8. MISCELLANEOUS

- a.** This Order Form is attached to and incorporated into the Subscription Services Agreement between **Customer** and **LeadsOnline** dated **(Agreement)**.
- b.** This Order Form is governed by the terms of the Agreement between the parties. All terms not defined in this Order Form have the meanings ascribed to such terms in the Agreement. This Order Form and the Agreement constitute the entire agreement between the parties, and supersede all prior or contemporaneous negotiations, agreements, and representations, whether oral or written, related to this subject matter. No modification or waiver of any term of this Order Form is effective unless both parties sign an amendment to this Order Form. LeadsOnline may include a purchase order number on Customer's invoice solely for Customer's internal payment and record keeping processes, but any terms within any purchase order in response to a quote, order form or invoice will not modify or enlarge the obligations or liabilities of either party even if the parties sign it.

<< REMAINDER OF PAGE LEFT INTENTIONALLY BLANK—SIGNATURE PAGE TO FOLLOW >>

9. SIGNATURES FOR TOTALTRACK™ INVESTIGATIONS SYSTEM SUBSCRIPTION

- a. Each representative identified below represents and warrants that it has the full power, right and authority to enter into this Agreement on behalf of its respective party.

LEADSONLINE, LLC (LeadsOnline)	
SIGNATURE:	
NAME:	Alexander Finley
TITLE:	President & CEO
DATE:	
ADDRESS:	6900 Dallas Parkway, Suite 825, Plano, Texas 75024, United States

WALTON COUNTY GA SHERIFF (Customer)	
SIGNATURE:	
NAME:	
TITLE:	
DATE:	
ADDRESS:	1425 S Madison Ave, Monroe, Georgia 30655, United States

LEADS

ONLINE

NIGHTHAWK™

SUBSCRIPTION

ORDER FORM No. Q-12244-NH | AGENCY ID: 7308

CUSTOMER:

WALTON COUNTY GA SHERIFF

UNIT:

SHERIFF

1. SERVICE

- a. **Service.** LeadsOnline NightHawk™ for Law Enforcement Agency users (**Service**).
- b. **Authority.** Customer represents that it is a law enforcement agency or governing body of a law enforcement agency, an entity duly authorized by municipal, state county or federal government to enforce laws or investigate crimes, and the Eligible Users are employed by Customer in the Unit listed at the top of this Order Form.

2. PURPOSE

- a. **Law Enforcement Use.** Exclusively for the official law enforcement agency duties of Customer's Unit; information retrieved from the Service is for the exclusive use of Eligible Users with the exception of disclosure necessary to investigate and prosecute crimes within the jurisdiction of and investigated by Customer's Unit.

3. DEFINITIONS

- a. **Analysis Files** are records electronically submitted by a Customer to the Service for automated analysis including but not limited to unstructured images, video, audio or text submitted, and data related to communications or movements of devices, vehicles and other entities, which reference data for identifying locations including cell site lists, landmarks, and locations related to crimes. Analysis Files are typically generated by telecommunications network providers and systems, app providers, computers, extraction systems and are provided to Customer via a legal process or voluntarily by persons with the right to provide them. Analysis Files are Customer Property.

4. SERVICE RECIPIENT & ELIGIBLE USERS

- a. **Capacity and Eligible Users.** No more than the Quantity per Service Period listed below of named individual employees of Customer in its Sheriff, each with a unique login (**Eligible Users**).

Eligible User logins may not be shared and individuals in a division who are not Eligible Users may not access the Service.

During initial onboarding, Customer must provide LeadsOnline with the names and email addresses of Eligible Users (Customer may revise its Eligible Users Form a reasonable number of times each year).
- b. **Access.** Access to Analysis Files is limited to Eligible Users for Services on this Order Form, but may be shared with eligible users of other order forms if directed by Customer.

5. TERM, SERVICE PERIODS & SUBSCRIPTION FEES

- a. **Order Term.** This Order Form will become effective as of the Effective Date and remain in effect through the Service Periods listed below (**Initial Term**) and any renewal Service Periods or until termination by LeadsOnline or Customer as described below. The Effective Date shall be defined as the date of the last signature below.
- b. **Payment Terms.** Payment shall be made on or before each anniversary during the Initial Term and any renewal term thereafter.

START DATE	END DATE	RATE	QTY	TOTAL DUE
October 1, 2026	June 30, 2027	\$3,074.25	1	\$3,074.25
July 1, 2027	June 30, 2028	\$4,221.97	1	\$4,221.97

- c. **Renewals.** Neither party is obligated to renew this Order Form. Prior to the expiration of the Initial Term or any renewal term, the parties may renew this Order Form for additional one-year terms by LeadsOnline's submission of a valid invoice to Customer for the renewal Service Period at then-current pricing and Customer's payment of such invoice within thirty (30) days of renewal.

- d. **Applicable Taxes.** Fees are exclusive of sales, use, withholding, TPT, VAT, and other similar taxes, and if required by law Customer is responsible for payment of such taxes. Any taxes referenced and/or quoted are estimates only, and not all services may be subject to taxation. Final tax amounts will be determined based on applicable laws at the time of invoicing. Customer may provide a Tax Exemption Certificate if applicable.

6. FEATURES

NIGHTHAWK™ KEY FEATURES AND CHARACTERISTICS	
LeadsOnline NightHawk™ System	Upload and analyze multiple file types, including text and social media, to translate data into actionable leads and seamlessly share across your agency.
LeadsOnline S.I.F.T. System	Utilize the Subject Interaction Filtering Tool to analyze calls and messages, events, GPS trackers, gunfire acoustic identifiers, LPR hits, and other data points overlaid in real time to build your case.
LeadsOnline Link Chart System	Upload mugshots and case photos to better visualize people, places, and things associated to your case for communicating, managing, and navigating large-scale investigations.
LeadsOnline Collaboration System	Case-level access control allows you to restrict or grant access to other users inside and outside of your agency providing cross-collaboration into crime patterns outside of your jurisdiction.
LeadsOnline Toolbox	Use LeadsOnline's automated search warrant generation, automated phone lookups, repository of training materials, video tutorials, templates, resources, software, process guides, carrier and network specifications, contacts, subject matter assistance and other content relevant to criminal investigations.

7. TRAINING & REMOTE TECHNICAL SUPPORT

- a. **Registration.** Eligible User accounts include unlimited access to NightHawk, Help Documents, Affidavit/Preservation Templates, and NightHawk University.
- b. **Training.** Online new user NightHawk basic training included.
- Additional courses available via LeadsOnline Training Portal.
 - Other on-demand training webinars on digital evidence analysis are available in the LeadsOnline Toolbox.
- c. **Support.** Technical Support program is described at leadsonline.com/support.

8. MISCELLANEOUS

- a. This Order Form is attached to and incorporated into the Subscription Services Agreement between **Customer** and **LeadsOnline** dated **(Agreement)**.
- b. This Order Form is governed by the terms of the Agreement between the parties. All terms not defined in this Order Form have the meanings ascribed to such terms in the Agreement. This Order Form and the Agreement constitute the entire agreement between the parties, and supersede all prior or contemporaneous negotiations, agreements, and representations, whether oral or written, related to this subject matter. No modification or waiver of any term of this Order Form is effective unless both parties sign an amendment to this Order Form. LeadsOnline may include a purchase order number on Customer's invoice solely for Customer's internal payment and record keeping processes, but any terms within any purchase order in response to a quote, order form or invoice will not modify or enlarge the obligations or liabilities of either party even if the parties sign it.

<< REMAINDER OF PAGE LEFT INTENTIONALLY BLANK—SIGNATURE PAGE TO FOLLOW >>

9. SIGNATURES FOR NIGHTHAWK™ SUBSCRIPTION

- a. Each representative identified below represents and warrants that it has the full power, right and authority to enter into this Agreement on behalf of its respective party.

LEADSONLINE, LLC (LeadsOnline)		WALTON COUNTY GA SHERIFF (Customer)	
SIGNATURE:		SIGNATURE:	
NAME:	Alexander Finley	NAME:	
TITLE:	President & CEO	TITLE:	
DATE:		DATE:	
ADDRESS:	6900 Dallas Parkway, Suite 825, Plano, Texas 75024, United States	ADDRESS:	1425 S Madison Ave, Monroe, Georgia 30655, United States

LEADS ONLINE ORDER SUMMARY No. S-21257

AGENCY ID: 7308

CUSTOMER:

WALTON COUNTY GA SHERIFF

UNIT:

SHERIFF'S OFFICE

PRORATE *(Due Now)*

DUE DATE	SCOPE OF SERVICES	RATE	QTY	AMOUNT
10/01/26	TotalTrack Investigations System	\$11,872.50	1	\$11,872.50
10/01/26	NightHawk User License	\$3,074.25	1	\$3,074.25
Total:				\$14,946.75

YEAR ONE OPTIONAL RENEWAL

DUE DATE	SCOPE OF SERVICES	RATE	QTY	AMOUNT
07/01/27	TotalTrack Investigations System	\$16,304.90	1	\$16,304.90
07/01/27	NightHawk User License	\$4,221.97	1	\$4,221.97
Total:				\$20,526.87

PAYMENT TERMS & TAXES

Unless otherwise specified on the Order Form(s), Customer must pay all fees within 30 days of each anniversary during the Initial Term and any subsequent Renewal Term.

FEES ARE EXCLUSIVE OF SALES, USE, WITHHOLDING, VAT, TPT, AND OTHER SIMILAR TAXES, AND IF REQUIRED BY LAW CUSTOMER IS RESPONSIBLE FOR PAYMENT OF SUCH TAXES. ANY TAXES REFERENCED AND/OR QUOTED ARE ESTIMATES ONLY, AND NOT ALL SERVICES AND/OR HARDWARE MAY BE SUBJECT TO TAXATION. FINAL TAX AMOUNTS WILL BE DETERMINED BASED ON APPLICABLE LAWS AT THE TIME OF INVOICING.

CUSTOMER SHOULD PROVIDE A TAX EXEMPTION CERTIFICATE, IF APPLICABLE.



September 24, 2026

The Honorable David G. Thompson, Chairman
Walton County Board of Commissioners
111 South Broad Street
Monroe, Georgia 30655
davidg.thompson@co.walton.ga.us

**Re: Walton County Old Jail Facility Renovations | PPI Project No. A26-036
Additional Services #1 -Alternate Government Annex Planning**

Dear Chairman Thompson:

Precision Planning, Inc. (PPI) appreciates the opportunity to submit this proposal of additional services to Walton County (Client). This proposal is based upon our meeting on September 24, 2026. We offer the following project understanding, scope and fees.

PROJECT UNDERSTANDING

PPI understands that the Client wishes to develop an alternate solution to meeting the growing space needs of County departments. The property around the Walton County Government Center and Public Safety Complex will be evaluated and master planned for this purpose, to include the following departments:

- | | |
|----------------------|-----------------------|
| • Human Resources | • Elections |
| • Tax Assessor | • Fire Administration |
| • Tax Commissioner | • EMA |
| • Planning & Zoning | • EMA |
| • Board of Assessors | |

PROJECT COMPENSATION

PPI agrees to perform these additional services on an hourly basis according to the contracted hourly rates in the original agreement **Not to Exceed (N.T.E.) \$8,000.00**. Invoices will be based on actual manhours.

An executed copy of this agreement may be returned to me by e-mail. Precision Planning appreciates this opportunity to continue serving Walton County.

Sincerely,

Elizabeth A. Hudson, AIA, NCARB
Executive Vice President

LH/kb

g:\document\26\26-000\1502\walton county\old jail renovation\1 preliminary design\walton county old jail add svcs #1.doc

Authorization given this _____ day of
_____, 2026

By: _____

Printed Name/Title: _____