AMENDED AGENDA



CITY OF WAUPUN PLAN COMMISSION MEETING
Waupun City Hall – 201 E. Main Street, Waupun WI
Wednesday, August 31, 2022 at 4:30 PM

The Waupun Plan Commission will meet in-person, virtual, and teleconference on Wednesday, August 31, 2022 at 4:30 pm in the Waupun City Hall Council Chambers.

To Join Zoom Meeting:

https://us02web.zoom.us/j/87297514722?pwd=VWJQZUw0b245MkpKMzN4M05TSkQ4QT09

Meeting ID: 872 9751 4722

Passcode: 404145

By Phone: (312) 626-6799 US (Chicago)

CALL TO ORDER

ROLL CALL

<u>PERSONS WISHING TO ADDRESS THE PLAN COMMISSION</u>--State name, address, and subject of comments. (2 Minutes)

No Public Participation after this point.

FUTURE MEETINGS AND GATHERING INVOLVING THE PLAN COMMISSION

CONSIDERATION - ACTION

- 1. Approve minutes of the August 24, 2022 meeting.
- 2. Site Plan Review 1804 Shaler Dr.
- 3. Extraterritorial Certified Survey Map Review N11534 CTH M

ADJOURNMENT

Upon reasonable notice, efforts will be made to accommodate disabled individuals through appropriate aids and services. For additional information, contact the City Clerk at 920-324-7915.



M I N U T E S CITY OF WAUPUN PLAN COMMISSION Waupun City Hall – 201 E. Main Street, Waupun WI Wednesday, August 24, 2022 at 4:30 PM

CALL TO ORDER

Chairman Bishop called the Plan Commission meeting to order at 4:30 pm

ROLL CALL

Members Present: Mike Matoushek, Jerry Medema, Elton TerBeest, Chairman Rohn Bishop, Jeff Daane, Jon

Dobbratz, and Jill Vanderkin

Staff Present: Kathy Schlieve - Administrator, Dan VandeZande - City Attorney, Mike Beer - Fire Inspector, Susan

Leahy – Zoning Administrator Also Present: Phil Cosson

PERSONS WISHING TO ADDRESS THE PLAN COMMISSION--

None

FUTURE MEETINGS AND GATHERING INVOLVING THE PLAN COMMISSION

The next scheduled Plan Commission meeting will be on Wednesday, September 28, 2022 at 4:30 pm.

CONSIDERATION - ACTION

- Approve minutes of August 18, 2022 meeting.
 Motion by Matoushek 2nd by Medema to approve the minutes of the August 18, 2022 meeting.
- 2. Public Hearing regarding the proposed creation of Tax Incremental District No. 9, the proposed boundaries of the District, and the proposed Project Plan for the District.

Chairman Bishop read the call of the hearing and its purpose. Motion by TerBeest, 2nd by Dobbratz to open the Public Hearing

Kathy Schlieve discussed that Plan Commission will be presented with TIF District Project Plan and creation of TIF 9 boundaries. The land has been vacant for a number of years. The TIF will address public infrastructure and housing. There is a signed developer's agreement for Phase 1 of the Project Plan. This is a three (3)-phase project.

Phil Cosson from Ehlers appeared to discuss the plan and boundaries. He explained that to create a new TIF district the first item that needs to be done is the Plan Commission approves the resolution, then the Common Council approves it and then it goes to the Joint Review Board for final approval

He explained the three phases of the project plan, funding, timing of the plan, increment to the district, maps of the district, listing of all parcels contained in the TIF District, project list, tax payments to the Town of Chester, development assumptions, development agreements, and cash flow.

Dan VandeZande discussed the money involved with the plan and we need some buffer but also wanted to be conservative in case there are changes so we would still be in position that the cash flow would still work. Any expenditures that would come forward would go to the Council for approval.

There were no public appearances for the Public Hearing.

Motion by Matoushek, 2nd by Dobbratz to close the Public Hearing. Motion carried, unanimously.

3. Consideration and possible action on a "Resolution Establishing the Boundaries of and Approving the Project Plan for Tax Incremental District No. 9." The Resolution approves the project plan.

Motion by Dobbratz, 2nd by TerBeest to approve the resolution and project plan for Tax Incremental District No. 9 as presented.

Vote: Matoushek, Medema, TerBeest, Bishop, Daane, Dobbratz, Vanderkin – "AYE" Motion carried, unanimously 7-0.

4. Public Hearing - Annexation Petition of Debra E. Levey, Susan M. Rogahn, Janice G. Bauman, Nancy B. Hodgson, f/k/a Nancy B. Maleck, Arthur O. Claggett and Dwight E. Claggett to annex real estate located in the Town of Chester to the City of Waupun

Property Address: State Road 26, Waupun, WI 53963

Tax Parcel Number: 010-1315-0922-000

Chairman Bishop read the call of the hearing and its purpose.

Motion by Matoushek, 2nd by Vanderkin to open the Public Hearing

Kathy Schlieve explained the annexation pertains to project plan for TIF 9 and this was requested by Claggett family in advanced of plan, which allowed being included in the plan.

Dan VandeZande reported that the petition was reviewed by the Department of Administration and they believe this is in the public interest to move forward even though it may create a town island. He reviewed case law pertaining to town islands and is confident we are safe to do this. If this land is not annexed, we cannot include it in TIF 9.

There were no public appearances for the Public Hearing.

Motion by Matoushek, 2nd by TerBeest to close the public hearing. Motion carried, unanimously.

Motion by Medema, 2^{nd} by Dobbratz to recommend to the Common Council the approval of the Annexation Ordinance. Motion carried, unanimously.

5. Extraterritorial Stormwater Site Plan Review - Thomas Moul - 715 S Madison St.

Jeff Daane discussed the plan. A new owner recently acquired the land. The owner has allowed the construction company that is working on S. Madison St. to use some of this land for storage of equipment and material. In return, the contractor said they would make some improvements to the land. This property is not in the City limits and is in the Town of Chester. They are proposing a gravel area and new driveway onto Libby St. There is currently a building on the site, which has a permit taken out for demolition.

Jeff Daane will put a draft agreement together with recommendations from the Plan Commission, and Dan VandeZande will work on language for enforcing the agreement.

Motion by Matoushek, 2nd by Dobbratz to approve the site plan on the condition that the property owner signs the agreement with the following conditions:

Conditions:

- 1. The house will be removed by March 1, 2023
- 2. Blacktop is required in the road right of way.

- 3. 12" culvert installed below the driveway.
- 4. 75' grass area to the east of the newly installed gravel must be maintained for drainage.
- 5. Removal of existing driveway on Libby St.

Motion carried, unanimously.

6. Certified Survey Map Review of Kari Pattee for properties at 19 and 23 S. Madison St

Dan VandeZande explained the CSM. This has come before the Plan Commission before and it was recommended to hold off on the approval of it because the County had some concerns with it. They tried to go another route and just quick claim deed the land, but that did not work. Dan suggested getting approval of the Certified Survey Map and then some other actions will need to be done after this part is complete. Dan recommends approval of the CSM, but not recoding it until the quick claim deeds are done to fix the lot lines. This will solve 95% of the problems with this area.

Motion by Dobbratz, 2nd by Matoushek to recommend approval of the Certifies Survey Map of Kari Pattee for properties at 19 and 23 S. Madison St. Motion carried, unanimously

7. Site Plan Review - 5 Doty St

Sue Leahy discussed the plan as the owners were not in attendance. This will be a retail store with an asphalt tank located directly behind the building. There will be a fence around the entire property. They looked at a building downtown but that was not a good location for a storage tank outside. This property is zoned M-1 and meets the zoning requirements and does not require a Conditional Use Permit. Questions were asked as to hours of operation, who their customer base is, traffic concerns with a retail business, spill containment for the tank. Kathy stated that the Department of Corrections has a warehouse next to this property, but the rest of the area is predominantly residential and is concerned this could be disruptive to the neighborhood

Motion by Matoushek, 2nd by Dobbratz to table this item to a future meeting for more information from the owner. Motion carried, unanimously

ADJOURNMENT

Motion by Dobbratz, 2nd by Matoushek to adjourn the meeting. Motion carried, meeting adjourned at 5:12 pm

Minutes prepared by Trista Steinbach

ALL-PHASE HVAC LLC DEVELOPMENT

CITY OF WAUPUN DODGE COUNTY, WISCONSIN





East Wau PROJECT. LOCATION

SHEET INDEX

G - GENERAL SHEETS


TITLE SHEET

D - DETAIL SHEETS

CONSTRUCTION DETAILS

ST - SITE PLANS

FROSION CONTROL PLAN ST 1 ST 2 SITE IMPROVEMENT PLAN



UTILITIES

120 E. MAPLE AVENUE BEAVER DAM, WI 53916 PHONE: 920-887-6030 CONTACT: DAVID KROHN

WAUPUN UTILITIES 817 S MADISON STREET PHONE: 920-324-7920 CONTACT: STEVE BROOKS

TELEPHONE: 70 E. DIVISION STREET, FLOOR 1 FOND DU LAC, WI 54935 PHONE: 920-929-1013 CONTACT: CHUCK BARTELT

SANITARY & WATER: WAUPUN UTILITIES 817 S. MADISON STREET WAUPUN, WI 53963 PHONE: 920-324-7920 CONTACT: STEVE SCHRAMM

201 F MAIN STREET PHONE: 920-210-8200 CONTACT: JEFF DAANE

CHARTER COMMUNICATIONS N3760 C.T.H. "DJ" JUNEAU, WI 53039 PHONE: 920-349-3201



www.DiggersHotline.com

UTILITY LOCATIONS SHOWN ON PLANS ARE APPROXIMATE AND CONTRACTOR SHALL HAVE APPROPRIATE UTILITY MARK EXACT LOCATIONS PRIOR TO CONSTRUCTION.



LOCATION MAP




ENGINEERING | ARCHITECTURE | SURVEYING FUNDING | PLANNING | ENVIRONMENTAL 201 Corporate Drive, Beaver Dam WI 53916 (920) 887-4242 www.msa-ps.com ALL-PHASE HVAC LLC DEVELOPMENT CITY OF WAUPUN DODGE COUNTY, WI PARCEL #29213150933003

TITLE SHEET


21871000 G1

CONSTRUCTION SITE EROSION CONTROL REQUIREMENTS


- SECTION NR216.46 OF WISCONSIN STATE ADMINISTRATIVE CODE IDENTIFIES REQUIREMENTS
 FOR CONSTRUCTION SITE AND POST-CONSTRUCTION EROSION CONTROL. IT IS THE INTENT
 OF THESE PLANS TO SATISFY THESE REQUIREMENTS. THE METHODS AND STRUCTURES USED
 TO CONTROL EROSION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR
 SHALL IMPLEMENT AN APPROPRIATE MEANS OF CONTROLLING EROSION DURING SITE OPERATION
 AND UNTIL THE VEGETATION IS RE-ESTABLISHED. ADJUSTMENTS TO THE CONTROL SYSTEM
 SHALL BE MADE AS REQUIRED.
- ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE WISCONSIN DNR'S
 CONSERVATION PRACTICE STANDARDS. THESE STANDARDS ARE PERIODICALLY UPDATED AND
 IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN AND REFERENCE THE MOST RECENTLY
 RELEASED STANDARD.
- THIS INFORMATION IS ONLY ONE PART OF THE OVERALL EROSION CONTROL REQUIREMENTS.
 ADDITIONAL REQUIREMENTS MAY ALSO BE SHOWN ON THE CONTRACT DRAWINGS AND IN THE
 ACCOMPANYING SPECIFICATIONS.
- 4. ADDITIONAL EROSION CONTROL MEASURES, AS REQUESTED IN WRITING BY THE STATE OR LOCAL INSPECTORS, OR THE OWNER'S ENGINEER, SHALL BE INSTALLED WITHIN 24 HOURS.
- 5. THE AREA OF EROSIVE LAND EXPOSED TO THE ELEMENTS BY GRUBBING, EXCAVATION, TRENCHING, BORROW AND FILL OPERATIONS AT ANY ONE TIME SHALL BE MINIMIZED TO THE MAXIMUM EXTENT PRACTICABLE. FOR ANY DISTURBED AREA THAT REMAINS INACTIVE FOR GREATER THAN 7 WORKING DAYS, OR WHERE GRADING WORK EXTENDS BEYOND THE PERMANENT SEEDING DEADLINES, THE SITE MUST BE TREATED WITH TEMPORARY STABILIZATION MEASURES SUCH AS SOIL TREATMENT, TEMPORARY SEEDING AND/OR MULCHING. ALL DISTURBED AREAS SHALL BE TREATED WITH PERMANENT STABILIZATION MEASURES WITHIN 3 WORKING DAYS OF FINAL GRADING
- ALL EROSION CONTROL MEASURES AND STRUCTURES SERVING THE SITE MUST BE INSPECTED
 AT LEAST WEEKLY OR WITHIN 24 HOURS OF THE TIME 0.5 INCHES OF RAIN HAS OCCURRED.
 ALL NECESSARY REPAIR AND MAINTENANCE WILL BE DONE AT THIS INSPECTION TIME.
- ALL EROSION CONTROL DEVICES AND/OR STRUCTURES SHALL BE PROPERLY INSTALLED PRIOR
 TO CLEARING AND GRUBBING OPERATIONS WITHIN THEIR RESPECTIVE DRAINAGE AREAS.
 THESE SHALL BE PROPERLY MAINTAINED FOR MAXIMUM EFFECTIVENESS UNTIL VEGETATION
 IS RE-FSTABI ISHED.
- 8. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY INSTALLED PRIOR TO ANY SOIL DISTURBANCE.
- 9. ANY SLOPES STEEPER THAN 3H:1V SHALL BE STAKED WITH EROSION CONTROL FABRIC UNLESS INDICATED ON THE PLAN.
- 10. ALL WASTE AND UNUSED BUILDING MATERIALS (INCLUDING GARBAGE, DEBRIS, CLEANING WASTES, WASTEWATER, TOXIC MATERIALS, OR HAZARDOUS MATERIALS) SHALL BE PROPERLY DISPOSED OF AND NOT ALLOWED TO BE CARRIED OFF-SITE BY RUNOFF OR WIND.
- 11. WIND EROSION SHALL BE KEPT TO A MINIMUM DURING CONSTRUCTION. WATERING, MULCH, OR A TACKING AGENT MAY BE REQUIRED TO PROTECT NEARBY RESIDENCES AND WATER RESOURCES.
- 12. CHANNELIZED RUNOFF ENTERING THE PROJECT SITE FROM ADJOINING LANDS SHALL BE DIVERTED THROUGH NATURALLY OR ARTIFICIALLY EROSION-RESISTANT CONVEYANCES. IF CHANNELIZED RUNOFF CANNOT BE DIVERTED, SITE BEST MANAGEMENT PRACTICES MUST ACCOUNT FOR THE ADDITIONAL FLOW RATES AND EROSION POTENTIAL THAT SUCH RUNOFF PRESENTS.
- 13. THE CONTRACTOR SHALL TAKE ALL POSSIBLE PRECAUTIONS TO PREVENT SOILS FROM BEING TRACKED ONTO PUBLIC OR PRIVATE ROADWAYS. PAVED SURFACES ADJACENT TO CONSTRUCTION SITE VEHICLE ACCESS SHALL BE SWEPT AND/OR SCRAPED (NOT FLUSHED) PERIODICALLY TO REMOVE SOIL, DIRT, AND/OR DUST.
- 14. EROSION CONTROLS SHALL BE INSTALLED ON THE DOWNSTREAM SIDE OF TEMPORARY STOCKPILES. ANY SOIL STOCKPILE THAT REMAINS FOR MORE THAN 30 DAYS SHALL BE COVERED OR TREATED WITH STABILIZATION PRACTICES SUCH AS TEMPORARY OR PERMANENT SEEDING AND MULCHING. ALL STOCK PILES SHALL BE PLACED AT LEAST 75 FEET FROM STREAMS OR WETLANDS.
- 15. ADDITIONAL EROSION CONTROL FOR UTILITY CONSTRUCTION (STORM SEWER, SANITARY SEWER, WATER MAIN, ETC.) SHALL INCLUDE THE FOLLOWING:
 - a. PLACE EXCAVATED TRENCH MATERIAL ON THE HIGH SIDE OF THE TRENCH.
 b. BACKFILL, COMPACT, AND STABILIZE THE TRENCH IMMEDIATELY AFTER PIPE CONSTRUCTION.
 c. DISCHARGE OF TRENCH WATER OR DEWATERING EFFLUENT MUST BE PROPERLY TREATED
 TO REMOVE SEDIMENT IN ACCORDANCE WITH THE WDNR CONSERVATION PRACTICE
 STANDARD 1061 DEWATERING OR A SUBSEQUENT WDNR DEWATERING STANDARD PRIOR
 TO DISCHARGE INTO A STORM SEWER, DITCH, DRAINAGEWAY, OR WETLAND OR LAKE.
- 16. ALL DRAINAGE CULVERTS, STORM DRAIN INLETS, MANHOLES, OR ANY OTHER EXISTING STRUCTURES THAT COULD BE DAMAGED BY SEDIMENTATION SHALL BE PROTECTED ACCORDING TO THE VARIOUS METHODS PROVIDED IN THE PRINTED CONSERVATION PRACTICE STANDARDS.
- 17. ANY SOIL EROSION THAT OCCURS AFTER FINAL GRADING AND/OR STABILIZATION MUST BE REPAIRED AND THE STABILIZATION WORK REDONE.
- 18. THE FIRST SIX WEEKS AFTER INITIAL STABILIZATION, ALL NEWLY SEEDED AND MULCHED AREAS SHALL WATERED WHENEVER 7 DAYS ELAPSE WITHOUT A RAIN EVENT.
- 19. WHEN THE DISTURBED AREA HAS BEEN STABILIZED BY PERMANENT VEGETATION OR OTHER MEANS, TEMPORARY BMP'S SUCH AS SILT FENCES, STRAW BALES, AND SEDIMENT TRAPS SHALL BE REMOVED AND THESE AREAS STABILIZED.
- 20. ALL TEMPORARY BEST MANAGEMENT PRACTICES SHALL BE MAINTAINED UNTIL THE SITE IS STABILIZED.
- 21. ALL DISTURBED AREAS SHALL BE PERMANENTLY STABILIZED WITH SEED AND MULCH UNLESS OTHERWISE SPECIFIED. A MINIMUM OF FOUR INCHES OF TOPSOIL SHALL BE APPLIED TO ALL AREAS TO BE SEEDED OR SODDED.







SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)




GENERAL NOTES

ATTACH THE FABRIC TO THE POSTS WITH WIRE STAPLES OR WOODEN LATH AND NAILS

 TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.

SILT FENCE

- 2. WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 $\frac{1}{8}$ " x 1 $\frac{1}{8}$ " OF OAK OR HICKORY.
- 3. CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS: A) TWIST METHOD -- OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK METHOD -- HOOK THE END OF EACH SILT FENCE LENGTH.



TRENCH DETAIL






ENGINEERING | ARCHITECTURE | SURVEYING | FUNDING | PLANNING | ENVIRONMENTAL | 201 Corporate Drive, Beaver Dam WI 53916 | (920) 887-4242 | www.msa-ps.com

ALL-PHASE HVAC LLC DEVELOPMENT CITY OF WAUPUN DODGE COUNTY, WI PARCEL #29213150933003

CONSTRUCTION DETAILS


21871000 sheet



- TRACKING PAD WIDTH SHALL BE AT LEAST THE FULL WIDTH OF HTE EGRESS POINT OR 12' WIDE MINIMUM.
 TRACKING PAD LENGTH SHALL BE 50' FOR CONSTRUCTION SITES, 30' FOR SINGLE FAMILY RESIDENTIAL,
 OR AS SPECIFIED IN THE CONTRACT DOCUMENTS. LENGTH OF TRACKING PAD MAY NEED TO BE
 INCREASE OR ADDITIONAL SEDIMENT CONTROL PRACTICES SHALL BE INSTALLED BY THE CONTRACTOR
- INCREASE OR ADDITIONAL SEDIMENT CONTROL TO STATE SEDIMENT TRACK-OUT OCCURS.

 GEOTEXTILE FABRIC TYPE R SHALL BE INSTALLED BETWEEN THE STONE AND SUBGRADE ON SITES
- WHERE HIGH GROUND WATER IS OBSERVED.
 CONTRACTOR SHALL CLEAN STREET/ROADWAY ADJACENT TO ALL CONSTRUCTION ACCESS POINTS AT THE END OF EACH WORKDAY OR MORE FREQUENTLY IF REQUESTED.


STONE TRACKING PAD



- BEDDING AND HAUNCHING MATERIAL SHALL BE WELL-GRADED 3/4 TO 1/4 INCH CRUSHED STONE OR OTHER NON-COHESIVE MATERIAL NOT SUBJECT TO MIGRATION AND FREE OF DEBRIS ORGANIC MATERIAL, AND LARGE STONES.
- 2. BEDDING MATERIAL TO BE PLACED BEFORE SETTING PIPE, 4 INCH MINIMUM UNDER BARREL WITH 3 INCH MINIMUM UNDER BELL.
- INITIAL BACKFILL SHALL BE DENSELY COMPACTED, NON-COHESIVE FINELY DIVIDED MATERIAL FREE OF DEBRIS, ORGANIC MATERIAL, AND LARGE STONES.
- IN ROCK OR OTHER UNCOMPRESSIBLE MATERIALS, THE TRENCH SHALL BE OVEREXCAVATED A MINIMUM OF 6-INCHES AND REFILLED WITH GRANULAR MATERIAL.

CLASS "B" EMBEDMENT FOR RIGID PIPE DETAIL NO SCALE






TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE. THE CONTRACTOR SHALL DEMONSTRATE A METHOD OF MAINTENANCE, USING A SEWN FLAP, HAND HOLDS OR OTHER METHOD TO PREVENT ACCUMULATED SEDIMENT FROM ENTERING THE INLET.


INLET PROTECTION, TYPE C NO SCALE

GENERAL NOTES - INLET PROTECTION

INLET PROTECTION DEVICES SHALL BE MAINTAINED OR REPLACED AT THE DIRECTION OF THE ENGINEER MANUFACTURED ALTERNATIVES APPROVED AND LISTED ON THE DEPARTMENT'S EROSION CONTROL PRODUCT ACCEPTABILITY LIST MAY BE SUBSTITUTED. WHEN REMOVING OR MAINTAINING INLET PROTECTION, CARE SHALL BE TAKEN SO THAT THE SEDIMENT TRAPPED ON THE GEOTEXTILE FABRIC DOES NOT FALL INTO THE INLET. ANY MATERIAL FALLING INTO THE INLET SHALL BE REMOVED IMMEDIATELY.

- 1) FINISHED SIZE, INCLUDING FLAP POCKETS WHERE REQUIRED, SHALL EXTEND A MINIMUM OF 10" AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL
- (2) FOR INLET PROTECTION, TYPE C (WITH CURB BOX), AN ADDITIONAL 18" OF FABRIC IS WRAPPED AROUND THE WOOD AND SECURED WITH STAPLES. THE WOOD SHALL NOT BLOCK THE ENTIRE HEIGHT OF THE CURB BOX OPENING.
- 3) FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2X4.





- 1. SEE PLANS AND SPECIFICATIONS FOR SIZE AND TYPE OF CURB STOP AND BOX CORPORATION AND SERVICE LINE
- 2. COMMUNITY STANDARDS SHALL SUPERCEED THE DIMENSIONS FROM THE PROPERTY LINE.
- 3. TRACER WIRE SHALL BE INSTALLED ALONG ALL NEWLY INSTALLED WATER SERVICES (INCIDENTAL TO WATER SERVICE PIPING).

WATER SERVICE DETAIL NO SCALE


(NEXT TO CLEANOUT) CLEANOUT (APPROX. 5' FROM BLDG.) ERMINAL BOX & PVC CONDUIT (INCIDENTA TRACER WIRE FASTENERS (TYP. 10' MAX. (2 LB, MIN) RISER PIPE (OPTIONAL) - SERVICE WYE

ELEVATION VIEW

NOTES FOR LATERAL INSTALLATION

- 1. MININUM DEPTH OF COVER UNDER ROADWAY = 7 FEET
- 2. MININUM DEPTH OF COVER UNDER GRASS AREAS = 5 1/2 FEET.
- 3. MININUM DEPTH OF COVER UNDER GRASS AREAS WITH FROST PROTECTION = 3 FEET 6 INCHES.
- 4. LATERAL SLOPES SHALL BE 1/8 INCH PER FOOT MINIMUM AND 1/2 INCH PER FOOT MAXIMUM NOTES FOR TRACER WIRE INSTALLATION:
- THE TRACER WIRE SHALL REMAIN CONTINUOUS TO THE GREATEST EXTENT POSSIBLE.
 TRACER WIRE SHALL BE INSTALLED WITH THE NON-CONDUCTIVE SERVICE. PIPE TRACER WIRE TERMINAL CONDUITS SHALL BE INSTALLED DIRECTLY ABOVE THE SEWER LATERAL OR AS DETERMINED BY THE ENGINEER OR OWNER.
- 3. TRACER WIRE SHALL BE RESTRAINED BY CABLE-TIES, TAPE, OR BY NON-CORRESIVE FASTNER APPROVED BY THE OWNER, INSTALLED EVERY 10 FEET ALONG SERVICE. DO NOT WRAP TRACER WIRE AROUND THE PIPE. 4. TRACER WIRE SHALL RUN FROM THE WYE AND TERMINATE IN A TERMINAL BOX FLUSH WITH THE FINISHED GROUND. PROVIDE 2-FEET EXTRA TRACER WIRE IN ACCESS PIPE AND ATTACH TRACER WIRE TO TERMINAL BOLTS. (INCIDENTAL TO PIPE INSTALLATION)

SANITARY SEWER LATERAL DETAIL



WATER SERVICE AND SANITARY SEWER LATERAL DETAIL NO SCALE


ALL-PHASE HVAC LLC DEVELOPMENT CITY OF WAUPUN

DODGE COUNTY, WI PARCEL #29213150933003

CONSTRUCTION DETAILS


21871000 D2

ENGINEERING | ARCHITECTURE | SURVEYING FUNDING | PLANNING | ENVIRONMENTAL 201 Corporate Drive, Beaver Dam WI 53916 (920) 887-4242 www.msa-ps.com



TYPE INTEGRAL CURB AND WALK DETAIL

STANDARD SECTION



AGGREGATE BASE COURSE UNDER

CONCRETE (MINIMUM)

PIPE INSULATION DETAIL NO SCALE

DESIGNED BY: ARW Init

GENERAL PROJECT NOTES:


1. ALL EXISTING UTILITIES WITHIN THIS PLAN ARE SHOWN FOR INFORMATIONAL PURPOSES ONLY AND NO RESPONSIBILITY IS ASSUMED BY THE ENGINEER OR OWNER FOR THEIR ACCURACY OR DEGREE OF COMPLETION. THE CONTRACTOR IS RESPONSIBLE FOR MAKING HIS OWN DETERMINATION AS TO THE TYPE, LOCATION, AND ELEVATION OF ALL UNDERGROUND UTILITIES AS MAY BE NECESSARY TO AVOID DAMAGING ANY SUCH UTILITIES. THE CONTRACTOR SHALL CONTACT DIGGER'S HOTLINE AT (800) 242-8511 PRIOR TO ANY CONSTRUCTION SO THAT THE SITE MAY BE MARKED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF ANY UTILITIES.

- 2. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND ELEVATIONS IN THE FIELD. IF ANY ERRORS, DISCREPANCIES, OR OMISSIONS ARE APPARENT, BRING TO THE ATTENTION OF THE PROJECT ENGINEER PRIOR TO CONSTRUCTION OF ANYTHING AFFECTED SO THAT CLARIFICATION OR RE-DESIGN
- 3. UNLESS SPECIFIED WITHIN THIS CONSTRUCTION PLAN, NO EXISTING TREES SHALL BE DISTURBED OR DAMAGED. THE OWNER, IN WRITING, MUST APPROVE THE REMOVAL OF ANY EXISTING TREES IF THE CONTRACTOR BELIEVES THAT AN EXISTING TREE IS IN CONFLICT WITH THE PROPOSED IMPROVEMENTS. NO TREES OR TREE STUMPS SHALL BE BURIED ONSITE.
- 4. EXISTING KNOWN SURVEY MONUMENTS (SHOWN ON THE PLANS) ENCOUNTERED DURING CONSTRUCTION ARE TO BE PRESERVED AND LEFT UNDISTURBED. SHOULD THE CONTRACTOR ENCOUNTER UNKNOWN MONUMENTS, PROPERTY STAKES, ETC. (NOT SHOWN ON THE PLANS), THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER PRIOR TO ANY DISTURBANCE. FAILURE TO PRESERVE SUCH MONUMENTS SHALL NOT BE LLOWED AND REPLACEMENT BY A REGISTERED LAND SURVEYOR SHALL BE AT THE CONTRACTOR'S EXPENSE.
- . ELEVATIONS SHOWN WITHIN THIS PLAN REFERENCE THE NORTH AMERICAN VERTICAL DATUM.
- . REFER TO THE PROJECT ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR DETAILS PERTAINING TO THE PROPOSED BUILDINGS, ASSOCIATED ARCHITECTURAL FEATURES, AND SITE WORK SURROUNDING THE BUILDING
- 7. THE CONTRACTOR SHALL COORDINATE WITH ALL PRIVATE UTILITIES (GAS, ELECTRIC, TELEPHONE, CABLE TV, ETC.) REGARDING THE LOCATION SIZE, DEPTH, ETC. OF EXISTING AND PROPOSED SERVICE LINES WITHIN THE PROJECT SITE. THE CONTRACTOR SHALL COORDINATE THE RELOCATION OF ANY PRIVATE UTILITIES THAT ARE IN CONFLICT WITH THE PROPOSED IMPROVEMENTS. THE CONTRACTOR SHALL CAREFULLY WORK AROUND EXISTING UTILITY LINES, UTILITY POLES, UTILITY STRUCTURES, GUY WIRES, ETC. THAT ARE TO REMAIN UNDISTURBED. THE CONTRACTOR SHALL PROVIDE ANY NECESSARY TEMPORARY SHORING OR OTHER MEASURES TO PROTECT THESE FEATURES DURING CONSTRUCTION ACTIVITIES. (ALL INCIDENTAL TO CONSTRUCTION)

GENERAL EROSION CONTROL NOTES:


1. THE CONTRACTOR SHALL INSTALL ALL NECESSARY EROSION CONTROL MEASURES TO PREVENT EROSION ONTO THE ADJACENT PROPERTIES AND INTO THE ADJACENT EXISTING STREETS. ADDITIONAL EROSION CONTROL, NOT SHOWN ON THIS PLAN, MAY BE REQUIRED BY THE FIELD ENGINEER OR BY THE CITY DURING CONSTRUCTION (INCIDENTAL). EROSION CONTROL AND SITE STABILIZATION MEASURES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THIS CONSTRUCTION PLAN, THE PROJECT SPECIFICATIONS, THE LATEST EDITION OF THE WISCONSIN DINE EROSION CONTROL TECHNICAL STANDARDS, ANY LOCAL EROSION CONTROL & STORMWATER ORDINANCES, AND ANY CONDITIONS OF APPROVAL. INSTALL EROSION CONTROL MEASURES PRIOR TO INITIATION OF ANY SITE WORK. SEE THE "CONSTRUCTION SITE EROSION CONTROL REQUIREMENTS" FOR FURTHER EROSION CONTROL REQUIREMENTS AND NOTES.

- 2. CONTRACTOR SHALL PROTECT ALL EXISTING AND PROPOSED STREET INLETS, MANHOLES, DRAINAGE SWALES, CULVERTS, ETC. FROM SILTATION URING CONSTRUCTION AND UNTIL FINAL STABILIZATION OCCURS.
- . ALL EROSION CONTROL MEASURES AND STRUCTURES SHALL BE INSPECTED, MAINTAINED, AND DOCUMENTED BY THE CONTRACTOR WEEKLY AND WITHIN 24 HOURS AFTER A PRECIPITATION EVENT 0.5 INCHES OR GREATER. ALL NECESSARY REPAIR AND MAINTENANCE WILL BE DONE AT THIS INSPECTION TIME. THESE INSPECTIONS SHALL BE DOCUMENTED BY THE CONTRACTOR AND AVAILABLE TO THE ENGINEER ANDIOR OWNER UPON REQUEST. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO CONSTRUCTION OR INCLUDED IN THE CORRESPONDING EROSION CONTROL PRICE BID (IF APPLICABLE).



BASE THICKNESSES SHALL SUPERCEDE THE THICKNESSES SHOWN IN THIS DETAIL IF EXISTING CONDITIONS ARE GREATER (DETERMINED BY CITY IN THE FIELD).

ASPHALT PAVING DETAIL



CONCRETE SIDEWALK PAVING DETAIL

GENERAL TRAFFIC CONTROL NOTES:

IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO SCHEDULE HIS/HER WORK TO MINIMIZE THE INCONVENIENCE TO THE RESIDENTS AND BUSINESSES LOCATED ADJACENT TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE CITY AT LEAST TWO DAYS PRIOR TO CLOSING ANY

- 2. ALL TRAFFIC CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE LATEST EDITION OF THE UNITED STATES DEPARTMENT OF TRANSPORTATION MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS (MUTCD). THE CONTRACTOR IS RESPONSIBLE FOR ALL NECESSARY TRAFFIC CONTROL DURING THE DURATION OF CONSTRUCTION. THE CONTRACTOR SHALL INSPECT ALL TRAFFIC CONTROL MEASURES DAILY AND PERFORM ANY NECESSARY MAINTENANCE OR ADJUSTMENTS BASED ON THE ACTIVITIES PLANNED. ADDITIONAL TRAFFIC CONTROL MEASURES NOT SPECIFIED WITHIN THE CONTRACT DOCUMENTS MAY BE REQUIRED DURING CONSTRUCTION BY THE CITY AND ENGINEER (INCIDENTAL TO CONSTRUCTION). THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND CITY STAFF RELATIVE TO THE PLACEMENT AND MAINTENANCE OF ALL BARRICADES AND OTHER MEASURES USED.
- AFTER ALL CONSTRUCTION RELATED ACTIVITIES ARE COMPLETED, THE CONTRACTOR SHALL REMOVE ALL TRAFFIC CONTROL MEASURES. ANY DISTURBANCE OR DAMAGE RESULTING FROM THE REMOVAL OF THE TRAFFIC CONTROL MEASURES SHALL BE RESTORED OR REPAIRED TO THE SATISFACTION OF THE CITY.

GENERAL GRADING NOTES:

- ALL GRADING WORK SHALL BE PERFORMED IN ACCORDANCE WITH THIS CONSTRUCTION PLAN, THE PROJECT SPECIFICATIONS, AND ANY CONDITIONS OF APPROVAL
- 2. ALL PROPOSED GRADES SHOWN WITHIN THE PLANS ARE FINISHED GRADES. UNLESS SPECIFIED ON THE PLAN, THE CONTRACTOR SHALL CONSTRUCT/GRADE ALL CONCRETE, ASPHALT, AND GRASS AREAS TO A MINIMUM SLOPE OF 1.0%, 1.0%, AND 1.0%, RESPECTIVELY. THE MAXIMUM SURFACE SLOPE ACROSS HANDICAP PARKING STALLS AND WALKWAYS IN ANY DIRECTION SHALL BE 2.0% AND ACROSS HANDICAP ACCESSIBLE RAMPS SHALL BE 8.0%. THE MAXIMUM SURFACE SLOPE ACROSS THE PROPOSED PAVEMENT SHALL BE 6.0% UNLESS SPECIFIED OTHERWISE ON THE PLANS. THE CONTRACTOR SHALL NOTIFY THE ENGINEER, PRIOR TO CONSTRUCTION, OF ANY AREAS WHICH DO NOT SATISFY THE ABOVE MENTIONED SLOPES.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO MAKE HIS/HER OWN COMPUTATIONS FOR DETERMINATION OF EARTHWORK AND TOPSOIL QUANTITIES PRIOR TO BIDDING. IT IS RECOMMENDED THAT EACH BIDDER VISIT THE SITE TO VERIFY THE EXISTING CONDITIONS. NO CHANGES WILL BE MADE IN THE BID QUANTITY AMOUNT OR UNIT PRICE UNLESS CHANGES ARE MADE TO THE CONTRACT DRAWINGS AFTER BIDDING OF THE
- NO STOCKPILES (TOPSOIL OR EARTH MATERIAL) SHALL REMAIN AFTER ALL GRADING WORK IS COMPLETED UNLESS DIRECTED OTHERWISE BY THE OWNER. IF AFTER THE COMPLETION OF ALL SITE GRADING AND SUBGRADE PREPARATION WORK THERE IS EXCESS FILL MATERIAL, THE CONTRACTOR SHALL HAUL/STOCKPILE THE MATERIAL AT A LOCATION(S) AS DESIGNATED BY THE OWNER OR DISPOSE OF THE MATERIAL AS DIRECTED BY THE OWNER. IF THERE IS A SHORTAGE OF FILL MATERIAL, THE CONTRACTOR SHALL PURCHASE/IMPORT THE MATERIAL FROM OFFSITE. ALL GRADING AND SUBGRADE PREPARATION WORK AS WELL AS ANY DISPOSAL OF EXCESS MATERIAL AND/OR IMPORTING OF MATERIAL SHALL BE INCIDENTAL TO THE UNCLASSIFIED EXCAVATION BID ITEM.
- FILL PLACED WITHIN 10 FEET OR LESS FROM THE OUTSIDE EDGE OF A BUILDING SHALL BE SUITABLE EXCAVATED SOIL FREE OF ORGANIC DEBRIS, CLAY BALLS, AND AGGREGATE LARGER THAN 1.5-INCHES. THE FILL MATERIAL WITHIN THESE AREAS SHALL BE SPREAD AND COMPACTED UNIFORMLY IN 6-INCH TO 8-INCH MAXIMUM LIFTS TO AT LEAST 95 PERCENT MAXIMUM DRY DENSITY PER MODIFIED PROCTOR (ASTM D1557). ALL OTHER FILL AREAS WITHIN THE PROJECT SITE SHALL BE SPREAD AND COMPACTED IN 12-INCH MAXIMUM LIFTS TO AT LEAST 93 PERCENT DRY DENSITY PER MODIFIED PROCTOR (ASTM D1557).

GENERAL PAVING NOTES:

ALL PROPOSED PAVEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THIS CONSTRUCTION PLAN, THE PROJECT SPECIFICATIONS, THE REQUIREMENTS OF THE OWNER, THE LATEST EDITION OF THE WISCONSIN DEPARTMENT OF TRANSPORTATION SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION, AND ANY CONDITIONS OF APPROVAL.

ALL SAWCUTTING OF EXISTING ASPHALT AND CONCRETE SHALL BE INCIDENTAL TO PAVING.

GENERAL RESTORATION NOTES:

1. ALL PROPOSED RESTORATION SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THIS CONSTRUCTION PLAN, THE PROJECT SPECIFICATIONS, THE REQUIREMENTS OF THE OWNER, AND ANY CONDITIONS OF APPROVAL.

2. ALL DISTURBED OPEN SPACE AREAS SHALL BE TOPSOILED (MINIMUM 6" THICK), SEEDED, FERTILIZED, AND MULCHED IN ACCORDANCE WITH THE CONSTRUCTION PLANS, THE PROJECT SPECIFICATIONS, THE LATEST EDITION OF THE WISCONSIN DEPARTMENT OF TRANSPORTATION SPECIFICATIONS FOR HIGHWAY AND STREET CONSTRUCTION, AND THE WISCONSIN DNR CONSERVATION PRACTICE STANDARDS 1058 & 1059

WORK OUTSIDE OF PROJECT PROPERTY NOTES:


1. ALL DISTURBANCE WITHIN THE EXISTING CITY RIGHT-OF-WAY SHALL BE KEPT TO A MINIMUM. ALL PAVEMENT, GRASS AREAS, ETC. DISTURBED WITHIN THESE AREAS DURING CONSTRUCTION SHALL BE RESTORED EQUAL TO OR BETTER THAN PRE-CONSTRUCTION CONDITIONS AND TO THE SATISFACTION OF THE CITY. EXISTING GRAVEL BASE AND PAVEMENT DISTURBED WITHIN THE EXISTING STREET SHALL BE RESTORED WITH EQUAL THICKNESS AND WORKMANSHIP TO EXISTING CONDITIONS OR AS DIRECTED BY THE CITY. THE CONTRACTOR SHALL COORDINATE WITH THE CITY STAFF REGARDING BACKFILL AND COMPACTION REQUIREMENTS FOR ANY WORK PERFORMED WITHIN THESE AREAS.


GENERAL UTILITY NOTES:


1. ALL PROPOSED UTILITIES SHALL BE INSTALLED IN ACCORDANCE WITH THIS CONSTRUCTION PLAN, THE PROJECT SPECIFICATIONS, THE REQUIREMENTS OF THE OWNER, THE LATEST EDITION OF THE WISCONSIN STANDARD SPECIFICATIONS FOR SEWER & WATER CONSTRUCTION (FOR SANITARY & WATER), THE LATEST EDITION OF THE WISCONSIN DEPARTMENT OF TRANSPORTATION SPECIFICATIONS FOR HIGHWAY AND BRIDGE CONSTRUCTION (STORM), AND ANY CONDITIONS OF APPROVAL.

- 2. LENGTHS OF ALL UTILITIES ARE TO CENTER OF STRUCTURES AND MAY VARY SLIGHTLY FROM PLAN. LENGTHS SHALL BE VERIFIED IN THE FIELD DURING CONSTRUCTION AS MEASURED BY THE FIELD ENGINEER AND THE CONTRACTOR SHALL BE PAID ACCORDING TO THE ACTUAL LENGTH OF PIPING INSTALLED.
- 3. A 7.0 FEET DEPTH OF COVER OVER ALL NEWLY INSTALLED WATER PIPING IS DESIRED AND SHALL BE MAINTAINED UNLESS FIELD CONDITIONS PROHIBIT. THE CONTRACTOR SHALL MAINTAIN A MINIMUM DEPTH OF COVER OF 5.0 FEET UNLESS DIRECTED OTHERWISE BY THE OWNER. ALL NEWLY INSTALLED WATER PIPING WITH COVER LESS THAN 7.0 FEET SHALL BE INSULATED ACCORDING TO THE SPECIFICATIONS AND INSULATION DETAIL. INSULATION SHALL ALSO BE INSTALLED AT ALL LOCATIONS WHERE STORM SEWER CROSSES THE WATER PIPING, WATER SERVICES, AND HYDRANT LEADS. MINIMUM VERTICAL SEPARATION DISTANCE WHERE WATER PIPING CROSSES OVER SEWERS IS 6 INCHES. MINIMUM VERTICAL SEPARATION DISTANCE WHERE WATER PIPING CROSSES UNDER SEWERS IS 18 INCHES.
- 4. THE CONTRACTOR SHALL COORDINATE SANITARY AND WATER LATERAL LOCATIONS WITH THE OWNER AND THE BUILDING PLANS PRIOR TO CONSTRUCTION. UNLESS DIRECTED OTHERWISE BY THE OWNER, THE CONTRACTOR SHALL STUB THE SANITARY AND WATER LATERALS APPROXIMATELY 5 FEET FROM THE PROPOSED BUILDING LOCATION AND MARK ALL STUBS WITH A 2'x4' EXTENDING A MINIMUM OF 2 FEET ABOVE THE FINISHED GROUND SURFACE
- 5. TRACER WIRE SHALL BE INSTALLED ALONG ALL SANITARY LATERALS, WATER SERVICES, AND STORM SEWER (INCIDENTAL TO THE SPECIFIC PIPING). TRACER WIRE SHALL BE SURFACED AT ALL WATER SERVICE VALVES (TO BUILDINGS), SANITARY LATERAL TRACER WIRE TERMINAL BOXES, AND STORM INLETS AND MANHOLES.
- 6. ALL SAWCUTTING, BENDS, FERNCO CONNECTORS, FITTINGS, AND OTHER MATERIALS NOT SPECIFICALLY ITEMIZED ON THE BID BUT NECESSARY TO PROVIDE A COMPLETE WORKING SYSTEM AND TO MAKE A WATERTIGHT CONNECTION TO THE EXISTING SANITARY, WATER, OR STORM PIPING SHALL BE INCIDENTAL TO CONSTRUCTION. ALL PROPOSED SANITARY SEWER, WATER, AND STORM PIPING CONNECTIONS INTO EXISTING PIPING OR STRUCTURES SHALL BE INCIDENTAL TO CONSTRUCTION. ALL EXISTING SANITARY SEWER, WATER, AND STORM PIPE ABANDONMENT AS WELL AS THE REMOVAL OF EX. MANHOLES, HYDRANTS, VALVE MANHOLES, AND VALVE BOXES THAT ARE NO LONGER IN USE SHALL BE INCIDENTAL TO CONSTRUCTION. ALL EXISTING SANITARY, WATER OR STORM PIPING TO BE ABANDONED SHALL BE MADE BY COMPLETELY FILLING EACH END OF
- THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS (SHORING, BRACING, ETC.) AND SHALL CAREFULLY INSTALL THE NEW SANITARY SEWER, WATER, AND STORM SEWER IMPROVEMENTS SO AS NOT TO DISTURB ANY EXISTING PRIVATE UTILITY STRUCTURES OR PIPING AS WELL AS TO PREVENT ANY DISTURBANCE TO EXISTING SITE FEATURES THAT ARE TO REMAIN UNDISTURBED. ANY DISTURBANCE OR DAMAGE (AS DETERMINED BY THE OWNER) SHALL BE REPAIRED AND/OR REPLACED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER












822-387 JEROME G & A FILE NO. DRAFTED BY:

CHECKED BY: RC 822-387

PROJ.

2022 AND SURVE



CLIENT/ OWNER:

A. & GAYLE R. DEYOUNG TRUST DATED APRIL 26, 1995 . C.T.H. "M" N11534 C WAUPUN, SCOTT

53963

⋝


OWNER

& SHERRI A. H. "M" C.T.H. "M" L, WI 53963 RAYMOND J. N11594 C. WAUPUN,



7007

GENERAL



CLIENT/ OWNER:

1995 SCOTT A. & GAYLE R. DEYOUNG LIVING TRUST DATED APRIL 26, 1 N11534 C.T.H. "M" WAUPUN, WI 53963

OWNER

& SHERRI 1. "M" RAYMOND J. & SHER N11594 C.T.H. "M" WAUPUN, WI 53963



G & A FILE NO.

JEROME CHECKED BY: RC DRAFTED BY:

SHEET 4 OF 5

822-387 822-387

PROJ. DWG.

BEAVER DAM WISCONSIN AND SURVEY ROBERT W CONDON S-1851 WISCON (

CERTIFIED SURVEY MAP NO DODGE COUNTY

BEING LOT 1 OF BLOCK 1 LOTS 2, 3, AND 4 OF BLOCK 2 OF STOFFEL PLAT AND UNPLATTED LANDS; ALL LOCATED IN PART OF THE SE1/4 OF THE NW1/4, AND PART OF THE SW1/4 OF THE NW1/4, SECTION 8, T. 13 N, R. 15 E, TOWN OF CHESTER, DODGE COUNTY, WISCONSIN. CONTAINING: 1,000,302 SQ.FT. (22.964 ACRES)

SURVEYOR'S CERTIFICATE

t Quarter of the Town 13 North, I, ROBERT W. CONDON, Professional Land Surveyor, do hereby certify that by the order of Scott A. & Gale R. DeYoung Living Trust Dated April 26, 1995, I have surveyed, monumented, mapped and divided Lot 1, Block 1, Lots 2, 3 and 4, Block 2, Stoffel Plat and unplatted lands all located in a part of the Southeast Quarter of the Northwest Quarter and a part of the Southwest Quarter of the Northwest Quarter, Section 8, Town 13 North, Range 15 East, Town of Chester, Dodge County, Wisconsin, described as follows:

Commencing at the West Quarter corner of Section 8; thence Northwest Quarter, 487.04 feet to the point of beginning; thence North 88°07'09" East along the South line of the Northwest Quarter, 487.04 feet to the point of beginning; thence North 40°01'02" West along the Southeasterly extension of the Southwest line of Lot 5, Block 2 of Stoffel

Plat, 114.17 feet to the Southwest corner of said Lot 5; thence North 50°01'31" East along the Southeast line of said Lot 5, 159.94 feet to the Southwest corner of Lot 4,

thence North 40°00′24" West along the Southwest line of said Lot 4, 280.15 feet to the Northwest corner thereof and being a point on the Southeast right-of-way line of County Trunk Highway M; thence North 50°01′31" East along the Southeast right-of-way line of County Trunk Highway M and the Northwest line of the Lots 4, 3 and 2, Block 2 of Stoffel Plat, 359.97 feet to the Northeast corner of said Lot 2; thence South 39°58′58" East along the Northeast line of Lot 1, Block 2, Outlot A, Lots 7, 6, 5, 4, 3 and 2, Block 1 of Stoffel Plat, 905.90 feet to the Southwest corner of Lot 1, Block 1 of Stoffel Plat; thence North 39°58′29" West along the Southwest line of said Lot 1, 280.15 feet to the Northwest corner thereof and being a point in the Southeast right-of-way line of County Trunk Highway M; thence North 50°01′31" East along the Southeast right-of-way line of County Trunk Highway M and the Northwest line of said Lot 1, 149.99 feet to the Northeast corner of said Lot 1 and being a point on the West line of Lot 1, Certified Survey Map, No. 2846;

thence South 39°59'09" East along the Northeast line of said Lot 1 and the West line of Lot 1, Certified Survey Map, No. 2846, 279.77 feet to the Southeast corner of Lot 1, Block 1, Stoffel Plat; thence South 50°00'51" West along the West line of Lot 1, Certified Survey Map, No. 2846, 4.87 feet; thence South 45°39'09" East along the West line of Lot 1, Certified Survey Map, No. 2846, 87.74 feet; thence North 88°00'05" East along the West line of Lot 1, Certified Survey Map, No. 2846, 105.50 feet; thence South 00°02'35" West along the West line of Lot 1, Certified Survey Map, No. 2846 and being a point in the South line of the Northwest Quarter and the North line of Certified Survey Map as recorded in Volume 4, page 103; thence South 88°07'09" West along the North line of Certified Survey Map as recorded in Volume 4, page 103 and the South line of the Northwest Quarter, 1,298.27 feet to the point of beginning.

use or record if any.

IDO FURTHER CERTIFY that this is a true and correct representation of the boundaries of the land surveyed and that I fully complied with the Provisions of Chapter 236.34 of the Wisconsin State Statutes and the Subdivision Provisions of the Dodge County Land Use Code and the **Town** of **Chester** Subdivision Ordinance to the best of my knowledge and belief.

ROBERT W. CONDON
Professional Land Surveyor, No. 1851
Dated: August 17, 2022
File No.: 822-387

1995 R. DEYOUNG D. APRIL 26, 1 A. & GAYLE R. TRUST DATED , 4 C.T.H. "M" C.T.H. N11534 SCOTT

53963

⋝

WAUPUN,

& SHERRI N11594 C.T.H. "M" WAUPUN, WI 53963 っ RAYMOND WAUPUN,

CLIENT/ OWNER:

OWNER

PULDA

Ä

00 SEAL: PROFESSIONAL SERVICES
PROFESSIONAL SERVICES
PROFESSIONAL SERVICES
REST SLIFER STREET, P.O. BOX 373 PORTAGE, M. 53001
PHONE: PORTAGE: (800) 742–7788 SULIC (800) 644–6877
FAX: (800) 742–7448: SULIC (800) 644–6877
FAX: (800) 742–6454 E-MAL: SULIC (800) 644–6877
FAX: (800) 742–6454 E-MAL: SULIC (800) 644–6877
FAX: (800) 742–6454 E-MAL: SULIC (800) 644–6877
FAX: (800) 740–6454 E-MAI: SULIC (800) 644–6877
FAX: (800) 740–7454 E-MAI: SULIC (800) 740– GROTHMAN

2002 WISCON

WISCON	00000	Page NO SUR	00000000000
	服教画		
G & A FILE NO. 822-387	DRAFTED BY: A. JEROME	CHECKED BY: RC	PROJ. 822-387

822-387

SHEET 5 OF 5

822-387

DWG.

CERTIFIED SURVEY MAP NO. DODGE COUNTY

BEING LOT 1 OF BLOCK 1 LOTS 2, 3, AND 4 OF BLOCK 2 OF STOFFEL PLAT AND UNPLATTED LANDS; ALL LOCATED IN PART OF THE SEV4 OF THE NWV4, AND PART OF THE SWV74 OF THE NWV4, SECTION 8, T. 13 N, R. 15 E, TOWN OF CHESTER, DODGE COUNTY, WISCONSIN CONTAINING: 1,000,302 SQ.FT. (22.964 ACRES)

CITY of WAUPUN RESOLUTION

RESOLVED THAT this Certified Survey Map within the City of Waupun, extraterritorial jurisdiction is hereby approved and accepted by the City of Waupun Planning Commission.

Date	Date
Mayor	City Clerk

PULDA

ġ