

SPECIAL TOWNSHIP BOARD MEETING LOCATION: 7527 HIGHLAND ROAD, WHITE LAKE - ANNEX BOARD ROOM TUESDAY, APRIL 22, 2025 – 5:00 PM

White Lake Township | 7525 Highland Rd | White Lake, MI 48383 | Phone: (248) 698-3300 | www.whitelaketwp.com

AGENDA

- 1. CALL TO ORDER
- 2. PLEDGE OF ALLEGIANCE
- 3. ROLL CALL
- 4. APPROVAL OF AGENDA
- 5. PUBLIC COMMENT

6. NEW BUSINESS

- A. <u>REQUEST TO APPROVE CHANGE ORDER FOR UNDER FLOOR DRAINAGE SYSTEM -</u> <u>PUBLIC SAFETY BUILDING</u>
- 7. ADJOURNMENT

Procedures for accommodations for persons with disabilities: The Township will follow its normal procedures for individuals with disabilities needing accommodations for effective participation in this meeting. Please contact the Township Clerk's office at (248) 698-3300 X-7 at least five days in advance of the meeting. An attempt will be made to provide reasonable accommodations.



Law Enforcement Public Safety & Fire Justice Municipal Corporate/Commercial

Redstone Architects, Inc.

30700 Telegraph Road, Suite 1677, Bingham Farms, MI 48025

04/21/2025

Memo to White Lake Township Board:

Based on the recommendation of the Township's geotechnical engineering company, G2, the Redstone Architects design team has submitted Bulletin #11 which includes a new under-slab drainage design and a waterproof membrane specification. It is the consensus of the construction and design professionals that these solutions will mitigate the standing water around and under the Public Safety Building that was initially discovered in October of 2024.

Redstone Architects supports the need for the change order to protect the building.

History

The Redstone design team provided a design, as it pertains to the footings, walls and slab on grade, for the White Lake Township (WLT) Public Safety Building (PSB) lower level based on recommendations from the Townships Geotechnical Engineering company, G2. The Geotechnical report, dated September 8, 2023, was made available to the design team and contained the following recommendations.

Below-Grade Wall Recommendations:

The drainage recommendation in the Geotech report read as follows: "We recommend a perimeter foundation drain system be incorporated at the foundation level to prevent the development of hydrostatic pressures on below-grade floors and walls. The perforated or slotted drain pipe should be protected with coarse aggregates. The drain pipe and aggregate should be wrapped with a non-woven filter fabric to prevent the migration of surrounding soil fines into the aggregate and drain pipe. The drainage system should outlet water to a sump/pump system designed to remove the collected water."

The drainage system for the underground walls and footings were designed to be perimeter foundation drainage only.

Floor Slab Recommendations:

The slab on grade for the PSB lower level received the following recommendations: "If moisture sensitive floor coverings are planned, or if greater protection against vapor transmission is desired, a vapor barrier, consisting of at least 10-mil plastic sheeting, may be placed over the capillary break layer beneath floor slabs."

As recommended by the G2 report and flooring manufacturers, a vapor barrier should be provided under the slabs on grade to prevent ground moisture from penetrating the concrete and damaging the floor installation. A vapor barrier was specified and bid for under the slab of the PSB lower level.

Construction 2024:

In late October 2024, during the excavation of the lower-level footings for the PSB, McCarthy and Smith noticed standing water. They created three (3) test pits to evaluate the cause and extent of the water. Finding significant water McCarthy and Smith notified G2 to determine the next steps.

G2 visited the site and provided a report dated October 28, 2024. The G2 report speculated that the water was perched groundwater and recommended constructing sumps to pump the water out of the building's subgrade area. McCarthy and Smith constructed two pits and installed pumps to begin pumping the water out of the area. The pumps operated for a few weeks and the site appeared to dry up while the pumps were running. However, once the pumps stopped operating the water resurfaced.

In a subsequent report dated February 24, 2025, G2 issued an opinion that the Township construct an under-slab dramage system for the PSB to mitigate issues that may arise from the ground water. McCarthy and Smith contacted Redstone Architects to discuss the design of an under-slab drainage system. Several meetings and discussions were conducted between the engineers, architect, and contractors to determine a solution that is most cost-effective and efficient.

In addition to the drainage system, a waterproofing membrane will be needed to replace the vapor barrier. A vapor barrier is not intended to be submerged in water and will not be a viable solution considering the amount of water. A waterproof membrane is designed to withstand and protect the building from these water conditions.

Bulletin #11 incorporates both the recommendations of G2 and the consensus of the design and construction professionals.

Thank you.



Bulletin #11

ARCHITECTS, INC. Architecture · Planning · Interior Design

| | | Date: | April 14, 2025 | | | | | |
|--|--|-------------|----------------|--|--|--|--|--|
| То: | Aaron Phillips | | | | | | | |
| Company: | McCarthy & Smith | | | | | | | |
| Project Name: | White Lake Township Public Safety Building | Project No: | 3702.00 | | | | | |
| | Civic Center Development | | F07 | | | | | |
| Distribution: | White Lake Township | | | | | | | |
| | McCarthy & Smith | | | | | | | |
| DOCUMENTS ISSUED WITH THIS BULLETIN: Documents: Drawings: Specifications: 06 20 13, 09 93 00 | | | | | | | | |
| This Bulletin forms part of the Contract Documents and modifies the original Bidding Documents dated | | | | | | | | |

June 03, 2024. Acknowledge receipt of this Bulletin in the space provided in the Bid Form. Failure to do so may subject Bidder to disqualification.

Architectural

Architectural Specifications

| ITEM #1: | 06 20 13 EXTERIOR FINISH CARPENTRY (NEWLY ISSUED) |
|----------|--|
| ITEM #2: | 09 93 00 STAINING AND TRANSPARENT FINISHING (NEWLY ISSUED) |

Architectural Drawings

| N/A |
|-----|
| |

Structural Drawings

| N/A | |
|-----|--|
| | |

END OF BULLETIN

Redstone Architects, Inc. Project #3702.00 Issued for Bulletin #11 04/14/2025 White Lake T Public Safety Building Civic Center Development Bid Package #3

SECTION 06 20 13 - EXTERIOR FINISH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Exterior trim.

1.2 DEFINITIONS

- A. MDO: Plywood with a medium-density overlay on the face.
- B. PVC: Polyvinyl chloride.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of process and factory-fabricated product. Indicate component materials, dimensions, profiles, textures, and colors and include construction and application details.
 - 1. Include data for wood-preservative treatment from chemical-treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used and net amount of preservative retained. Include chemical-treatment manufacturer's written instructions for finishing treated material.
- B. Samples for Initial Selection: For each type of product involving selection of colors, profiles, or textures.
- C. Samples for Verification:
 - 1. For each species and cut of lumber and panel products, with half of exposed surface finished; 50 sq. in. for lumber and 8 by 10 inches for panels.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Stack lumber, plywood, and other panels flat with spacers between each bundle to provide air circulation.
 - 1. Protect materials from weather by covering with waterproof sheeting, securely anchored.
 - 2. Provide for air circulation around stacks and under coverings.

Redstone Architects, Inc. Project #3702.00 Issued for Bulletin #11 04/14/2025 White Lake T Public Safety Building Civic Center Development Bid Package #3

1.5 FIELD CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecast weather conditions permit work to be performed and at least one coat of specified finish can be applied without exposure to rain, snow, or dampness.
- B. Do not install finish carpentry materials that are wet, moisture damaged, or mold damaged.
 - 1. Indications that materials are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
 - 2. Indications that materials are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

- A. Lumber: DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, comply with applicable rules of any rules-writing agency certified by the American Lumber Standard Committee's (ALSC) Board of Review. Grade lumber by an agency certified by the ALSC's Board of Review to inspect and grade lumber under the rules indicated.
 - 1. Factory mark each piece of lumber with grade stamp of inspection agency, indicating grade, species, moisture content at time of surfacing, and mill.
 - 2. For exposed lumber, mark grade stamp on end or back of each piece.
- B. Softwood Plywood: DOC PS 1.
- C. Hardboard: ANSI A135.4.

2.2 WOOD-PRESERVATIVE-TREATED MATERIALS

- A. Preservative Treatment by Pressure Process: AWPA U1; Use Category UC3b.
 - 1. Kiln dry lumber and plywood after treatment to a maximum moisture content of 19 and 18 percent, respectively.
 - 2. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.
 - 3. For exposed items indicated to receive transparent finish, do not use chemical formulations that contain colorants or that bleed through or otherwise adversely affect finishes.

- 4. Do not use material that is warped or does not comply with requirements for untreated material.
- 5. Mark lumber with treatment-quality mark of an inspection agency approved by the ALSC's Board of Review.
 - a. For exposed lumber indicated to receive a stained or natural finish, mark end or back of each piece.
- 6. Mark plywood with appropriate classification marking of an inspection agency acceptable to authorities having jurisdiction.
 - a. For exposed plywood indicated to receive a stained or natural finish, mark back of each piece.
- 7. Application: Where indicated on Drawings.

2.3 EXTERIOR TRIM

- A. Lumber Trim for Opaque-Stained Finish:
 - 1. Species and Grade:
 - a. Quarter Sawn White Oak; AB 1 Common.
 - 2. Maximum Moisture Content: 15 percent.
 - 3. Face Surface: Surfaced (smooth).
 - 4. Factory Priming: Factory coated on both faces and all edges, with exterior primer compatible with topcoats specified.

2.4 FABRICATION

- A. Back out or kerf backs of standing and running trim wider than 5 inches, except members with ends exposed in finished work.
- B. Ease edges of lumber less than 1 inch in nominal thickness to 1/16-inch radius and edges of lumber 1 inch or more in nominal thickness to 1/8-inch radius.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine finish carpentry materials before installation. Reject materials that are wet, moisture damaged, and mold damaged.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean substrates of projections and substances detrimental to application.
- B. Prime lumber and moldings to be painted, including both faces and edges, unless factory primed.
 - 1. Cut to required lengths and prime ends.
 - 2. Comply with requirements in Section 09 91 13 "Exterior Painting."

3.3 INSTALLATION, GENERAL

- A. Do not use materials that are unsound, warped, improperly treated or finished, inadequately seasoned, or too small to fabricate with proper jointing arrangements.
 - 1. Do not use manufactured units with defective surfaces, sizes, or patterns.
- B. Install exterior finish carpentry level, plumb, true, and aligned with adjacent materials.
 - 1. Use concealed shims where necessary for alignment.
 - 2. Scribe and cut exterior finish carpentry to fit adjoining work.
 - 3. Refinish and seal cuts as recommended by manufacturer.
 - 4. Install to tolerance of 1/8 inch in 96 inches for level and plumb. Install adjoining exterior finish carpentry with 1/32-inch maximum offset for flush installation and 1/16-inch maximum offset for reveal installation.
 - 5. Coordinate exterior finish carpentry with materials and systems in or adjacent to it.
 - 6. Provide cutouts for mechanical and electrical items that penetrate exterior finish carpentry.

3.4 INSTALLATION OF STANDING AND RUNNING TRIM

- A. Install flat-grain lumber with bark side exposed to weather.
- B. Install cellular PVC trim to comply with manufacturer's written instructions.
- C. Install trim with minimum number of joints as is practical, using full-length pieces from maximum lengths of lumber available. Do not use pieces less than 24 inches long, except where necessary.
 - 1. Use scarf joints for end-to-end joints.
 - 2. Stagger end joints in adjacent and related members.
- D. Fit exterior joints to exclude water.

- 1. Cope at returns and miter at corners to produce tight-fitting joints, with full-surface contact throughout length of joint.
- 2. Plane backs of casings to provide uniform thickness across joints, where necessary for alignment.
- E. Where face fastening is unavoidable, countersink fasteners, fill surface flush, and sand unless otherwise indicated.

3.5 ADJUSTING

- A. Replace exterior finish carpentry that is damaged or does not comply with requirements.
 - 1. Exterior finish carpentry may be repaired or refinished if work complies with requirements and shows no evidence of repair or refinishing.
- B. Adjust joinery for uniform appearance.

3.6 CLEANING

- A. Clean exterior finish carpentry on exposed and semiexposed surfaces.
- B. Touch up factory-applied finishes to restore damaged or soiled areas.

3.7 **PROTECTION**

- A. Protect installed products from damage from weather and other causes during construction.
- B. Remove and replace finish carpentry materials that are wet, moisture damaged, and mold damaged.
 - 1. Indications that materials are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
 - 2. Indications that materials are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

END OF SECTION

White Lake T Section 6, Item A. Public Safety Building Civic Center Development Bid Package #3

SECTION 09 93 00 - STAINING AND TRANSPARENT FINISHING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Wood stains.

1.2 ACTION SUBMITTALS

- A. Product Data:
 - 1. For each type of product.
 - 2. Include preparation requirements and application instructions.
 - 3. Indicate VOC content.
- B. Samples for Initial Selection: Manufacturer's standard color sheets, showing full range of available colors for each type of exposed finish.
- C. Samples for Verification: Sample for each type of finish system and in each color and gloss of finish required on representative samples of actual wood substrates.
 - 1. Size: 8 inches square or 8 inches long.
 - 2. Apply coats on Samples in steps to show each coat required for system.
 - 3. Label each coat of each Sample.
 - 4. Label each Sample for location and application area.
- D. Product List: Cross-reference to finish system and locations of application areas. Use same designations indicated on Drawings and in schedules. Include color designations.

1.3 DELIVERY, STORAGE, AND HANDLING

- A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.
 - 1. Maintain containers in clean condition, free of foreign materials and residue.
 - 2. Remove rags and waste from storage areas daily.

1.4 FIELD CONDITIONS

A. Apply finishes only when temperature of surfaces to be finished and ambient air temperatures are between 50 and 95 deg F.

Redstone Architects, Inc. Project #3702.00 Issued for Bulletin #11 04/14/2025 White Lake T Section 6, Item A. Public Safety Building Civic Center Development Bid Package #3

- B. Do not apply finishes when relative humidity exceeds 85 percent, at temperatures of less than 5 deg F above the dew point, or to damp or wet surfaces.
- C. Do not apply exterior finishes in snow, rain, fog, or mist.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Behr Paint Company; Behr Process Corporation.
 - 2. Benjamin Moore & Co.
 - 3. PPG Paints.
 - 4. Sherwin-Williams Company (The).

2.2 SOURCE LIMITATIONS

A. Source Limitations: Obtain each coating product from single source from single manufacturer.

2.3 MATERIALS, GENERAL

- A. Material Compatibility:
 - 1. Provide materials for use within each coating system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
- B. Low-Emitting Materials: For field applications that are inside the weatherproofing system, 90 percent of paints and coatings shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- C. Stain Colors: As selected by Architect from manufacturer's full range.

2.4 WOOD STAINS

- A. Stain, Exterior, Solvent Based, Semitransparent: Solvent-based, oil or oil/alkyd, semitransparent, pigmented stain for new wood surfaces.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

Redstone Architects, Inc. Project #3702.00 Issued for Bulletin #11 04/14/2025 White Lake T Section 6, Item A. Public Safety Building Civic Center Development Bid Package #3

- a. Behr Paint Company; Behr Process Corporation.
- b. Benjamin Moore & Co.
- c. PPG Paints.
- d. Sherwin-Williams Company (The).

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Maximum Moisture Content of Exterior Wood Substrates: 15 percent, when measured with an electronic moisture meter.
- C. Maximum Moisture Content of Interior Wood Substrates: 13 percent, when measured with an electronic moisture meter.
- D. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.
- E. Proceed with finish application only after unsatisfactory conditions have been corrected.
 - 1. Beginning finish application constitutes Contractor's acceptance of substrates and conditions.

3.2 PREPARATION

- A. Remove hardware, covers, plates, and similar items already in place that are removable. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and finishing.
 - 1. After completing finishing operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.
- B. Clean and prepare surfaces to be finished according to manufacturer's written instructions for each substrate condition and as specified.
 - 1. Remove dust, dirt, oil, and grease by washing with a detergent solution; rinse thoroughly with clean water and allow to dry. Remove grade stamps and pencil marks by sanding lightly. Remove loose wood fibers by brushing.
 - 2. Remove mildew by scrubbing with a commercial wash formulated for mildew removal and as recommended by stain manufacturer.
- C. Exterior Wood Substrates:

White Lake T Section 6, Item A. Public Safety Building Civic Center Development Bid Package #3

- 1. Scrape and clean knots, and apply coat of knot sealer before applying primer.
- 2. Prime edges, ends, faces, undersides, and backsides of wood.
 - a. For solid hide stained wood, stain edges and ends after priming.
 - b. For varnish-coated stained wood, stain edges and ends and prime with varnish. Prime undersides and backsides with varnish.
- 3. Countersink steel nails, if used, and fill with putty or plastic wood filler tinted to final color. Sand smooth when dried.

3.3 APPLICATION

- A. Apply finishes according to manufacturer's written instructions.
 - 1. Use applicators and techniques suited for finish and substrate indicated.
 - 2. Finish surfaces behind movable equipment and furniture same as similar exposed surfaces.
 - 3. Do not apply finishes over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
- B. Apply finishes to produce surface films without cloudiness, holidays, lap marks, brush marks, runs, ropiness, or other surface imperfections.

3.4 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
- B. After completing finish application, clean spattered surfaces. Remove spattered materials by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from finish application. Correct damage by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- D. At completion of construction activities of other trades, touch up and restore damaged or defaced finished wood surfaces.

3.5 EXTERIOR WOOD-FINISH-SYSTEM SCHEDULE

- A. Wood Substrates, Wood Trim:
 - 1. Semitransparent Stain System-As Basis of Design
 - 2. Sherwin-Williams- Nicole Bennett Florio (878) 236-2075

White Lake T Section 6, Item A. Public Safety Building Civic Center Development Bid Package #3

- **a.** Prime Coat: WoodScapes Exterior Polyurethane Semi-Transparent Wood Stain, A15 Series
- b. Top coat: WoodScapes Exterior Polyurethane Semi-Transparent Wood Stain, A15 Series

END OF SECTION

MEP Engineering Lighting Design Commissioning Building Technology Sustainable Design



BULLETIN

| PBA Project Name: | White Lake Township |
|---------------------|------------------------|
| | Public Safety Building |
| PBA Project Number: | 2023-0062 |
| Bulletin Number: | 11 |
| Date: | April 14th, 2025 |

THIS IS NOT AN ORDER FOR THE WORK. Contractor shall not proceed with this work until receipt of Change Order.

This Bulletin is issued after contract award to obtain a completely itemized breakdown quotation from the Contractor for changes in the Work in accordance with the General Conditions and Supplementary General Conditions for the approval by the Owner and Architect/Engineer.

All requirements contained in the Contract Documents shall apply to this Bulletin. All incidental work necessary to complete the Work shall be included in the Contractor's quotation even though not particularly mentioned.

Parts of the Specifications and Drawings referred to herein supersede previously issued data and form a part of this Bulletin.

When submitting quotation, break down prices according to items listed in this Bulletin.

Payment will be made in accordance with method of payment described in the Contract Documents according to quotation submitted after approval by Owner and Architect/Engineer.

The final completion date is not to be affected by reason of this Bulletin.

Specifications Issued: None

Drawings Issued: M200, M201.

Mechanical Drawing Items:

MD-1 Refer to Sheet M200 (Re-issued).

1. Revised underground subsoil drainage as indicated.

MD-2 Refer to Sheet M201 (Re-issued).

Bulletin No. 11 PBA Project No. 2023-0062

1. Revised CO's serving subsoil drainage as indicated.

End of Bulletin

\\pba.local\projects\2023\2023-0062-00\Construction Administration\Revisions\Bulletin Writeups\Bulletin 11\Bulletin #11.docx





SECTION 07 13 26 - SELF-ADHERING SHEET WATERPROOFING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Blindside sheet waterproofing.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
 - 1. Review waterproofing requirements including surface preparation, substrate condition and pretreatment, minimum curing period, forecasted weather conditions, special details and sheet flashings, installation procedures, testing and inspection procedures, and protection and repairs.
 - 2. Review transitions within waterproofing system and between waterproofing and adjacent air barrier.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, and tested physical and performance properties of waterproofing.
 - 2. Include manufacturer's written installation instructions for evaluating, preparing, and treating substrate.
- B. Shop Drawings: Show locations and extent of waterproofing and details of substrate joints and cracks, expansion joints, sheet flashings, penetrations, inside and outside corners, tie-ins with adjoining waterproofing, air barrier, and other termination conditions.
 - 1. Include setting drawings that indicate layout, sizes, sections, profiles, and joint details of pedestal-supported concrete pavers.

1.4 FIELD CONDITIONS

A. Environmental Limitations: Apply waterproofing within the range of ambient and substrate temperatures recommended in writing by waterproofing manufacturer. Do not apply waterproofing to frozen, damp, or wet substrates.

Redstone Architects, Inc. Project #3702.00 Issued for Bulletin #10 04/09/25 White Lake T Section 6, Item A. Public Safety Building Civic Center Development Bid Package #3

- 1. Do not apply waterproofing when snow, rain, fog, or mist is present.
- B. Maintain adequate ventilation during preparation and application of waterproofing materials.

1.5 COORDINATION

- A. Coordinate Work under this Section with adjacent concrete foundation work, including fill, subdrainage systems.
- B. Coordinate requirements for concrete formwork to provide suitable substrate for waterproofing and to minimize penetrations through waterproofing.
- C. Coordinate formwork and form bracing requirements for blindside sheet waterproofing. Coordinate restrictions on use of form ties and other components as necessary to eliminate or minimize penetrations through blindside sheet waterproofing.

PART 2 - PRODUCTS

2.1 SOURCE LIMITATIONS

A. Waterproofing System: Obtain waterproofing materials, protection course molded-sheet drainage panels from single source from single manufacturer.

2.2 BLINDSIDE SHEET WATERPROOFING

- A. Blindside Sheet Waterproofing for Horizontal Applications: Uniform, flexible, multilayered-composite sheet membrane that forms a permanent bond with fresh concrete placed against it; complete with accessories and preformed shapes for an unbroken waterproofing assembly; with the physical properties as specified below:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Carlisle Coatings & Waterproofing Inc.
 - b. GCP Applied Technologies Inc.
 - c. Polyguard Products, Inc.
 - d. W. R. Meadows, Inc.
 - e. Sika Corporation .
 - 2. Physical Properties:
 - a. Low-Temperature Flexibility: Pass at minus 20 deg F; ASTM D1970/D1970M.
 - b. Peel Adhesion to Concrete: 10 lbf/in. minimum; ASTM D903, modified.

Redstone Architects, Inc. Project #3702.00 Issued for Bulletin #10 04/09/25 White Lake T Public Safety Building Civic Center Development Bid Package #3

- c. Lap Adhesion: 5 lbf/in. minimum; ASTM D1876, modified.
- d. Hydrostatic-Head Resistance: 230 ft.; ASTM D5385/D5385M, modified.
- e. Puncture Resistance: 200 lbf minimum; ASTM E154/E154M.
- f. Water Vapor Permeance: 0.1 perm maximum; ASTM E96/E96M, Water Method.
- g. Ultimate Elongation: 335 percent minimum; ASTM D412, modified.
- B. Mastic, Adhesives, and Detail Tape: Liquid mastic and adhesives, and adhesive tapes recommended by waterproofing manufacturer.

2.3 ACCESSORIES FOR WATERPROOFING

- A. Furnish accessory materials as recommended in writing by waterproofing manufacturer for intended use and compatibility with sheet waterproofing.
 - 1. Furnish liquid-type accessory materials that comply with VOC limits of authorities having jurisdiction.
- B. Substrate Patching Membrane: Low-viscosity, two-component, modified asphalt coating.
- C. Metal Termination Bars: Aluminum or stainless steel bars, approximately 1 by 1/8 inch, predrilled at 9-inch centers.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements and other conditions affecting performance of waterproofing.
 - 1. Verify that concrete has cured and aged for minimum time recommended in writing by waterproofing manufacturer.
 - 2. Verify that substrate is visibly dry and within the moisture limits recommended in writing by manufacturer. Test for capillary moisture by plastic sheet method in accordance with ASTM D4263.
 - 3. Verify that compacted subgrade is dry, smooth, sound, and ready to receive waterproofing sheet.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean, prepare, and treat substrates in accordance with manufacturer's written installation instructions. Provide clean, dust-free, and dry substrates for waterproofing application.
- B. Mask off adjoining surfaces not receiving waterproofing to prevent spillage and overspray affecting other construction.
- C. Remove grease, oil, bitumen, form-release agents, paints, curing compounds, and other penetrating contaminants or film-forming coatings from concrete.
- D. Remove fins, ridges, mortar, and other projections.
- E. Fill form tie holes, honeycomb, aggregate pockets, holes, and other voids.
- F. Prepare, fill, prime, and treat joints and cracks in substrates. Remove dust and dirt from joints and cracks in accordance with ASTM D4258.
 - 1. Install sheet strips of width in accordance with manufacturer's written installation instructions and center over treated construction and contraction joints and cracks exceeding a width of 1/16 inch or 1/8 inch for modified bituminous deck-paving waterproofing.
- G. Bridge and cover isolation joints, expansion joints, and discontinuous deck-to-wall and deck-to-deck joints with overlapping sheet strips of widths in accordance with manufacturer's written installation instructions.
 - 1. Invert and loosely lay first sheet strip over center of joint. Firmly adhere second sheet strip to first and overlap to substrate.
- H. Corners: Prepare, prime, and treat inside and outside corners in accordance with manufacturer's written installation instructions.
 - 1. Install membrane strips centered over vertical inside corners. Install 3/4-inch fillets of liquid membrane on horizontal inside corners and as follows:
 - a. At footing-to-wall intersections, extend liquid membrane in each direction from corner or install membrane strip centered over corner.
 - b. At plaza-deck-to-wall intersections, extend liquid membrane or sheet strips onto deck waterproofing and to finished height of sheet flashing.
- I. Prepare, treat, and seal vertical and horizontal surfaces at terminations and penetrations through waterproofing and at drains and protrusions.

White Lake T Section 6, Item A. Public Safety Building

Public Safety Building Civic Center Development Bid Package #3

3.3 INSTALLATION OF BLINDSIDE SHEET WATERPROOFING

- A. Install blindside sheet waterproofing in accordance with manufacturer's written installation instructions.
- B. Place and secure molded-sheet drainage panels over substrate. Lap edges and ends of geotextile to maintain continuity.
- C. Vertical Applications: Install sheet with face against substrate. Accurately align sheets and maintain uniform side and end laps of minimum dimensions required by membrane manufacturer. Overlap and seal seams, and stagger and tape end laps to ensure watertight installation. Mechanically fasten to substrate.
 - 1. Securely fasten top termination of membrane with continuous metal termination bar anchored into substrate and cover with detail tape.
 - 2. Ensure transition with other waterproofing membrane.
- D. Horizontal Applications: Install sheet with face against substrate. Accurately align sheets and maintain uniform side and end laps of minimum dimensions required by membrane manufacturer. Overlap and seal seams, and stagger and tape end laps to ensure watertight installation.
- E. Corners: Seal lapped terminations and cut edges of sheet waterproofing at inside and outside corners with detail tape.
- F. Seal penetrations through sheet waterproofing to provide watertight seal with detail tape patches or wraps and a liquid-membrane troweling.
- G. Install sheet waterproofing and accessory materials to produce a continuous watertight tie into adjacent waterproofing.
- H. Repair tears, voids, and lapped seams in waterproofing not complying with requirements. Tape perimeter of damaged or nonconforming area extending 6 inches beyond repaired areas in all directions. Apply a patch of sheet waterproofing and firmly secure with detail tape.

3.4 INSTALLATION OF MOLDED-SHEET DRAINAGE PANELS

- Place and secure molded-sheet drainage panels, with geotextile facing away from wall or deck substrate, in accordance with manufacturer's written installation instructions. Use adhesive or another method that does not penetrate waterproofing. Lap edges and ends of geotextile to maintain continuity. Protect installed molded-sheet drainage panels during subsequent construction.
 - 1. For vertical applications, install board insulation before installing drainage panels.

Section 6, Item A. White Lake T Public Safety Building

Civic Center Development Bid Package #3

3.5 INSTALLATION OF INSULATION DRAINAGE PANELS

- Install insulation drainage panels over waterproofed surfaces. Cut and fit to within 3/4 Α. inch of projections and penetrations.
- Β. Ensure that drainage channels are aligned vertically and free of obstructions.
- C. On vertical surfaces, set insulation drainage panels in adhesive or tape applied in accordance with manufacturer's written installation instructions.
- D. On horizontal surfaces, loosely lay insulation drainage panels in accordance with manufacturer's written installation instructions. Stagger end joints and tightly abut insulation units.

3.6 FIELD QUALITY CONTROL

Manufacturer's Field Service: Engage a site representative qualified by waterproofing A. membrane manufacturer to inspect substrate conditions, surface preparation, membrane application, flashings, protection, and drainage components; and to furnish daily reports to Architect.

3.7 PROTECTION, REPAIR, AND CLEANING

- A. Do not permit foot or vehicular traffic on unprotected membrane.
- B. Protect waterproofing from damage and wear during remainder of construction period.
- C. Protect installed insulation drainage panels from damage due to UV light, harmful weather exposures, physical abuse, and other causes. Provide temporary coverings where insulation is subject to abuse and cannot be concealed and protected by permanent construction immediately after installation.
- D. Correct deficiencies in or remove waterproofing that does not comply with requirements; repair substrates, reapply waterproofing, and repair sheet flashings.
- E. Clean spillage and soiling from adjacent construction using cleaning agents and procedures recommended in writing by manufacturer of affected construction.

END OF SECTION





BULLETIN NO. 5

PROJECT: White Lake Township Civic Center Site Development

OWNER:

White Lake Township

LANDSCAPE ARCHITECT/ ENGINEER: Beckett & Raeder, Inc. 535 W. William, Suite 101 Ann Arbor, MI 48103

DATE: April 15, 2025

This Bulletin is intended to revise contract documents and to form the basis for certain adjustments in cost from the contract sum for the above referenced project. It is not an authorization to proceed with any changes in work.

Except as otherwise specifically mentioned, the general character of the work covered by the Bulletin shall be the same as originally specified for the project, and all incidental items required in connection with the work hereinafter described shall be included even though not specifically mentioned. Where an item is mentioned with no additional specifications given, reference is to be made to the original specifications. All applicable parts of the original Plans and Specifications shall apply.

Cost/credit for the work changes shall be provided on the Construction Manager's required form. Quote each item of this Bulletin on this form, as an Addition, Deduction or No Change. Submit an itemized breakdown of each item showing cost of labor, material, equipment, insurance, taxes, fees, overhead, profit and all associated incidental costs.

Failure to quote this Bulletin in a timely manner shall not be cause to increase the contract amount or contract time.

THIS BULLETIN IS NOT AN ORDER FOR THE WORK. Do not proceed with the revisions described herein until they are authorized by the Construction Manager.

DRAWINGS:

- C6.0 Utility Plan (A) (re-issued sheet)

 a. Storm tie-in added for Public Safety Building underslab drainage system.
- C6.24 Utility Plans & Profiles Storm 8 (re-issued sheet)
 a. Storm tie-in added for Public Safety Building underslab drainage system.
- 3. C6.25 Utility Plans & Profiles Storm 9 (new sheet)
 a. Storm tie-in added for Public Safety Building underslab drainage system.

SPECIFICATIONS

1. None

END OF BULLETIN #5



| | | | · | , | | \mathbf{X} | | | |
|--------------|------------|--|---|-----------------------------|-------------------|--|--|--|--|
| STORM | SEWER STRU | ICTURE TABLE | | STORM SEWER STRUCTURE TABLE | | | | | |
| STRUCTURE ID | RIM ELEV | INVERT ELEVATIONS | | STRUCTURE ID | INVERT ELEVATIONS | | | | |
| FES 70 | 944.16 | INV 6" NE 943.56 | | | | INV 6" N 950.16 | | | |
| FES40 | 943.10 | INV 6" NE 942.50 | | STR CB510 | 953.50 | INV 12" NE 949.37 INV 12" SW 949.27 | | | |
| STR CB 610 | 967.75 | INV 6" N 964.20 INV 6" E 964.18 INV 6" SE 964.09 | | STR CB520 | 952.97 | INV 12" NE 948.88 INV 12" NW 948.78 | | | |
| | | INV 12" NW 963.00 | | STR CB530 | 952.63 | INV 12" SE 948.28 INV 6" NE 949.43 INV 18" NW 947.67 | | | |
| STR CB 620 | 967.21 | INV 6" E 963.79 INV 12" NE 962.30 | | | | INV 18" SE 947.26 | | | |
| STR CB 630 | 967.10 | INV 18" NE 961.61 INV 12" SW 962.01 | | STR CB540 | 952.64 | INV 6" NE 947.66 INV 12" S 947.66 INV 18" NW 947.17 | | | |
| | | INV 18 INV 961.51 INV 6" SE 964.03 | | STR CB545 | 951.80 | INV 12" N 948.11 | | | |
| STR CB 650 | 967.30 | INV 6" W 964.42 INV 12" NW 964.44 | | STR CB550 | 952.31 | INV 18" SE 946.72 INV 18" NW 946.62 | | | |
| | | INV 12" SE 963.79 | | STR FES165 | 942.51 | INV 12" N 941.32 | | | |
| STR CB 660 | 967.59 | INV 6" SVV 964.16 INV 6" S 964.03 | | STR FES560 | 948.29 | INV 18" SE 946.50 | | | |
| STR CB 670 | 967.47 | INV 12" NW 963.69 INV 12" SE 963.50 INV 6" SW 964.69 | | STR MH135 | 966.84 | INV 8" W 959.48 INV 12" N 955.99 INV 12" S 950.89 | | | |
| | | INV 12" NW 963.41 | | STR MH145 | 955.80 | INV 12" N 950.33 | | | |
| STR CB 675 | 967.58 | INV 12" SE 963.19 INV 6" W 964.06 INV 12" NW 963.09 | | | | INV 12 5 943.21 INV 12" N 942.28 | | | |
| STR CB 680 | 966.68 | INV 12" SE 962.61 INV 6" S 963.91 | | STR MH155 | 951.00 | INV 8" NW 945.56 INV 12" S 941.74 | | | |
| | | INV 18" SW 962.01 | | STR OCS150 | 950.00 | INV 12" SW 945.00 | | | |
| STR CB500 | 954.00 | INV 6" NW 950.42 INV 12" SW 949.77 | { | MH 45 | 953.25 | INV 6" NE 945.45 INV 6" NE 948.29 INV 6" SW 945.45 | | | |

PARCEL LINE

RIGHT-OF-WAY LINE

PROPOSED STORM LINE

PROPOSED SANITARY LINE

PERFORATED PIPE

PROPOSED ELECTRICAL LINE

PROPOSED GAS LINE

LIMIT OF WORK LINE

UTILITIES NOTES

.....

1000000

- 1. PROPOSED CONTOUR LINES AND SPOT ELEVATIONS REFLECT FINISH GRADES. HOLD DOWN SUBGRADE ELEVATIONS ACCORDINGLY. ADJUST RIM ELEVATIONS OF ALL UTILITIES AFFECTED BY WORK IN THIS CONTRACT. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE ON THE SITE. ANY AREA THAT APPEARS TO NOT PROPERLY DRAIN SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE LANDSCAPE ARCHITECT/ ENGINEER FOR RESOLUTION.
- 2. CONTRACTOR SHALL VERIFY ALL EXISTING UTILITY LOCATIONS, DEPTHS AND ELEVATIONS PRIOR TO CONSTRUCTION. NO CHANGES IN CONTRACT PRICE WILL BE AWARDED FOR ACTUAL DISCREPANCIES IN UTILITY LOCATIONS DUE TO THE FAILURE TO VERIFY ACTUAL FIELD LOCATIONS.
- 3. THE CONTRACTOR SHALL RESTORE ALL AREAS DISTURBED BY HIS CONSTRUCTION OPERATIONS TO A CONDITION EQUAL TO OR BETTER THAN THAT EXISTING PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CLEAN UP AND HAUL AWAY ALL
- CONSTRUCTION DEBRIS AND LITTER CAUSED BY HIS OPERATIONS. 4. CONTRACTOR SHALL PROTECT ALL EXISTING UTILITIES FROM DAMAGE DURING CONSTRUCTION. ANY DAMAGE INCURRED SHALL
- BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- 5. ALL UTILITY CROSSINGS SHALL HAVE A MINIMUM OF 18" VERTICAL CLEARANCE. 6. SEE ARCHITECTURAL AND MECHANICAL SHEETS FOR CONTINUATION OF UTILITIES WITHIN STRUCTURES.
- 7. RIM ELEVATION SPECIFIED IS TO BOTTOM OF CURB (EDGE OF METAL).
- 8. CONTRACTOR SHALL COORDINATE LOCATION AND ORIENTATION OF PRECAST CONCRETE STRUCTURE TO PROVIDE FOR CASTING TO BE LOCATED IN CUIRB LINE AS SHOWN.

UTILITY LEGEND

| • • | PROPOSED STORM WATER |
|--------------|---|
| | PROPOSED STORM WATER |
| Bee | FLARED END SECTION |
| | PROPOSED STORM WATER LEVEL |
| | SPREADER OUTLET |
| | PROPOSED STORM WATER |
| OCS | OUTLET CONTROL STRUCTURE |
| ●C.O. | PROPOSED CLEANOUT |
| м | PROPOSED WATERMAIN GATE VALVE IN BOX |
| ~ | PROPOSED WATERMAIN |
| • | HYDRANT |
| | PROPOSED WATERMAIN |
| • | REDUCER |
| _ | SITE LIGHTING (SEE ELECTRICAL |
| T | DRAWINGS) |
| _ | BARRIER FREE SIGN TYPE' A' |
| \checkmark | |

STONE FILTER BERM

B R (i) Beckett&Raeder

Landscape Architecture Planning, Engineering & Environmental Services

Beckett & Raeder, Inc. 535 West William, Suite 101 Ann Arbor, MI 48103 734 **663.2622** ph 734 **663.6759** fx

2" SANITARY FM, SERVICE VALVE AND CHECK VALVE (BY OTHERS)

Consultants

Seal

Project Title

White Lake Township **Civic Center** Site Development

White Lake, Michigan

Sheet Title

| Dates | |
|------------|---------------------------------------|
| Dates | Issued for |
| 08.01.2023 | SCHEMATIC DESIGN |
| 12.19.2023 | 100% DESIGN DEVELOPMENT |
| 02.02.2024 | JPA PERMIT |
| 05.24.2024 | BID PACKAGE #2 - UTILITIES & SITEWORK |
| 06.13.2024 | BID PACKAGE #2 - ADDENDUM #1 |
| 06.28.2024 | ISSUED FOR CONSTRUCTION |
| 10.01.2024 | SESC PERMIT COMMENT RESPONSE |
| 11.15.2024 | BULLETIN #1 |
| 12.10.2024 | BULLETIN #2 |
| 01.09.2025 | BULLETIN #3 |
| 04.09.2025 | BP #2 BULLETIN #4 |
| 04 15 2025 | BP #2 BULLETIN #5 |

Quality Control

- Drawn: LD Checked: LD
- Approved: BB

Sheet Number

Project Number 2023024

C6.0 UTILITY PLAN (A)











STORM SERVICE 50 PROFILE SCALE: HORIZONTAL- 1' = 30' VERT- 1" = 3'



B R (j) Beckett&Raeder Landscape Architecture Planning, Engineering & Environmental Services

Beckett & Raeder, Inc. 535 West William, Suite 101

Ann Arbor, MI 48103 734 **663.2622** ph 734 **663.6759** fx

Consultants

Seal

Project Title

White Lake Township **Civic Center** Site Development

White Lake, Michigan

Sheet Title

| | Dates | |
|-----|------------|-------------------|
| | Dates | Issued for |
| | 11.15.2024 | BULLETIN #1 |
| | 12.10.2024 | BULLETIN #2 |
| ^ | 04.09.2025 | BP #2 BULLETIN #4 |
| /5\ | 04.15.2025 | BP #2 BULLETIN #5 |
| | | |

Quality Control

Drawn: LD Checked: LD

Approved: BB

2023024

Project Number

Sheet Number



Know what's **below. Call** before you dig.

C6.24 UTILITY PLANS & PROFILES - STORM 8 28





B R (i) Beckett&Raeder Landscape Architecture Planning, Engineering & Environmental Services

Beckett & Raeder, Inc. 535 West William, Suite 101 Ann Arbor, MI 48103 734 **663.2622** ph 734 **663.6759** fx

Consultants

Seal

Project Title

White Lake Township **Civic Center** Site Development

White Lake, Michigan

Sheet Title

)ates

Dates 11.15.2024 12.10.2024 04.09.2025

Issued for BULLETIN #1 BULLETIN #2 BP #2 BULLETIN #4 5 \ 04.15.2025 BP #2 BULLETIN #5



Approved: BB

Project Number 2023024

Sheet Number

C6.25 UTILITY PLANS & PROFILES - STORM 9²⁹

- 8" WATERMAIN 6" STORM



Know what's **below. Call** before you dig.



February 24, 2025

Mr. Aaron A. Phillips **Project Director** McCarthy & Smith, Inc. 24317 Indoplex Circle Farmington Hills, Michigan 48335

RE: Opinion Letter on Under-slab Drainage White Lake Civic Center Development – Public Safety White Lake Township, Oakland County, Michigan G2 Proposal No. 233354R1

Dear Mr. Phillips:

We understand the area of the Public Safety Building has been excavated to an elevation corresponding to the underside of the proposed lower-level floor slab. At this elevation, we understand water is visible in isolated areas and as a result consideration is being given to the construction of an under-slab drainage system for the purpose of mitigating issues that may arise with seasonal variations in the level of the observed water.

We understand the below grade wall portion of the perimeter foundations of the Public Safety building will incorporate drainage; thus, we anticipate groundwater entering the footprint Public Safety building from the surrounding areas will be captured by the wall drainage system and carried away from the building footprint. However, seasonal variations in the amount of precipitation at the site may result in changes to the amount of water delivered through the soil to the under-slab area.

It is our opinion that the construction of an under-slab drainage system will serve to mitigate issues that may arise due to the amount of water delivered to the under-slab area. Under-slab drainage systems typically consist of slotted PVC pipe, encapsulated in stone, spaced longitudinally every 10 to 20 feet. The system should be sloped to promote gravity drainage and should be connected to a sump-pump system. Water from the sump-pump system should be discharged to a point where the water can drain away from the building footing print by gravity. We recommend cleanouts be provided along the length of all drainage systems to allow for future maintenance.

Prolonged high-frequency operation of sump-pump systems could result in pre-mature failure of the pump. We therefore recommend sump-pump systems include a fail-safe pump. To mitigate issues that may arise due to a power-outage, we recommend the sump-pump system also include a power fail-safe such as being tied to a generator system or battery backup.

g2consultinggroup.com

Headquarters 1866 Woodslee St Ann Arbor 1350 Eisenhower Pl Chicagoland 1186 Heather Dr

Troy, MI 48083 Ann Arbor, MI 48108 Lake Zurich, IL 60047

P 248.680.0400 F 248.680.9745 P 734.390.9330 P 847.353.8740

F 734.390.9331 F 847.353.8742 30 February 24, 2025 G2 Project No. 233354 Page 2





We appreciate the opportunity to provide construction engineering services to you and look forward to continue working with you on this project.

Sincerely,

G2 Consulting Group, LLC

OF Michael G. Dagher, P.E. 36KER Project Manager DINEER No. MGD/JBS/jbs 62589 ESSIO

as 33

Jason B. Stoops, P.E. Associate / Project Consultant



March 13. 2025

Mr. Aaron A. Phillips **Project Director** McCarthy & Smith, Inc. 24317 Indoplex Circle Farmington Hills, Michigan 48335

RE: Opinion Letter on Under-slab Drainage White Lake Civic Center Development – Public Safety White Lake Township, Oakland County, Michigan G2 Proposal No. 233354R1

Dear Mr. Phillips:

We understand the area of the Public Safety Building has been excavated to an elevation corresponding to the underside of the proposed lower-level floor slab. At this elevation, we understand water is visible in isolated areas and as a result consideration is being given to the construction of an under-slab drainage system for the purpose of mitigating issues that may arise with seasonal variations in the level of the observed water.

We understand the below grade wall portion of the perimeter foundations of the Public Safety building will incorporate drainage; thus, we anticipate groundwater entering the footprint Public Safety building from the surrounding areas will be captured by the wall drainage system and carried away from the building footprint. However, seasonal variations in the amount of precipitation at the site may result in changes to the amount of water delivered through the soil to the under-slab area.

It is our opinion that the construction of an under-slab drainage system will serve to mitigate issues that may arise due to the amount of water delivered to the under-slab area. Under-slab drainage systems typically consist of slotted PVC pipe, encapsulated in stone, spaced longitudinally every 10 to 20 feet. The system should be sloped to promote gravity drainage and should be connected to a sump-pump system. Water from the sump-pump system should be discharged to a point where the water can drain away from the building footing print by gravity. We recommend cleanouts be provided along the length of all drainage systems to allow for future maintenance.

Prolonged high-frequency operation of sump-pump systems could result in pre-mature failure of the pump. We therefore recommend sump-pump systems include a fail-safe pump. To mitigate issues that may arise due to a power-outage, we recommend the sump-pump system also include a power fail-safe such as being tied to a generator system or battery backup.

g2consultinggroup.com

Headquarters 1866 Woodslee St Ann Arbor 1350 Eisenhower Pl Chicagoland 1186 Heather Dr

Troy, MI 48083 Ann Arbor, MI 48108 Lake Zurich, IL 60047

F 248.680.9745 P 248.680.0400 P 734.390.9330 P 847.353.8740

F 734.390.9331 F 847.353.8742 32 March 13, 2025 G2 Project No. 233354 Page 2





We understand consideration is being given to minimizing the footprint of the under-slab drainage system. Provided that some degree of risk of groundwater accumulation beneath the surface of the slab can be tolerated, the under-slab drainage footprint could be reduced to targeted areas. If the risk of groundwater accumulation beneath the slab cannot be tolerated, we recommend the under-slab drainage system encompass the footprint of the proposed building.

We appreciate the opportunity to provide construction engineering services to you and look forward to continue working with you on this project.

Sincerely,

G2 Consulting Group, LLC

Michael G. Dagher, P.E. Project Manager

MGD/JBS/jbs



Jason B. Stoops, P.E. Associate / Project Consultant

| | | | | | | | | | | | | | | | | | - 5 | Sectio | n 6, Item |
|----------------------|-----------------------------|-----------------------|------------------|---|-------------------------------------|-----------------------------|--|---------------------------|---------------------------|-----------------------------------|--------------------------|---------------------|-----------|---|------------------------|---------------------------------------|------------------------------------|----------------|--------------------|
| | | | CONTR | ACTOR | QUOTAT | ΓΙΟΝ | - WORK | K ITE | MS I | DETA | AIL. | | | = to be complete = predetermined | l by Cont or automa | ractor atic calcula | tion | | |
| | Date: April 11, 2 | 025 | | | - | | Pro | ject Na | me: | Whit | e Lake C | ivic Ce | enter | | | | | | |
| Contr | actor: Cortis Bro | thers | | | | | A/E / A/E | Projec | t #: | | | | | | | | | | |
| | Check One | Check if PRI | ME Contractor | Ch | eck if Subcontr | actor | | С | M: | McCa | arthy & S | mith, I | nc. | | | | | | |
| F | BULLETIN NO: | 5 | C | CD NO: | | | ASI NO: | | | | | Co | ontrac | tor CHANGE R | EQUES | T NO: | | | 5 |
| Description of Work: | | | | | | | | | | | | | | | | | | | |
| Install | Storm For Bu | ılletin 5 (No | ote: Stub to |) be left (| outside of J | p <mark>ad</mark> fo | or connect | tion:) | | | | | | | | | | | |
| A. | MATERIALS an | nd PURCHASI | ED EQUIPM | ENT | | | | Enter | negative woi | quantity rk items. | for deleted | D | O NOT | INCLUDE State Sales | Tax. | | | | |
| | Description | | | | | | | Qua | ntity | М | easure | | Char | ge Price | Per | | TO | ΓAL | ¢1.000.00 |
| | 2 - Dirt Out | | | | | | | | 50 | | CY | \$ \$ | | 36.00 | | | | | \$1,800.00 |
| | 3 - 6" Pipe Mat | erials (Yard Ma | terials) | | | | | | 2 | | LS | \$ | | 725.00 | | | | | \$1,450.00 |
| | 4 - 4' MH | | | | | | | | 1 | | EA | \$ | | 3,150.00 | | | | | \$3,150.00 |
| | 5 - Rim & Cov | er | | | | | | | 1 | | EA | \$ | | 550.00 | | | | | \$550.00 |
| | ** To add rows: 0 | COPY row, then | INSERT COP | ED CELLS, | then re-numbe | er. ** | | | 0 | | EA | | | Sub-7 | otal Mate | erial Amou | nt = | | \$6.950.00 |
| | | | | | | | | | | | | | | 6% St | ate Sales | Tax Amou | nt = | | \$417.00 |
| | | | | | | | | | | | | | | Sub-T | otal Mate | erial Amou | nt = | | \$7,367.00 |
| | | | | | | | | | | | | | 10% C | overhead & Profit N | fark-up ((| 0% if Credi | it) = | | \$736.70 |
| | | | | | | | | | | | | | | То | tal Mate | rial Amou | nt = | | \$8,103.70 |
| В. | LABOR | On first quot | tation provide | breakdow | n of rate for re | eview by | y McCarthy | & Smith | n. Rate | to incl | uded burd | en and I | 10% C | H&P per contrac | t. | | | | |
| | | | 5 | Approved HOURLY Straight Time RATE (a) | TOTAL Straight Time HOURS (b) | Appi Hot 1- Time F | roved TC urly 1-1/2 Rate (c) HOU | OTAL 2 Time URS (d) | App Ho Do Time l | roved urly uble Rate (e) | TOTA Double ' HOUR | AL Time S (f) | | TOTAL Straight Time AMOUNT = a x b | 1- A | FOTAL -1/2Time MOUNT = c x d | TOTA Double T AMOU =e x f | L ime VT | |
| | Craft/Trad Classificatio | le: LABOR n: | \$ | 88.00 | 32 | \$ | - | | \$ | - | | | = | \$ 2,816 | 00 \$ | - | \$ | - | |
| | Craft/Trad Classificatio | le: n: OPERATOR | \$ | 95.00 | 64 | \$ | - | | \$ | - | | | = | \$ 6,080 | 00 \$ | - | \$ | - | |
| | Craft/Trad Classificatio | le: n: | 5 | i - | | \$ | - | | \$ | - | | | = | \$ | \$ | - | \$ | - | |
| | Craft/Trad Classificatio | le: n: | 5 | · - | | \$ | - | | \$ | - | | | = | \$ | \$ | - | \$ | - | |
| | ** To add rows: 0 | COPY row, then | INSERT COPI | ED CELLS, | then re-numbe | er. ** | | | | | | Sub-To | otals = | \$ 8,896 | 00 \$ | - | \$ | - | |
| | ** WHEN ADDIN | IG ROWS, LINK | PROPERLY 1 | O LABOR I | RATE SUMMA | RY TAB | ** | | | | Sub- | Total Fie | eld Lal | oor Amount (Straight | time + x1.5 | time + x2 tim | ne) = | | \$8,896.00 |
| | | | | | | | | | | | If net credit | t, reductio | on in cre | dit to omit 10% Over | nead & Pro | fit in labor r | ate = | not | applicable |
| | | | | | | | | Enter | negative | augntity | for deleted | | | | Fotal La | bor Amou | nt = | | \$8,896.00 |
| C. | FIELD EQUIPM | IENT RENTA | LS | | | | | Enter | woi | rk items. | ior utilitie | | | | | | | | |
| | Field Equipment I | Description (i.e. | Backhoe, mar | lift, etc N | ot Job Vehicle | s) | | Qua | ntity | M | easure | | Char | ge Price | Per | | | | A |
| | 1 - Loader | | | | | | | | 16 | | HR | \$ ¢ | | 195.00 | | | | | \$3,120.00 |
| | 3 - Dozer | | | | | | | | 16 | | HR | s s | | 163.00 | | | | | \$2,608.00 |
| | ** To add rows: 0 | COPY row, then | INSERT COP | ED CELLS, | then re-numbe | er. ** | | | | | | * | | Sub-Total Fie | d Equipn | nent Amou | nt = | | \$9,440.00 |
| | | | | | | | | | | | | | 0% C | overhead & Profit N | lark-up ((| 0% if Credi | it) = | | \$0.00 |
| | | | | | | | | | | | | | | Total Field | Equipm | ent Amou | nt = | | \$9,440.00 |
| D. | UNIT PRICES: 1 | Include materi | al, labor, all t | axes other | costs and fee | s | | Enter | negative woi | quantity rk items. | for deleted | | | | | | | | |
| | Field Equipment l | Description (i.e. | Backhoe, mar | lift, etc N | ot Job Vehicle | s) | | Qua | ntity | М | easure | | Char | ge Price | Per | | | | |
| | 1 - | | | | | | | | | | HR | \$ | | 215.00 | | | | | \$0.00 |
| | 2- | CODV 4 | NEEDTCOD | ED CELLS | <i>a</i> 1 | ** | | | | | HR | \$ | | 131.00 | | <u> </u> | | | \$0.00 |
| Б | SUBCONTRAC | TOP MADE I | | ED CELLS, | inen re-numbe | <i></i> | | | | | | | | 100 | ii Unit Pi | rice Amou | nt = | | \$0.00 |
| E. | Name of Subcontr | actor | 01 | | | | | | | | | | | | | | | Amo | unt |
| | 2 - | | | | | | | | | | | | | | | | | | \$0.00 |
| | 3 - | | | | | | | | | | | | | | | | | | \$0.00 |
| | ** To add rows: O | COPY row, then | INSERT COP | ED CELLS, | then re-numbe | er. ** | | | | | | | | Sub-Total S | ıbcontrac | tor Amoun | its = | | \$0.00 |
| | | | | | | | | | | | | | 5% C | verhead & Profit N | lark-up ((| 0% if Credi | it) = | | \$0.00 |
| | | | | | | | | | | | | | | Total St | bcontrac | tor Amou | nt = | | \$0.00 |
| ΤΟΤΑΙ | AMOUNT FOR BULLETIN NO | R WORK ITE 0. 5 | M NO. | CCD NO. | | | ASI NO | | | | Contra | ctor CI | HANG | E REQUEST N | 0 | | 1 | | |
| | | | | | | | | | | | A. | | | Tot | ıl Materi | al Amoun | .t = | | \$8,103.70 |
| | | | | | | | | | | | В. | | | T | otal Lab | or Amoun | it = | | \$8,896.00 |
| | | | | | | | | | | | C. | | | Total Field | Equipme | nt Amoun | it = | | \$9,440.00 |
| | | | | | | | | | | | D. | | | Total | Unit Pri | ce Amoun | it = | | \$0.00 |
| | | | | | | | | | | | E. | | Т | otal Subcontracto | r Mark-u | ap Amoun | it = | | \$0.00 |
| | | | | | | Bond | % 1% |) | | | F. | | TO | | Bond | Premium | = | | \$264.40 |
| | | | | | | | | | | | | | TOT | AL AMOUNT F | OR WO | KK ITEN | v1 = | 9 | 526,704.1 <u>0</u> |

Г

| | ~ | | OUCT | TION - | | | D | | | | = to be comple | ted by | Contractor | | |
|-----------|---|-------------------------|------------------------|-----------------|-----------|-------------------|------------|---|-------------|--------------|---|--|--|-------------------|--|
| | CONT | RACTOR | QUOTA | TION - V | VORF | K ITEMS | DET | AIL | | | = predetermine | d or a | utomatic calculati | on | |
| | Date: April 15, 2025 | | | | Proje | ect Name: | Whit | e Lake C | harter 1 | Fown | ship Bid Pacl | kage : | #3 - New Publi | ic Safety H | Building |
| Cont | ractor: Metropolitan Concrete | | | A/E | E / A/E I | Project #: | Reds | tone Arc | hitects | | | | | | |
| | Check One Check if PRIME Contract | or 🗆 Che | eck if Subcontra | actor | | CM: | McCa | arthy & S | Smith, I | nc. | | | | | |
|] | BULLETIN NO: | CCD NO: | | ASI | NO: | | | | Co | ntrac | tor CHANGE | REQ | UEST NO: | | #01 |
| scriț | ption of Work: | | | | | | | | | | | | | | |
| rni | ish and install Precon Under slab | Membran | e | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| <u>،</u> | MATERIALS and PURCHASED FOU | IPMENT | | | | Enter negative | quantity | for deleted | D |) NOT | INCLUDE State Sa | les Tax. | | | |
| | Description | | | | | Ouentity | ork items. | 0000000 | | Char | no Drigo | р | lon | тота | r |
| | 1 - Vapor barrier (credit for base bid mat | erial) | | | | Quantity |) ea | easure | \$ | Char | (275.00) | | ea | 101A | -\$2,750.0 |
| | 2 - Tape (credit for base bid material) | | | | | 20 |) ea | | \$ | | (15.00) | 6 | ea | | -\$300.0 |
| | 3 - | | | | | | | | | | | | | | \$0.0 |
| | 4 - | | | | | | | | | | | | | | FALS |
| | 3 - Shipping/Freight (when applicable) | | | | | 1 | IS | | ¢ | | | I | s | | \$0.0 |
| | ** To add rows: COPY row, then INSERT | COPIED CELL | S, then re-num | ıber. ** | | 1 | | | Ψ | | Sut | -Total | Material Amount | t = | -\$3,050.0 |
| | | | | | | | | | | | 6% | State | Sales Tax Amount | t = | -\$183.0 |
| | | | | | | | | | | 00/ 0 | Sut | -Total | Material Amount | = | -\$3,233.0 |
| | | | | | | | | | 1 | 0% U | vernead & Profi | i wiark Fotal 1 | -up (0% II Credit) Material Amount | = c | -\$3,233.0 |
| 3. | LABOR On first quotation pro | vide breakdow | n of rate for | review by Mo | Carthv | & Smith. R | ate to ir | cluded bu | rden and | 1 10% | OH&P per con | ntract. | | | |
| • | ······································ | Approved | | Approved | | Anr | oroved | | | | TOTAL | | TOTAL | TOTAL | ٦ |
| | | HOURLY Straight Time | TOTAL Straight Time | Hourly 1-1/2 | 1-1/2 | TAL Ho Time Do | ourly | Double | AL Time | | Straight Tim AMOUNT | e | 1-1/2Time AMOUNT | Double Time | |
| | | RATE (a) | HOURS (b) | Time Rate (c) | HOU | RS (d) Time | Rate (e) | HOUR | S (f) | | = a x b | | = c x d | =e x f | |
| | Craft/Trade: Credit labor to install vapor Classification: barrier | r \$ (85.00) | 24 | \$- | | \$ | - | | | = | \$ (2,0 | 40.00) | \$- | \$- | |
| | Craft/Trade: Labor to pour in 3 pours Classification: instead of 2 pours | \$ 85.00 | 96 | \$ - | | \$ | - | | | = | \$ 8,1 | 60.00 | s - | \$- | |
| | Craft/Trade: Labor for added day of | \$ 85.00 | 16 | ¢ | | ¢ | | | | _ | \$ 12 | 50.00 | ¢ | ¢ | |
| | Classification: sawcuting | \$ 85.00 | 10 | ə - | | Þ | | | | = | \$ 1,5 | 50.00 | ş - | ə - | |
| | Craft/Trade: Classification: | \$ - | | \$ - | | \$ | | | | = | \$ | - | s - | \$- | |
| | ** To add rows: COPY row, then INSERT (| COPIED CELL | S, then re-num | ıber. ** | | | | | Sub-Tot | als = | \$ 7,4 | 80.00 | \$- | \$ - | 4 |
| | ** WHEN ADDING ROWS, LINK PROPEI | RLY TO LABOR | RATE SUMM | ARY TAB ** | | | | Sub- | Total Fie | ld Lat | or Amount (Strai | ght time | + x1.5 time + x2 time) | . = | \$7,480.0 |
| | | | | | | | | If net credit | , reduction | 1 in cre | dit to omit 10% Ov | erhead | & Profit in labor rate | e = | \$537.0 |
| a | | | | | | Enter negative | e quantity | for deleted | | | | 100 | ai Lador Anioun | L = | \$7,480.0 |
| C. | FIELD EQUIPMENT RENTALS | | | | | wo | ork items. | | | ~ | | | | | |
| | Field Equipment Description (i.e. Backhoe | , manlift, etc | Not Job Vehic | eles) | | Quantity | M | easure | s | Charg | 2 900 00 | P | er | | \$8 700 0 |
| | 2 - | ouggy on ano p | Jouro | | | | , cu | | Ŷ | | 2,00000 | | | | \$0.0 |
| | 3 - | | | | | | | | | | | | | | \$0.0 |
| | ** To add rows: COPY row, then INSERT (| COPIED CELL | S, then re-num | ıber. ** | | | | | 1 | 0% 0 | Sub-Total F | ield E | quipment Amount | : = | \$8,700.0 |
| | | | | | | | | | 1 | 070 U | Total Fi | eld Eq | uipment Amount | = | \$9,570.0 |
| D. | UNIT PRICES: Include material, labor. | all taxes othe | r costs and f | ees | | Enter negative | e quantity | for deleted | | | | | | | |
| | Field Equipment Description (i.e. Backhoe | manlift. etc | Not Job Vehic | les) | | Ouantity | M | easure | | Char | e Price | Р | er | | |
| | 1 - | ,, | | | | Quality | ea | | | | <u></u> | _ | | | |
| | 2 - | | a 1 | | | | | | | | | | | - | \$0.0 |
| | ** To add rows: (DPV row than INSERT (| COPIED CELL | S, then re-num | iber. ** | | | | | | | Т | otal U | nit Price Amount | t = | \$0.0 |
| | To dad Tows. COT I Tow, then INSERT | | | | | | | | | | | | | - | A |
| E. | SUBCONTRACTOR MARK-UP | | | | | | | | | | | | | | \$115,385.0 |
| E. | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers | | | | | | | _ | | - | | _ | | | \$0.0 |
| E. | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - | | | | | | | | | | | | | | φ0.0 |
| E. | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - 3 | | 0.4 | , | | | | | | | | a : | | | \$0.0 |
| E. | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - 3 - ** To add rows: COPY row, then INSERT 0 | COPIED CELL | S, then re-num | ıber. ** | | | | | | 5% 0 | Sub-Total | Subco | ontractor Amounts | | \$0.0 \$0.0 \$115,385.0 \$5 760 2 |
| Е. | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - 3 - ** To add rows: COPY row, then INSERT O | COPIED CELL | S, then re-num | ıber. ** | | | | | | 5% O | Sub-Total Iverhead & Profi Total | Subco t Mark Subco | ontractor Amounts -up (0% if Credit) | s =) = t = | \$0.0 \$0.0 \$115,385.0 \$5,769.2 \$121,154.2 |
| E. DTA | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - 3 - ** To add rows: COPY row, then INSERT C | COPIED CELL | S, then re-num | ıber. ** | | | | | | 5% C | Sub-Total Iverhead & Profi Total | Subco t Mark Subco | ontractor Amounts -up (0% if Credit) ontractor Amount | ; =) = : = | \$0.0 \$0.0 \$115,385.0 \$5,769.2 \$121,154.2 |
| E. DTA | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - 3 - ** To add rows: COPY row, then INSERT O L AMOUNT FOR WORK ITEM NO. BULLETIN NO. | COPIED CELL | S, then re-num | iber. ** | SI NO. | | | Contra | ctor CH | 5% O | Sub-Total werhead & Profi Total & REQUEST | Subco t Mark Subco NO. | ontractor Amounts -up (0% if Credit) ontractor Amount | | \$0.0 \$0.0 \$115,385.0 \$5,769.2 \$121,154.2 |
| E. DTA | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - 3 - ** To add rows: COPY row, then INSERT of L AMOUNT FOR WORK ITEM NO. BULLETIN NO. | COPIED CELL CCD NO. | S, then re-num | iber. ** A | SI NO. | | | Contra | ctor CH | 5% 0 | Sub-Total Werhead & Profi Total SE REQUEST | Subco t Mark Subco NO. | ontractor Amounts up (0% if Credit) ontractor Amount | | \$0.0 \$115,385.0 \$5,769.2 \$121,154.2 |
| E. DTA | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - 3 - ** To add rows: COPY row, then INSERT (L AMOUNT FOR WORK ITEM NO. BULLETIN NO. | COPIED CELL | S, then re-num | uber. ** A | SI NO. | | | Contra A. B. | ctor CH | 5% O | Sub-Total werhead & Profi Total EE REQUEST | Subco t Mark Subco NO. | ontractor Amounts up (0% if Credit) ontractor Amount faterial Amount 1 Labor Amount | | \$0.0 \$0.0 \$115,385.0 \$5,769.2 \$121,154.2 -\$3,233.0 \$7,480.0 |
| E. DTA | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - 3 - ** To add rows: COPY row, then INSERT (L AMOUNT FOR WORK ITEM NO. BULLETIN NO. | COPIED CELL CCD NO. | S, then re-num | iber. ** A | SI NO. | | | Contra A. B. C. | ctor CH | 5% O | Sub-Total Verhead & Profi Total SE REQUEST T Total Fiel | Subco t Mark Subco NO. Otal M Total d Equ | ontractor Amounts up (0% if Credit) ontractor Amount faterial Amount I Labor Amount ipment Amount | | \$0.0 \$115,385.0 \$121,154.2 \$121,154.2 -\$3,233.0 \$7,480.0 \$9,570.0 |
| E.)TA | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - 3 - ** To add rows: COPY row, then INSERT (LAMOUNT FOR WORK ITEM NO. BULLETIN NO. | COPIED CELL | S, then re-num | iber. ** A | SI NO. | | | Contra A. B. C. D. | ctor CH | 5% O | Sub-Total Verhead & Profi Total EE REQUEST T Total Fiel Total | Subco t Mark Subco NO. otal M Total d Equ al Un: | Intractor Amounts -up (0% if Credit) Intractor Amount faterial Amount I Labor Amount ipment Amount it Price Amount | | \$0.0 \$115,385.0 \$5,769.2 \$121,154.2 \$3,233.0 \$7,480.0 \$9,570.0 \$0,0 |
| E. | SUBCONTRACTOR MARK-UP Name of Subcontractor 1 - DC Byers 2 - 3 - ** To add rows: COPY row, then INSERT of L AMOUNT FOR WORK ITEM NO. BULLETIN NO. | COPIED CELL | S, then re-num | ber. ** A | SI NO. | | | Contra A. B. C. D. E. F | ctor CH | 5% 0 IANG | Sub-Total Veerhead & Profi Total E REQUEST T Total Fiel Tot Subcontrac | Subco t Mark Subco NO. otal M Total d Equ al Un ctor M | Intractor Amounts -up (0% if Credit) Intractor Amount I Labor Amount ipment Amount it Price Amount Iark-up Amount Bond Preserview | | \$0.0 \$115,385.0 \$5,769.2 \$121,154.2 \$121,154.2 \$3,233.0 \$7,480.0 \$9,570.0 \$0,0 \$121,154.2 \$104.2 \$104.2 |



D.C. BYERS CO., INC. 14495 E. Eight Mile Rd. Warren, MI 48089 Ph: (313) 875-0545 Date: 4-21-2025 To: Metropolitan Attn: Tony Project: White Lake Twp – Public Safety

REVISED PROPOSAL

Under Slab Membrane Waterproofing

Furnish and install under slab membrane waterproofing at the under slab of the basement slab only. The membrane will be applied over a well compacted substrate and applied over the interior concrete footings (interior footings will not be encased in waterproofing) We will detail all thru slab penetrations, interior columns, and up the interior perimeter walls per manufacturer's details.

| We priced up (4) systems per request of the architect. | Quote is for this product |
|---|---------------------------|
| The price increase comes from revised details and pricing from the manufacturer's | |
| Precon Under Slab Membrane by W.R. Meadows\$115 | 5,385.00 |
| SikaProof A+12 by Sika Corp\$18 | 8,100.00 |

**We did not fine tune the details with Polyguard or GCP at this time!!

| UnderSeal UnderSlab Membrane by Polyguard | \$163,000.00 |
|---|--------------|
| Preprufe 300R by GCP (Grace) | \$197,000.00 |

Exclusions:

*Any work needed to be done to the substrate to properly install the waterproofing per manufacturer's recommendations.

*Encasing of the interior or exterior footings with waterproofing / Applying above the interior footings

*Any concrete prep, patching, etc

*Waterproofing any area besides underneath the basement

*Dewatering or demucking

Notes:

***Substrate must be Well compacted and free of water/puddles, etc**

Respectfully submitted, D.C. Byers Company., Inc.

Thomas Stackpoole, Vice President

| From: | Tony <tony@metropolitanconcrete.com></tony@metropolitanconcrete.com> |
|--------------|--|
| Sent: | Monday, April 21, 2025 2:57 PM |
| То: | Noah Steiner |
| Cc: | Chuck Kassley |
| Subject: | External RE: WLT PSB Under slab waterproofing |
| Attachments: | CO 5166 Precon product Waterproofing rev 3.pdf; SikaProof product |
| | Waterproofing Rev 1.pdf |

Noah see the attached revised proposals. The price went up substantially for DC Byers. There were elements of each that DC byers was not made aware of from the suppliers and there was a large misunderstanding between DC Byers and the Sika rep on material pricing. As we discussed the letter from WR Meadows referring to the stable substrate being stable for the laser screed is a very general statement. The definition of stable can vary depending on what side you are on. If WR Meadows wants to come and test the substrate and the base material prior to installation and sign off on it saying we can use a laser screed and they will be responsible for any damage I will use a laser screed and revise the number. Outside of that I would strongly suggest that if a decision is made we should set up a meeting with ourselves, DC byers and the rep of whichever way we decide to go and make sure that everyone has a clear understanding of the conditions, how the product needs to be installed and any precautions and affects on pouring operations.

Tony Volpe Estimator



Metropolitan Concrete Corp. 6581 Metro Parkway Sterling Heights, MI 48312 O: 586-264-3370 M: 586-615-7611 Tony@MetropolitanConcrete.com https://link.edgepilot.com/s/5b37a9ce/nkuGMUKZXUKIVa5V_nsDYw?u=http://www.metropolitanconcr ete.com/



From: Noah Steiner <<u>nsteiner@mccarthysmith.com</u>> Sent: Monday, April 21, 2025 12:33 PM To: Tony <<u>tony@metropolitanconcrete.com</u>> Subject: FW: WLT PSB Under slab waterproofing

| hite Lake Charte | r Townshi | n C | ivic Ce | nter | Deve | onmer | it | | | | | | 1 | | Section | on 6, It |
|--|-----------------------------|--------------------------------------|-------------------------------------|---|-----------------------|-----------------------------------|------------------------------------|------------------------|---|------------------|--|-----------|---|--------------------------------|------------------------|------------|
| | CONTRAC | TOR | | TION - | WORK | C ITFMS | DFT | ATL | | | = to be comple | eted by | Contractor | L | | |
| | | | QUUIA | | | | | | L | | | | #2 Norre Del | 1: - C - f | 4. D. 11 | • |
| Date: April 15, 2025 | | | | | Proj | ject Name: | Whit | e Lake C | harter 1 | owns | hip Bid Pac | kage | #3 - New Pul | olic Safe | ty Build | ing |
| ontractor: Professional Thermal Systems Inc. A/I | | | | A/E / A/E | Project #: | Reds | tone Arc | mith In | | | | | | | | |
| | | | | ractor | | CM: | witte | artify & S | , | ι. | | | | | | |
| BULLETIN NO: 11 | CCD | NO: | | A | SI NO: | | | | Cor | ntract | or CHANG | E RE | QUEST NO: | | | |
| cription of Work: | | | | | | | | | | | | | | | | |
| rm Piping and Drain Tile | Work | | | | | | | | | | | | | | | |
| . MATERIALS and PURCHA | SED EQUIPMEN | Т | | | | Enter negative wo | quantity rk items. | for deleted | DO | NOT I | NCLUDE State Sa | ales Tax | | | | |
| Description | | | | | | Quantity | M | easure | С | harge | Price | F | Per | TC | DTAL | |
| 1 - Drain Tile and Fittings | | | | | | 1 | | | \$ | | 3,657.00 | | | | | \$3,657.00 |
| 2 - Fabric Material | | | | | | 1 | | | \$ | | 685.00 | | | | | \$685.00 |
| 3 - Storm Pipe Material | | | | | | 65 | ton | | 5 | | 22,464.00 | + | on | | 3 | \$2 161 24 |
| 5 - Peastone | <u> </u> | | | | | 169 | ton | | s | | 33.25 | t t | on | | | \$5,661.50 |
| 8 - Class II Sand | | | | | | 150 | ton | | s | | 15.33 | t | on | | | \$2,299.50 |
| ** To add rows: COPY row, th | hen INSERT COPIED | O CELLS | s, then re-num | ber. ** | | | | | | | Sul | b-Tota | l Material Amou | int = | \$ | 36,928.25 |
| | | | | | | | | | | | 6% | State | Sales Tax Amou | int = | | \$2,215.70 |
| | | | | | | | | | | | Sul | b-Tota | l Material Amou | int = | \$ | 39,143.95 |
| | | | | | | | | | 10 | % Ov | erhead & Profi | it Marl | k-up (0% if Cred | it) = | | \$3,914.39 |
| | | | | | | | | | | | | Total | Material Amou | nt = | \$ | 43,058.34 |
| LABOR On first q | uotation provide bro | eakdow | n of rate for 1 | review by | McCarthy | & Smith. R | ate to i | ncluded bu | ırden and | 10% | OH&P per co | ontrac | t. | | | |
| | App HOI Straig RAT | oroved URLY ght Time TE (a) | TOTAL Straight Time HOURS (b) | Approve Hourly 1-1/2 Time Rate | ed TO 1-1/2 HOU | TAL App Time Do RS (d) Time | roved ourly uble Rate (e) | TOTA Double HOUR | AL Fime S (f) | | TOTAL Straight Tim AMOUNT = a x b | ie | TOTAL 1-1/2Time AMOUNT = c x d | TOT. Double AMOU =e x | AL Time JNT f | |
| Plumber | s | 102.08 | 532 | s - | | s | ÷ | | | = 5 | 54,3 | 06.56 | s - | s | - | |
| Craft/Trade: Classification: | \$ | - | | s - | | \$ | - | | | = 5 | 5 | - | s - | s | - | |
| Craft/Trade: Classification: | \$ | - | | s - | | \$ | - | | | = 5 | 5 | - | s - | s | - | |
| Classification: | S | - | | s - | | \$ | - | | | - 5 | ; | - | s - | \$ | - | |
| ** To add rows: COPY row, ti | hen INSERT COPIED |) CELLS | S. then re-num | ber. ** | | | | | Sub-Total | ls = | 54,3 | 06.56 | s - | \$ | - | |
| ** WHEN ADDING ROWS, L | INK PROPERLY TO | LABOR | RATE SUMM | ARY TAB | ** | | | Sub- | Total Field | d Labo | r Amount (Stra | ight time | e + x1.5 time + x2 tir | ne) = | \$ | 54,306.56 |
| | | | | | | | 1 | If net credit, | reduction in | n credit | to omit 10% Ov | /erhead | & Profit in labor r | ate = | not a | applicable |
| | | | | | | | | | | | | Tot | al Labor Amou | nt = | \$ | 54,306.56 |
| . FIELD EQUIPMENT RENT | TALS | | | | | Enter negative wo | quantity rk items. | for deleted | | | | | | | | |
| Field Equipment Description | (i.e. Backhoe, manlift | t, etc 1 | Not Job Vehic | les) | | Quantity Meas | | easure | С | Charge Price Per | | | | | | |
| 1 - Excavator and Skid Stea | r | | | | | 160 |) S | | | 200.00 | | | | | \$ | 32,000.00 |
| 2 - Spoil Removal | | | | | | 240 | | S | | | 10.00 | 10.00 | | | | \$2,400.00 |
| 3 - Dewatering | | | | | | 1 | | | \$ | | 2,856.00 | | | | | \$2,856.00 |
| ** To add rows: COPY row, th | hen INSERT COPIED | O CELLS | S, then re-num | ber. ** | | | | | | | Sub-Total I | Field E | quipment Amou | ınt = | \$ | 37,256.00 |
| | | | | | | | | | 10 | % Ov | erhead & Profi | it Marl | c-up (0% if Cred | it) = | | \$3,725.60 |
| | | | | | | | | | | | Total Fi | eld Eq | uipment Amou | nt = | \$ | 40,981.60 |
| . UNIT PRICES: Include mat | erial, labor, all taxe | es other | costs and fee | es | | Enter negative wo | quantity rk items. | for deleted | | | | | | | | |
| Field Equipment Description | (i.e. Backhoe, manlift | ì, etc Ì | Not Job Vehic | les) | | Quantity | M | easure | С | harge | Price | F | Per | | | |
| 1 - | | | | | | | | | | | | | | | | \$0.00 |
| 2 - | | | | | | | | | | | | | | | | \$0.00 |
| ** To add rows: COPY row, th | hen INSERT COPIED | O CELLS | S, then re-num | ber. ** | | | 1 | | | | Т | otal U | nit Price Amou | nt = | | \$0.00 |
| SUBCONTRACTOR MARK | K-UP | | | | | | | | | | | | | | | |
| Name of Subcontractor | | | | | | | | | | | | | | | Amou | ınt |
| 1 - | | | | | | | | | | | | | | | | \$0.00 |
| 2 - | | | | | | | | | | | | | | | | \$0.0 |
| 3 - | | | | | | | | | | | | | | | | \$0.0 |
| ** To add rows: COPY row, th | hen INSERT COPIED | O CELLS | S, then re-num | ber. ** | | | | | | | Sub-Tota | l Subc | ontractor Amour | nts = | | \$0.0 |
| | | | | | | | | | 5 | % Ov | erhead & Profi | t Marl | c-up (0% if Cred | it) = | | \$0.00 |
| TAL AMOUNT FOR WORK I | TEM NO. | | | | | I. | l | | | | Total | Subco | ontractor Amou | nt = | | \$0.0 |
| BULLETIN NO. 11 | CC | D NO. | | | ASI NO. | | | Contra | ctor CHA | ANGI | REQUEST | 'NO. | | | | |
| | | | | | | | | А. | | | Т | otal N | Iaterial Amour | nt = | \$4 | 43,058.34 |
| | | | | | | | | В. | | | | Tota | l Labor Amour | nt = | \$5 | 54,306.5 |
| | | | | | | | | C. | | | Total Fiel | d Equ | ipment Amour | nt = | \$4 | 10,981.6 |
| | | | | | | | | D. | | | Tot | tal Un | it Price Amour | nt = | | \$0.0 |
| | | | | | | ı | | E. | | Tot | al Subcontra | ctor M | lark-up Amour | nt = | | \$0.0 |
| | | | | D | 10/ | | | | | | | | Hond Promiun | | | |
| | | | | Bond % | 1% | J | | г. | - | 07 | | - | | | 5 | \$1,383.46 |

Г

Material & Labor Detail

| Project Name: | White Lake Pub Safe Bull 11 |
|----------------------|-----------------------------|
| Bid ID: | 041125 |
| Report Time: | 4/15/2025 1:48 PM |
| Profile Name: | Standard |
| Labor Book: | Standard |
| Scoped By: | Base Bid1 |

AutoBid Version: 2021 v1

39

Trimble Navigation Material & Labor Detail

There was one calculation message. Project Name: White Lake Pub Safe Bull 11 Bid ID: 041125 Data Calculated: 4/15/2025 1:21:44 PM Base Bid; **D:**

Page 1 Report Time: 4/15/2025 1:48:13 PM

| Ріре | | | | | | |
|--------------------------------|--------------|---------------|--------------------|--------------------|---------------------|--|
| PVC - DWV - DWV | | | | | | |
| Item Size | 05 | Price | Mat Cost | Unit Lab Hr | Total Hrs | |
| Pine <u>Size</u> | QI¥ | <u>r rice</u> | <u>191at. U081</u> | UIIIL LAU III | <u>1 Utal III's</u> | |
| 6 | 1,198 | 5.64 | 6,756 | 0.09 | 114 | |
| PVC - DWV - DWV Totals: | | | | | | |
| - | 1,198 | | 6,756 | _ | 114 | |
| Pipe Totals: | 1,198 | | 6,756 | _ | 114 | |
| Ninnles | | | | | | |
| PVC - Plain End Sch 40 - ' | Thread | | | | | |
| L | | | | | | |
| <u>Item Size</u> Nipple | Qty | Price | <u>Mat. Cost</u> | <u>Unit Lab Hr</u> | <u>Total Hrs</u> | |
| 6 | 2 | 26.86 | 54 | 0.10 | 0 | |
| PVC - Plain End Sch 40 - Th | read Totals: | | | | | |
| - | 2 | _ | 54 | _ | 0 | |
| Nipples Totals: | 2 | | 54 | | 0 | |
| T | | | | | | |
| Fittings | | | | | | |
| PVC - Hub x Hub Plastic | DWV - Solv | Wld | | | | |
| Item Size | Otv | Price | Mat. Cost | Unit Lab Hr | Total Hrs | |
| 1/16 Bend | <u>×4</u> | <u></u> | <u></u> | <u>e me 200 m</u> | <u> </u> | |
| 6 | 1 | 57.81 | 58 | 0.66 | 1 | |
| 1/4 Bend | | | | | | |
| 6 | 34 | 49.96 | 1,699 | 0.68 | 23 | |
| 1/8 Bend | | | | | | |
| 6 | 28 | 43.79 | 1,226 | 0.66 | 19 | |
| Combination | | | | 4.00 | | |
| 6 | 34 | 137.37 | 4,671 | 1.03 | 35 | |
| Coupling | 19 | 10.48 | 251 | 0.65 | 12 | |
| Wyve | 10 | 19.40 | 551 | 0.05 | 12 | |
| 6 | 23 | 69.05 | 1,588 | 0.98 | 23 | |
| PVC - Hub x Hub Plastic DW | VV - SolvWld | Totals: | , | | | |
| - | 138 | | 9,592 | | 112 | |
| Fittings Totals: | 138 | | 9,592 | | 112 | |
| Carriers | | | | | | |
| Carriers | | | | | | |
| | | | | | | |
| Item Size | Qty | Price | Mat. Cost | <u>Unit Lab Hr</u> | <u>Total Hrs</u> | |

Trimble Navigation Material & Labor Detail

There was one calculation message. Project Name: White Lake Pub Safe Bull 11 Bid ID: 041125 Data Calculated: 4/15/2025 1:21:44 PM Base Bid;

Carriers

Misc. Consumables Totals:

Grand Totals

Page 2 Report Time: 4/15/2025 1:48:13 PM

0

0

292

Total Hrs

| Carriers | | | | | | |
|-------------------------------|--------------|--------------|------------------|--------------------|------------------|--|
| <u>Item Size</u> | Qty | Price | Mat. Cost | <u>Unit Lab Hr</u> | <u>Total Hrs</u> | |
| BWV BACK WATER VALVE | * | | | | | |
| | 2 | 221.00 | 442 | 1.00 | 2 | |
| FCO CLEANOUT* | | | | | | |
| | 32 | 175.00 | 5,600 | 2.00 | 64 | |
| Carriers Totals: | | | | | | |
| _ | 34 | _ | 6,042 | _ | 66 | |
| Carriers Totals: | 34 | | 6,042 | | 66 | |
| | | | | | | |
| Misc. Consumables | | | | | | |
| - Plastic Joints Glue & Cle | eaner - | | | | | |
| | | | | | | |
| <u>Item Size</u> | Qty | <u>Price</u> | <u>Mat. Cost</u> | <u>Unit Lab Hr</u> | <u>Total Hrs</u> | |
| Glue & Cleaner | | | | | | |
| Cement - PVC | 2 | 5.89 | 10 | 0.00 | 0 | |
| Cleaner-All Purpose | 2 | 6.33 | 10 | 0.00 | 0 | |
| - Plastic Joints Glue & Clean | er - Totals: | | | | | |

3

3

20

20

Material Cost

\$22,464

* Items flagged with an asterisk may have their price and labor overwritten in Excel's Rapid Reports

Richard Sisson Trucking, Inc <richardsissontrucking@gmail.com> Tue, Mar 25,

23, 11:18 AM

to me

Good Morning Steve,

Here is the pricing you requested, -Peastone \$35.50/Ton -6A Limestone \$35.25/Ton -Class II Sand \$16.25/Ton these rates include material, trucking and tax. Please let myself or Cory know if you have any questions.

McCarthy & Smith, Inc.

Printed on Thu Apr 10, 2020 ac of the printed

Job #: 1204-23 White Lake Charter Township New Civic Center Development - BP #3 New Public Safety Building 10911 Elizabeth Lake Rd White Lake , Michigan 48383

Building Pad Water Issue

Description

Taken Date 04/08/2025 at 12:35 pm

Upload Date 04/08/2025 at 12:35 pm

Uploaded By Jeff Robinette

File Name A1B22E66-3833-4DFC-9...



Building Pad Water Issue

Description

Taken Date 04/08/2025 at 11:45 am

Upload Date 04/08/2025 at 11:45 am

Uploaded By Noah Steiner

File Name 92038B4B-1077-4A0C-8...



McCarthy & Smith, Inc.

Printed on Thu Apr 10, 2625 at 01. TO printed

Job #: 1204-23 White Lake Charter Township New Civic Center Development - BP #3 New Public Safety Building 10911 Elizabeth Lake Rd White Lake , Michigan 48383

Building Pad Water Issue

Description

Taken Date 04/08/2025 at 11:45 am

Upload Date 04/08/2025 at 11:45 am

Uploaded By Noah Steiner

File Name 45237500-3AE4-4B39-B...



Building Pad Water Issue

Description

Taken Date 04/02/2025 at 01:36 pm

Upload Date 04/02/2025 at 01:37 pm

Uploaded By Noah Steiner

File Name 1DD19083-E696-4AF5-B...



Printed on Thu Apr 10, 2



Job #: 1204-23 White Lake Charter Township New Civic Center Development - BP #3 New Public Safety Building 10911 Elizabeth Lake Rd White Lake , Michigan 48383

Building Pad Water Issue

Description

Taken Date 03/25/2025 at 08:33 am

Upload Date 03/25/2025 at 08:33 am

Uploaded By Jeff Robinette

File Name 12568422-A54F-4548-A...



Building Pad Water Issue

Description

Taken Date 03/25/2025 at 08:32 am

Upload Date 03/25/2025 at 08:32 am

Uploaded By Jeff Robinette

File Name BC81624C-6B19-423D-B...



Printed on Thu Apr 10, 2

McCarthy & Smith, Inc.

Job #: 1204-23 White Lake Charter Township New Civic Center Development - BP #3 New Public Safety Building 10911 Elizabeth Lake Rd White Lake , Michigan 48383

Building Pad Water Issue

Description

Taken Date 03/19/2025 at 04:29 pm

Upload Date 03/19/2025 at 04:43 pm

Uploaded By Noah Steiner

File Name WLT-3.19-(22).JPG



Building Pad Water Issue

Description

Taken Date 02/25/2025 at 01:38 pm

Upload Date 02/25/2025 at 01:38 pm

Uploaded By Noah Steiner

File Name 76C09FDA-CFB7-4DD3-...



McCarthy & Smith, Inc.

Printed on Thu Apr 10, 2

Job #: 1204-23 White Lake Charter Township New Civic Center Development - BP #3 New Public Safety Building 10911 Elizabeth Lake Rd White Lake , Michigan 48383

Building Pad Water Issue

Description

Taken Date 01/27/2025 at 12:43 pm

Upload Date 01/27/2025 at 12:58 pm

Uploaded By Noah Steiner

File Name 728E0425-FD0A-4BA5-9...



Building Pad Water Issue

Description

Taken Date 01/27/2025 at 12:42 pm

Upload Date 01/27/2025 at 12:42 pm

Uploaded By Noah Steiner

File Name 433D742C-5131-4A30-B...



McCarthy & Smith, Inc.

Printed on Thu Apr 10, 2025 at 01. To printed

Job #: 1204-23 White Lake Charter Township New Civic Center Development - BP #3 New Public Safety Building 10911 Elizabeth Lake Rd White Lake , Michigan 48383

Building Pad Water Issue

Description

Taken Date 01/16/2025 at 09:01 am

Upload Date 01/16/2025 at 09:02 am

Uploaded By Jeff Robinette

File Name 589A2A41-A9F9-4863-B...



Building Pad Water Issue

Description

Taken Date 01/10/2025 at 01:28 pm

Upload Date 01/10/2025 at 01:35 pm

Uploaded By Noah Steiner

File Name C4F39F5C-CC8B-41BB-9...





Printed on Thu Apr 10, 2

Job #: 1204-23 White Lake Charter Township New Civic Center Development - BP #3 New Public Safety Building 10911 Elizabeth Lake Rd White Lake , Michigan 48383

Building Pad Water Issue

Description

Taken Date 12/19/2024 at 09:08 am

Upload Date 04/10/2025 at 12:46 pm

Uploaded By Noah Steiner

File Name 6A921B21-1EF5-42CA-B...



Building Pad Water Issue

Description

Taken Date 11/19/2024 at 12:32 pm

Upload Date 04/10/2025 at 12:48 pm

Uploaded By Noah Steiner

File Name F49DEFB8-031F-4218-A...



Printed on Thu Apr 10, 2



Building Pad Water Issue

Description

Taken Date 11/14/2024 at 12:44 pm

Upload Date 04/10/2025 at 12:49 pm

Uploaded By Noah Steiner

File Name 171C98BA-2BA9-4775-B...





Building Pad Water Issue

Description

Taken Date 10/30/2024 at 12:32 pm

Upload Date . 04/10/2025 at 12:47 pm

Uploaded By Noah Steiner

File Name 982DC3C6-F389-43FF-A...





Job #: 1204-23 White Lake Charter Township New Civic Center Development - BP #3 New Public Safety Building 10911 Elizabeth Lake Rd

Printed on Thu Apr 10, 2

White Lake , Michigan 48383

Building Pad Water Issue

Description

Taken Date 10/28/2024 at 08:33 am

Upload Date 04/10/2025 at 12:45 pm

Uploaded By Noah Steiner

File Name 3E02BB57-3841-48AC-A...

